



ENVIRONMENTAL & SOCIAL IMPACT ASSESSMENT
ON TWANTE CANAL IMPROVEMENT PROJECT
IN YANGON, MYANMAR

ESIA REPORT

August 2019



ENVIRONMENTAL & SOCIAL IMPACT ASSESSMENT
ON TWANTE CANAL IMPROVEMENT PROJECT
IN YANGON, MYANMAR

ESIA REPORT

August 2019



DIRECTORATE OF WATER RESOURCES
AND IMPROVEMENT OF RIVER SYSTEMS



DIRECTORATE OF WATER RESOURCES
AND IMPROVEMENT OF RIVER SYSTEMS

**ENVIRONMENTAL & SOCIAL IMPACT ASSESSMENT
ON TWANTE CANAL IMPROVEMENT PROJECT
IN YANGON, MYANMAR**

ESIA REPORT

August 2019



**Directorate of Water Resources and Improvement of River Systems
Ministry of Transport and Communication
The Republic of the Union of Myanmar**

TABLE OF CONTENTS

CHAPTER 1: CONTEXT OF THE PROJECT

1.1	Introduction.....	1-1
1.2	Background of the Project.....	1-1
1.3	Outline of the Project and Project Components	1-2
1.3.1	Objectives of the Project.....	1-2
1.3.2	Project Components.....	1-2
1.3.3	Project Area.....	1-2
1.3.4	Project Period.....	1-4
1.4	Project Proponent and EIA Team.....	1-4
1.4.1	Objectives of the Proposal and Process.....	1-4
1.4.2	Project Proponent.....	1-4
1.4.2.1	Project Proponent Information	1-5
1.4.3	M ESIA Preparation Team	1-7
1.4.3.1	Resource & Environment Myanmar Ltd. (REM)	1-7
1.4.3.2	EDCF Environmental and Social Impact Assessment Team.....	1-9
1.5	Expected Effects of the Proposed Project.....	1-10
1.6	Implementation Framework of the ESIA	1-11
1.6.1.	Categorization of the Project: Subject to EIA.....	1-11
1.6.2	Project Implementation Schedules and ESIA Implementation Schedules.....	1-11

CHAPTER 2: OVERVIEW OF POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK

2.1	Overview of Myanmar Policies, Legislation and Institutions Concerning Environmental Management during Development Project Implementation and Environmental Impact Assessment.....	2-1
2.2	Institutional Framework on Environmental Management.....	2-1
2.2.1	National Environmental Conservation Committee (NECC).....	2-1
2.2.2	National Environmental Conservation and Climate Change Committee (NECCCC).....	2-2
2.2.3	Ministry of Natural Resources and Environmental Conservation (MONREC).....	2-2
2.3.	Other Relevant Legislations Related to EIA and Environmental Management of the Project.....	2-3
2.3.1	The Constitution of the Union of Myanmar (2008)	2-3
2.3.2	Environmental Policy (1994)	2-4
2.3.3	National Land Use Policy (2016)	2-4

2.3.4	Environmental Conservation Law (2012)	2-4
2.3.5	Environmental Conservation Rules (2014)	2-6
2.3.6	Environmental Impact Assessment Procedure (2015) ("EIA Procedure 2015").....	2-6
2.4	Environmental Framework.....	2-11
2.4.1.	Water Environment	2-11
2.4.2.	Forestry/Biodiversity	2-13
2.4.3.	Cultural Heritages	2-13
2.4.4.	Health Standards for Project with Health Impacts... ..	2-15
2.5	Legal and Policy Framework on the Land Acquisitions and Resettlement.....	2-17
2.5.1	Relevant Policies, laws and regulations.....	2-17
2.5.2	Overview of Legal System on Land Acquisition and Resettlement of Myanmar.....	2-19
2.5.3.	Institutional Framework on Land Acquisition and Involuntary Resettlement in Myanmar.....	2-19
2.6	International Conventions, Treaties and Agreements.....	2-20
2.7	Legal and Regulatory Framework of Development, Planning and Management for Yangon City.....	2-23
2.7.1	The State Level – The Constitution of Myanmar	2-23
2.7.2	Yangon City Development Committee.....	2-23
2.7.3	City of Yangon Development Law (1990).....	2-24
2.7.4	City of Yangon Municipal Act (1922)	2-26
2.8	Environmental Quality Standards.....	2-26
2.9	Environmental Requirements for the Project.....	2-29
2.9.1	Requirement of the EDCF Safeguard Policy.....	2-29
2.9.2	Requirements for the Project by EIA Notification (2015) of Myanmar.....	2-29

CHAPTER 3: PROJECT DESCRIPTION AND ALTERNATIVE ANALYSIS

3.1	Descriptions of the proposed project.....	3-1
3.1.1	Main components.....	3-1
3.1.1.1	Component 1: Channel Training	3-4
3.1.1.2	Component 2: Flood Embankment.....	3-8
3.1.2	Implementation Schedules.....	3-11
3.2	Project Executing Agency.....	3-12
3.3	Project Alternatives.....	3-13
3.3.1	Analysis of the Alternatives: 'Action' vs. 'No action' Scenarios.....	3-13

3.3.2	Analysis of Technical Alternatives.....	3-15
-------	---	------

CHAPTER 4: DESCRIPTIONS OF THE SURROUNDING ENVIRONMENT

4.1	Setting the Study Limits.....	4-1
4.1.1	Study Boundaries of the EIA.....	4-1
4.2	Methodology and Objectives.....	4-8
4.2.1	Environmental Quality Survey.....	4-8
4.2.2	Biodiversity Survey.....	4-11
4.2.3	Socioeconomic Study.....	4-12
4.3	Public Administration and Planning.....	4-14
4.3.1	Socioeconomic Profile.....	4-16
4.3.2	Local Governments and Spatial Planning System.....	4-16
4.3.3	Socioeconomic Planning System at the National Level (National Long-Term Plan and Short-Term Plan)	4-17
4.3.4	Development Plan for Greater Yangon.....	4-18
4.3.5	Growth Areas and Economic Corridors.....	4-19
4.4	Legally Protected National, Regional or State Areas, Protected areas and Parks.....	4-20
4.4.1	Hlawga Wildlife Park.....	4-21
4.4.2	Urban Greenery Area.....	4-24
4.4.3	Threatened Species.....	4-27
4.5	Physical Components.....	4-27
4.5.1	Climate and Meteorology.....	4-27
4.5.2	Topography.....	4-29
4.5.3	Geology and Seismicity.....	4-30
4.5.4	Soil.....	4-34
4.5.5	Natural Hazards.....	4-36
4.5.6	Hydrologic Conditions.....	4-36
4.5.7	Environmental Quality.....	4-38
4.5.7.1	Air Quality.....	4-38
4.5.7.2	Noise and Vibration.....	4-46
4.5.7.3	Water Quality.....	4-48
4.6	Biological Components.....	4-55
4.6.1	Description of Valued or Sensitive Environmental Areas and Habitats.....	4-72
4.6.2	Species of Economic Value	4-73

4.7	Infrastructure Facilities.....	4-74
4.7.1	Social Infrastructures.....	4-74
4.7.2	Information and Communication Infrastructure	4-81
4.7.3	Waste Management.....	4-81
4.7.4	Transportation.....	4-81
4.7.4.1	Transportation of Twente Township.....	4-83
4.7.4.2	Transportation of Dala Township.....	4-83
4.7.4.3	Transportation of SeikyiKhanaungto Township.....	4-84
4.7.4.4	Transportation of Kyimyindaing Township.....	4-84
4.7.5	Traffic Accident Trends.....	4-85
4.7.5.1	Safety and Stability of Inland Water Transport.....	4-85
4.8	Socio-Economic Components.....	4-87
4.8.1	Location of the Project Area.....	4-87
4.8.2	Socioeconomic Profile.....	4-92
4.8.2.1	Demography.....	4-92
4.8.2.1.1	Population of Myanmar.....	4-92
4.8.2.1.2	Population of Yangon Region.....	4-94
4.8.2.1.3	Population of Twente, Dala, SeikkyiKhanaungto, and Kyimyindaing Township	4-94
4.8.3	Poverty	4-102
4.8.4	Gender	4-103
4.8.4.1	Legal Framework on Gender Issues.....	4-103
4.8.4.2	Current Gender Situation and Inequality.....	4-104
4.8.5.	Ethnicity and Religion.....	4-106
4.8.6	Education.....	4-108
4.8.7	Economic Profile.....	4-112
4.8.8	Industry.....	4-114
4.8.9	Labor Force.....	4-116
4.8.10	Land Use Status.....	4-128
4.8.11	Public Health Condition.....	4-132
4.12	Cultural Components.....	4-138
4.13	Landscape.....	4-140
4.13.1	Kyimyindaing Township.....	4-141
4.13.2	SeikkyiKhanaungto Township.....	4-142

4.13.3	Dala Township.....	4-143
4.13.4	Twente Township.....	4-144

CHAPTER 5 IMPACT AND RISK ASSESSMENT AND MITIGATION MEASURES

5.1	Impact Assessment Methodology.....	5-1
5.1.1	Scope of Assessment.....	5-1
5.1.2	Geographical Scope and Study Area Boundaries.....	5-3
5.1.3	Methodology for Significance Assessment of the Identified Impacts	5-9
5.1.3.1	Event Magnitude Rankings from those Affecting an Area.....	5-9
5.1.3.2	Duration: Events Range Occurring from those Affecting an Area.....	5-9
5.1.3.3	Extent: Degree/permanence of Disturbance.....	5-9
5.1.3.4	Probability: Events Range of Occurrence from those Affecting an Area.....	5-10
5.2	Scope of Environmental Impact Assessment (Pre-construction, Construction, Operation and Disclosure Phases)..	5-11
5.2.1	Identification and Assessment of Physical Environmental Impacts.....	5-11
5.2.2	Impact Assessment on Ambient Air Quality.....	5-12
5.2.2.1	Impact Estimation by Calculation using Emission Factors of Construction Equipment.....	5-13
5.2.2.2	Impact Estimation by Direct Measurement Method.....	5-16
5.2.2.3	Greenhouse Gases.....	5-19
5.2.2.4	Mitigation Measures for Atmospheric Emissions	5-19
5.2.3	Impact Assessment on Noise and Vibration.....	5-20
5.2.3.1	Direct Measurement Method for Noise and Vibration.....	5-21
5.2.3.2	Noise and Vibration Survey Methodology.....	5-21
5.2.3.3	Noise and Vibration Sampling Locations.....	5-22
5.2.3.4	Noise and Vibration Baseline Results.....	5-22
5.2.3.5	Mitigation Measures for Reduction of Noise and Vibration.....	5-23
5.2.4	Impact Assessment on Water Quality.....	5-24
5.2.4.1	Water Survey Methodology.....	5-25
5.2.4.2	Sampling Locations for Surface Water Quality.....	5-27
5.2.4.3	Surface Water Survey Results.....	5-28
5.2.4.4	Mitigation Measures for Water Quality.....	5-31
5.2.5	Impact Assessment on Soil.....	5-31
5.2.5.1	Assessment of Baseline Soil Conditions.....	5-32
5.2.5.2	Mitigation Measures of Impacts on Soil.....	5-34

5.3	Identification and Assessment of Impacts on Biodiversity.....	5-35
5.3.1	Biodiversity Survey Methodology.....	5-35
5.3.2	Forests.....	5-36
5.3.3	Flora Species and their Habitat.....	5-36
5.3.3.1	Description of Valued or Sensitive Ecological Habitats.....	5-38
5.3.3.2	Species of Economic Value.....	5-39
5.3.3.3	Rehabilitation and Restoration of Mangrove Trees.....	5-46
5.3.3.4	Mitigation Measures for Ecological Components.....	5-46
5.4	Impact Assessment on Receiving Environmental Bodies.....	5-46
5.4.1	Hydrology.....	5-4
5.4.2	Geology and Soil.....	5-49
5.4.3	Land Use.....	5-49
5.4.4	Wildlife.....	5-51
5.4.5	Recreation.....	5-51
5.4.5.1	Protected Areas.....	5-51
5.4.5.2	Hlawga Wildlife Park.....	5-51
5.4.5.3	Urban Greenery Areas.....	5-51
5.4.6	Landscape.....	5-53
5.4.7	Cultural Resources.....	5-53
5.4.8	Impact Assessment on Solid Wastes.....	5-57
5.4.8.1	Mitigation Measures for Solid Wastes.....	5-58
5.5	Impact Assessment on Climate Change.....	5-59
5.6	Impact Assessment on Socioeconomic Components	5-59
5.6.1	Impacts on Land and Tangible Properties.....	5-60
5.6.2	Disturbance of Shipyard business operations in SeikgyiKanaungto Section.....	5-64
5.6.3	Loss of Income and Business Opportunities.....	5-67
5.6.4	Safety and Stability of Inland Water Transport.....	5-68
5.6.5	Long-term Income and Livelihood Enhancement and General Improvement of Living Condition (including Traffic, Health and Sanitation Conditions etc.)	5-71
5.6.6	Evaluation of the Impacts.....	5-71
5.6.7	Land Acquisition and Resettlement Action Plan (LARAP)	5-75
5.6.7.1	Major Components of LARAP.....	5-75
5.6.7.2	The Land Compensation and Resettlement Committees.....	5-76
5.7	Vulnerability Assessment	5-79

5.7.1	Identification of Vulnerable Groups among Affected Households.....	5-79
5.7.2	Minority Groups.....	5-80
5.7.3	Gender Consideration.....	5-80
5.7.4	Political and Social Organizations.....	5-81
5.8	Impact Assessment on Natural Disasters.....	5-82
5.8.1	Natural Hazards by Floods.....	5-82
5.8.1.1	Channel Training.....	5-84
5.8.1.2	Flood Embankment.....	5-84
5.8.2	Natural Hazards by Seismicity.....	5-85
5.9	Characterization and Assessment of Overall Impacts and Residual Impacts and Risks.....	5-88
5.9.1	Trans-boundary and Cumulative Impacts.....	5-92
5.9.2	Risk Mitigation Plan.....	5-92

CHAPTER 6: CUMULATIVE IMPACT ASSESSMENT

6.1	Legal/Institutional Background.....	6-1
6.2	Methodology and Approach: Rapid Cumulative Impact Assessment (RCIA)	6-1
6.3	Cumulative Impact Assessment.....	6-2
6.3.1	Identification of VECs and Boundaries.....	6-2
6.3.2	Relevant Existing and Future Private and Public Project Development.....	6-3
6.3.3	Assessment of Cumulative Impacts on VECs.....	6-9
6.3.4	Design of the Management Strategies: Measures to Mitigate the Project's Contribution to the Cumulative Impacts.....	6-12

CHAPTER 7: ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN

7.1	Background.....	7-1
7.2	Relevant Laws and Guidelines of ESMP	7-1
7.2.1	Requirements of Myanmar's EIA Procedure (2015)	7-1
7.2.2	Requirements of the EDCF Safeguard Policy.....	7-1
7.3	Summary of Impacts & Mitigation Measures.....	7-3
7.4	Institutional Arrangement.....	7-4
7.4.1	Overview.....	7-4
7.4.2	Responsibilities of the Project Proponent (DWIR/PMU).....	7-4
7.4.3	Contractor(s)(& Sub-contractors).....	7-6
7.4.4	Environmental and Social Consultant(s) (as applicable)	7-6

7.4.5	On-site Project Implementation Committee (OPIC) - TBC.....	7-7
7.5	Key Legal Requirements of the Project.....	7-7
7.6	Environmental and Social Management and Monitoring Plans (ESMMP).....	7-9
7.6.1	Monitoring, Evaluation and Reporting.....	7-20
7.6.1.1	Overall Budget for Implementation of the ESMP	7-20
7.6.1.2	Monitoring Costs.....	7-20
7.6.2	Management Sub-plans during Construction and Operation Phases.....	7-21
7.6.3	Schedules.....	7-25
7.6.4	Site Inspections	7-26

CHAPTER 8: PUBLIC CONSULTATION AND INFORMATION DISCLOSURE

8.1	Purpose and Objectives	8-1
8.2	Procedural Requirements and Summary of the Activities Taken.....	8-1
8.3	Identification of Stakeholders and Project Affected Groups.....	8-4
8.4	Detailed Activities.....	8-6
8.4.1	Activities during Scoping Stage	8-6
8.4.1.1	Consultations with the Government Organizations at Scoping Phase.....	8-6
8.4.1.2	Project Perception Survey.....	8-8
8.4.1.3	Public Consultation Meeting (PCM) for Scoping Stage.....	8-12
8.4.1.4	Summarized Outcomes of PCMs at the Scoping Stage.....	8-15
8.4.1.5	Information Disclosure at the Scoping Stage.....	8-17
8.4.2	Activities during EIA Stage.....	8-17
8.4.2.1	Consultations with the Government Organizations during the EIA Stage.....	8-17
8.4.2.2	Public Consultation Meeting (PCM) at the EIA Stage.....	8-18
8.4.2.3	Information Disclosure at the EIA Stage.....	8-21
8.5	Focus Group Discussions (FGDs)	8-22
8.6	Results of Public Consultations.....	8-23
8.7	Recommendations.....	8-25

CHAPTER 9: GRIEVANCE REDRESS MECHANISM (GRM)

9.1	Background.....	9-1
9.2	Guidelines for GRM Establishment.....	9-1
9-3	Purpose, Objectives and Key Principles for GRM Establishment.....	9-2
9.3.1	Purpose.....	9-2

9.3.2	Objectives.....	9-2
9.3.3	Key Principles of the GRM Establishment.....	9-2
9.4	Status of GRM establishment for the proposed project	9-2
9.5	Future Recommendations for Effective GRM Operation project	9-3
9.5.1	Installation of the Grievance Boxes.....	9-3
9.5.2	Establishment of the Site Grievance Redress Team (SGRT).....	9-4
9.5.3.	Establishment of the Grievance Redress Committee (GRC)).....	9-4

CHAPTER 10: CONCLUSIONS AND RECOMMENDATIONS

10.1	Conclusions.....	10-1
10.1.1	Overall conclusion.....	10-1
10.1.2	Social Impact Assessment and Mitigation Recommendations.....	10-2
10.2	Commitments.....	10-4
10.3	Further Recommendations.....	10-5

Annex 1. Composition of the Compensation Committee

Annex 2. Kymingtain Township Map

Annex 3. Seikyi Kanaungto Township Map

Annex 4. Dala Township Map

Annex 5. Twante Project Area (Map)

Annex 6. Approval Letter of Scoping Report

Annex 7. Public Consultation Meeting (PCM) Minutes during the Scoping Report

Annex 8. Public Consultation Meeting (PCM) Minutes during the EIA Report

Annex 9. Minutes of Focused Group Discussions

Annex 10. PCM Presentation slides during the EIA stage

Annex 11. List of Participants of PCM during the Scoping Stage

Annex 12. List of Participants of PCM during the EIA Stage

Annex 13. Socio-economic Survey Questionnaire Form

EXECUTIVE SUMMARY

1 Background of the Project

This EIA report is prepared to conduct the Environmental and Social Impact Assessment (ESIA) for the proposed Twante Canal Improvement Project, which is comprised of two phases: The first phase consists of Channel training & Flood embankment and the second phase aims to develop multi-purpose barrages including the detailed design, component, geographical coverage and financing schemes, etc.

This ESIA report covers the Phase 1. The first stage of implementation of the Twante (Twantay) Canal Improvement Project ("the Project" hereafter) will be carried out by the ODA loan of Economic Development Cooperation Fund (EDCF) from the Government of the Republic of Korea. The Project is expected to benefit local community in the region and people using the canal by providing safe navigation, smooth flow of cargos, bank protection, flood protection and development in tourism.

1.1 Objectives of the Project

The project, Twante (Twantay) Canal, the main inland transport waterway which connects the Yangon River to Ayeyarwady Delta, the largest granary of Myanmar, aims to provide safety and efficiency to the waterway transport, by speeding up the flow of goods, and consequently boost economic development by more robust waterway transport and logistics, halt floods and protect the area from collapsing riverbanks. Once completed, the Project is also expected to boost tourism in the region and generate job opportunities in associated industries.

1.2 Project Component

The Project is composed of the following two components:

Component 1- Waterway maintenance- Shore protection – Embankment construction (5.88km) and Bed erosion protection construction (A= 55,500 m²)

Component 2- Flood protection- Embankment construction for flood protection (3 sections, 39.5 km)

1.3 Project Area

The project area, part of the Twante Canal (between 0 mile and 6.5 mile) and part of the yangon river(the right bank of a river) is located in the Yangon South District of Yangon Region. The geographical coverage of the area is part of the Dala Township, SeikkyiKhanaungto Township, Kyimyindaing Township and Twante Township. (See in Figure 1.3-1 below.)




Figure 1.3-1: General Layout Plan of Twante (Twantay) Canal

1.4 Project Period

DWIR under MOTC will be the Executing Agency for the Project and also be responsible for overall project monitoring and progress reporting including schedules, budgets, staff and other requirements to the EDCF. Since the Draft Final Report of the Feasibility Study had been submitted to DWIR in December 2017, the approval process of the Project implementation including social and environmental assessment has been progressed in due course in Myanmar. The Project will be implemented over a period of 6 years since the bidding for the detailed engineering design as shown in Figure 1.4-1.

Activities	Year1				Year2				Year3				Year4				Year5				Year6			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Selection of Consultant & Detailed Design																								
Bidding																								
Land Acquisition & Compensation																								
Contractor Selection																								
Construction & Supervision																								

Figure 1.4-1: Project Implementation Schedule

1.5 Project Proponent and EIA Team

Project Proponent

Proponent Name:	Directorate of Water Resources and Improvement of River Systems(DWIR), Ministry of Transport and Communications(MOTC)		Company Registration Number by DICA (if any):	
Contact name of Proponent:	Director General, DWIR			
Proponent`s address for correspondence:	No-400, Lower Pazundaung Road, Yangon Myanmar			
Telephone(fixed/mobile):	+95-1-292961(office)	Fax: +95-4-290230	E-mail address:	lwinoocapthtun@gmail.com

Team Leader of the Study Team

Name (Surname, Given name)	Registration / License No. by ECD (if applied)	Organization	Contact details	Area of expertise
U Zaw Naing Oo	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel : +95 9 73013448 Mobile : +95 9 976886587 Email: zawnaingoo@enviromyanmar.net	ESIA / ESMMP

Members of the team (Except the team leader)

Name (Surname, Given name)	Registration / License No. by ECD (if applied)	Organization	Contact details	Area of expertise
U Win Naing Tun	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Resettlement Action Plan, Cultural Heritage
Daw Khin Ohnmar Htwe	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Stakeholder Engagement Plan and Public Consultation

Ms. Jerry JH Kim	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448 +95 9976654118(Myanmar)	Socio Economy
U Thura Aung	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Geology and Soil, Waste Management
U Soe Yu Htun	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Meteorology, Modelling for Air Quality
Daw Phyu Phyu Shein	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Socio Economy, Facilitation of Meeting
Daw Nan Thazin Oo	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Socio Economy, Facilitation of Meeting
Daw Naing Naing Win	Certificate for Transitional Consultant Registration No. 0025 (See in Appendix)	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
U Thet Naing Aung	Certificate for Transitional Consultant Registration No. 0025 (See in Appendix)	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
U Myat Ko Ko Hein	Certificate for Transitional Consultant Registration No. 0025 (See in Appendix)	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity

Daw Than Than Htay	Certificate for Transitional Consultant Registration No. 0025 (See in Appendix)	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
Daw Phyoe Khaing Zar Wint	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Water Pollution Control
U Ngwe Moe	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Risk Assessment and Hazard Management
Daw Lai Lai Win	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Environmental Impact Assessment and Reporting
Daw Chit Hsu San	Certificate for Transitional Consultant Registration No. 0117 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Legal Expert

1.6 EDCF Environmental and Social Impact Assessment Team

EDCF Environmental and Social Impact Assessment Team is counterpart consultants hired by the Export-Import Bank of Korea to assist the successful completion of the EIA exercises, particularly in compliance with the EDCF Safeguard Policy. The Team is a consortium of ISAN Corporation (as project manager), YOOSHIN ENGINEERING Corporation (in charge of environmental impact assessment), and GAIA CONSULT Inc. (in charge of social impact assessment and Framework Resettlement Action Plan).

No.	Name	Firm	Field	Remarks
1	Mr. Kang, Yoonmin	ISAN	ESIA	ESIA Team Leader
2	Mr. Yun, Daeil	ISAN	EIA	Director
3	Mr. Nam, Teaho	ISAN	EIA	General Manager
4	Mr. Jeon, Kyungyoel	ISAN	EIA	Director
5	Mr. Joung, Oukyoung	ISAN	EIA	Director
6	Mr. Kim, Seongwoon	ISAN	EIA	General Manager
7	Mr. Lee, Sanghoon	YOOSHIN	EIA	Director

8	Mr. Kim, Hyunmoo	YOOSHIN	EIA	General Manager
9	Mr. Kim, Sungho	YOOSHIN	EIA	General Manager
10	Mr. Lee, Hwajung	YOOSHIN	EIA	General Manager
11	Mr. Kim, Byungsun	YOOSHIN	EIA	General Manager
12	Ms. Lee, Eunyong	GAIA	SIA & Framework RAP	CEO, Social Team Leader
13	Ms. Lee, Juhyun	GAIA	SIA & Framework RAP	General Manager
14	Mr. Im, Uijin	GAIA	SIA & Framework RAP	General Manager
15	Mr. Kim, Jongwook	GAIA	SIA & Framework RAP	General Manager

1.7 Project Implementation Schedule and ESIA Implementation Schedule

Project implementation schedule was established while considering similar projects in Korea and Myanmar, construction quantities, climate conditions (dry and wet seasons) in the Project site. Total 6 years are required for the Project including 3 months for Consultant selection, 9 months for detailed design and tender service, and 60 months for construction and supervision as seen in Table 1.7-1 shows the annual investment plan based on construction quantities.

The ESIA exercise took about 12 months. The activities have started in Jan 2018 and officially completed in December 2018. Assignment of the main tasks across the period are illustrated in Table 1.7-1 right below.

Table 1.7-1: ESIA Implementation Schedule

Step	Main Task	Process Plan (12 month)															
		M 1	M 2	M 3	M 4	M 5	M 6	M 7	M 8	M 9	M 10	M 11	M 12	M 13	M 14	M 15	M 16
1	Establishing evaluation plan through preliminary survey	■	■	■	■												
	Project proposal Submission				■	■	■										
2	Scoping investigation (Stakeholder Analysis)					■	■	■									
	Information disclosure & public consultation (1st)						■										
	Scoping and TOR writing and submission						■	■	■								
	Scoping and TOR confirmation (MONREC)													■			
3	ESIA investigation							■	■	■	■						
	Information disclosure & public consultation (2nd)									■							
	Drafting ESIA report													■	■		
4	ESIA Report Submission, Review and Approval (MONREC)														■	■	■

2 Policy and Regulatory Framework

The Environmental and Social Impact Assessment (ESIA) was prepared for Twante Canal Improvement Project with DWIR, Ministry of Transportation and Communication (MOTC) by a sub-consultant, Resource and Environment Myanmar Co., Ltd technically supervised by the Korean ESIA Consortium Team (led by the Korea Engineering Consultant ISAN), in due compliance with the environmental legal systems in Myanmar, mainly the Environmental Conservation Law(2012), the Environmental Conservation Rules (2014), EIA Procedure and Environmental Quality Standard (Emission) (2015) and EIA Procedure(2015). In addition, the Economic Development Cooperation Fund (EDCF) Safeguard Policy was also observed to ensure the environmental and social sustainability as promoted by the Export-Import Bank of Korea, the executing entity of the EDCF. Additionally, internationally accepted practices based on Asian Development Bank (ADB) and World Bank (WB)'s environmental and social safeguard policies was referred as good practices as appropriate. In particular, in order to adopt the international good practice, Best Available Technology (BAT), socio economic impacts of the proposed project, establishment of the public grievance mechanism (GRM) as well as participation and consultation of the stakeholders (including related government and non-government organizations in Myanmar) were considered in conducting ESIA).

3 Description of the Proposed Project

The Twante (Twantay) Canal Improvement Project is composed of two phases: The first phase consists of Channel training & Flood embankment. The second phase aims to development of multi-purpose barrages. This ESIA paper only covers the first phase. The detailed design, component, geographical coverage and financing schemes for the second phase shall be planned in the future.

Project components at Phase 1 comprise measures to resolve urgent and serious problems such as bed and bank erosion and flood damages. Channel training measures are designed to reduce the flow velocity due to the tidal flow and to stabilize the flow field in the Twante (Twantay) Canal whereas flood embankment measures are to secure not to over the design flood level during the largest spring tide. This project component will ensure less physical, social, and environmental damages due to bed and bank erosion and flood and protect lives, properties, and livelihood of affected persons.

The Project is composed of the following two components:

Component 1- Waterway maintenance- Shore protection – Embankment construction (5.88km) and Bed erosion protection construction (A= 55,500 m²)

Component 2- Flood protection- Embankment construction for flood protection (3 sections, 39.5 km)

The location map of the project components phase 1 is shown in Figure 3-1.




Figure 3-1: Location Map of Proposed Project Components at Phase 1

3.1 Project Alternatives

Alternative analysis is important as it guides the project to identify ways in a timely manner to accomplish the project purpose in the most technically robust, efficient and cost-effective manner. From EIA perspective, alternatives are sought to avoid or minimize environmental impacts. In both cases, only technically and economically feasible alternatives are considered.

Analysis of the Alternatives: 'Action' vs, 'No action' Scenario

Environmental, socio-economic, considerations of both the 'Action (of the proposed project)' Option and 'No Action' Option are made in comparison as below. Addition, two technical options of 'including a Diversion Channel' Option and 'not including' one, are also reviewed far below:

Table 3.1-1: Analysis of the Alternatives: 'Action' vs, 'No action' Scenario

Expected Impacts	'Action' Scenario (of the Proposed Project)	'No action' (Status quo) Scenario	Remarks
Environmental	<ul style="list-style-type: none"> ● Temporarily environmentally negative influences are expected to occur by execution of a project such as: ● dust generation, noise pollution, sediment discharge, and damage to the ecosystem of the waterside are expected to occur. 	<ul style="list-style-type: none"> ● Short-term environmental changes don't occur if the project isn't conducted. ● Currently, erosion, sedimentation, and scour are constantly occurring, which can cause serious safety problems if we don't conduct project. 	<p>These are temporary effects and expected to be stabilized at the operational stage once the construction is completed.</p> <p>During the construction period, the effective environmental impact management plan (EMP) need to be set in place to minimize the environmental impacts.</p>
Social	<ul style="list-style-type: none"> ● Permanent or temporary disturbance of livelihood and loss of land and other types of properties for the residents that are subject to land acquisition for the construction and other project activities. ● Possible economic loss of the shipyard, fishery and other canal and river-based operations, either temporarily or permanently due to the construction and other project activities ● Active flood prevention measures of the project shall lead to saved lives and less damages to the livelihood of the communities located adjacent/nearby the Twante Canal, after the construction completion 	<ul style="list-style-type: none"> ● No disturbance of livelihood of the community nearby the project area during construction (e.g temporary/permanent loss of land, inconvenience of movements, longer commuting time etc.) ● The historic trends indicate that the bank erosion, sedimentation and scouring of the bottom of the canal is getting speedier: With no timely prevention, the social costs of the lost lives due to safety accidents in inland water transportation and consequent welfare loss would disproportionately aggravate. ● Fishing activities and inland water transport (freight, regular passenger boat as well as tourist boats etc) would not be disturbed but maintain the current level of traffic volume in short term. However, due to the worsening sedimentation and aggravating bed scouring problem, the traffic volume will decrease and fishing activities may also be affected in a 	<p>The overall social welfare of the adjacent communities in "No Action" Scenario is expected to be less than the "Action" scenario in mid- and long-term.</p> <p>Expected negative social impacts to the affected communities during construction could be minimized or offset through effective impact management and compensation measures.</p>

	<ul style="list-style-type: none"> ● Bed scouring prevention measures of the project will also reduce the traffic accident along the canal while increasing the stability and safety of the inland water transport, after the construction completion ● Fishing activities and inland water transport (freight, regular passenger boat as well as tourist boats etc) may be disturbed to a certain degree during the construction but the effects are expected to be marginal in scale and only temporary. 	longer term.	
Economic	<ul style="list-style-type: none"> ● Immediate and direct economic loss may occur due to the land and property losses and damages due to construction to directly affected persons and households. ● Other types of interruptions of business of temporary nature, due to the agricultural land loss and (temporary or permanent) halt of the shipyard operations along the canal would occur. ● Prevented yearly land loss due to bank erosion along the Twante Canal leading to economic gain (estimated to be 1,115 sqm per annum in annum in Twante Township, Seikkyi Khanaungto Township, Kyimyingdaing Township and Dala Township, worthy of US\$ 0.225 	<ul style="list-style-type: none"> ● No disturbance of livelihood of the community nearby the project area during construction (e.g temporary/permanent loss of land, loss of jobs (e.g. temporary fishery halting or relocation of the fishing and other Twante canal-related economic activities etc.) ● In the longer term, however, worsening sedimentation, bed scouring, deteriorating bank conditions leading to higher risk of safety inland transport accidents, flooding damages, loss of land and other types of losses, will result in ever increasing economic losses. 	<p>Mid- and long-term economic benefits is estimated to outnumber the short-term costs the project host community would pay in a short and temporary term during construction.</p> <p>Expected negative economic impacts to the affected communities during construction could be minimized or offset through effective impact management and compensation measures.</p>

	<p>million yearly after the construction completion)</p> <ul style="list-style-type: none"> ● Increased efficiency gains of the inland water transport users and industry due to safer and faster movement ● With the New Town Development Plan in Twante and Seikkyi Kanaungto Township, as part of 2040 Greater Yangon Strategic Urban Development Plan (SUDP), the economic return from the prevented land loss through prevention of the bank erosion and flooding is expected to be even higher in the region over time. 		
--	---	--	--


4 Description of the Environment

4.1 Setting the Area of Influence (AoI)

The Ayeyarwady Delta is located in the southern part of the middle plains of Myanmar. It consists of three regions: Yangon, Ayeyarwady, and part of the Bago region. The Ayeyarwady Division is where the Ayeyarwady (local name Irrawaddy) River splits into many streams and drains into the Andaman Sea. On the southern and western sides of the Ayeyarwady Division is the Andaman Sea and Bay of Bengal. The Gulf of Martaban also lies to the east of the division. The Project site is located in the Twante (Twantay) Township, Dala Township, Kyimyingdaing Township and Seikkyi Khanaungto Township of Yangon South District, Yangon Region.

4.2 Topographic Condition

According to the Digital Elevation Model (DEM) shown in Figure 4.2-1, topographical condition around the Twante (Twantay) Canal is characterized by typical feature of delta plain. The aerial distribution of ground levels is range from El. 0 m to El. 5 m which cover 626km² and occupy 87% of total area.



Source: 1:50,000 DEM of Survey Department.

Figure 4.2-1: Distribution Map of Ground Level for Southern Part

4.3 Land Use

The land use of the project area is mainly urban, farmland and canal. In June 2018, YRG has announced the 2040 Greater Yangon Strategic Urban Development Plan (SUDP). SUDP designates


Twante Township and Seikkyi Khanaungto Township and Dala Township as Phase 1 development focus area (largely due to the geographical proximity to the CBD in downtown Yangon).

4.4 Soil

There are four main types of soil are found in the entire project area and southern part of Yangon Region. They are:

- Meadow & Meadow Alluvial soil
- Lateritic Soil
- Saline Swampy & Meadow Gluey Soil
- Dune Forest and Beach Sand

Only Meadow Alluvial soils occupy the entire project area as shown in Figure 4.3-1.



Source: Data from the Land Use Division, Myanmar 2006

Figure 4.3-1: Soil Map of Yangon Region

4.5 Climate and Meteorology

Yangon has a tropical monsoon climate and it is characterized by strong monsoon influences, has a considerable amount of sunlight, a high rate of rainfall, and high humidity. There are three well-

defined seasons: Summer, 'rainy season' and 'cool (and dry) season'. Summer months are from March to Mid-May; heavy rain falls from Mid-May to the end of October (the 'rainy season') and the cool season starts in November up to the end of February. The Yangon Region features a lengthy rainy season from May through October where a substantial amount of rainfall (2837mm) is received; and a dry season from November through April, where little rainfall is seen (120mm).

4.6 Environmental Parameters

4.6.1 Air Quality

The principal sources of emissions to the atmosphere in the immediate vicinity of the Project area are likely to be from agricultural open-air burning, wood burning for domestic purposes (i.e. heating and cooking), industrial fumes and exhaust emissions from road transportation.

There is no available air quality baseline data of the entire project area so far. Therefore, the primary data on key ambient air quality parameters will be collected at four selected locations during environmental baseline data collection period to understand baseline conditions.

4.6.2 Noise and Vibration

The sources of noise pollution are likely to include the port yard, near the Seikkyi Khanaungto stream to the north of the Project site, noise from small boat and ship in the canal and road traffic from the nearby main road. The village households located within close proximity of the Project site have been identified so that can affect the noise pollution.

4.6.3 Water Quality

During the scoping phase, there is no available water quality data and the primary data on water quality will be collected one time at six representative water sensitive receivers to characterize baseline water quality around the project site.




Figure 4.6-1: Locations of Environmental Quality Monitoring Stations

4.6.4 Result Findings

Air Quality: For air quality parameters, CO, NO₂, NO, PM_{2.5}, PM₁₀, SO₂, Temperature and Relative humidity were measured at the four monitoring points as the baseline survey in 2018.

According to the surveying results on ambient air quality, all parameters hit the targets under emission guideline values (National Environmental Quality (Emission) Guideline, 2015) except SO₂, which was incredibly exceed than the target guideline value at three sampling locations. With reference to the experiences of REM field surveyors, vehicle emissions would be one of the main possible reasons for such highly emission of SO₂ at these locations.

Noise and Vibration: According to the survey results, day-time and night-time noise levels are above the residential standards and the result is quite reasonable because the sampling locations are along the existing canal as the high commercial area with the high traffic issue at all stations so that the proposed project area should be compared with the industrial and commercial area standard (70 dB). However, the vibration level is still under the standard of “road side level of residential area” (Japan).

Water Quality: Although there was no surface water standard in National Emission guidelines for comparative assessments, the baseline survey was conducted to compare and check any change in water quality parameters during and after the accomplishment of the project activities.

4.7 Biological Environment

The detailed biodiversity survey was undertaken during environmental baseline data collection period.

4.7.1 Spatial Distribution of Mangrove Species

Mangrove can be found in low altitude coastal and sub-coastal areas along river valleys and across watersheds. A mangrove is a tree, shrub, palm or ground fern, generally exceeding one half meter in height that normally grows above mean sea level in the intertidal zone of marine coastal environments and estuarine margins. A mangrove is also the tidal habitat comprising such trees and shrubs.

4.7.2 Flora

During the field survey period of Twante canal project, five economically important plant species among 76 were collected. Among them, two merchantable hardwood species such as Pyin-ka-doe and Padauk are included in Hardwood Group 1 which is extracted from Myanmar Timber Enterprise (MTE) and the rest of species such as Dani, Wanet and Nget-pyaw in local market.

4.7.3 Fauna

During the field survey period of Twante canal project, 5 groups of fauna: mammals (5 species), birds (55 species), insects (27 species including 22 butterflies and 5 dragonflies), Herpet (10 species) and Fish (23 species) were identified. Out of these, six economically important aquatic species such as Hilsa, Seabass, Pangas Catfish, Croaker, Indian salmon and Monsoon River Prawn were collected, and the rest species of fauna were not collected as economically important species.

4.7.4 Rehabilitation and Restoration of Mangrove Trees

The mitigation measures for restoration of mangrove trees shall be carefully taken and cash compensation will be taken when there will be unavoidable of clearance for construction activities.

The possible tree compensation plan should be developed such as seeding the same species in nursery for re-plantation by consulting with the project proponent, DWIR, Ministry of Natural Resources and

Environmental Conservation (MONREC) and the consultant adequately in terms of visual contrast and aesthetics of the receiving area at the available and suitable place in the region.

4.8 Demography of the Four Affected Townships

4.8.1 Twante Township Boundary and Population

Twante Township (also known as Twantay Township) is a township in the Yangon Region of Burma (Myanmar). It is located west across the Hlaing River from the city of Yangon. The principal town and administrative seat is Twante. The longest man-made canal in Myanmar is Twante canal and it is also a shortcut waterway to Ayawaddy river to Yangon river which divides Twante Township with its length of 35 km and there is one bridge that spans the canal is called Twante bridge. The 220 villages of Twante Township are organized into 65 village tracts and 8 urban wards with 227,953 residents in total with 52,307 households (as of March 2017), mostly of Barman ethnicity (about 76%) and Kayin (about 23%). Majority are Buddhists and Christians, Muslims and Hindu believes also resides in smaller groups. Twante Township is well known for its pottery activities handled by a few families over several generations. It is also an area of fish farming in Yangon region. Agriculture and Fishery top the source of the population's livelihoods, followed by canal related economic activities. About 13,000 persons are reported to be in canal-related industry.

4.8.2 Dala Township Boundary and Population

Dala Township is located at the South of Yangon. Between North Latitudes 16° 20" and 16° 32" and between East longitude 96° 16" and 96° 18" and the area coverage is about 86.51 square mile and on the southern bank of Yangon River across from downtown of Yangon. The township made up of 23 wards and 23 village track (including 50 villages), is bounded by the Yangon river in the north and east, the Twante Canal in the west, and Twante Township in the south. There are 7 miles from east to west and 10 miles from south to north. There are Yangon River in the eastern, Kawmhu Township in the South. In the western, there is Twante Township and Yangon River in the North. Total population is 154,563 with 35,223 households (as of March 2018). More than 95 % of the people who live in these townships are Barman, followed by Kayin, and Rakhine people. Composition of religions is similar to that of Twante. Dala Township is less developed than Twante Township and its economic infrastructures are yet to be developed. Tertiary sector industry such as services and sales are dominant. Those in canal related industry counts as high as 20,522, proportionally higher than that of Twante Township: The livelihood of Dala residents are more dependent on the canal-related industry than Twante Township.

4.8.3 Seikkyi Khanaungto Township Boundary and Population

Seikkyi Kanaungto Township is an isolated artificial island and is located on the southwestern bank of Yangon River across from downtown Yangon. The township comprises eight wards, and is bounded by the Yangon River in the north, the Twante Canal in the east, and Twante Township in the south and west. The township is still largely rural and undeveloped mainly because it still lacks a bridge across the Yangon River to downtown. It is located between North latitude 16° 45" and 16° 48", from east to west is mile and south to north is 2.3 mile. In eastern, there are Yangon River and Dala Township, Twante Township in east, Kawmu Township in West, Twante Township and Dala Township in South and in north bordering with Yangon River and Kyimyinedine Township. This relatively smaller township has a total of 33,944 residents (as of March 2017) with 7,778 households. Majority are of Barman ethnicity (about 95%). The rest are Mons, Kayins, Rakhines and Chins. The majority earn a living from sales and canal related business (such as shipyard operations etc.) and

unemployment rates (above 4%) are relatively higher here than in Dala and Twante Township (with 2% level each). However, the average income level is significantly higher than in Twante and Dala.

4.8.4 Kyimyindaing Township Boundary and Population

Kyimyindaing Township is located on the western part of Yangon. Kyimyindaing Township is located between 16° 46' 51" N, 16° 49' 45" N and 96° 6' 75" E, 96° 7' 48" E. There are 2 miles from east to north and 2.08 miles from south to north. The total square mile of township is 4.808.

There are Sanchaung Township in eastern and being border with Alone Township and Seikkyi Khaunaungto Township in southern. In northern, there are border with Kamaryut Township and Hlaingtaryar Township.

Kyimyindaing Township is situated above sea level of 35 feet. Kyimyindaing Township is fewer in river and creeks. Most of the creek are flowing from north to south. The famous river in township is Hlaing River (Yangon River) and flow through the center of the township from north to south. In the east, there is Pun Hlaing river and flowing from west to east through Yangon River. In summer, Yangon River in water become saltwater and not available to drink and also cannot use for Agricultural. Pun Hlaing River is only about 3 feet in depth of water and cannot pass boats.

5 EIA Approach & Methodology

5.1 Impact Assessment

The impact assessment process comprises a systematic approach for the evaluation of the main project components and their associated activities throughout the project lifecycle. The assessment process mainly comprises followings (Ref: General Environmental Impact Assessment Guideline, 2017):¹

- Screening and Scoping;
- Baseline Information;
- Project Alternatives and Design;
- Key Issues and Selection of Valued Ecosystem Component Impact Assessment;
- Impacts Identification and Evaluation;
- Residual Impact Identification;
- Mitigation and Monitoring.

The overall impact significance assessments are listed in Table 5-1. Some of significant and moderate negative impacts are expected during preparation and construction phase and some significant benefits are expected to occur during the operation period.

¹General Environmental Impact Assessment Guideline, The Republic of The Union of Myanmar Ministry of Natural Resources and Environmental Conservation, September 2017.

Table 5-1: Overall Significance Assessment for Environmental and Social Impacts during Construction and Operation Phases

(M: Magnitude/ D: Duration/ E: Extent/ P: Probability)

Impact Parameter	Descriptions	M	D	E	P	(Pre-) & Construction Phase	Mitigation Measures	
						Impact Evaluation	Necessary	Not Necessary
Air Emission	The construction activities could generate dust and SO ₂ in high condition according to baseline generation. Affected people nearby the construction site are likely to suffer.	4	2	1	3	21 (-)	√	
Greenhouse gases	Any correlation of greenhouse gas emission cannot be reflected.	1	2	1	1	4		√
Noise and Vibration	The related impact of noise and vibration for those who lived nearby the construction site during operation period of the noisy machinery is human health, loss of hearing, stress and insomnia.	4	2	1	4	28 (-)	√	
Water Quality	Potential to increase run-off and erosion, predominantly during construction, increasing turbidity and impacting water quality.	4	2	1	3	21 (-)	√	
Solid Wastes	Generation of waste and hazardous waste from construction activities could lead to water and soil contamination if not managed properly.	3	2	1	3	18 (-)	√	
Biodiversity (Forest, Flora, Fauna)	Ecosystem: Protected or Conservation area Flora: Mangrove natural conservation forest was identified in the project site or the Area of Influence (AoI).	4	2	2	4	32 (-)	√	
Climate Change	There is no correlation action of the project activity with climate change impact.	1	2	1	1	4		√

Soil	Soil run-off is expected by removal of vegetation cover for 30 m ROW.	2	2	1	3	15 (-)		√
Geology and Soil	No activity is related with changes in existing geology and soil condition.	1	2	1	1	4		√
Land use	Land use changes is expected within 30 m ROW along with Twante canal of the project area due to flood embankment and economic activities around the Project area.	3	2	1	3	18 (-)	√	
Hydrology	No hydrology condition is expected.	1	2	1	1	4		√
Wildlife	No wildlife is expected to find nearby community area.	1	2	1	1	4		√
Protected Area	No protected area is related with the project activity.	1	2	1	1	4		√
Recreation Area	There was no recreation centre within the proposed project area.	1	2	1	1	4		√
Visual Resource	Removal of mangroves will be slightly changed in visual for those who lived in the 30 m ROW.	3	2	1	3	18 (-)	√	
Cultural Resource	No cultural resource will be built within 30 m ROW area.	1	2	1	1	4		√
Socioeconomic Components	Involuntary resettlement: A level of land acquisition and involuntary resettlements of residents along the canal area (esp. ROW) that are subject to construction will take place. (Estimated: 120 ha) with 2,697 PAFs & 2,028 structures to be affected)	5	4	2	5	55 (-)	√	
	Income and Livelihood Loss (1): Shipyard community About 40 shipyard operators and workers (about 10 employees per shipyard) with their families in Kanaungto Township may be affected in their income and livelihood in case of permanent (or temporary) halt of the	1	1	1	3	(-)	√	

	shipyard operations. (in case of the adjustment of the current 30 m ROW boundary tentatively set by the project proponent (DWIR))							
	Income and Livelihood Loss (2): Fishers & Irrigated Farmers Fishers and other residents whose livelihoods are dependent upon the canal (i.g. farmers whose plots are being irrigated by the canal and Yangon river) may be also temporarily affected in their livelihood due to the temporary blockage and inaccessibility of the canal area subject to construction work.	3	2	2	4	28 (-)	√	
Natural Disasters	Any project activity cannot be triggers for the natural disaster impacts. Even annual inundation impact by natural floods will be minimized after project construction. Positive impacts can be expected.	1	2	1	1	4		√
Occupational Health	Construction dust and noise will affect the workers' health.	3	2	4	3	27 (-)	√	
Community and Public Health	The nearby communities with the construction site is temporarily encountered with the dust and noise emissions, social stress with the foreigners and workers from non-regional area.	3	2	1	3	18 (-)	√	
Impact Parameter	Descriptions	M	D	E	P	Operation Phase	Mitigation Measures	
							Necessar y	Not Necessar y
Natural Disaster	Annual inundation by floods during the abnormal conditions within the regions such as extreme weather	4	4	3	5	55 (+)		√

	conditions will be reduced or minimized and even benefited by the project as the project itself represent the channel training, bank embankment and flood protection.						
Socioeconomic Components	<p>The regional communities will receive more opportunities for employment, food supplies, and fuel stations, facilitation of inland water transportation, distribution of the goods (in/out) of the region.</p> <p>Canal improvement project can also positively effect on the development of regional inland water transportation system to navigate safely within the region which in turn seeking the improvement of livelihood for the employment opportunity and motivate regional economic development process.</p>	4	4	4	4	48 (+)	√
Natural Disasters	Positive impacts can be expected from waterway maintenance activity and flood protection.	4	4	3	5	55 (+)	√
Soil	Soil run-off will be no further encountered within 30 m ROW due to bank protection activity of the project.	3	4	1	4	32 (+)	√
Community and Public Health	The regional residents will get received the medical care through CSR program of the project.	3	4	3	3	30 (+)	√

(+)= Positive Impact

(-)= Negative Impact

No Remark (+ nor -) = Neutral

<15 = No Impact

Overall event magnitude is scored from low (15) to very high (>60) by adding the individual parameter scores:



5.2 Mitigation Measures

Mitigation Measures of the construction phase for environmental and social impacts will be managed under an Environmental and Social Management Plan (ESMP). The main measures that can be considered are outlined in Table 5-2.

Table 5-2: Preliminary Mitigation Measures – Pre-Construction and Construction Stage

Stage	Activities	Mitigation Measures
Before Construction	Private and public land acquisition for ROW	[Location and design selection & Alignment of ROW] Propose bank alignment which can minimize social and environmental impacts at detailed design phase considering existing canal alignment, residential areas and roads
		[Land Acquisition and Resettlement Action Plan (LARAP)] Assess the scale of the land acquisition, physical and economic dislocation of the host communities and population & establish Resettlement Action Plan (RAP) in accordance with the Myanmar law and regulations as well as the EDCF Safeguard Policy and implement in a timely manner
During Construction	Air Pollution and Noise	<ul style="list-style-type: none"> - Do not use expired construction equipment for lifetime. - Manage the periodic maintenance of construction machinery and equipment. - Regularly inspect and supervise the usage and maintenance of vehicles for construction and transportation. - Load construction materials or wastes according to the capacity of equipment, always cover the cargo box of vehicles to avoid dropping of soils, rocks, sand, or gravel during transportation. - Avoid construction works from 10:00 PM to 5:00 AM in the villages or dense populated areas. - Minimize use of car horn nearby residence area. - Sprinkle water frequently in and around the construction site when the weather is hot, dry, and windy. - Maintain the cleanliness of access roads within 200m radius from the place where lots of soil and rock are located.
	Water Environment	<ul style="list-style-type: none"> - Prohibit to bury wastes under the ground or throw away them into rivers. Treat the waste oil and liquid wastes according to related regulation. - Prohibit to clean construction vehicles or equipment near cultivated areas to prevent from the pollution of lands and rivers by inflow of mud or waste oil. Minimize use of cleaning water to minimize water contamination. - Store chemical materials, equipment, and construction materials on highland areas to prevent environmental contamination during the flood. - Cover or isolate the stored materials, and install side ditches around the open-storage to prevent materials to be washed away. - Employ firms to manage basic sanitary facilities, temporary toilet, etc.

		for the temporary construction camp.
	Solid Wastes	<ul style="list-style-type: none"> - Transport and treat solid waste immediately and appropriately not to be thrown out nearby areas and villages. - Store surplus soil and rocks at designated places. Prepare the waste landfill employ technical designs for clearing existing vegetation, compaction, and restoration of land scape. - Install the barrier layer to prevent contamination for water, soil, crops, etc. - Do not allow overload and insufficient capacity of vehicle for transportation. Cover the cargo box of vehicles to avoid dropping of soils, rocks, sand, or gravel during transportation. - Management of Temporary Construction Camp - Provide basic sanitation facilities - Prepare waste disposal facilities to collect wastes every day hiring waste treatment firms.
	Local Community	<ul style="list-style-type: none"> - Construction workers should be instructed to minimize conflicts with local residents. - The consultant should instruct construction workers in measures for public health and safety to minimize impacts on health and danger factors - Effective grievance redress mechanism (GRM) should be established to minimize any construction-related safety and other concerns are addressed in a timely manner. - Ensure the required environment, health and safety standards of the construction sites and associated facilities and activities of the workers
	Safety	<ul style="list-style-type: none"> - Install the fences around the construction site with warning signs to restrict unauthorized people's approach. - Minimize the environmental impacts and assign responsible staffs for monthly report. - Post the campaign slogan for working safety. - Install a sign to slow down the vehicle speed inside the construction site. Assign a responsible staff for guiding drivers to load and unload construction materials. - Provide adequate lightings at night. - Prohibit overload from vehicle's capacity, especially check the cargos not to be fallen out on roads. - Provide a personal protective equipment such as safety boots and gloves, and emergency medicine. - Knowledge about hygiene and occupational safety for workers should be instructed. - Strictly instruct the fire safety. - Store high fire-risk materials such as gasoline away from possible

		<p>sources of ignition such as stove, welding, etc.</p> <ul style="list-style-type: none"> - Install fire cautious signs. - Store fuel in reliable containers and check to ensure leakage. - Provide reliable oil and fuel with equipping an anti-leakage facility around fueling equipment. - Install a roof on the waste oil storage. - Mark the construction work schedule, project name, client's name and its contact number, and targeted object on the sign board. - Avoid rush hour for the transportation, load and unload of construction materials. - If construction works obstruct public traffic, temporary roads for pedestrians and alternative transportation should be provided. - Store construction materials in the space where the traffic is not disturbed. - Remove temporary construction materials promptly with 24 hours not to disturb the traffic. - Repair the damaged roads by transportation.
	Ecosystem	<ul style="list-style-type: none"> - Carry out watering treatment when perform borrow pit clearing, site ground leveling and flood embankment. - Establish Mangrove habitat protection measures the project area
During Operation		<ul style="list-style-type: none"> - Positive effects are expected after completion of the construction, and negative impacts for long-term period are not expected. However, increase wastes and wastewater by population growth, over speeding vehicles are expected. Therefore, local government should establish constant and long-term management measures.

6 Public Consultation and Disclosure

The objective of this task is to conduct project disclosure and public consultation in order to obtain the suggestions/ concerns for developing the appropriate ESIA Study and Environmental Management Plan.

The project disclosure will be conducted in compliance with EIA Procedure 2015. DWIR disclosed the planned project via DWIR website and at DWIR Yangon Office (<http://www.dwir.gov.mm>). The ESIA team proposed the effective disclosure methods to meet the requirements in EIA Procedure. There are a series of consultation and discussion meetings along with the EIA survey including the focus group discussions (see details in Chapter 8). Four PCMs were organized on 26th to 29th January 2019 at the Administrative Offices of Twante, Dala, SeikkyiKhanaungto and Kyimyindaing Townships.

Table 6-1: Public Consultation Meeting for EIA at the Scoping Stage

Time and Date	<p>1) Thursday, 20 September 2018</p> <p>1st session (for Twante Township): 1:00 PM to 3:00 PM</p> <p>2) Friday, 21 September 2018</p> <p>2nd session (for Dala Township): 9:00 AM to 11:00 AM, 3rd session (Seikkyi Kanaung Township): 1:00 PM to 3:00 PM</p> <p>3) Thursday, 15 November 2018</p> <p>(for Kyimyindaing Township): 3:00 PM to 4:00 PM</p>
Venue	<p>Administrative Office of Twante Township,</p> <p>Administrative Office of Dala Township,</p> <p>Administrative Office of Seikkyi Kanaung Township,</p> <p>Administrative Office of Kyimyindaing Township,</p>
Invitees	<p>-Director, Environmental Conservation Department in Yangon Division, MONREC</p> <p>-General Administration Department, Yangon Southern District Officers, General - Administration Department in Twante, Dala and Seikkyi - Kanaungto Townships</p> <p>-Officers, Myanmar Port Authority, Ministry of Transportation and Communication</p> <p>-Local residents in and around the respective three township</p> <p>-Project proponent (DWIR) and related government organizations (Department of Planning, Department of Marine administration, Myanmar Shipyards)</p> <p>-Other organizations and individuals who are interested in the Project</p> <p>(Such as Ayeiksit, Saytanar Emergency Association, Anargatalinyaung Philanthropic Association)</p>
Attendee	<p>Twante: 85 people (men:75, women:10)</p> <p>Dala: 72 people (men:60, women:15)</p> <p>Seikkyi Kanaungto: 63 people (men: 53, women: 10)</p> <p>Kyimyindine :9 people (men:9, women: 0)</p> <p>Kyimyindine :15 people (men:13, women: 2)</p>
Agenda	<p>Introducing about the meeting by Township Administrator</p> <p>Explaining about the project by Project Proponent (DWIR)</p> <p>Explain about the EIA project</p> <p>Major positive and negative environmental and social impacts on the draft scoping results</p> <p>Scope of the EIA study</p> <p>Further schedule of EIA Implementation</p> <p>Q&A</p>
Language Used	In local language: Myanmar language

Source: EIA Study Team

Table 6-2: Focus Group Discussions

Meeting Dates	Place
30th October 2018	Thar Gyi Ward, Dala Township with local people
31st October 201	Pyawbwe Lay Village, Twante Village with local people
1st November 2018	Seikkyi (West) Ward, Seikkyi Kanaungto Township with local people
24th December 2018	Taung Thu Gyi Restaurant, Seikkyi Khanaungto Township with Shipyard Association
24th December 2018	Hpayar Gyi Village, Twente Township with Farmers

**Table 6-3: Public Consultation Meeting for EIA at the Final (EIA Inseption) Stage**

Meeting Dates	Stakeholders	Number of Participants
26 th January 2019	Seikkyi-Khanaungto Township	
	1. Government officials	32
	2. Parliamentarian	1
	3. Project Proponent's representatives (DWIR)	6
	3. EIA Consultant (TEAM)	5
	4. NGOs	14
	5. Local people	64
	6. Shipyard association	17
	Total	139
28 th January 2019	Twente Township	
9:00 am to 11:00 am	1. Government officials	17

	2.Project Proponent's representatives (DWIR)	1
	3. Parliamentarian	2
	3.EIA Consultant (TEAM)	9
	4. NGOs	2
	5. Local People	147
	Total	178
28 th January 2019 2:00 pm to 4:00 pm	Dala Township	
	1.Government officials	17
	2.Project Proponent's representatives (DWIR)	2
	3. Parliamentarian	5
	3.EIA Consultant (TEAM)	9
	4. NGOs	3
	5. Local People	83
	Total	119
29 th January 2019 9:00 am to 11:00 am	Kyimyindaing Township	
	1.Government officials	16
	2.Project Proponent's representatives (DWIR)	1
	3. Parliamentarian	1
	3.EIA Consultant (TEAM)	8
	4. NGOs	4
	5. Local People	12
	Total	42
Agenda	<p>Introducing about the meeting by Township Administrator</p> <p>Explaining about the project by Project Proponent (DWIR)</p> <p>Explain about the EIA project by Local Consultants</p> <p>Major positive and negative environmental and social impacts on the EIA results and findings</p> <p>Propose alternative finding</p> <p>Details of EIA Implementation</p> <p>Q&A</p>	
Language Used	In local language: Myanmar language	

7 Conclusions

Based on the scoping and final EIA results and findings, Terms of Reference (ToR) and Draft EIA report have been prepared for the ESIA Report. They have been undertaken in a professional manner, in accordance with EIA Procedure as well as other Myanmar Legislation and applicable standards/requirements along with any applicable guidelines. In addition, the ESIA has been carried out in accordance with the Safeguard Policy of the Economic Development Corporation Fund (EDCF) of the Export-Import Bank of Korea, a potential financier of the proposed project.

The following commitments shall be implemented by the Project as shown in Table 10-1.

Table 7-1: Project Key Commitments

Sections of ESIA Report	Key Commitments
Chapter 1. Context of the Project	The EIA report shall be prepared in accordance with the EIA procedure of Myanmar(2015) with the project proponent (DWIR)and highly experienced third-party consultants as per mentioned.
Chapter 2. Overview of Policy, Legal and Institutional Framework	<p>The project owner shall earnestly carry out all national and local laws, regulations and requirements on environmental protection, clearly define main duties and responsibilities of environmental protection departments of the project, establish and optimize its rules and regulations.</p> <p>The project shall conform on the followings:</p> <ul style="list-style-type: none"> - relevant standardizations for ambient air quality (NEQG) - relevant standardizations for wastewater discharges (General application of NEQG) - relevant standardizations for Construction noise and vibration (Industrial noise standard of NEQG) - relevant guidelines for solid wastes by the concerned departments (YCDC, Yangon City) - will separate the domestic wastes, construction wastes such as asbestos and hazardous wastes when disposed. - will follow strictly the local and international relevant laws, guidelines, and procedure while implementing environmental and social management plans as mentioned in the EIA report. - shall monitor the EMP and SEP in accordance with the EMoP as designated in the EIA report. <p>In addition, the project shall observe the key relevant principles of the EDCF Safeguard Policy and other international good practices (of ADB and World Bank) as appropriate.</p>
Chapter 3. Project Descriptions and Alternative Analysis	The project commits to utilize and maintain the facilities' designs and modernized equipment and machinery as described in Project description for construction period.
Chapter 4. Description of Surrounding Environment	The project commits not to disturb the Existing Environmental and socioeconomic Conditions and will keep forwards maintaining the natural conditions and developing the regional livelihood and living standards as far as possible.
Chapter 5. Impact and Risk Assessment and Mitigation Measures	<p>The project commits to precisely follow the discussed mitigation measures for avoiding or reducing such environmental and socioeconomic impacts generated in temporarily or permanently by the Project activities during both the construction and operation phases.</p> <p>Arrangement of personal protective equipment such as gloves, helmet, mask, glasses and other tools, safety boots and uniforms for each worker so that the workers can keep themselves safe from any kinds of accident and the occupational health training will also be provided.</p>

		The labor recruitment policy must be formulated in such a way that local laborers can be prioritized (esp. directly affected persons and families) for employment in the project.
		Construction risk management plan shall be prepared and implemented.
Chapter 6. Cumulative Impact Assessment	6.	The project will also consider the cumulative impacts by the project activities and keep maintaining to minimize the potential negative impacts and maximizing the benefits positively.
Chapter 7. Environmental and Social Management Plan	7.	The project commits to follow up the main tasks for Environmental and Social Consideration of the project implementation team and project management team in accordance with the main parts of CEMP & OEMP and the relevant sub-plans.
		The project will ensure to hire the contractor and subcontractor with highly qualified and licensed organizations and/or personnel with the adequately satisfied environmental management certification bodies for the construction activities.
		The project contractor/subcontractor will ensure to purchase the construction machinery and equipments, and the natural resources from adequate licensed suppliers accordingly.
		The compliance monitoring report along with the checklist will be indexed and annexed with the monthly and annual monitoring report. It may be required to submit the annual monitoring report to Department of Environmental Conservation for renewing of the Environmental Clearance Certificate each year.
		The project will develop and implement a monitoring and reporting plan as presented in the said section.
Chapter 8. Public Consultation and Information Disclosure		The project commits to engage the affected community and any project stakeholder in adequate manner and meaningfully consult them for any environmental and/or social issue related with the project activities.
		Land acquisition and resettlement action plan (LARAP or RAP) will be consulted and informed to the concerned stakeholders with active manner and will also link to the regional social development schemes.
Chapter 9. Grievance Redress Mechanism.	9.	The project management units and focal person will also proactive address any project-related grievances raised in accordance with the established grievance redress process and procedure in a timely manner.
Chapter 10. Conclusions and Recommendations	10.	The project will follow strictly the commitments and further suggestions as illustrated in Table 10.2-1 and section 10.3.

To sum up, the construction and operation of the proposed Twente Canal Development project is feasible from the perspective of environmental protection and social losses with the fully implementation of respective social and resettlement action plan by the highly spirits of the project proponents, DWIR. Upon completion of the project construction, the project is expected to generate the positive benefits that can extirpate the negative impacts during the construction period.

အစီရင်ခံစာ အကျဉ်းချုပ်

၁။ စီမံကိန်းနောက်ခံအကြောင်းအရာများ

ဤပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ချက်အစီရင်ခံစာသည် တွံတေးတူးမြောင်းဘက်စုံဖွံ့ဖြိုးရေးစီမံကိန်းအတွက် ပတ်ဝန်းကျင်နှင့်လူမှုရေးရာထိခိုက်မှုဆန်းစစ်ချက်အတွက် ရည်ရွယ်ဆောင်ရွက်ခဲ့ခြင်း ဖြစ်ပါသည်။ စီမံကိန်းတွင် အဆင့် ၂ ဆင့်ပါဝင်ပြီး ပထမအဆင့်မှာ ရေကြောင်းပြုပြင်ထိန်းသိမ်းရေးနှင့် ကမ်းထိန်းနံရံတို့ပါဝင်ပြီး ဒုတိယအဆင့်တွင် ဘက်စုံအသုံးပြုရသော ရေထိန်းကမ်းပတ်တာတစ်ခု တည်ဆောက်ရန် စီမံကိန်းအသေးစိတ်ဒီဇိုင်းပုံစံ ၊ ပါဝင်မည့်လုပ်ငန်းများ၊ မြေမျက်နှာသွင်ပြင်အနေအထား နှင့် ငွေကြေးဆိုင်ရာကဏ္ဍများ အစရှိသဖြင့် ပါဝင်ပါသည်။

တွံတေးတူးမြောင်းဘက်စုံဖွံ့ဖြိုးရေးစီမံကိန်း၏ ပထမဆင့်အကောင်အထည်ဖော်ရေးကို ကိုရီးယားပြည်သူ့သမ္မတနိုင်ငံ အစိုးရ ၊ Economic Development Cooperation Fund (EDCF) မှ Official Development Assistance (ODA) ထောက်ပံ့ပေးမှုဖြင့် ဆောင်ရွက်မည်ဖြစ်ပါသည်။ စီမံကိန်း၏ မျှော်မှန်းချက်တွင် စီးပွားရေးဖွံ့ဖြိုးတိုးတက်စေရန်အတွက် တွံတေးတူးမြောင်းတစ်လျှောက်တွင် လုံခြုံစိတ်ချရပြီး ကုန်းတွင်းပိုင်းရေကြောင်းစနစ်တစ်ခု ဖိပြင်စွာဖြစ်ပေါ်လာခြင်း ၊ ကုန်စည်စီးဆင်းမှု အဆင်ပြေချောမွေ့စေခြင်း ၊ ကမ်းပါးပြိုမှုမှ ကာကွယ်ခြင်း ၊ ရေကြီးရေလျှံခြင်းမှ ကာကွယ်ပေးခြင်း ၊ ခရီးသွားလုပ်ငန်းများ ဖွံ့ဖြိုးတိုးတက်စေခြင်း စသည့်အကျိုးကျေးဇူးများ တိုးတက်ဖြစ်ထွန်းလာစေနိုင်ပါသည်။

၁.၁။ စီမံကိန်းရည်ရွယ်ချက်

တွံတေးတူးမြောင်းသည် မြန်မာနိုင်ငံ၏အကြီးဆုံးစပါးကျီဒေသဖြစ်သော ဧရာဝတီမြစ်ဝကျွန်းပေါ်ဒေသနှင့်ရန်ကုန်မြစ်ဝကို ကုန်းတွင်းရေကြောင်းဖြင့်ဆက်သွယ်ထားပြီး ရေကြောင်းပြုပြင်ထိန်းသိမ်းခြင်းအားဖြင့် မြစ်ကြောင်းတစ်လျှောက်တွင် သင်္ဘော ရေယာဉ်များအတွက် လုံခြုံစိတ်ချရသော မြစ်ကြောင်းသွားလာမှု၊ ကုန်စည်စီးဆင်းမှုများ ချောမွေ့မြန်ဆန်လာစေမှုတို့အတွက် ရည်ရွယ်ပြီးအကျိုးဆက်အားဖြင့် ရေကြောင်းဆက်သွယ်ရေး နှင့် သယ်ယူပို့ဆောင်ရေးများ ချောမွေ့မြန်ဆန်လာကာ ဒေသတွင်း စီးပွားဖွံ့ဖြိုးတိုးတက်လာစေခြင်း ၊ ရေကြီးမှုနှင့် မြစ်ကမ်းပါးပြိုမှုတို့အား ကာကွယ်ပေးခြင်း စသည့်အကျိုးကျေးဇူးများ ရရှိမည်ဖြစ်ပါသည်။ စီမံကိန်းတည်ဆောက်ပြီးစီးပါက ဒေသတွင်းတွင် ခရီးသွားလာမှုလုပ်ငန်းများ ဖွံ့ဖြိုးတိုးတက်လာပြီး သက်ဆိုင်ရာလုပ်ငန်းများတွင် အလုပ်အကိုင်အခွင့်အလမ်းများလည်း ရရှိလာစေမည် ဖြစ်ပါသည်။

၁.၂။ စီမံကိန်းအစိတ်အပိုင်း


စီမံကိန်းတွင် အဓိကအားဖြင့် အပိုင်း (၂) ပိုင်း ပါဝင်ပါသည်။

အစိတ်အပိုင်း ၁ : ရေကြောင်းပြုပြင်ထိန်းသိမ်းခြင်း - ကမ်းပြိုမှုကာကွယ်ခြင်း - ကမ်းထိန်းနံရံတည်ဆောက်ခြင်း (၅.၈၈ ကီလိုမီတာ) နှင့် မြစ်ကြမ်းပြင်တိုက်စားမှု ကာကွယ်ခြင်း (ဧရိယာ = ၅၅ , ၅၀၀ စတုရန်းမီတာ)

အစိတ်အပိုင်း ၂ : ရေကြီးမှုကာကွယ်ခြင်း - ကမ်းထိန်းနံရံတည်ဆောက်ခြင်း (၃ ပိုင်း ၊ ၃၉.၅ ကီလိုမီတာ)

၁.၃။ စီမံကိန်းဧရိယာ

စီမံကိန်းဧရိယာသည် ရန်ကုန်တိုင်း ၊ တောင်ပိုင်းခရိုင်တွင်တည်ရှိသော တွံတေးတူးမြောင်း၏ '0' မိုင် မှ ၆.၅ မိုင်အတွင်း အကောင်အထည်ဖော်ဆောင်ရွက်မည် ဖြစ်ပါသည်။ ပထဝီအနေအထားအရ ဒလမြို့နယ် ၊ ဆိပ်ကြီးခနောင်တိုမြို့နယ် ၊ ကြည့်မြင်တိုင်မြို့နယ်နှင့် တွံတေးမြို့နယ်တို့ဖြင့် မြေမျက်နှာပြင်သွင်ပြင်ချင်း ဆက်စပ်လျက်ရှိပါသည်။ (ပုံ ၁.၃-၁ တွင် ကြည့်ပါ)။



ပုံ ၁.၃-၁ : တွံတေးတူးမြောင်း စီမံကိန်းပြမြေပုံ

၁.၄။ စီမံကိန်းအချိန်ကာလ

ပို့ဆောင်ရေးနှင့်ဆက်သွယ်ရေးဝန်ကြီးဌာနလက်အောက်ရှိ ရေအရင်းအမြစ်နှင့် မြစ်ချောင်းများ ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာနသည် စီမံကိန်းအကောင်အထည်ဖော်ဆောင်ရွက်ရေးအတွက် လိုအပ်သော အချိန်ဇယား ၊ ဘက်ဂျက် ၊ ဝန်ထမ်းနှင့် EDCF ၏ အခြားလိုအပ်ချက်များ စသည်တို့ကို ပြင်ဆင်ရေးဆွဲကာ စီမံကိန်းကို တာဝန်ယူအကောင်အထည်ဖော်မည်ဖြစ်ပါသည်။ စီမံကိန်းဖြစ်မြောက်နိုင်စွမ်းလေ့လာဆောင်ရွက်မှု အစီရင်ခံစာမူကြမ်းအား ၂၀၁၇ ခုနှစ် ဒီဇင်ဘာလတွင် ရေအရင်းအမြစ်နှင့်မြစ်ချောင်းများ ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာနသို့ တင်သွင်းခဲ့ပြီး စီမံကိန်းအကောင်အထည်ဖော်ရေးအတွက် လူမှုရေးနှင့် သဘာဝ

ပတ်ဝန်းကျင်ဆန်းစစ်မှုလုပ်ငန်းများအား မြန်မာနိုင်ငံမှ အချိန်မီအတည်ပြုချက်ရရှိရန် ဆောင်ရွက်ရမည် ဖြစ်ပါသည်။ စီမံကိန်းအတွက် အသေးစိတ်အင်ဂျင်နီယာဒီဇိုင်းအတွက် ခေါ်ယူခြင်းမှစကာ ပြီးမြောက်သည်အထိ အချိန်ကာလအားဖြင့် ၆ နှစ်ကျော်ကြာ (ပုံ ၁.၄-၁ တွင် ပြထားသည့်အတိုင်း) ဆောင်ရွက်ရမည် ဖြစ်ပါသည်။

Activities	Year1				Year2				Year3				Year4				Year5				Year6			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Selection of Consultant & Detailed Design																								
Bidding																								
Land Acquisition & Compensation																								
Contractor Selection																								
Construction & Supervision																								

ပုံ ၁.၄-၁ : စီမံကိန်းအကောင်အထည်ဖော်ဆောင်ရွက်မှု အချိန်ပြဇယား

၁.၅။ စီမံကိန်းပိုင်ရှင်နှင့် ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်လေ့လာမည့် အဖွဲ့အစည်း

စီမံကိန်းပိုင်ရှင်

Proponent Name:	Directorate of Water Resources and Improvement of River Systems(DWIR), Ministry of Transport and Communications (MOTC)		Company Registration Number by DICA (if any):	
Contact name of Proponent:	Director General, DWIR			
Proponent`s address for correspondence:	No-400, Lower Pazundaung Road, Yangon Myanmar			
Telephone(fixed/mobile):	+95-1- 292961(office)	Fax: +95-4- 290230	E-mail address:	lwino0.capthtun@gmail.com

လေ့လာမည့်အဖွဲ့အစည်းခေါင်းဆောင်

Name (Sur name, Given name)	Registration / License No. by ECD (if applied)	Organization	Contact details	Area of expertise
U Zaw Naing Oo	Certificate for Transitional Consultant Registration No. 0002	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel : +95 9 73013448 Mobile : +95 9 976886587 Email: zawnaingoo@enviromyanmar.net	ESIA / ESMMP

လေ့လာမည့်အဖွဲ့အစည်း၏ အဖွဲ့ဝင်များ

Name (Sur name, Given name)	Registration / License No. by ECD (if applied)	Organization	Contact details	Area of expertise
U Win Naing Tun	Certificate for Transitional Consultant Registration No. 0002	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Resettlement Action Plan, Cultural Heritage
DawKhinOhn marHtwe	Certificate for Transitional Consultant Registration No. 0002	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Stakeholder Engagement Plan and Public Consultation
Ms. Jerry JH Kim	Certificate for Transitional Consultant Registration No.	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township.	Socio Economy

	0002		Tel: +95 9 73013448 +95 9976654118(Myanmar)	
UThura Aung	Certificate for Transitional Consultant Registration No. 0002	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Geology and Soil, Waste Management
U Soe Yu Htun	Certificate for Transitional Consultant Registration No. 0002	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Meteorology, Modelling for Air Quality
DawPhyuPhy uShein	Certificate for Transitional Consultant Registration No. 0002	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Socio Economy, Facilitation of Meeting
Daw Nan ThazinOo	Certificate for Transitional Consultant Registration No. 0002	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Socio Economy, Facilitation of Meeting
DawNaingNa ing Win	Certificate for Transitional Consultant Registration No. 0025	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
U ThetNaing Aung	Certificate for Transitional Consultant Registration No. 0025	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity

U MyatKoKo Hein	Certificate for Transitional Consultant Registration No. 0025	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
Daw Than ThanHtay	Certificate for Transitional Consultant Registration No. 0025	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
DawPhyoeKh aingZar Wint	Certificate for Transitional Consultant Registration No. 0002	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Water Pollution Control
U Ngwe Moe	Certificate for Transitional Consultant Registration No. 0002	Resource& Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Risk Assessment and Hazard Management
DawLaiLai Win	Certificate for Transitional Consultant Registration No. 0002	Resource& Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Environmental Impact Assessment and Reporting
Daw Chit Hsu San	Certificate for Transitional Consultant Registration No. 0117	Resource& Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Legal Expert

၁.၆။ ကိုရီးယားနိုင်ငံ Economic Development Cooperation Fund (EDCF) မှ သဘာဝ ပတ်ဝန်းကျင် နှင့် လူမှုသက်ရောက်မှုများအား အကဲဖြတ်မည့်အဖွဲ့အစည်း

ကိုရီးယားနိုင်ငံ Economic Development Cooperation Fund (EDCF) မှ သဘာဝပတ်ဝန်းကျင် နှင့် လူမှုပတ်ဝန်းကျင်သက်ရောက်မှုအား EDCF Safeguard Policy နှင့် အညီ အကဲဖြတ်ရန် အကြံပေးမည့်

အဖွဲ့အား ငှားရမ်းထားပါသည်။ အကြံပေး ကုမ္ပဏီများမှာ ISAN Corporation (as project manager), YOOSHIN ENGINEERING Corporation (ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်လေ့လာခြင်း ခေါင်းဆောင်), နှင့် GAIA CONSULT Inc. (လူမှုပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်လေ့လာခြင်း ခေါင်းဆောင်) တို့ဖြစ်ကြပါ သည်။

No.	Name	Firm	Field	Remarks
1	Mr. Kang, Yoonmin	ISAN	ESIA	ESIA Team Leader
2	Mr. Yun, Daeil	ISAN	EIA	Director
3	Mr. Nam, Teaho	ISAN	EIA	General Manager
4	Mr. Jeon, Kyungyoel	ISAN	EIA	Director
5	Mr. Joung, Oukyoung	ISAN	EIA	Director
6	Mr. Kim, Seongwoon	ISAN	EIA	General Manager
7	Mr. Lee, Sanghoon	YOOSHIN	EIA	Director
8	Mr. Kim, Hyunmoo	YOOSHIN	EIA	General Manager
9	Mr. Kim, Sungho	YOOSHIN	EIA	General Manager
10	Mr. Lee, Hwajung	YOOSHIN	EIA	General Manager
11	Mr. Kim, Byungsun	YOOSHIN	EIA	General Manager
12	Ms. Lee, Eunyoung	GAIA	SIA & RAP	Senior Manager Social Team Leader
13	Ms. Lee, Juhyun	GAIA	SIA & RAP	General Manager
14	Mr. Im, Uijin	GAIA	SIA & RAP	General Manager
15	Mr. Kim, Jongwook	GAIA	SIA & RAP	General Manager

၁.၇။ စီမံကိန်းအကောင်အထည်ဖော်မည့်ကာလနှင့် ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်း ဆောင်ရွက်မည့် ကာလ

မြန်မာနိုင်ငံနှင့် ကိုးရီးယားနိုင်ငံရှိ လုပ်ငန်းတူစီမံကိန်းအမျိုးအစားများအပေါ် အခြေခံ၍ လုပ်ငန်း ပမာဏ၊ ရာသီဥတုအခြေအနေ (ခြောက်သွေ့ရာသီ၊ စိုစွတ်ရာသီ) စသည့်အချက်အလက်များအား အခြေခံ အဖြစ် ထည့်သွင်းစဉ်းစားကာ စီမံကိန်းအကောင်အထည်ဖော်မည့်ကာလအား ရေးဆွဲခဲ့ပါသည်။ အကြံပေး ပညာရှင်အဖွဲ့အားရွေးချယ်ခြင်းအတွက် ၃လ၊ အသေးစိတ်ဒီဇိုင်းနှင့်တင်ဒါခေါ်ယူခြင်းများအ တွက် ၉ လ နှင့် ဆောက်လုပ်ရေးလုပ်ငန်းများနှင့် ကြီးကြပ်ကွပ်ကဲမှုလုပ်ငန်းများအတွက် လပေါင်း ၆၀ အပါအဝင်

စီမံကိန်းအကောင်အထည်ဖော်မည့်ကာလမှာ စုစုပေါင်း ၆ နှစ်ခန့် လိုအပ်မည် ဖြစ်ပါသည်။

သဘာဝပတ်ဝန်းကျင်နှင့်လူမှုထိခိုက်မှုဆန်းစစ်ခြင်းလုပ်ငန်းများအကောင်အထည်ဖော်ဆောင်ရွက်မည့်ကာလမှာ ၁၄ လဖြစ်ပါသည်။ လုပ်ငန်းများကို ၂၀၁၈ ခုနှစ် ဇန်နဝါရီလတွင် စတင်ခဲ့ပြီး ၂၀၁၉ ခုနှစ် ဖေဖော်ဝါရီလတွင် အဆုံးသတ်ပြီးစီးရန် မျှော်လင့်ထားပါသည်။ ဆောင်ရွက်မည့်အဓိကလုပ်ငန်းစဉ်များအား အချိန်ကာလနှင့်အတူ ဇယား ၁.၇-၁ တွင် ဖော်ပြထားပါသည်။

ဇယား ၁.၇-၁ : သဘာဝပတ်ဝန်းကျင်နှင့် လူမှုရေးရာထိခိုက်မှု ဆန်းစစ်ချက် အကောင်အထည်ဖော်ဆောင်ရွက်မည့် အချိန်ဇယား

Step	Main Task	Process Plan (12 month)															
		M 1	M 2	M 3	M 4	M 5	M 6	M 7	M 8	M 9	M 10	M 11	M 12	M 13	M 14	M 15	M 16
1	Establishing evaluation plan through preliminary survey	■	■	■	■												
	Project proposal Submission				■	■	■										
2	Scoping investigation (Stakeholder Analysis)					■	■	■									
	Information disclosure & public consultation (1st)						■										
	Scoping and TOR writing and submission						■	■	■								
	Scoping and TOR confirmation (MONREC)													■			
3	ESIA investigation							■	■	■	■						
	Information disclosure & public consultation (2nd)									■							
	Drafting ESIA report													■	■		
4	ESIA Report Submission, Review and Approval (MONREC)														■	■	■

၂။ မူဝါဒနှင့် လမ်းညွှန်ချက် ဖွဲ့စည်းမှု မူဘောင်

တွံတေးတူးမြောင်း၏ ပတ်ဝန်းကျင်နှင့်လူမှုရေးထိခိုက်မှုဆန်းစစ်ခြင်းအား ပို့ဆောင်ရေးနှင့် ဆက်သွယ်ရေးဝန်ကြီးဌာန၊ ရေအရင်းအမြစ် နှင့် မြစ်ချောင်းများ ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန နှင့်အတူ Resource and Environment Myanmar Co., Ltd. မှ ကိုရီးယား အင်ဂျင်နီယာ အကြံပေး ကုမ္ပဏီ ISAN Consultant တို့၏နည်းပညာကြီးကြပ်မှုဖြင့် လေ့လာသွားမည်ဖြစ်ပြီး မြန်မာနိုင်ငံတွင် လက်ရှိထုတ်ပြန်ထားရှိသည့် ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဥပဒေ (၂၀၁၂) ၊ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးနည်းဥပဒေ(၂၀၁၄) ၊ ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်း လုပ်ထုံးလုပ်နည်းနှင့် အမျိုးသားပတ်ဝန်းကျင်ဆိုင်ရာ အရည်အသွေး (ထုတ်လွှင့်မှု)လမ်းညွှန် ချက်များ (၂၀၁၅) အရ လိုက်နာ ဆောင်ရွက်မည်ဖြစ်သည့်အပြင် Export-Import Bank- Korea ၏ Economic Development Cooperation Fund-EDCF အား သီးခြားလိုက်နာဆောင်ရွက်ခြင်းမူအရ EDCF ၏ Safeguard Policy ကိုလည်း ပတ်ဝန်းကျင်နှင့် လူမှုရေးရာ ဖြည့်ဆည်း ဆောင်ရွက်ပေးရန်အလို့ငှာ အခြေခံထား လေ့လာသွားမည်ဖြစ်ပါသည်။ ထို့အပြင် နိုင်ငံတကာမှလက်ခံထားရှိသောအလေ့အကျင့်များ အားလေ့လာရန် အခြားဖြစ်နိုင်ချေရှိသည့် အကောင်းဆုံးနည်းလမ်းဖြစ်သော နစ်နာမှုများ၊ မကျေနပ်ချက်များကို လက်ခံဖြေရှင်းပေးရေးစနစ် (လူထုဟစ်တိုင်စနစ်)ကို အကောင်အထည်ဖော် ဆောင်ခြင်းအားဖြင့် လူထုအား ပူပေါင်းပါဝင်စေခြင်းနှင့် စီမံကိန်းနှင့် သက်ဆိုင်သူများ (ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ရာတွင် ဦးဆောင်ပါဝင်နိုင်မည့် မြန်မာနိုင်ငံရှိ အစိုးရနှင့် အစိုးရမဟုတ်သော အဖွဲ့အစည်းများအပါအဝင်) နှင့် ဆွေးနွေးညှိနှိုင်းခြင်းများအား ဆောင်ရွက်သွားမည်ဖြစ်ပါသည်။

၃။ အဆိုပြု စီမံကိန်းဖော်ပြချက်

တွံတေးတူးမြောင်းဘက်စုံဖွံ့ဖြိုးတိုးတက်ရေး စီမံကိန်းအား အပိုင်းနှစ်ပိုင်းဖြင့်ဖွဲ့စည်းထားပါသည်။ ပထမအပိုင်းတွင် ရေလမ်းကြောင်း ထိန်းသိမ်းခြင်း နှင့် ရေထိန်းနံရံတည်ဆောက်ခြင်းတို့ပါဝင်ပါသည်။ ဒုတိယအပိုင်းတွင် ကမ်းထိန်းတာတည်ဆောက်ခြင်းတို့လုပ်ဆောင်မည်ဖြစ်ပါသည်။ ဤအစီရင်ခံစာသည် ပထမအပိုင်းအတွက်သာ အကြီးဝင်ပါသည်။ အသေးစိတ်ဒီဇိုင်း၊ အစိတ်အပိုင်းများ၊ ငွေကြေးထောက်ပံ့မှုများ ပါဝင်သည့် ဒုတိယအပိုင်းအား နောင်တွင်လုပ်ဆောင်နိုင်ရန် ရည်ရွယ်ထားပါသည်။

စီမံကိန်း၏အစိတ်အပိုင်း (၁) တွင် အရေးတကြီးဆောင်ရွက်ရန်လိုအပ်သော ဆိုးရွားသော ပြဿနာများဖြစ်သည့် ကမ်းပါးတိုက်စားခြင်း နှင့် ရေကြီးရေလျှံခြင်း စသည်တို့ဖြေရှင်းရန်ပါဝင်ပါသည်။ တွံတေးတူးမြောင်း ရေကြောင်းပြုပြင်ထိန်းသိမ်းမှုများကြောင့် ဒီရေအတက်အကျ နှင့် ရေစီးဆင်းမှု တည်ငြိမ် စေပြီး ကမ်းပါးနံရံတည်ဆောက်ခြင်းကြောင့် အမြင့်ဆုံးဒီရေတက်ချိန်တွင် ကမ်းပါးနံရံအား မကျော်လွန်စေရန် တိုင်းတာထိန်းသိမ်းပေးမည် ဖြစ်ပါသည်။


ဤစီမံကိန်းသည် ရုပ်ပိုင်းဆိုင်ရာပတ်ဝန်းကျင် ၊ လူမှုစီးပွားရေး နှင့် ရေတိုက်စားခြင်းကြောင့် ဖြစ်ပေါ်သည့် ပတ်ဝန်းကျင်ထိခိုက်ပျက်စီးမှုများ၊ ရေကြီးခြင်း နှင့် အသက်လုံခြုံမှုများ နှင့် အသက်မွေးဝမ်းကြောင်းများ ထိခိုက်နစ်နာမှုများအား ကာကွယ်ပေးမည်ဖြစ်ပါသည်။

စီမံကိန်းအား အဓိကအားဖြင့် အပိုင်းနှစ်ပိုင်းဖြင့် ဖွဲ့စည်းထားပါသည်။

အစိတ်အပိုင်း ၁ : ရေကြောင်းပြုပြင်ထိန်းသိမ်းခြင်း - ကမ်းပြိုမှုကာကွယ်ခြင်း - ကမ်းထိန်းနံရံတည်ဆောက်ခြင်း (၅.၈၈ ကီလိုမီတာ) နှင့် မြစ်ကြမ်းပြင်တိုက်စားမှု ကာကွယ်ခြင်း (ဧရိယာ = ၅၅ , ၅၀၀ စတုရန်းမီတာ)

အစိတ်အပိုင်း ၂ : ရေကြီးမှုကာကွယ်ခြင်း - ကမ်းထိန်းနံရံတည်ဆောက်ခြင်း (၃ ပိုင်း ၊ ၃၉.၅ ကီလိုမီတာ)

စီမံကိန်းအစိတ်အပိုင်း ၁ ၏ တည်နေရာပြမြေပုံကို ပုံ ၃-၁ တွင် ဖော်ပြထားပါသည်။



ပုံ ၃-၁: စီမံကိန်းအစိတ်အပိုင်း ၁ ၏ တည်နေရာပြမြေပုံ

၃.၁။ စီမံကိန်းဆိုင်ရာ အခြားနည်းလမ်းများ

စီမံကိန်းဆိုင်ရာ အခြားနည်းလမ်းရွေးချယ်ခြင်းသည် စီမံကိန်းအား နည်းပညာပိုင်း အားကောင်းသောစီမံကိန်းဖြစ်ရန် ရည်ရွယ်ချက်ပြီးမြောက်ရန် အချိန်မီနည်းလမ်းသိရှိရန် စီမံကိန်းအားအကျိုးရှိစွာ နှင့်ကုန်ကျစရိတ်ကို ထိရောက်သောနည်းလမ်း ဖြစ်စေရန်အရေးကြီးသော အချက်ဖြစ်ပါသည်။ စီမံကိန်းအတွက် အလားအလာရှိနိုင်သော အခြားနည်းလမ်းများအားခွဲခြမ်းစိတ်ဖြာခြင်းသည် စီမံကိန်းအား နည်းပညာပိုင်း အကျိုးရှိစွာ နှင့် ကုန်ကျစရိတ် ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်လေ့လာခြင်း ရှုထောင့်အရ အလားအလာရှိနိုင်သော နည်းလမ်းသည် ပတ်ဝန်းကျင်ထိခိုက်မှု လျော့ချရန် နှင့် ရှောင်ရှားရန်ဖြစ်ပါသည်။ နည်းပညာပိုင်း နှင့် စီးပွားရေးရှုထောင့် စသည့် အပိုင်းနှစ်ခုဖြင့် အလားအလာရှိနိုင်သော နည်းလမ်းကို စဉ်းစားပါသည်။

အခြားနည်းလမ်းများကိုဆန်းစစ်ခြင်း "စီမံကိန်းအကောင်အထည်ဖော်ခြင်း" နှင့် "စီမံကိန်းအကောင်အထည်ဖော်ဆောင်ရွက်မှုမရှိခြင်း"

အဆိုပြုစီမံကိန်း၏ သဘာဝပတ်ဝန်းကျင် ၊ လူမှုစီးပွားနှစ်ရပ်လုံးအပေါ်တွင်အခြေခံကာ **"စီမံကိန်းအကောင်အထည်ဖော်ခြင်း"** နှင့် **"စီမံကိန်းအကောင်အထည် ဖော်ဆောင်ရွက်မှုမရှိခြင်း"** နှစ်ရပ်အား အောက်ပါအတိုင်း နှိုင်းယှဉ်ဖော်ပြအပ်ပါသည်။ ထို့အပြင် ရေလွှဲမြောင်းထားရှိခြင်း နှင့် မထားရှိခြင်း စသော နည်းပညာပိုင်း ဖြစ်ရပ်နှစ်ခုကိုလည်း နှိုင်းယှဉ်စဉ်းစားထားပါသည်။ ထို့အတွက် အသေးစိတ်အား ပတ်ဝန်းကျင်နှင့်လူမှုရေးရာထိခိုက်မှုဆန်းစစ်ခြင်းကဏ္ဍတွင်ဖော်ပြထားပါသည်။

ဇယား ၃.၁-၁: “စီမံကိန်းအကောင်အထည်ဖော်ခြင်း” နှင့် “စီမံကိန်းအကောင်အထည်ဖော်ဆောင်ရွက်မှုမရှိခြင်း” အပေါ်တွင် ဆန်းစစ်ချက်များ

အလားအလာရှိသည့် သက်ရောက်မှု	စီမံကိန်းအကောင်အထည်ဖော်ဆောင်ရွက်ခြင်း အနာဂတ်ဖြစ်နိုင်ချေ (ရည်ရွယ်ထားသော စီမံကိန်း)	စီမံကိန်းအကောင်အထည်ဖော်ဆောင်ရွက်မှု မရှိခြင်း (အနာဂတ်ဖြစ်နိုင်ချေ)	မှတ်ချက်
ပတ်ဝန်းကျင်	<ul style="list-style-type: none"> လုပ်ငန်းအကောင်အထည်ဖော်ခြင်းကြောင့် ပတ်ဝန်းကျင် အပေါ် သက်ရောက်နိုင်သည့် အလားအလာ များမှာ: အမှန်များထုတ်လွှတ်ခြင်း၊ အသံဆူညံခြင်း၊ သဲနုန်းများ ထုတ်လွှတ်ခြင်း၊ နှင့် ကမ်းနားရှိ ဇီဝမျိုးကွဲ များ အပေါ် သက်ရောက်မှုများရှိနိုင်ပါသည်။ 	<ul style="list-style-type: none"> အကယ်၍ လုပ်ငန်း အကောင်အထည်မဖော်ပါက ရေတို အရ သက်ရောက်မှု မရှိနိုင်ပါ လက်ရှိတွင် ရေတိုက်စားခြင်း၊ အနည်ထိုင်ခြင်း နှင့် ကမ်းတိုက်စားခြင်းများ ဆက်တိုက်ဖြစ်ပေါ်နေသော စီမံ ကိန်းအကောင်အထည်မဖော်ပါက ဆိုးရွားစွာ လုံခြုံမှုမ ရှိခြင်းများ ဆက်တိုက်ဖြစ်ပေါ်နိုင်ပါသည်။ 	<p>ဆောက်လုပ်ရေးလုပ်ငန်းများ ပြီးစီး၍ လုပ်ငန်း လည်ပတ်ချိန် ရောက်ပါက တည်ငြိမ်သွားပြီး သက် ရောက်မှုများက ယာယီသာဖြစ်ပါသည်။</p> <p>ဆောက်လုပ်ရေးကာလတွင် ပတ်ဝန်းကျင်ထိခိုက်မှု များ လျော့နည်းစေရန် ကောင်းမွန်သော ပတ်ဝန်း ကျင် စီမံခန့်ခွဲမှုအစီအစဉ် ဆောင်ရွက်ရန်လို အပ်ပါ သည်။</p>
လူမှုစီးပွား	<ul style="list-style-type: none"> ရေကြီးမှုအားတိုင်းတာကာကွယ်ခြင်းလုပ်ငန်းသည် အ သက်လုံခြုံမှုရှိခြင်း နှင့် စီမံကိန်းအားလုံးပြီး စီးသွားပါ က တွံတေး တူးမြောင်းအနီးရှိ ဒေသခံများ အသက်မွေးဝမ်း ကျောင်းများ ဆုံးရှုံးမှုမှ လျော့နည်းသွားမည်ဖြစ်ပါသည်။ ကမ်းပြိုမှုအားထိန်းသိမ်းသည့် လုပ်ငန်းဆောင်ရွက်မှု ကြောင့် တူးမြောင်းအတွင်း သွားလာသည့် ရေယာဉ်များ မတော်တဆ တိုက်ခြင်းမှကာကွယ် အပြင်စီမံကိန်းအား လုံး ပြီးစီးသွားပါက ရေယာဉ်သွားလာမှုများ လုံခြုံမှုရှိ ပြီး တည်ငြိမ်စွာ သွားလာနိုင်မည်ဖြစ်ပါသည်။ ဆောက်လုပ်ငန်းကာလအတွင်းတွင် ငါးများခြင်းလုပ်ငန်း ၊ ရေကြောင်းသွားလူများ (ကုန်တင်ပို့ခြင်း၊ ပုံမှန် ခရီးသည် လှေများ အပါအဝင် ခရီးသွားဧည့်သည် လှေများ) အ နောက်အယုတ် အနည်းငယ်ဖြစ်နိုင်ပြီး ယင်းသက်ရောက် မှုမှာ အနည်းငယ်နှင့် ယာယီသာ ဖြစ်ပါသည်။ 	<ul style="list-style-type: none"> ဆောက်လုပ်ရေးကာလတွင် လုပ်ငန်းဧရိယာအတွင်း ရှိ နေထိုင်သူများ၏ အသက်မွေးဝမ်းကျောင်းများ ထိခိုက်မှု မရှိပါ။ ဥပမာအားဖြင့် (ယာယီ၊ ရာသက်ပန် မြေဆုံးရှုံးမှု၊ သွားလာရာတွင် အခက်အခဲများ၊ မြေယာဆုံးရှုံးမှုများ၊ ဆက်သွယ်ရာတွင် အချိန်ကြာ မြင့်မှုများ) သမိုင်းစဉ်ဆက်တစ်လျှောက်ဖြစ်ပွားခဲ့သောကမ်းပါး တိုက် စားခြင်း၊ အနည်ထိုင်ခြင်း၊ မြစ်ကြမ်းပြင်တိုက် စားခြင်းများ သည်ပို၍မြန်ဆန်လာသဖြင့် အချိန်မှီမ ကာကွယ်ပါက လူမှုရေး အသက်လုံခြုံမှုများအတွက် ကုန်းတွင်းပိုင်း ယာဉ်များမှ မတော်တဆထိခိုက်မှုများ အတွက် ကုန်ကျစရိတ်များ ရာခိုင်နှုန်းမြင့်လာနိုင်ပါ သည်။ ငါးမြားခြင်းလုပ်ငန်း ရေကြောင်းသွားလူများ (ကုန် တင်ပို့ခြင်း၊ ပုံမှန်ခရီးသည်လှေများ အပါအဝင် ခရီး သွားဧည့်သည်လှေများ) အနောက်အယုတ် အနည်း ငယ်ဖြစ်နိုင်ပြီး ယင်းသက်ရောက်မှုမှာ အနည်းငယ်နှင့် ယာယီသာ ဖြစ်ပါသည်။ သို့သော်လည်း၊ နန်းများအ နည်ထိုင်ခြင်း နှင့် ကမ်းနံရံတိုက်စားမှုများကြောင့် 	<p>စီမံကိန်းအားဆောင်ရွက်မှု မရှိခြင်းသည် စီမံကိန်း ဆောင်ရွက်မှုထက် ရေရှည်တွင် အနီးအနားရှိ ပြည် သူလူထုအတွက် လူမှုရေးထိခိုက်နစ်နာမှုများ ပိုမို ဖြစ်ထွန်းစေနိုင်ပါသည်။</p> <p>ဆောက်လုပ်ရေးကာလတွင် လူမှုစီးပွားရေးအား ထိ ခိုက်နိုင်သည့် အလားအလာရှိသော ဆိုးကျိုးများ အား ထိခိုက်မှု လျော့နည်းစေသည့် ကောင်း မွန်သည့်အစီအစဉ်မှာ ထိခိုက်မှုများအတွက် လျော် ကြေးငွေများပြန်လည်ပေးခြင်းဖြင့် လျော့ချ နိုင်မည် ဖြစ်ပါသည်။</p>

		အနောက်အယုတ် ဖြစ်စေ သည့်အပြင်၊ ရေယာဉ်များ လျော့နည်းလာပြီး ငါးများသော လုပ်သားများအတွက် ရေရှည်သက် ရောက်မှုများရှိနိုင်သည်။	
စီးပွားရေး	<ul style="list-style-type: none"> ကုန်းတွင်းပိုင်း ပို့ဆောင်ဆက်သွယ်ရေးများ အသုံးပြုခြင်းကြောင့် အသုံးပြုမှုများ လျော့နည်းလာမည်ဖြစ်သည်။ ရေတိုက်စားခြင်းကြောင့် တွဲတေးတူးမြောင်း တလျှောက် နှစ်စဉ်မြေဆုံးရှုံးမှုများမှ ကာကွယ်ပေးပြီး စီးပွားရေးအရ (၁၁၁၅ sqm per annum in annum ခန့်တိုမြို့ နှင့် ဒလမြို့တို့တွင် (၁၁၁၅ sqm per annum in annum အပြင် ဆောက်လုပ်ရေးလုပ်ငန်း ပြီးစီးပါက အမေရိကန် ဒေါ်လာ ၀.၂၂၅ သန်းတန်သည့် အကျိုးအမြတ် ရနိုင်သည်။ ကုန်းတွင်းအပိုင်း ရေယာဉ်အသုံးပြုသူ သွားလာမှုများတိုးတက်လာပြီး လုံခြုံ လျှင်မြန်စွာသွားလာနိုင်မည် ဖြစ်ပါသည်။ ၂၀၄၀ Greater Yangon Strategic Urban Development Plan (SUDP)၊ အဆိုပါတွဲတေး နှင့် ခန့်တိုမြို့ သစ်ဖွံ့ဖြိုးရေး ၊ မြေယာဆုံးရှုံးမှု ရေတိုက်စားမှု ရေကြီးမှုများအားကာကွယ်ခြင်းဖြင့် ဒေသအတွင်း စီးပွားရေး ပိုမိုမြင့်မားမည်ဟုမျှော် လင့်ရပါသည်။ 	<ul style="list-style-type: none"> ဆောက်လုပ်ရေးကာလတွင် လုပ်ငန်းဧရိယာအတွင်း ရှိ နေထိုင်သူများ၏ အသက်မွေး ဝမ်းကျောင်းများ ထိခိုက်မှု မရှိပါ။ ဥပမာအားဖြင့် (ယာယီ၊ ရာသက်ပန် မြေဆုံးရှုံးမှု ၊ အလုပ်အကိုင်ဆုံးရှုံးမှုများ) ၊ (ယာယီ ငါးဖမ်းမှု အထစ်အပေါ့ ဖြစ်စေခြင်း၊ ငါးဖမ်း နေရာများ ပြန်နေရာပေးခြင်း နှင့် အခြားသော တွဲတေးတူး မြောင်း နှင့် ပက်သက်သည့် စီးပွားရေးလုပ်ငန်းများ) ရေရှည်အားဖြင့် ကမ်းပါးတိုက်စားခြင်း၊ အနည်ထိုင်ခြင်း၊ မြစ်ကြမ်းပြင်တိုက်စားခြင်းများသည် ကုန်းတွင်းသွားလာမှုများတွင် မလုံခြုံမှု ၊ မတော်တဆ အန္တရာယ်ဖြစ်များ များပြားလာနိုင်ပြီး ရေကြီးခြင်းကြောင့် ပျက်စီးဆုံးရှုံးမှုများ၊ မြေယာဆုံးရှုံးမှုများ၊ အခြားသောဆုံးရှုံးမှုများသည် ရေရှည်စီးပွားရေး ဆုံးရှုံးမှုများ ဖြစ်နိုင်သည်။ 	<p>ဆောက်လုပ်ရေးကာလတွင် စီမံကိန်းအား လက်ခံသည့် အဖွဲ့အစည်းအနေဖြင့် ရေလတ် (သို့) ရေရှည် စီးပွားရေး ပို၍အကျိုးအမြတ်ရရှိမည်ဖြစ် သည်။</p> <p>ဆောက်လုပ်ရေးကာလတွင် အလားအလာရှိ သော ဆိုးကျိုးများအား ထိခိုက်မှု လျော့နည်းစေသည့် ထိရောက်မည့်အစီအစဉ်၊ လျော်ကြေးငွေ များပေးခြင်း ဖြင့် လျော့ချနိုင်မည် ဖြစ်ပါသည်။</p>


၄။ ပတ်ဝန်းကျင်ဆိုင်ရာ ဖော်ပြချက်

၄.၁။ လေ့လာမည့်လွှမ်းမိုးမှု ဧရိယာသတ်မှတ်ခြင်း

ဧရာဝတီမြစ်ဝှမ်းဒေသသည် မြန်မာပြည် အလယ်ပိုင်းလွင်ပြင်ဒေသ၏ တောင်ဘက်တွင် တည်ရှိပါသည်။ ယင်းဒေသသည် ရန်ကုန်၊ ဧရာဝတီနှင့် ပဲခူးဒေသ တစ်စိတ်တစ်ပိုင်း တို့ဖြင့် ပါဝင်ဖွဲ့စည်းထားပါသည်။ ဧရာဝတီမြစ်သည် ဧရာဝတီတိုင်းအတွင်းတွင် မြစ်ချောင်းများအဖြစ် ခွဲဖြာလျက် အတ်ဒမန်ပင်လယ် (Andaman Sea) အတွင်းသို့ စီးဝင်ပါသည်။ ဧရာဝတီတိုင်း၏ တောင်ဘက်တွင် အတ်ဒမန်ပင်လယ် (Andaman Sea) နှင့် အနောက်ဘက်တွင် ဘင်္ဂလားပင်လယ်အော်တို့ တည်ရှိပြီး အရှေ့ဘက်တွင်လည်း မုတ္တမပင်လယ်ကွေ့ တည်ရှိပါသည်။ စီမံကိန်းနေရာမှာ ရန်ကုန်တိုင်းဒေသကြီး၊ တောင်ပိုင်းခရိုင်ရှိ တွံတေးမြို့နယ်၊ ဒလမြို့နယ်၊ ကြည့်မြင်တိုင်မြို့နယ်နှင့် ဆိပ်ကြီးခနောင်တိုမြို့နယ် တို့တွင် ဖြစ်ပါသည်။

၄.၂။ မြေမျက်နှာသွင်ပြင် အနေအထား

ပုံ ၄.၂-၁ တွင် ပြထားသော Digital Elevation Model (DEM) အရ တွံတေးတူးမြောင်း ဝန်းကျင်ရှိ မြေမျက်နှာပြင်အနေအထားမှာ မြစ်ဝှမ်းဒေသ၏အင်္ဂါရပ်များဖြင့် ဖွဲ့စည်းထားပါသည်။ မြေမျက်နှာပြင်အမြင့် မှာ ၁.၀ မီတာမှ ၁.၅ မီတာ ရှိပြီး ၆၂၆ စတုရန်းကီလိုမီတာ လွှမ်းခြုံလျက် စုစုပေါင်းဧရိယာ၏ ၈၇% ရှိပါသည်။



Source: 1:50,000 DEM of Survey Department.

ပုံ ၄.၂-၁ : ရန်ကုန်တောင်ပိုင်းဒေသ၏ မြေပြင်အခြေအနေပြမြေပုံ

၄.၃။ မြေအသုံးချမှု


စီမံကိန်း ဧရိယာ၏ မြေအသုံးချမှုမှာ အဓိကအားဖြင့် မြို့ပြ၊ လယ်ယာမြေနှင့် တူးမြောင်း တို့ ဖြစ်ပါသည်။ ၂၀၁၈ ခုနှစ် ဇွန်လတွင် YRG မှ ရန်ကုန်မြို့ပြ ဖွံ့ဖြိုးရေး မဟာဗျူဟာ စီမံကိန်း (SUDP) (၂၀၄၀) ကို ကြေငြာခဲ့ပါသည်။ တွံတေးမြို့နယ်၊ ဆိပ်ကြီးခရိုင်တို့ မြို့နယ်နှင့် ဒလမြို့နယ်တို့ကို ပထမ အဆင့် ဖွံ့ဖြိုးရေး ဧရိယာအဖြစ် သတ်မှတ်ခဲ့ပါသည်။

၄.၄။ မြေဆီလွှာ

စီမံကိန်း ဧရိယာတစ်ခုလုံးနှင့် ရန်ကုန်တိုင်းဒေသကြီး၏ တောင်ဘက်တွင် အဓိက မြေဆီလွှာ ၄ မျိုး တွေ့ရှိရပါသည်။ ယင်းတို့မှာ

- Meadow & Meadow Alluvial soil
- Lateritic Soil
- Saline Swampy & Meadow Gley Soil
- Dune Forest and Beach Sand

ပုံ ၄.၄-၁ တွင် ပြထားသည့်အတိုင်း စီမံကိန်း ဧရိယာတစ်ခုလုံးမှာ Meadow Alluvial မြေဆီလွှာ အမျိုးအစား ဖြစ်ပါသည်။



Source: Data from the Land Use Division, Myanmar 2006

ပုံ ၄.၄-၁ : ရန်ကုန်တိုင်းဒေသကြီး၏ မြေဆီလွှာအမျိုးအစားပြ မြေပုံ

၄.၅။ ရာသီဥတုနှင့် မိုးလေဝသ

ရန်ကုန် ရာသီဥတုမှာ အပူပိုင်းမှတ်သုံးရာသီဥတု ဖြစ်ပြီး ပြင်းထန်သည့် မှတ်သုံးရာသီဥတု၊ အပူချိန် မြင့်မားခြင်း၊ မိုးများခြင်း၊ စိုထိုင်းဆမြင့်မားခြင်း စသည့် အင်္ဂါရပ်များ ရှိပါသည်။ နွေရာသီ၊ မိုးရာသီနှင့် ဆောင်း (ခြောက်သွေ့) ရာသီဟူ၍ ရာသီဥတု သုံးမျိုးရှိပါသည်။ နွေရာသီမှာ မတ်လမှ မေလ အလယ်ထိ ဖြစ်ပြီး မိုးများသည့်လများမှာ မေလအလယ်မှ အောက်တိုဘာလ အကုန်အထိဖြစ်ကာ နိုဝင်ဘာလမှ စတင် ကာ ဖော်ဖော်ဝါရီလကုန် အထိမှာ ဆောင်းရာသီ ဖြစ်ပါသည်။ ရန်ကုန်ဒေသ၏ မေလမှ နိုဝင်ဘာလအထိ ရှည်လျားသည့် မိုးရာသီအရ မိုးရေချိန်မှာ (၂၈၃၇ မီလီမီတာ) ရှိပြီး ခြောက်သွေ့ရာသီ ဖြစ်သော နိုဝင်ဘာလမှ ဧပြီလအထိတွင် မိုးရေချိန် အနည်းငယ်သာ (၁၂၀ မီလီမီတာ) ရှိပါသည်။

၄.၆။ ပတ်ဝန်းကျင်ဆိုင်ရာအချက်အလက်များ

၄.၆.၁။ လေထု အရည်အသွေး

လေထုတွင်းသို့ လွှတ်ထုတ်သည့် အဓိကအရင်းမြစ်များမှာ စီမံကိန်းဧရိယာဝန်းကျင်ရှိ စိုက်ပျိုး ရေးဆိုင်ရာ ဟင်းလင်းပွင့်မီးရှို့ခြင်း၊ အိမ်သုံးရန်အတွက် ထင်းမီးရှို့ခြင်း (အပူပေးခြင်း နှင့် ချက်ပြုတ်ခြင်း)၊ စက်မှုလုပ်ငန်းဆိုင်ရာ အစိုးအငွေ့များနှင့် သယ်ယူပို့ဆောင်ရေးမှ ထုတ်လွှတ်မှုများ ဖြစ်ပါသည်။


စီမံကိန်း ဧရိယာ တစ်ခုလုံးအတွက် လေထုအရည်အသွေး အခြေခံအချက်အလက်များမှာ မရှိပါ။ ထို့ကြောင့် အခြေခံအခြေအနေများသိရှိရန် ပတ်ဝန်းကျင်ဆိုင်ရာ အခြေခံအချက်အလက်များ ကောက်ယူ နေစဉ် ကာလအတွင်း သတ်မှတ်ထားသည့် နေရာ ၄ နေရာတွင် အဓိကလေထုအရည်အသွေး ဆိုင်ရာအ ချက်အလက်များ ကောက်ယူသွားမည် ဖြစ်ပါသည်။

၄.၆.၂။ ဆူညံသံနှင့် တုန်ခါမှု

ဆူညံသံ အရင်းအမြစ်မှာ စီမံကိန်းနေရာ မြောက်ဘက် ဆိပ်ကြီးခနောင်တိုချောင်း အနီး ဆိပ်ကမ်း အပါအဝင် တူးမြောင်း အတွင်းရှိသော သင်္ဘောများနှင့် အနီးအနားရှိ အဓိကလမ်းမကြီးမှ ယာဉ်သွားလာမှု များမှ ဖြစ်ပါသည်။ စီမံကိန်းနေရာနှင့် အနီးဆုံးရှိ ဆူညံသံ သက်ရောက်ခံရနိုင်သော ရွာအိမ်ခြေများကို ခွဲခြား ဖော်ထုတ်ထားပါသည်။

၄.၆.၃။ ရေအရည်အသွေး

နယ်ပယ်တိုင်းတာသတ်မှတ်သည့်ကာလအတွင်း ရေအရည်အသွေးဆိုင်ရာ အချက်အလက်များ မရ ရှိနိုင်၍ စီမံကိန်းနေရာဝန်းကျင်ရှိ ရေအရည်အသွေးဆိုင်ရာ အခြေခံအချက်အလက်များ ကောက်ယူရန် စီမံ ကိန်းတစ်ခုလုံးအားခြုံငုံကိုယ်စားပြုသည့် သတ်မှတ်ထားသည့် နေရာ ၆ နေရာ တွင် တစ်ကြိမ်စစ်တမ်း ကောက်ယူမည်ဖြစ်ပါသည်။



ပုံ ၄.၆-၁ : ပတ်ဝန်းကျင်အရည်အသွေးများ စောင့်ကြပ်ကြည့်ရှုစစ်ဆေးမည့် တည်နေရာများပြ မြေပုံ

၄.၆.၄။ လေ့လာတွေ့ရှိချက်များ

လေအရည်အသွေး : လေအရည်အသွေးပြဆန်းစစ်ချက်များတွင် CO, NO₂, NO, PM_{2.5}, PM₁₀, SO₂၊ အပူချိန် နှင့် စိုထိုင်းဆ စသော အခြေခံအချက်အလက်များ ၂၀၁၈ ခုနှစ်တွင် နေရာ ၄ နေရာတွင် တိုင်းတာ ဆန်းစစ်ခဲ့ပါသည်။ တွေ့ရှိချက်များအရ လေအရည်အသွေးပြ ထုတ်လွှတ်မှုများအားလုံးမှာ ဆာလဖိုင်ဒိုင် အောက်ဆိုဒ် ဓာတ်ငွေ့သည် NEQG တန်ဖိုးများ (National Environmental Quality (Emission) Guideline, 2015) ထက် နေရာ ၃ နေရာတွင် ကျော်လွန်နေသည်မှလွဲ၍ အခြားဓာတ်ငွေ့များမှာ ကျော်လွန်နေခြင်းမရှိပါ။ ဆန်းစစ်လေ့လာသူများ၏ တွေ့ရှိချက်အရ ၎င်းနေရာများ တွင်ဆာလဖိုင်ဒိုင် အောက်ဆိုဒ်ဓာတ်ငွေ့ မြင့်တက်နေရသည့် အကြောင်းရင်းများထဲမှတစ်ခုမှာ ယာဉ်သွားယာဉ်လာများပြား လွန်းခြင်းမှ ဖြစ်နိုင်ကြောင်းတွေ့ရှိရပါ သည်။

ဆူညံသံနှင့်တုန်ခါမှု : ဆန်းစစ်လေ့လာချက်များအရ နေ့အချိန်နှင့် ညအချိန် ဆူညံသံအဆင့်များမှာ လူနေအိမ်ခြေနေရာများတွင် ရှိရမည့်တန်ဖိုးများထက် ကျော်လွန်လျက်ရှိကြောင်းတွေ့ရပြီး ထိုသို့ ဖြစ်ရသည့် အကြောင်းရင်းမှာလည်း လေ့လာမှုပြုလုပ်သည့်နေရာများသည် တူးမြောင်းတစ်လျှောက်တွင် စီးပွားရေးလုပ်ငန်းများရှိရာနေရာများဖြစ်ပြီး မော်တော်ယာဉ်များသွားလာမှု မြင့်မားသောနေရာများ ဖြစ်နေပါသည်။

ထို့ကြောင့် အသံဆူညံမှုအဆင့်များအား စက်ရုံအလုပ်ရုံများအတွက် စံသတ်မှတ်ထားချက် (70 dB) နှင့်သာနှိုင်းယှဉ်ဖော်ပြသင့်ပေသည်။ ဆူညံသံအဆင့်မြင့်မားနေသော်လည်း တုန်ခါမှုအဆင့်များမှာ လူနေ

အိမ်ခြေအနီးရှိ လမ်းမများတွင်ရှိရမည့်အဆင့် (ဂျပန်နိုင်ငံစံသတ်မှတ်ချက်) နှင့် နှိုင်းယှဉ်ကြည့်သောအခါ စံသတ်မှတ်ချက် တန်ဖိုးများအောက် လျော့နည်းနေကြောင်း တွေ့ရှိရပါသည်။

ရေအရည်အသွေး : NEQG တွင် မျက်နှာပြင်ရေအရည်အသွေးအတွက် နှိုင်းယှဉ်ဖော်ပြရန် စံသတ်မှတ်ချက်များ မရှိသော်လည်း အခြေခံအချက်အလက်များကောက်ယူထားရှိပြီး စီမံကိန်းဆောင်ရွက်နေစဉ် နှင့် ဆောင်ရွက်အပြီးတွင် ရေအရည်အသွေးတန်ဖိုးများ ပြောင်းလဲမှု ရှိ မရှိအားနှိုင်းယှဉ် စစ်ဆေး သိရှိနိုင်ပါရန် ရည်ရွယ်ပါသည်။

၄.၇။ ဇီဝပတ်ဝန်းကျင်

ပတ်ဝန်းကျင်ဆိုင်ရာအခြေခံအချက်အလက်များကောက်ယူချိန်တွင် ဇီဝမျိုးစုံမျိုးကွဲများကိုလည်း လေ့လာဆန်းစစ်ခဲ့ပါသည်။

၄.၇.၁။ ဒီရေတောမျိုးစိပ်ပင်များ ပျံ့နှံ့ပေါက်ရောက်မှု

ဒီရေတောများအား မြစ်ကြောင်းတစ်လျှောက် ရေရရှိသော ကမ်းရိုးတန်းမြေနှိမ့်နေရာများနှင့် ဒီရေရောက် ကုန်းရေစပ်သောနေရာများတွင် တွေ့ရှိရပါသည်။ ဒီရေပင်ဆိုသည်မှာ သစ်ပင် ၊ ချုံပုတ်ပင် ၊ အုန်းပင် သို့မဟုတ် ခြံစည်းရိုးပင်ကဲ့သို့ အပင်မျိုးဖြစ်ပြီး ယေဘုယျအားဖြင့် တစ်မီတာခွဲလောက်အထိ အမြင့်ရှိတတ်ပြီး ဒီရေပင်ရောက်နိုင်သော ရေငံကမ်းရိုးတန်းဒေသများနှင့် မြစ်ဝှမ်းဒေသများတွင် ပေါက်ရောက်နိုင်ပါသည်။ ဒီရေတောပင်ဆိုသည်မှာ ဒီရေရောက်နေရာများတွင် ပေါက်ရောက်သောအပင်များလည်း အပါအဝင်ဖြစ်ပါသည်။

၄.၇.၂။ အပင်များ

တွံတေးတူးမြောင်းစီမံကိန်းအတွက် လက်တွေ့ကွင်းဆင်းလေ့လာရာတွင် အပင်အမျိုးအစား ၇၆ မျိုး အနက် ၅ မျိုးမှာ စီးပွားရေးအရ အရေးပါသောမျိုးစိပ်များဖြစ်ပါသည်။ ၎င်းတို့အနက် ၂ မျိုး (ပျဉ်းကတိုး နှင့် ပိတောက်) မှာ သစ်မာအမျိုးအစား အုပ်စု ၁ တွင် ပါဝင်ပြီး ကူးသန်းကုန်သွယ်နိုင်သော သစ်မာအမျိုးအစားများဖြစ်ကာ မြန်မာနိုင်ငံ သစ်လုပ်ငန်းအင်တာပရိုက်စ် (MTE) မှ ထုတ်လုပ်နေသော အမျိုးအစားတွင် ပါဝင်ပါသည်။ ကျန်မျိုးစိပ် ၃ မျိုးတွင် ပြည်တွင်းဈေးကွက်ဝင်အပင်များဖြစ်သော ဓနိ ၊ ဝါးနက် နှင့် ငှက်ပျောပင်များ ပါဝင်ပါသည်။

၄.၇.၃။ သတ္တဝါများ

တွံတေးတူးမြောင်းစီမံကိန်းအတွက် လက်တွေ့ကွင်းဆင်းလေ့လာရာတွင် သတ္တဝါအုပ်စုကြီး ၅ ခု အနက် နို့တိုက်သတ္တဝါ မျိုးစိတ် ၅ မျိုး၊ ငှက်မျိုးစိတ် ၅၅ မျိုး၊ တွားသွားသတ္တဝါ ၁၆ မျိုး၊ ကုန်းနေရေနေ

သတ္တဝါ ၁၀ မျိုး၊ ငါးမျိုးစိတ် ၂၃ မျိုး၊ လိပ်ပြာ မျိုးစိတ် ၂၇ မျိုးကို တွေ့ရှိရပါသည်။ ဤသတ္တဝါများအနက် စီးပွားရေးအရ အရေးပါသော Hilsa, Seabass, Pangas Catfish, Croaker, Indian salmon and Monsoon River Prawn ကဲ့သို့သော ရေသတ္တဝါမျိုးစိတ် ၆ မျိုးကို တွေ့ရပြီး အခြားသတ္တဝါမျိုးစိတ်များမှာ စီးပွားရေးအရ အရေးမပါလှပါ။

၄.၇.၄။ ဒီရေတောအပင်များကို ပြန်လည်စိုက်ပျိုးထိန်းသိမ်းခြင်း

ဒီရေတောအပင်များကို ပြန်လည်ထိန်းသိမ်းရေးအတွက် ဆောင်ရွက်ရမည့် လျော့ချရေးနည်းလမ်းများကို ဂရုတစိုက်ဆောင်ရွက်မည်ဖြစ်ပြီး မလွှဲရှောင်သာ၍ မဖြစ်မနေခုတ်လှဲရမည့်အပင်များအတွက်လည်း ငွေကြေးအားဖြင့်သော်လည်းကောင်း၊ လျော်ကြေးပေးချေရပါမည်။

ဖြစ်နိုင်ချေရှိသော အပင်အစားထိုးစိုက်ပျိုးခြင်းလုပ်ငန်းစဉ်ကိုလည်း မျိုးစိတ်တူအပင်များအား အပင်ဖောက်ကာ ဒေသတွင်းတွင် ပြန်လည်စိုက်ပျိုးပေးခြင်းအား စီမံကိန်းပိုင်ရှင်ဖြစ်သော ရေအရင်းအမြစ်နှင့် မြစ်ချောင်းများ ဖွံ့ဖြိုးတိုးတက်ရေး ဦးစီးဌာန (DWIR) ၊ သဘာဝသယံဇာတနှင့် ပတ်ဝန်းကျင်ထိန်းသိမ်းရေး ဝန်ကြီးဌာန နှင့် အကြံပေးအဖွဲ့ဝင်များ ညှိနှိုင်းကာ ဖြစ်နိုင်ချေရှိသောနေရာ ၊ မြင်ကွင်းပသာဒအနေ နှင့် လည်း သင့်တော်မည့် နေရာတွင် ဆောင်ရွက်သွားပါမည်။

၄.၈။ စီမံကိန်းနယ်မြေ ၄ မြို့နယ်၏ လူဦးရေစစ်တမ်း

၄.၈.၁။ တွံတေးမြို့နယ် နယ်နိမိတ်နှင့် လူဦးရေ

တွံတေးမြို့နယ်သည် မြန်မာနိုင်ငံ ရန်ကုန်တိုင်းဒေသကြီး အတွင်းရှိ မြို့နယ်တစ်ခု ဖြစ်ပါသည်။ ရန်ကုန်မြို့ အနောက်ဘက် လှိုင်မြစ် တစ်ဘက်ကမ်းတွင် တည်ရှိပါသည်။ အဓိကမြို့ဖြစ်ပြီး အုပ်ချုပ်မှုဆိုင်ရာ ရုံးစိုက်ရာမြို့လည်းဖြစ်ပါသည်။ တွံတေးတူးမြောင်းမှာ မြန်မာနိုင်ငံတွင် အရှည်ဆုံး လူလုပ်တူးမြောင်း ဖြစ်ပြီး ၃၅ ကီလိုမီတာ အရှည်ရှိကာ တွံတေးမြို့နယ်ကို ဖြတ်လျက် ဧရာဝတီမြစ်နှင့် ရန်ကုန်မြစ်ကို အနီးဆုံးသွားနိုင်သည့် ရေလမ်းခရီး ဖြစ်ပါသည်။ ယင်းတူးမြောင်းကို ပေါင်းကူးထားသည့် တံတားတစ်ခုရှိပြီး တွံတေးတံတားဟု ခေါ်ဆိုပါသည်။

ကျေးရွာ ၂၂၀ အား ဖွဲ့စည်းထားသည့် ကျေးရွာ အုပ်စု ၆၅ စု နှင့် ရပ်ကွက် ၈ ရပ်ကွက်တွင် စုစုပေါင်း အိမ်ထောင်စု စာရင်း ၅၂၃၀၇ ရှိကာ နေထိုင်သူ ၂၂၇၉၅၃ ဦးရှိပါသည်။ အများအားဖြင့် ဗမာလူမျိုး ၇၆% နှင့် ကရင်လူမျိုး ၂၃% ခန့် ရှိပြီး အဓိက ကိုးကွယ်သည့် ဘာသာမှာ ဗုဒ္ဓဘာသာနှင့် ခရစ်ယာန်ဘာသာ ဖြစ်ကာ အစ္စလာမ်နှင့် ဟိန္ဒူ ဘာသာ ကိုးကွယ်သူ အနည်းငယ်သာ ရှိပါသည်။ တွံတေးမြို့နယ်သည် မိသားစုအချို့မှ မျိုးဆက်များစွာ ထိန်းသိမ်းလုပ်ကိုင် လာသည့် အိုးခွက် လုပ်ငန်းများကြောင့် လူသိများပါသည်။ ရန်ကုန်ဒေသ အတွင်း ငါးဖမ်းသည့် ဧရိယာလည်း ဖြစ်ပါသည်။ စိုက်ပျိုးရေးနှင့် တံငါလုပ်ငန်းမှာ လူဦးရေ၏ ပထမ အသက်မွေးဝမ်းကျောင်းမှု အရင်းမြစ် ဖြစ်ပြီး ယင်းနောက်တွင် တူးမြောင်းနှင့် ဆက်စပ်သည့် လုပ်ငန်းများ ဖြစ်ပါသည်။ တူးမြောင်းနှင့် ဆက်စပ်သည့် လုပ်ငန်းများတွင် လုပ်ကိုင်သူမှာ ၁၃၀၀၀ ခန့်ရှိပါသည်။

၄.၈.၂။ ဒလမြို့နယ် နယ်နိမိတ်နှင့် လူဦးရေ

ဒလမြို့နယ်မှာ ရန်ကုန်မြို့ တောင်ဘက်တွင် တည်ရှိပါသည်။ မြောက်လတ္တီကျု ၁၆ ဒီဂရီ ၂၀ မိနစ် နှင့် ၁၆ ဒီဂရီ ၃၀ မိနစ် ကြား နှင့် အရှေ့ လောင်ဂျီကျု ၉၆ ဒီဂရီ ၁၆ မိနစ် နှင့် ၉၆ ဒီဂရီ ၁၈ မိနစ် ကြား တည်ရှိကာ ဧရိယာမှာ ၈၆.၅၁ စတုရန်းမိုင်ရှိပြီး ရန်ကုန်မြို့မှလယ်မှ ဖြတ်သွားလျှင် ရန်ကုန်မြစ် တောင်ဘက်ကမ်းတွင် တည်ရှိပါသည်။ ရပ်ကွက် ၂၃ ရပ်ကွက်နှင့် ကျေးရွာအုပ်စု ၂၃၇ (ကျေးရွာ ၅၀ အပါအဝင်) ဖြင့် ဖွဲ့စည်းထားပြီး အရှေ့ဘက်နှင့် မြောက်ဘက်တွင် ရန်ကုန်မြစ်၊ အနောက်ဘက်တွင် တွံတေးတူးမြောင်းနှင့် တောင်ဘက်တွင် တွံတေးမြို့နယ်တို့ တည်ရှိပါသည်။ အရှေ့မှ အနောက်ဘက်သို့ ၇ မိုင် နှင့် တောင်မှ မြောက်သို့ ၁၀ မိုင် ရှိပါသည်။ ရန်ကုန်မြစ်၏ အရှေ့ဘက်၊ ကော့မှူးမြို့နယ်၏ တောင်ဘက်တွင် ရှိပါသည်။ အနောက်ဘက်တွင် တွံတေးမြို့နယ်နှင့် မြောက်ဘက်တွင် ရန်ကုန်မြစ် ရှိပါသည်။

စုစုပေါင်း လူဦးရေ ၁၅၄၅၆၃ ဦး နှင့် အိမ်ထောင်စု ၃၅၂၂၃ (မတ်လ ၂၀၁၈ အရ) ရှိပါသည်။ ယင်းမြို့ နယ်တွင် နေထိုင်သူ ၉၅% ကျော်မှာ ဗမာ လူမျိုးဖြစ်ပြီး ကရင်နှင့် ရခိုင်လူမျိုးများလည်း နေထိုင်ကြပါသည်။ ကိုးကွယ်မှုပုံစံမှာ တွံတေးမြို့နယ်နှင့် အတူတူ ဖြစ်ပါသည်။ ဒလမြို့နယ်မှာ တွံတေးမြို့နယ်ထက် ဖွံ့ဖြိုးမှု နည်းပါးပြီး စီးပွားရေးဆိုင်ရာအခြေခံအဆောက်အအုံများမှာ ဖွံ့ဖြိုးလာဖို့ ရှိပါသည်။ ဝန်ဆောင်မှုနှင့် ရောင်းချမှု ကဲ့သို့ တတ်ယ အဆင့် လုပ်ငန်းကဏ္ဍများသာ များပါသည်။ တူးမြောင်းနှင့် ဆက်စပ်သည့် လုပ်ငန်း လုပ်ကိုင်မှုမှ ၂၀၅၂၂ ရှိပြီး အချိုးအရ တွံတေး မြို့နယ်ထက် များပြားပါသည်။ အချိုးအစားအရ ပြောရလျှင် ဒလမြို့နယ် တွင် နေထိုင်သူများသည် တူးမြောင်းနှင့် ဆက်စပ်သည့် လုပ်ငန်းများနှင့် အသက်မွေးဝမ်း ကျောင်းမှုမှာ တွံတေးမြို့နယ်ထက် ပိုများပါသည်။

၄.၈.၃။ ဆိပ်ကြီးခနောင်တိုမြို့နယ် နယ်နိမိတ်နှင့် လူဦးရေ

ဆိပ်ကြီးခနောင်တိုမြို့နယ်မှာ သီးခြားကျွန်းတစ်ခုဖြစ်ပြီး ရန်ကုန်မြို့ထဲမှ ဖြတ်သွားလျှင် ရန်ကုန်မြစ် တောင်ဘက်ကမ်းတွင် တည်ရှိပါသည်။ ရပ်ကွက် ၈ခုဖြင့် ဖွဲ့စည်းထားပြီး မြောက်ဘက်တွင် ရန်ကုန်မြစ်၊ အရှေ့ဘက်တွင် တွံတေးတူးမြောင်း၊ တောင်ဘက်နှင့် အနောက်ဘက်တွင် တွံတေးမြို့နယ်တို့ ဝန်းရံလျက် ရှိပါသည်။ ရန်ကုန်မြစ်ကို ဖြတ်ကာ မြို့ထဲသို့ သွားလာရန် တံတား မရှိသောကြောင့် ကျေးလက်ဆန် ကာ ဖွံ့ဖြိုးမှု နည်းပါးလျက် ရှိပါသည်။ မြောက်လတ္တီကျု ၁၆ ဒီဂရီ ၄၅ မိနစ် နှင့် ၁၆ ဒီဂရီ ၄၈ မိနစ် ကြား တည်ရှိပြီး၊ အရှေ့မှ အနောက်သို့ တစ်မိုင်နှင့် တောင်မှ မြောက်သို့ ၂.၃ မိုင်ရှိပါသည်။ အရှေ့ဘက်တွင် ရန်ကုန်မြစ်၊ ဒလမြို့နယ်နှင့် တွံတေးမြို့နယ်၊ အနောက်ဘက်တွင် ကော့မှူးမြို့နယ်၊ တောင်ဘက်တွင် တွံတေးမြို့နယ် နှင့် ဒလမြို့နယ်၊ မြောက်ဘက်တွင် ရန်ကုန်မြစ်နှင့် ကြည့်မြင်တိုင်မြို့နယ် တို့ တည်ရှိပါသည်။

သေးငယ်သည့် မြို့နယ်ဖြစ်သည့် အလျောက် လူဦးရေ ၃၃၉၄၄ ဦး (မတ် ၂၀၁၇) နှင့် အိမ်ထောင်စု ၇၇၇၈ စု ရှိပါသည်။ အဓိကအားဖြင့် ဗမာလူမျိုးများ (၉၅% ခန့်) ဖြစ်ပါသည်။ ကျန် လူမျိုးများမှာ မွန်၊ ကရင်၊ ရခိုင်နှင့် ချင်းလူမျိုးများ ဖြစ်ပါသည်။ အဓိက အသက်မွေးမှုမှာ အရောင်းအဝယ်နှင့် တူးမြောင်းနှင့် ဆက်စပ်သည့် လုပ်ငန်းများ (သင်္ဘောကျင်း လုပ်ငန်း ကဲ့သို့ စသည်) ဖြစ်ပြီး အလုပ်လက်မဲ့နှုန်း (၄% အထက်) မှာ

ဒလနှင့် တွံတေးမြို့နယ် (၂% စီ) ထက် ပိုများပါသည်။ သို့သော်လည်း ပျမ်းမျှ ဝင်ငွေ ပမာဏမှာ တွံတေး နှင့် ဒလမြို့နယ်ထက် သိသိသာသာ မြင့်မားပါသည်။

၄.၈.၄။ ကြည့်မြင်တိုင်မြို့နယ် နယ်နိမိတ်နှင့် လူဦးရေ

ကြည့်မြင်တိုင်မြို့နယ်မှာ ရန်ကုန်မြို့၏ အနောက်ဘက်တွင် တည်ရှိပါသည်။ မြောက်လတ္တီကျု ၁၆ ဒီဂရီ ၄၆ မိနစ် ၅၁ စက္ကန့် နှင့် ၁၆ ဒီဂရီ ၄၉ မိနစ် ၄၅ စက္ကန့် ကြား နှင့် အရှေ့ လောင်ဂျီကျု ၉၆ ဒီဂရီ ၆ မိနစ် ၇၅ စက္ကန့် နှင့် ၉၆ ဒီဂရီ ၇ မိနစ် ၄၈ စက္ကန့် ကြား တည်ရှိပါသည်။ အရှေ့မှ အနောက်ဘက်သို့ ၂ မိုင် နှင့် တောင်မှ မြောက်သို့ ၂.၀၈ မိုင် ရှိပါသည်။ စုစုပေါင်းဧရိယာ အကျယ်အဝန်းမှာ ၄,၈၀၈ စတုရန်း မိုင် ဖြစ်ပါသည်။ အရှေ့ဘက်တွင် စမ်းချောင်းမြို့နယ်နှင့်အလုံမြို့နယ် ၊ တောင်ဘက်တွင် ဆိတ်ကြီးခနောင်တို မြို့နယ်များနှင့် နယ်နိမိတ်ထိစပ်လျက်ရှိပါသည်။ မြောက်ဘက်တွင် ကမာရွတ်မြို့နယ် နှင့် လှိုင်သာယာ မြို့နယ် တည်ရှိပါသည်။

ကြည့်မြင်တိုင်မြို့နယ်သည် ပင်လယ်ရေမျက်နှာပြင်အထက် ၃၅ ပေ အမြင့်တွင် တည်ရှိပါသည်။ ကြည့်မြင်တိုင်မြို့နယ်တွင် မြစ်ချောင်းများ အနည်းငယ်သာရှိပါသည်။ ချောင်းအများစုမှာ မြောက်ဘက်မှ တောင်ဘက်သို့ စီးဆင်းကြပါသည်။ မြို့နယ်အတွင်း ထင်ရှားသည့်မြစ်မှာ လှိုင်မြစ်ဖြစ်ပြီး၊ မြို့နယ်အ လယ်တွင် မြောက်ဘက်မှတောင်ဘက်သို့ စီးဆင်းပါသည်။ အရှေ့ဘက်တွင် ပန်းလှိုင်မြစ်ရှိပြီး အနောက် ဘက်မှ အရှေ့ဘက်ရှိ ရန်ကုန်မြစ်သို့ စီးဝင်ပါသည်။ နွေရာသီတွင် ရန်ကုန်မြစ်ရေသည် ဆားငံရေဝင်သော ကြောင့် သောက်သုံး၍ မရနိုင်သလို စိုက်ပျိုးရေးတွင်လည်း အသုံးပြု၍မရနိုင်ပါ။ ပန်းလှိုင်မြစ်သည် ၃ ပေမျှ သာနက်ပြီး လှေများသွားလာ၍ မရနိုင်ပါ။

၅။ ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ချက် နည်းလမ်းအသွယ်သွယ်

၅.၁။ ထိခိုက်မှုဆန်းစစ်ချက်

ထိခိုက်မှုဆန်းစစ်ချက်လုပ်ငန်းစဉ်တွင် စီမံကိန်း၏အဓိကလုပ်ငန်းအစိတ်အပိုင်းများ နှင့် ဆက်စပ် ရာလုပ်ငန်းများအား စီမံကိန်းကာလတစ်လျှောက်လုံးတွင် စနစ်တကျ အကဲဖြတ်ဆန်းစစ်ခြင်းများ ပါဝင်ပါ သည်။ ဆန်းစစ်ချက်လုပ်ငန်းစဉ်တွင် အောက်ပါလုပ်ငန်းစဉ်များအား အဓိကထားထည့်သွင်း စဉ်းစားသွား မည် ဖြစ်ပါသည်။ (ရည်ညွှန်းချက်။ ယေဘုယျပတ်ဝန်းကျင်ဆိုင်ရာထိခိုက်မှုဆန်းစစ်ချက်မူဝါဒ ၊ ၂၀၁၇)

- နယ်ပယ်သတ်မှတ်တိုင်းတာခြင်း နှင့် ကနဦးဆန်းစစ်ခြင်း
- အခြေခံအချက်အလက်များကောက်ယူခြင်း
- စီမံကိန်းအခြားနည်းလမ်းနှင့် ဒီဇိုင်း
- အဓိကကျသောကဏ္ဍများနှင့် တန်ဖိုးထားထိန်းသိမ်းရမည့်ဂေဟစနစ်အချက်အလက်များ အပေါ်

ထိခိုက်နိုင်ဖွယ်ရာများကို ဆန်းစစ်အကဲဖြတ်ခြင်း

- ထိခိုက်မှုများကို ခွဲခြားဆန်းစစ်အကဲဖြတ်ခြင်း
- ကျန်ရှိနိုင်သော ထိခိုက်မှုများကို ခွဲခြားဆန်းစစ်အကဲဖြတ်ခြင်း
- လျော့ချခြင်းများနှင့်စောင့်ကြပ်စစ်ဆေးခြင်း

ထိခိုက်မှုများကို ခြုံငုံဆန်းစစ်အကဲဖြတ်ချက်များအား ဇယား ၅-၁ တွင် စာရင်းပြုစုထားပြီး ဆောက်လုပ်ရေးကာလအတွင်း ဆိုးရွားစွာထိခိုက်မှုများနှင့် လုပ်ငန်းလည်ပတ်ချိန်တွင် ရရှိလာမည့် ရရှိမည့် အကျိုးခံစားခွင့်များကို တင်ပြထားပါသည်။

ဇယား ၅-၁ : ဆောက်လုပ်ရေးကာလနှင့် လုပ်ငန်းလည်ပတ်စဉ်ကာလအတွင်း ပတ်ဝန်းကျင်နှင့် လူမှုရေးရာ ထိခိုက်မှုများကို ခြုံငုံသုံးသပ်ချက်များ

ဆန်းစစ်ချက်များ	ဖော်ပြချက်များ	M	D	E	P	ဆောက်လုပ်ရေးကာလ	လျော့ချရေး နည်းလမ်းများ	
						ခန့်မှန်းသက်ရောက်မှု	လို	မလို
လေထုထဲသို့ ထုတ်လွှတ်မှု	ဆောက်လုပ်ရေးလုပ်ငန်းများသည် ဖုန်မှုန့်နှင့် ရှိရင်းစွဲ မြင့်မားနေသော ဆာလဖိုင်ဒိုင် အောက်ဆိုဒ်တို့ကို ဖြစ်ပေါ် စေနိုင်ပါသည်။ ဆောက်လုပ်ရေးလုပ်ငန်းနှင့် အနီးနားတွင် ရှိနေသောသူများကို သက်ရောက်နိုင်ဖွယ် ရာ ရှိပါသည်။	4	2	1	3	21 (-)	✓	
ကမ္ဘာကြီးပူဇွန်စေသော ဓာတ်ငွေ့များ	ဖန်လုံအိမ်အာနိသင်ထုတ်လွှတ်မှုနှင့် ပတ်သက်သော ဓာတ်ငွေ့များ မထွက်ရှိနိုင်ပါ။	1	2	1	1	4		✓
ဆူညံသံနှင့် တုန်ခါမှု	အသံဆူညံသော စက်ပစ္စည်းများလည်ပတ်မောင်းနှင် နေစဉ်တွင် အနီးအနားရှိသူများမှာ ဆူညံသံနှင့် တုန်ခါမှု ကို ခံစားရ နိုင်ဖွယ်ရာရှိပြီး အကြားအာရုံ ချို့တဲ့ခြင်း၊ စိတ်ဖိစီးမှု နှင့် အိပ်မပျော်သော ရောဂါများ ခံစားရနိုင်ပါ သည်။	4	2	1	4	28 (-)	✓	
ရေအရည်အသွေး	ဆောက်လုပ်ရေးကာလတွင် ရေတိုက်စားမှုများ ရေစီးမှု များကြောင့် ရေနောက်ကျိုမှု နှင့် ရေအရည်အသွေးကို	4	2	1	3	21 (-)	✓	

	ထိခိုက်နိုင် စေပါသည်။							
အစိုင်အခဲ စွန့်ပစ်ပစ္စည်းများ	ဆောက်လုပ်ရေးလုပ်ငန်းမှ စွန့်ပစ်ပစ္စည်းနှင့် အန္တရာယ်ရှိ စွန့်ပစ်ပစ္စည်းများကို သင့်လျော်စွာ စီမံစ၍ စွန့်ပစ်ခြင်း မရှိပါက ရေ နှင့် မြေဆီလွှာကို ညစ်ညမ်းစေနိုင်ပါသည်။	3	2	1	3	18 (-)	✓	
ဖိပ်မျိုးစုံမျိုးကွဲ (အပင်၊ သတ္တဝါ နှင့် သစ်တော)	ဂေဟစနစ်၊ ကာကွယ်တောကြိုးဝိုင်းဧရိယာလက်ရှိ စီမံကိန်းနယ်နိမိတ်တွင် ဒီရေတောများ တွေ့ရပါသည်။	4	2	2	4	32 (-)	✓	
ကမ္ဘာကြီးပူဇွန်လောမူ	စီမံကိန်း လုပ်ငန်းသည် ကမ္ဘာကြီးပူဇွန်စေသော အကြောင်းရင်းများနှင့် ပတ်သက် ဆက်နွယ်မှု မရှိပါ။	1	2	1	1	4		✓
မြေဆီလွှာ	ROW ဥပဒေ မီတာအတွင်းရှိ အပင်များ ကို ရှင်းလင်းရမည် ဖြစ်သောကြောင့် မြေဆီလွှာ ပြိုဆင်းမှုများကို ဖြစ်နိုင်ပါ သည်။	2	2	1	3	15 (-)		✓
ပထဝီအနေအထားနှင့် မြေ	စီမံကိန်းလုပ်ငန်းများမှာ မြေပထဝီအနေအထားကို ပြောင်းလဲမသွားစေနိုင်ပါ။	1	2	1	1	4		✓
မြေအသုံးချမှု	စီမံကိန်း ROW ဥပဒေ မီတာအတွင်းရှိ တူးမြောင်းမြေနေရာ မှာ ရေကြီးမှုကို ကာကွယ်ရန် တာရိုးတည်ဆောက်ခြင်း နှင့် စီမံကိန်းနယ်နိမိတ်တစ်ဝိုက် စီးပွားရေးလုပ်ငန်းများ ကြောင့် ပြောင်းလဲနိုင်ဖွယ်ရာ ရှိပါသည်။	3	2	1	3	18 (-)	✓	

ရေပြင်လေ့လာရေး	ရေပြင်လေ့လာရေးများကိုလည်း မထိခိုက်နိုင်ပါ။	1	2	1	1	4		✓
သားရဲတိရစ္ဆာန်	လူနေအိမ်ခြေများနှင့် နီးစပ်သောကြောင့် သားရဲများ မတွေ့ရပါ။	1	2	1	1	4		✓
ကြီးဝိုင်းဧရိယာ	စီမံကိန်းကြောင့် ကာကွယ်တောများအပေါ်တွင် ထိခိုက်မှု မရှိနိုင်ပါ။	1	2	1	1	4		✓
အပန်းဖြေစခန်း	စီမံကိန်း နယ်နိမိတ်တွင် အပန်းဖြေစခန်းများလည်း မရှိပါ။	1	2	1	1	4		✓
မြင်ကွင်းပသာဒ	စီမံကိန်း မီတာ ၃၀ အတွင်းရှိ လမုပင်များအား ခုတ်ထွင်ရှင်း လင်းရမည်ဖြစ်သောကြောင့် မြင်ကွင်းအနည်းငယ် ပြောင်းလဲသွားနိုင်ပါသည်။	3	2	1	3	18 (-)	✓	
ယဉ်ကျေးမှုအမွေအနှစ်	စီမံကိန်း မီတာ ၃၀ အတွင်းတွင် ယဉ်ကျေးမှု အမွေအနှစ် အဆောက်အဦများ မရှိပါ။	1	2	1	1	4		✓
လူမှုစီးပွား	ဆန္ဒမပါသော ပြောင်းရွှေ့မှု စီမံကိန်းဆောက်လုပ်ရေး နေရာများတွင် မြေယာညှိနှိုင်းမှု နှင့် ဆန္ဒမပါသော ပြောင်းရွှေ့မှုများ ကြုံတွေ့ရနိုင်ပါသည်။	4	4	3	5	55 (-)	✓	
သဘာဝ ဘေးအန္တရာယ်	စီမံကိန်းလုပ်ငန်းများကြောင့် မည်သည့်သဘာဝဘေးအန္တရာယ်နှင့်မျှ ပတ်သက်ဆက်သွယ်မှု မရှိပါ။ နှစ်စဉ် ရေကြီးမှု သဘာဝဘေးအန္တရာယ်ပင် လျော့ပါးသက်သာ	1	2	1	1	4		✓

	စေနိုင်ပါသည်။ ကောင်းကျိုးများသာ ဖြစ်မည်ဟု ယူဆနိုင်ပါသည်။							
လုပ်သားများ ကျန်းမာရေး	ဆောက်လုပ်ရေးလုပ်ငန်းမှ ဖုန်မှုန့်များ ၊ အသံဆူညံမှုများကြောင့် လုပ်သားများကျန်းမာရေးထိခိုက်နိုင်ပါသည်။	3	2	4	3	27 (-)	✓	
လူထုကျန်းမာရေး	စီမံကိန်းဆောက်လုပ်ရေးဧရိယာအနီးတစ်ဝိုက်တွင် နေထိုင်သူများအနေဖြင့် ဆောက်လုပ်ရေးမှ ဖုန်မှုန့်များ ၊ အသံဆူညံမှုများ ယာယီကြုံတွေ့ရဖွယ် ရှိပါသည်။ ထို့အပြင် နိုင်ငံခြားသားများ၊ ပြင်ပနယ်များမှ ရောက်ရှိလာသော လုပ်သားများကြောင့် လူမှုရေး စိတ်ဖိစီးမှုအနည်းငယ် ကြုံတွေ့နိုင်ပါသည်။	3	2	1	3	18 (-)	✓	

ဆန်းစစ်ချက်များ	Descriptions	M	D	E	P	စီမံကိန်းလည်ပတ်စဉ်ကာလ	လျော့ချရေးနည်းလမ်းများ	
							လို	မလို
သဘာဝ ဘေးအန္တရာယ်	စီမံကိန်းတွင် မြစ်ကြောင်းထိန်းသိမ်းရေး ၊ ရေထိန်းနံရံနှင့်ရေကြီးမှု ကာကွယ်ရေး ဆောက်လုပ်မှုလုပ်ငန်းများကြောင့် ရာသီဥတု လွန်ကဲချိန်များတွင် ဖြစ်တတ်သော ဒေသတွင်း နှစ်စဉ်ရေကြီးမှုမှာ လျော့ပါးသက်သာသွားနိုင်ပါသည်။	4	4	3	5	55 (+)		✓
လူမှု အကျိုးစီးပွား	ဒေသခံများအနေဖြင့် ဆောက်လုပ်ရေးလုပ်ငန်းများ ၊ ကုန်းတွင်းရေကြောင်းခရီးသွားလာမှုများမှတစ်ဆင့် အလုပ်အကိုင်အခွင့်အလမ်းများ ရရှိနိုင်စေပြီး လူမှုစီးပွားဘဝများ ဖွံ့ဖြိုးတိုးတက်လာစေနိုင်ပါသည်။ တွံတေးတူးမြောင်းဘက်စုံဖွံ့ဖြိုးတိုးတက်ရေး စီမံကိန်းကြောင့် ရေကြောင်းခရီးသွားလာရာတွင် ရေကြောင်းသွားလာရေး စနစ်ကောင်းမွန်လာပြီး ယခင်ထက် လုံခြုံစိတ်ချစွာဖြင့် သွားလာရမည်ဖြစ်သော ကြောင့် အသက်ဘေးအန္တရာယ် ဖြစ်ပွားမှုများလျော့နည်းလာနိုင်ပြီး ဒေသတွင်း ဖွံ့ဖြိုးတိုးတက်စေနိုင်ပါသည်။	4	4	2	5	50 (+)		✓

မြေဆီလွှာ	စီမံကိန်းတွင် ကမ်းထိန်းနံရံ တည်ဆောက်မှု ပါဝင်သောကြောင့် တူးမြောင်းတစ်လျှောက်တွင် မြေပြိုမှု များ နောက်ထပ်ကြုံတွေ့ရနိုင်ဖွယ် မရှိတော့ပါ။	3	4	1	4	32 (+)		✓
ပြည်သူလူထုကျန်းမာရေး	ဒေသတွင်း နေထိုင်သူ ပြည်သူများအနေဖြင့် စီမံကိန်း၏ CSR လုပ်ငန်းအကောင်အထည်ဖော်ဆောင်ရွက်မှုများမှ တဆင့် ဆေးဝါးကုသရေးနှင့် သက်ဆိုင်သော စောင့်ရှောက်မှု အစရှိသော ကောင်းကျိုးများအား လက်ခံရဖွယ် ရှိပါသည်။	3	4	3	3	30 (+)		✓


(+)= Positive Impact

(-) = Negative Impact

No Remark (+ nor -) = Neutral

<15 = No Impact

Overall event magnitude is scored from low (15) to very high (>60) by adding the individual parameter scores:



၅.၂။ လျှော့ချရေးအစီအမံများ

ဆောက်လုပ်ရေးကာလတွင် သဘာဝ ပတ်ဝန်းကျင်နှင့်လူမှုရေးရာထိခိုက်မှုများကို လျှော့ချရေး အစီအမံများအား ပတ်ဝန်းကျင်နှင့်လူမှုရေးရာထိခိုက်မှုများကိုစီမံခန့်ခွဲမှုအစီအစဉ်အောက်တွင် ထားရှိ ဆောင်ရွက်သွားမည် ဖြစ်ပါသည်။ အဓိကကျသော လျှော့ချရေးအစီအမံများအား ဇယား ၅-၂ တွင် ထည့်သွင်းဖော်ပြထားပါသည်။

ဇယား ၅-၂ : အကြို-ဆောက်လုပ်ရေးနှင့် ဆောက်လုပ်ရေးကာလ လျှော့ချရေးအစီအစဉ်များ

အဆင့်	လုပ်ငန်းများ	လျှော့ပါးရေး အစီအမံများ
မဆောက်လုပ်မီ	ROW အတွက် ပုဂ္ဂလိက နှင့် ပြည်သူပိုင် မြေ ရယူမှု	(တည်နေရာနှင့် ဒီဇိုင်းရွေးချယ်မှု၊ ROW ထိန်းညှိခြင်း) အဆိုပြု မြစ်ကမ်း ထိန်းညှိမှုသည် အသေးစိတ် ဒီဇိုင်းကာလအဆင့် တွင်လက်ရှိ တူးမြောင်းလိုင်း၊ နေထိုင်သည့် နေရာများနှင့် လမ်းများအား ထည့်သွင်း စဉ်း စားခြင်းဖြင့် လူမှုရေးနှင့် ပတ်ဝန်းကျင်ဆိုင်ရာ သက်ရောက်မှုများကို လျော့ နည်းစေနိုင်ပါသည်။
		[မြေယာ ရယူမှုနှင့် ပြန်လည်နေရာခြင်း ဆောင်ရွက်မှု အစီအစဉ် (LARAP)] မြေ ရယူမှုမမီက၊ ဒေသနေလူထုနှင့် လူဦးရေ၏ ရုပ်ပိုင်းဆိုင်ရာနှင့် စီးပွားရေး ဆိုင်ရာ ကမောက်ကမဖြစ်မှုဆန်းစစ်ခြင်း၊ LARAP စတင်ခြင်း နှင့် အချိန်မှီ အကောင်အထည်ဖော် ဆောင်ရွက်ခြင်း
During Construction	လေထု ညစ်ညမ်းမှုနှင့် ဆူညံသံ	<ul style="list-style-type: none"> - သက်တမ်းလွန် ဆောက်လုပ်ရေး ပစ္စည်းများ အသုံးမပြုခြင်း။ - ဆောက်လုပ်ရေး စက်ပစ္စည်းများ အချိန်မှန် ထိန်းသိမ်းဆောင်ရွက်ခြင်း။ - ဆောက်လုပ်ရေးနှင့် သယ်ယူပို့ဆောင်ရေး အတွက် ယာဉ်များကို အသုံးပြု မှု နှင့် ထိန်းသိမ်းပြုပြင်ခြင်းကို ပုံမှန် စုံစမ်းခြင်းနှင့် ကြီးကြပ်ခြင်း။ - သယ်ယူပို့ဆောင်သည့် ကာလအတွင်းမြေကြီးများ၊ ကျောက်များ ၊ သဲများ ပြုတ်ကျခြင်းမှ ရှောင်ရှားရန် ယာဉ်များအား အမြဲ ဖုံးအုပ် သယ်ဆောင်ခြင်း ၊ ဆောက်လုပ်ရေး ပစ္စည်းများ သို့မဟုတ် စွန့်ပစ်ပစ္စည်းများ အား ကိရိယာ၏ သယ်ဆောင်နိုင်စွမ်းအရသာ သယ်ဆောင်ခြင်း။ - ရွာများ သို့မဟုတ် လူဦးရေ ထူထပ်သည့်နေရာများတွင် ည ၁၀း၀၀ နာရီ မှ နံနက်၅း၀၀နာရီအထိ ဆောက်လုပ်ရေးလုပ်ငန်းများ ဆောင်ရွက်မမှ ရှောင်ရှားခြင်း။ - လူနေသည့် ဧရိယာအတွင်း ကားဟွန်း အသုံးပြုမှု လျှော့ချခြင်း။ - ရာသီဥတုပူခြင်း၊ ခြောက်သွေ့ခြင်းနှင့်လေတိုက် နေစဉ်အတွင်း ဆောက် လုပ် ရေးနေရာအတွင်းနှင့် အနီးတစ်ဝိုက်ကို ရေမကြာခဏ ဖြန်းခြင်း။ - မြေကြီးနှင့် ကျောက်များ ထားရှိသည့်နေရာမှ၂၀၀ မီတာ အချင်းဝက် အ တွင်းရှိ သွားလာသည့် လမ်းများအား သန့်ရှင်း ထိန်းသိမ်းခြင်း။
	ရေဝန်းကျင်	<ul style="list-style-type: none"> - စွန့်ပစ်ပစ္စည်းများ မြေမြုပ်မှု သို့မဟုတ် မြစ် အတွင်းသို့ စွန့်ပစ်မှုမှ တားမြစ်

		<p>ခြင်း။</p> <ul style="list-style-type: none"> - ရွံ့ သို့မဟုတ် စွန့်ပစ်ဆီများကြောင့် မြေနှင့် မြစ်များညစ်ညမ်းခြင်းမှ ကာကွယ်ရန် ဆောက်လုပ်ရေး ယာဉ်များ သို့မဟုတ် စက်ပစ္စည်းများ စိုက်ပျိုးရေးဧရိယာများ အနီး သန့်ရှင်းရေးလုပ်မှုကို တားမြစ်ခြင်း။ - ရေကြီးရေလျှံစဉ်အတွင်း ပတ်ဝန်းကျင်ဆိုင်ရာ ညစ်ညမ်းမှုမှာ ကာကွယ်ရန် ဓာတုပစ္စည်းများ၊ ကိရိယာများနှင့် ဆောက်လုပ်ရေးပစ္စည်းများအား ကုန်းမြေမြင့်တွင် သိုလှောင်ခြင်း။ - သိုလှောင်ပစ္စည်းများအား ဖုံးအုပ်ထားခြင်း သို့မဟုတ် ခွဲခြားထားခြင်း၊ ပစ္စည်းများ ရေနှင့် စီးပျော့ခြင်းမှ တားဆီးရန် ဟင်းလင်းဖွင့် သိုလှောင်မှုများ အနီး ဘေးထွက်မြောင်းများ ထားရှိခြင်း။ - ယာယီဆောက်လုပ်ရေး တန်းလျားများအတွက် အခြေခံသန့်ရှင်းရေး အဆောက်အဦများ၊ ယာယီ အိမ်သာများစသည့် တို့အား စီမံခန့်ခွဲရန် အဖွဲ့များ ခန့်ထားခြင်း။
အစိုင်အခဲ စွန့်ပစ် ပစ္စည်းများ		<ul style="list-style-type: none"> - အစိုင်အခဲ စွန့်ပစ် ပစ္စည်းများအနီးအနားရှိဧရိယာ များနှင့် ရွာများသို့ မစွန့်ပစ် စေရန် လျင်လျင်မြန်စွာနှင့် သင့်လျော်စွာ သယ်ယူပို့ဆောင်ခြင်းနှင့် ပြုပြင် ဆောင်ရွက်ခြင်း။ - သတ်မှတ်ထားသည့် နေရာတွင်မြေကြီးများနှင့် ကျောက်များအား သိုလှောင်ခြင်း။ - လက်ရှိ သဘာဝပေါက်ပင်များ ရှင်းလင်းခြင်း၊ မြေသိပ်ခြင်းနှင့် မြေ ယာရှုခင်းများ ပြန်လည် ထိန်းသိမ်းခြင်း အတွက်စွန့်ပစ်ပစ္စည်း စွန့်ပစ်သည် . နေရာ ပြင်ဆင်ခြင်း။ - ရေ၊ မြေဆီလွှာ၊ ကောက်ပဲသီးနှံ စသည့် တို့အတွက် ညစ်ညမ်းခြင်းမှ ကာကွယ်ရန် အတားအဆီး အလွှာ ထည့်သွင်းခြင်း။ - သယ်ယူပို့ဆောင်ခြင်းအတွက် ဝန်ပို့တင်ခြင်းနှင့် စွမ်းဆောင်ရည် မလုံလောက်သည့် ယာဉ်များအား ခွင့်မပြုခြင်း။ - ယာယီ ဆောက်လုပ်ရေး တန်းလျားများ စီမံခန့်ခွဲခြင်း - အခြေခံ သန့်ရှင်းရေး အဆောက်အဦများ ဖြည့်ဆည်းပေးခြင်း - စွန့်ပစ်ပစ္စည်းများ နေ့စဉ် စုဆောင်း သိမ်းဆည်းရန်စွန့်ပစ်ပစ္စည်းများ ထိန်းသိမ်းသည့် အဖွဲ့အစည်းများ ငှားရမ်းကာစွန့်ပစ်ပစ္စည်းများအတွက် လိုအပ်သည့် အထောက်အပံ့ပစ္စည်းများ ပြင်ဆင်ခြင်း။
ဒေသခံ လူထု		<ul style="list-style-type: none"> - ဒေသခံ နေထိုင်သူများနှင့် ပဋိပက္ခဖြစ်ခြင်းများ လျော့နည်းစေရန် ဆောက်လုပ်ရေး လုပ်သားများအား လမ်းညွှန်ချက် ပေးသင့်ပါသည်။ - ပြည်သူ့ ကျန်းမာရေးနှင့် ဘေးအန္တရာယ် ကင်းရှင်းရေး အတွက် ကျန်းမာရေး အပေါ်သက်ရောက်မှုများနှင့် ဘေးအန္တရာယ်များ လျော့နည်းစေ ရန် အကြံပေးမှ ဆောက်လုပ်ရေး လုပ်သားများအား အစီအမံ လမ်းညွှန်ချက်များ ပေးသင့်ပါသည်။

		<ul style="list-style-type: none"> - ဆောက်လုပ်ရေး ဆက်စပ် ဘေးအန္တရာယ် ကင်းရှင်းရေးနှင့် အခြား စိုးရိမ်ပူပန်မှုများအား အချိန်မီ လျှော့ချနိုင်ရန် ထိရောက်သည့်မကျေနပ်မှု ဖြေရှင်းရေး ယန္တရားကို စတင်သင့်ပါသည်။ - ဆောက်လုပ်ရေးနေရာနှင့် ဆက်စပ် အဆောက်အဦများ၊ အလုပ်သမားများ၏ လုပ်ငန်းဆောင်ရွက်မှုများ အတွက် လိုအပ်သည့် ပတ်ဝန်းကျင်၊ ကျန်းမာရေးနှင့် ဘေးအန္တရာယ် ကင်းရှင်းရေး သတ်မှတ်ချက်များအား ထားရှိခြင်း
ဘေးအန္တရာယ် ကင်းရှင်းရေး		<ul style="list-style-type: none"> - ခွင့်ပြုချက်မရှိသည့် လူများ ချည်းကပ်ခြင်းမှ တားမြစ်ရန် ဆောက်လုပ်ရေး နေရာ ဝန်းကျင်အား ခြံခတ်ခြင်း သတိပေး ဆိုင်းဘုတ်များ တပ်ဆင်ခြင်း - လစဉ်အစီရင်ခံစာအတွက်တာဝန်ယူဆောင်ရွက်မည့် ဝန်ထမ်းခန့်ထားခြင်း နှင့် ပတ်ဝန်းကျင်ဆိုင်ရာ သက်ရောက်မှုများ လျှော့ချခြင်း။ - လုပ်ငန်းခွင် ဘေးအန္တရာယ် ကင်းရှင်းရေး အတွက် စည်းရုံးရေး ဆောင်ပုဒ်များ ထားရှိခြင်း။ - ဆောက်လုပ်ရေး နေရာ အတွင်း ယာဉ်များ အရှိန်လျှော့ရန် ဆိုင်းဘုတ်များ ထားရှိခြင်း။ ဆောက်လုပ်ရေးပစ္စည်းများတင်ချရန်မောင်းနှင်သူများအား လမ်းညွှန်ရန် အတွက် တာဝန်ရှိ ဝန်ထမ်း ခန့်ထားခြင်း။ - ညအချိန်တွင် လိုအပ်သည့် အလင်းရောင် ဖြည့်စည်းပေးခြင်း။ - ယာဉ်၏ဆောင်ရွက်နိုင်စွမ်းထက် ဆောင်ရွက်ခြင်းအား တားမြစ်ခြင်း ၊ အထူးသဖြင့် လမ်းပေါ်သို့ ကုန်ပစ္စည်းများ မကျစေရန် စစ်ဆေးခြင်း။ - ဖိနပ်များ၊ လက်အိတ်များနှင့် အရေးပေါ်သုံး ဆေးဝါးများ စသည့် တစ်ကိုယ်ရည်သုံး အကာအကွယ် ပစ္စည်းများ ဖြည့်ဆည်းပေးခြင်း။ - သန့်ရှင်းရေးနှင့် လုပ်ငန်းခွင် ဘေးအန္တရာယ် ကင်းရှင်းရေး အသိပညာများ ညွှန်ကြားထား သင့်ပါသည်။ - မီးဘေးအန္တရာယ် ကင်းရှင်းရေးအတွက် တင်းကြပ်စွာ ညွှန်ကြားထားခြင်း။ - ဓာတ်ဆီကဲ့သို့ မီးဘေး အန္တရာယ် မြင့်မားသည့် ပစ္စည်းများအား မီးဖို၊ ဂဟေဆက်ခြင်းစသည့်မီးလောင်စေနိုင်သည့် အရင်းမြစ်များမှ အဝေးတွင် သိုလှောင်ခြင်း။ - မီးဘေးသတိပေး ဆိုင်းဘုတ်များ တပ်ဆင်ခြင်း။ - လောင်စာများအားသင့်လျော်သည့် ပုံးများဖြင့် သိုလှောင်ပြီးယိုစိမ့်မှု မရှိစေရန် စစ်ဆေးခြင်း။ - လောင်စာဖြည့်သည့် ကိရိယာ အနီး သင့်လျော်သော ယိုစိမ့်မှု ကာကွယ်သည့် အထောက်အပံ့ ပစ္စည်းများ ထောက်ပံ့ခြင်း။ - စွန့်ပစ် ဆီသိုလှောင်ရုံ အပေါ်တွင် အမိုး တပ်ဆင်ခြင်း။ - ဆောက်လုပ်ရေး အချိန်ဇယား၊ စီမံကိန်း အမည်၊ ဆောင်ရွက်သူ အမည်နှင့် ဆက်သွယ်ရန် နံပါတ်များ မှတ်သားခြင်းနှင့် ရည်ရွယ်ချက်များအား ဆိုင်းဘုတ်ဖြင့် ဖော်ပြခြင်း။

		<ul style="list-style-type: none"> - သယ်ယူပို့ဆောင်ခြင်းနှင့် ဆောက်လုပ်ရေး ပစ္စည်းများ တင်ချခြင်းကို ရုံးတက်ရုံးဆင်းချိန်တွင် ရှောင်ရှားခြင်း။ - ဆောက်လုပ်ရေး လုပ်ငန်းများမှ အများပြည်သူ သွားလာမှုအား ပိတ်ဆို့ပါက လမ်းသွားလမ်းလာများအားယာယီလမ်းပေးခြင်း နှင့် အခြား သယ်ယူပို့ဆောင်ခြင်းများကို ဖြည့်ဆည်း သင့်ပါသည်။ - ဆောက်လုပ်ရေးပစ္စည်းများအား သွားလာမှုနည်းပါးသည့် နေရာတွင် သိုလှောင်ခြင်း။ - သွားလာမှုအား အနှောင့်အယှက်မဖြစ်စေရန် ယာယီဆောက်လုပ်ရေးပစ္စည်းများအား ၂၄နာရီ အတွင်း ဖယ်ရှားခြင်း။ - သယ်ယူပို့ဆောင်ခြင်းကြောင့် ပျက်စီးသွားသည့် လမ်းများအား ပြန်လည် ပြင်ဆင်ခြင်း။
	ဂေဟစနစ်	<ul style="list-style-type: none"> - တူးထားသည့် တွင်းများရှင်းလင်းခြင်း၊ မြေမျက်နှာပြင် ညှိခြင်းနှင့် ရေကြီးမှု ကာကွယ်ရန်။ တာရိုးစီခြင်းများ ဆောင်ရွက်ချိန်တွင် ရေလောင်း ပြုပြင်မှုများ ဆောင်ရွက် ခြင်း။ - စီမံကိန်းဧရိယာအား နေရင်း ဒီဇေယာ ကာကွယ်ရေး အစီအမံများ အကောင်အထည်ဖော် ဆောင်ရွက်ခြင်း။
လုပ်ငန်းလည်ပတ်သည့် ကာလ		<ul style="list-style-type: none"> - ဆောက်လုပ်ရေးလုပ်ငန်းများ ပြီးစီးချိန်တွင် ကောင်းမွန်သည့်သက်ရောက်မှုများရရှိနိုင်ပြီး ရေရှည်တွင် ဆိုးကျိုးသက်ရောက်မှုများ မရှိနိုင်ဟု ခန့်မှန်းရပါသည်။ သို့သော်လည်း လူဦးရေများ တိုးပွားလာခြင်းကြောင့် စွန့်ပစ်ပစ္စည်းနှင့် စွန့်ပစ်ရေများ များပြားလာခြင်းနှင့် အရှိန်မြှင့် မောင်းနှင်သော ယာဉ်များ ရှိလာမည်ဟု ခန့်မှန်းရပါသည်။ ထို့ကြောင့် ဒေသတွင်း အစိုးရသည် ရေရှည် စီမံခန့်ခွဲမှု အစီအမံများ အကောင်အထည်ဖော် ဆောင်ရွက်သင့်ပါသည်။

၆။ လူထုတွေ့ဆုံဆွေးနွေးခြင်း နှင့် သတင်းအချက်အလက်ထုတ်ပြန်ခြင်း

ယခုလုပ်ငန်းရပ်၏ ရည်ရွယ်ချက်မှာ သင့်တော်သော ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်လေ့လာခြင်း နှင့် ပတ်ဝန်းကျင် စီမံခန့်ခွဲမှုအစီအစဉ် ဆောင်ရွက်ခြင်းအတွက် အကြံပြုချက်များ၊ စိုးရိမ်ပူပန်များကို ရယူရန်အလို့ငှာ စီမံကိန်းသတင်းအချက်အလက်ထုတ်ပြန်ခြင်းနှင့် လူထုတွေ့ဆုံဆွေးနွေးခြင်းကို ဆောင်ရွက်ရခြင်းဖြစ်သည်။

စီမံကိန်း သတင်းအချက်အလက် ထုတ်ပြန်ခြင်းကို ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းဆိုင်ရာ လုပ်ထုံးလုပ်နည်း ၂၀၁၅ နှင့်အညီ ဆောင်ရွက်သွားပါမည်။ DWIR မှလည်း ဆောင်ရွက်ရန် ရည်ရွယ်ထားသည့် စီမံကိန်းအကြောင်းကို DWIR website နှင့် ရန်ကုန်ရှိ DWIR တွင်လည်း ထုတ်ပြန်ကြေငြာသွားပါမည်။ ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းဆောင်ရွက်သည့် အဖွဲ့မှလည်း ထိရောက်သည့် သတင်းအချက်အလက်ထုတ်ပြန်ခြင်းနည်းလမ်းကို ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းဆိုင်ရာ လုပ်ထုံးလုပ်နည်းနှင့်

အညီ အဆိုပြုတင်ပြသွားပါမည်။ အဓိကအုပ်စုလိုက်တွေ့ဆုံဆွေးနွေးခြင်းများ အပါအဝင် လူထုတွေ့ဆုံဆွေးနွေးခြင်း နှင့်သတင်းအချက်အလက်ထုတ်ပြန်ခြင်း အစည်းအဝေးများအား လေ့လာဆန်းစစ်မှုလုပ်ငန်းဆောင်ရွက်နေ စဉ်အတွင်း တွံတေး ၊ ဒလ ၊ ဆိပ်ကြီးခနောင်တို နှင့် ကြည့်မြင်တိုင် မြို့နယ်များ၏ မြို့နယ်အုပ်ချုပ်ရေးရုံးများတွင် ၂၀၁၉ ခုနှစ် ဇန်နဝါရီလ ၂၆ ရက်မှ ၂၉ ရက်အတွင်း နောက်ဆုံး ပြုလုပ်ခဲ့ပါသည်။

ဇယား ၆-၁ : နယ်ပယ်အတိုင်းအတာ သတ်မှတ်ခြင်းအဆင့်တွင် ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းဆိုင်ရာ လူထုတွေ့ဆုံဆွေးနွေးပွဲ အကျဉ်းချုပ်

နေ့ရက် နှင့် အချိန်	၁) ကြာသာပတေး၊ စက်တင်ဘာ ၁၉ ရက်၊ ၂၀၁၈ 9:00 AM to 12:00 AM ၂) သောကြာ၊ စက်တင်ဘာ ၂၀ ရက်၊ ၂၀၁၈ ပထမပိုင်း၊ မနက် ၉ နာရီမှ ၁၂ နာရီထိ၊ ဒုတိယပိုင်း နေ့လည် ၁ နာရီမှ ညနေ ၃ နာရီထိ
နေရာ	တွံတေးမြို့နယ် အုပ်ချုပ်ရေးမှူးရုံး ဒလမြို့နယ် အုပ်ချုပ်ရေးမှူးရုံး ဆိပ်ကြီးခနောင်တိုမြို့နယ် အုပ်ချုပ်ရေးမှူးရုံး
ဖိတ်ကြားထားသူများ	- ညွှန်ကြားရေးမှူး၊ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေး ဦးစီးဌာန၊ ရန်ကုန်တိုင်း၊ သယံဇာတနှင့် ပတ်ဝန်းကျင်ထိန်းသိမ်းရေး ဝန်ကြီးဌာန - ရန်ကုန်တောင်ပိုင်းခရိုင် ဦးစီးမှူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန - တွံတေး၊ ဒလ၊ ဆိပ်ကြီးခနောင်တို နှင့် ကြည့်မြင်တိုင်ရှိ အထွေထွေအုပ်ချုပ်ရေးဌာနများ - အရာရှိများ၊ မြန်မာ့ဆိပ်ကမ်းအာဏာပိုင်၊ ပို့ဆောင်ရေးနှင့် ဆက်သွယ်ရေး ဝန်ကြီးဌာန - သက်ဆိုင်မြို့နယ်သုံးခုနှင့် အနီးဝန်းကျင်ရှိ နေထိုင်သူများ - စီမံကိန်း အဆိုပြုသူ နှင့် သက်ဆိုင်ရာ အစိုးရအဖွဲ့အစည်းများ - အခြားအဖွဲ့အစည်းများနှင့် စီမံကိန်းစိတ်ဝင်စားသည့်သူများ
တက်ရောက်သူများ	တွံတေး။ ၈၅ ယောက် (ကျား - ၇၅၊ မ - ၁၀) ဒလ။ ၇၂ ယောက် (ကျား - ၆၀၊ မ - ၁၅) ဆိပ်ကြီးခနောင်တို။ ၆၃ ယောက် (ကျား - ၅၃၊ မ - ၁၀) ကြည့်မြင်တိုင်။ ၉ ယောက် (ကျား - ၉)
အစီအစဉ်	မြို့နယ်အုပ်ချုပ်ရေးမှူးမှ အစည်းအဝေးအကြောင်း မိတ်ဆက်ပြောကြားခြင်း DWIR မှ စီမံကိန်းအကြောင်းရှင်းလင်းပြောကြားခြင်း ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအကြောင်း ရှင်းလင်းခြင်း နယ်ပယ်အတိုင်းအတာသတ်မှတ်ချက်ရလဒ်မူကြမ်းအရ အဓိက ကောင်းကျိုး၊

	ဆိုးကျိုး တွေရှိချက်များ ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်လေ့လာခြင်း၏ နယ်ပယ်အတိုင်းအတာ ဆောင်ရွက်ရမည့် ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်း လုပ်ငန်းစဉ်
အသုံးသည့် ဘာသာစကား	ဒေသသုံးစကား၊ မြန်မာဘာသာစကား

ရည်ညွှန်းချက် - ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းလေ့လာမှုအဖွဲ့

ဇယား ၆-၂: အဓိကအုပ်စုများနှင့်တွေ့ဆုံဆွေးနွေးခြင်း

နေ့ရက်	နေရာ
၂၀၁၈ ခုနှစ် အောက်တိုဘာ ၃၁ ရက်	သာကြီးရပ်ကွက် ၊ ဒလမြို့နယ်မှ ပြည်သူလူထုများ
၂၀၁၈ ခုနှစ် အောက်တိုဘာ ၃၁ ရက်	ပျော်ဖွယ်လေးရွာ ၊ တုံတေးမြို့မှ ပြည်သူလူထုများ
၂၀၁၈ ခုနှစ် နိုဝင်ဘာလ ၁ ရက်	ဆိပ်ကြီး (အနောက်) ရပ်ကွက် ၊ ဆိပ်ကြီးခနောင်တိုမြို့နယ်မှ ပြည်သူလူထုများ
၂၀၁၈ ခုနှစ် ဒီဇင်ဘာလ ၂၄ ရက်	တောင်သူကြီး စားသောက်ဆိုင် ၊ ဆိပ်ကြီးခနောင်တိုမြို့နယ်မှ သဘောကျင်းပိုင်ရှင်များအသင်း
၂၀၁၈ ခုနှစ် ဒီဇင်ဘာလ ၂၄ ရက်	ဘုရားကြီးရွာ ၊ တုံတေးမြို့နယ်မှ လယ်သမားများ



ဇယား ၆-၃ : ပတ်ဝန်းကျင်ထိခိုက်မှုလေ့လာဆန်းစစ်ခြင်းများအတွက် နောက်ဆုံးအဆင့် လူထုတွေ့ဆုံဆွေးနွေးပွဲ

နေ့ရက်	သက်ဆိုင်ရာ ပါဝင်ဆွေးနွေးသူများ	အစည်းအဝေးတက်ရောက်သူအရေအတွက်
၂၀၁၉ ခုနှစ် ဇန်နဝါရီလ ၂၆ ရက်	ဆိပ်ကြီးခနောင်တိုမြို့နယ်	
	၁. အစိုးရအရာရှိများ	၃၂
	၂. လွှတ်တော်အရာရှိ	၁
	၃. စီမံကိန်းပိုင်ရှင် ကိုယ်စားလှယ်များ (DWIR)	၆
	၄. ပတ်ဝန်းကျင်ဆိုင်ရာ အကြံပေးပညာရှင်အသင်း	၅
	၅. NGOs	၁၄
	၆. ဒေသခံများ	၆၄
	၇. သဘောကျခြင်းပိုင်ရှင်များ အသင်း	၁၇
	စုစုပေါင်း	၁၃၉
၂၀၁၉ ခုနှစ် ဇန်နဝါရီလ ၂၈ ရက် နံနက် ၉ နာရီ မှ ၁၁ နာရီထိ။	တွံတေးမြို့နယ်	
	၁. အစိုးရအရာရှိများ	၁၇
	၂. လွှတ်တော်အရာရှိ	၁
	၃. စီမံကိန်းပိုင်ရှင် ကိုယ်စားလှယ်များ (DWIR)	၂
	၄. ပတ်ဝန်းကျင်ဆိုင်ရာ အကြံပေးပညာရှင်အသင်း	၉
	၅. NGOs	၂
	၆. ဒေသခံများ	၁၄၇
	စုစုပေါင်း	၁၇၈
၂၀၁၉ ခုနှစ် ဇန်နဝါရီလ ၂၈ ရက် နေ့လည် ၂ နာရီမှ ၄ နာရီထိ။	ဒလမြို့နယ်	
	၁. အစိုးရအရာရှိများ	၁၇
	၂. လွှတ်တော်အရာရှိ	၂
	၃. စီမံကိန်းပိုင်ရှင် ကိုယ်စားလှယ်များ (DWIR)	၅
	၄. ပတ်ဝန်းကျင်ဆိုင်ရာ အကြံပေးပညာရှင်အသင်း	၉
	၅. NGOs	၃
	၆. ဒေသခံများ	၈၃

	စုစုပေါင်း	၁၁၉
၂၀၁၉ ခုနှစ် ဇန်နဝါရီလ ၂၉ ရက် နံနက် ၉ နာရီ မှ ၁၁ နာရီထိ။	ကြည့်မြင်တိုင်မြို့နယ်	
	၁. အစိုးရအရာရှိများ	၁၆
	၂. လွှတ်တော်အရာရှိ	၁
	၃. စီမံကိန်းပိုင်ရှင် ကိုယ်စားလှယ်များ (DWIR)	၁
	၄. ပတ်ဝန်းကျင်ဆိုင်ရာ အကြံပေးပညာရှင်အသင်း	၈
	၅. NGOs	၄
	၆. ဒေသခံများ	၁၂
	စုစုပေါင်း	၄၂
အစီအစဉ်	<ul style="list-style-type: none"> - မြို့နယ်အုပ်ချုပ်ရေးမှူးမှ အစည်းအဝေးအကြောင်း မိတ်ဆက်ခြင်း - စီမံကိန်းပိုင်ရှင် (DWIR) မှ စီမံကိန်း အကြောင်း ရှင်းပြခြင်း - စီမံကိန်း၏ သဘာဝပတ်ဝန်းကျင်နှင့် လူမှု ပတ်ဝန်းကျင်အပေါ်တွင် ထိခိုက်နိုင်ဖွယ်ရာများအား ပြည်တွင်း ပညာရှင်များမှ ရှင်းပြခြင်း - သဘာဝပတ်ဝန်းကျင်နှင့် လူမှုပတ်ဝန်းကျင် အပေါ် တွင် လေ့လာတွေ့ရှိချက်များအရ အဓိက ကောင်းကျိုးနှင့် ဆိုးကျိုးသက်ရောက်မှုများအား ရှင်းပြခြင်း - ရှောင်ရှားနိုင်မည့်အခြားနည်းလမ်းများအား ရှာဖွေ ဆန်းစစ်ခြင်း - သဘာဝပတ်ဝန်းကျင်နှင့် လူမှု ပတ်ဝန်းကျင် အပေါ် တွင် ထိခိုက်နိုင်ဖွယ်ရာများအား လျော့ချ ရေးနှင့် စီမံခန့်ခွဲမှုလုပ်ငန်းစဉ်များအား ရှင်းပြခြင်း - အမေးအဖြေကဏ္ဍ 	
ဘာသာစကား	မြန်မာ	

၇။ နိဂုံးချုပ်

ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်း အစီရင်ခံစာအတွက် ဆောင်ရွက်ရမည့်လုပ်ငန်းတာဝန်များကို နယ်ပယ် အတိုင်းအတာသတ်မှတ်ချက် ရလဒ်များပေါ်မူတည်၍ ပြင်ဆင်ထားပါသည်။ ဆက်လက်ဆောင်ရွက်ရမည့် လုပ်ငန်းတာဝန်များကို ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းဆိုင်ရာ လုပ်ထုံးလုပ်နည်းများနှင့် အညီ သာမက မြန်မာနိုင်ငံတွင် ပြဌာန်းထားသော အခြားဥပဒေများ၊ အသုံးပြုနိုင်သည့် သက်ဆိုင်ရာ စံချိန်စံညွှန်းများ၊ လမ်းညွှန်များ၏ လိုအပ်ချက်နှင့်အတူ ကျွမ်းကျင်ပိုင်နိုင်စွာ ဆောင်ရွက်သွားပါမည်။ ထို့အပြင် ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းကို အဆိုပြုစီမံကိန်းအတွက် ငွေကြေးထောက်ပံ့နိုင်ခြေရှိသည့် Export-Import Bank of Korea ၏ Economic Development Corporation Fund (EDCF) မှ ချမှတ်ထားသော Safeguard Policy နှင့်လည်း ကိုက်ညီအောင် လုပ်ဆောင်သွားမည်ဖြစ်သည်။

အောက်ပါစီမံကိန်းဆိုင်ရာ ကတိကဝတ်များအား စီမံကိန်းအနေဖြင့် ဇယား ၇-၁ တွင် ဖော်ပြထားသည့်အတိုင်း လိုက်နာဆောင်ရွက်ပါမည်။

ဇယား ၇-၁ : စီမံကိန်းဆိုင်ရာ ကတိကဝတ်များ

အခန်းများ	ကတိကဝတ်များ
အခန်း ၁	ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ချက်အစီရင်ခံစာအား သက်ဆိုင်ရာ စီမံကိန်းပိုင်ရှင်မှ ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ချက် အစီအစဉ်များအတိုင်း ပြင်ဆင်ပြီး အတွေ့အကြုံရှိသော အကြံပေးပညာရှင်များအား တတိယအဖွဲ့အစည်းအဖြစ် ဆောင်ရွက်စေပါမည်။
အခန်း ၂	<p>စီမံကိန်းပိုင်ရှင်သည် ပတ်ဝန်းကျင်ထိခိုက်မှုကာကွယ်ရေးနှင့်သက်ဆိုင်သော ပြည်တွင်း နှင့် သက်ဆိုင်ရာဌာနများမှ ထုတ်ပြန်ထားသော ဥပဒေ ၊ နည်းဥပဒေ နှင့် လိုအပ်ချက်များ ၊ စောင့်ထိန်း လိုက်နာရမည့် တာဝန်ဝတ္တရားများ နှင့် တာဝန်ယူမှု တာဝန်ခံမှုများအားလုံးကို လိုက်နာဆောင်ရွက်ပါမည်။</p> <p>စီမံကိန်းအနေဖြင့် အောက်ပါအချက်များအား လေးစားလိုက်နာပါမည်။</p> <ul style="list-style-type: none"> - လေထုထုတ်လွှတ်မှုအတွက် သက်ဆိုင်ရာစံချိန်စံညွှန်းသတ်မှတ်ချက်များ (NEQG) - ရေဆိုးစွန့်ထုတ်ရေးအတွက် သက်ဆိုင်ရာစံချိန်စံညွှန်းသတ်မှတ်ချက်များ (General application of NEQG) - အသံဆူညံမှုနှင့်တုန်ခါမှုအတွက် သက်ဆိုင်ရာစံချိန်စံညွှန်းသတ်မှတ်ချက်များ (Industrial noise standard of NEQG) - စွန့်ပစ်ပစ္စည်းများစွန့်ပစ်ရာတွင် သက်ဆိုင်ရာစံချိန်စံညွှန်းသတ်မှတ်ချက်များ (YCDC, Yangon City) - လူသုံးနေ့စဉ်သုံး စွန့်ပစ်ပစ္စည်းများ ၊ ဆောက်လုပ်ရေးသုံး စွန့်ပစ်ပစ္စည်းများ နှင့် အန္တရာယ်ရှိသော စွန့်ပစ်ပစ္စည်းများကို သီးခြားခွဲခြားကာ စွန့်ပစ်ပါမည်။ - ပတ်ဝန်းကျင်နှင့်လူမှုရေးရာထိခိုက်မှုများကို စီမံခန့်ခွဲရာတွင် ပြည်တွင်း နှင့် နိုင်ငံတကာ ဥပဒေများ ၊ စံချိန်စံညွှန်းများ နှင့် လုပ်ငန်းစဉ်အစီအစဉ်များအား အစီရင်ခံစာတွင် တင်ပြထားသည့်အတိုင်း တင်းကြပ်စွာ လိုက်နာဆောင်ရွက်ပါမည်။ - ပတ်ဝန်းကျင်စီမံခန့်ခွဲမှုအစီအစဉ်နှင့် လူမှုရေးရာချိတ်ဆက်ဆောင်ရွက်မှုအစီအစဉ်များအား အစီ

	ရင်ခံစာတွင် ဖော်ပြထားသည့် စောင့်ကြပ်စစ်ဆေးမှုအစီအစဉ်များအတိုင်း လိုက်နာဆောင်ရွက်ပါမည်။
အခန်း ၃	စီမံကိန်းအနေဖြင့် ဒီဇိုင်းများ ၊ ခေတ်မီ စက်ပစ္စည်းကိရိယာများအား စီမံကိန်းအကြောင်းအရာတင်ပြချက်များတွင် ဖော်ပြထားသကဲ့သို့ အသုံးပြုကာ ထိန်းသိမ်းပြုပြင်ရေးများ ဆောင်ရွက်ပါမည်။
အခန်း ၄	စီမံကိန်းအနေဖြင့် လက်ရှိပတ်ဝန်းကျင်နှင့်လူမှုစီးပွားအခြေအနေများအား နောက်ယှက်ခြင်းမပြုပဲ သဘာဝအတိုင်းထိန်းသိမ်းထားပြီး ဒေသတွင်း အသက်မွေးဝမ်းကြောင်းနှင့် လူနေမှုအဆင့်အတန်းများ မြင့်မားလာအောင် တတ်စွမ်းသမျှ ဆောင်ရွက်ပါမည်။
အခန်း ၅	စီမံကိန်းအနေဖြင့် ဆွေးနွေးတင်ပြထားသော စီမံကိန်းမှ ပေါ်ထွက်လာမည့် ယာယီ သို့မဟုတ် အစဉ်အမြဲဖြစ်စေမည့် ပတ်ဝန်းကျင် နှင့် လူမှုစီးပွား ထိခိုက်မှုများအတွက် ထိခိုက်မှုလျှော့ချရေး အစီအမံများအား ဆောက်လုပ်ရေးနှင့်လည်ပတ်စဉ် ကာလတစ်လျှောက်လုံး လေးစားလိုက်နာ ဆောင်ရွက်ပါမည်။
	မတော်တဆထိခိုက်မှုများမှ ကာကွယ်နိုင်ရန် အလုပ်သမားများအတွက် တစ်ကိုယ်ရေကာကွယ်ရေး သုံးပစ္စည်းများဖြစ်ကြသည့် လက်အိတ် ၊ ဟဲလ်မက် ၊ မျက်နှာဖုံး ၊ မျက်မှန် နှင့် အခြားပစ္စည်းများ ၊ လုပ်ငန်းခွင်သုံးဘွတ်ဖိနပ် နှင့် လုပ်ငန်းခွင်ဝတ်စုံများကိုလည်း စီစဉ်ပေးထားမည်ဖြစ်ပြီး လုပ်ငန်းခွင်ကျန်းမာရေးစောင့်ရှောက်မှုသင်တန်းများကိုလည်း စီစဉ်ထားရှိပါမည်။
	အလုပ်သမားခန့်ထားရေးမူဝါဒကိုလည်း ဒေသခံအလုပ်သမားများအား စီမံကိန်းတွင် အလုပ်ခန့်ထားမှု လွယ်ကူချောမွေ့စေရေးအတွက် စီစဉ်ဆောင်ရွက်ပေးထားပါမည်။
	ဆောက်လုပ်ရေးလုပ်ငန်းအန္တရာယ်များ စီမံခန့်ခွဲထားရှိမှု အစီအစဉ်ကိုလည်း ပြင်ဆင်ထားပါမည်။
အခန်း ၆	စီမံကိန်းလုပ်ငန်းများမှ ဖြစ်ပေါ်လာနိုင်သော စပ်ဆက်သက်ရောက်နိုင်မှုများကို ထည့်သွင်းစဉ်းစားပြီး ထိခိုက်မှုများကို လျော့ပါးစေရေးနှင့် အကျိုးအမြတ်များ ပိုမိုဖြစ်ထွန်းလာရေးအတွက် အစဉ်တစိုက် ဆောင်ရွက်ပါမည်။
အခန်း ၇	ပတ်ဝန်းကျင်နှင့်လူမှုရေးရာများကို အကောင်အထည်ဖော်ဆောင်ရွက်မည့်အဖွဲ့ နှင့် စီမံကိန်း စီမံခန့်ခွဲမှုအဖွဲ့တို့ အတူတကွပူးပေါင်းကာ စီမံကိန်း ဆောက်လုပ်ရေးကာလနှင့် လုပ်ငန်းလည်ပတ်ရေးကာလ ပတ်ဝန်းကျင်စီမံခန့်ခွဲမှု အစီအစဉ်များအား ဆောင်ရွက်ပါမည်။
	ကန်ထရိုက်တာနှင့်တဆင့်ခံကန်ထရိုက်တာများအား ရွေးချယ်ရာတွင် ဆောက်လုပ်ရေးလုပ်ငန်းများအတွက် ပတ်ဝန်းကျင်စီမံခန့်ခွဲမှုတွင်လည်း အမှန်တကယ်လေးစားလိုက်နာဆောင်ရွက်မည့် အရည်အသွေးပြည့်ဝပြီး တရားဝင်မှတ်ပုံတင်ထားရှိသော လုပ်ငန်းအဖွဲ့အစည်း နှင့် လူပုဂ္ဂိုလ်များကိုသာ ငှားရမ်းအသုံးပြုပါမည်။
	စီမံကိန်းကန်ထရိုက်တာ/တဆင့်ခံကန်ထရိုက်တာများအနေဖြင့်လည်း ဆောက်လုပ်ရေးလုပ်ငန်းသုံး ပစ္စည်းများ နှင့် စက်ပစ္စည်းများ ၊ လိုအပ်သော သဘာဝရင်းမြစ်များကို ဝယ်ယူရာတွင် သက်ဆိုင်ရာ လိုင်စင်ရှိသည့် ရောင်းချသူများထံမှသာ ဝယ်ယူအသုံးပြုပါမည်။
	သက်ဆိုင်ရာ လေးစားလိုက်နာကြောင်းအစီရင်ခံစာအားလည်း လစဉ် ၊ သို့မဟုတ် နှစ်စဉ် စောင့်ကြပ်စစ်ဆေးမည်ဟု တင်ပြထားသည့်အတိုင်း တစ်သွေမသိမ်းဆောင်ရွက်ပါမည်။ ပတ်ဝန်းကျင် ထိန်းသိမ်းရေးဆိုင်ရာ လိုက်နာဆောင်ရွက်မှု သက်သေခံလက်မှတ် (ECC) အတိုင်း စောင့်ကြပ်စစ်ဆေးမှု အစီရင်ခံစာအား ပတ်ဝန်းကျင် ထိန်းသိမ်းရေးဦးစီးဌာနအား နှစ်စဉ် တင်ပြပါမည်။
	စီမံကိန်းသည် အစီရင်ခံစာသက်ဆိုင်ရာအခန်းတွင် တင်ပြထားသည့်အတိုင်း စောင့်ကြပ်စစ်ဆေးပြီး

	အစီရင်ခံစာတင်ပို့ခြင်းအား အကောင်အထည်ဖော်ဆောင်ရွက်ပါမည်။
အခန်း ၈	စီမံကိန်းသည် ပြည်သူလူထုနှင့် စီမံကိန်းနှင့်အဓိကသက်ဆိုင်သူများနှင့် ညှိနှိုင်းဆွေးနွေးရာတွင် စီမံကိန်းလုပ်ငန်းနှင့်သက်ဆိုင်သည့် မည်သည့် ပတ်ဝန်းကျင်နှင့်လူမှုရေးရာ ကိစ္စဖြစ်စေ အဆင်ပြေချောမွေ့စွာ ညှိနှိုင်းဆောင်ရွက်ပါမည်။ မြေယာရယူရေး နှင့် ပြန်လည်နေရာချထားရေး လုပ်ငန်းဆောင်ရွက်မှုအစီအစဉ်များအား သက်ဆိုင်သူများနှင့် ကြိုတင်အသိပေးတိုင်ပင်ပြီး ဒေသတွင်းလူမှုဆက်ဆံရေးတိုးတက်ဖွံ့ဖြိုးစေရေး လုပ်ငန်းများကိုလည်း ပိုမိုဖွံ့ဖြိုးတိုးတက်စေပါမည်။
အခန်း ၉	စီမံကိန်းစီမံခန့်ခွဲမှုအဖွဲ့ဝင်များနှင့် ချိတ်ဆက်ဆောင်ရွက်ရမည့်ပုဂ္ဂိုလ်သည် မည်သည့်ပစ္စည်းဆုံးရှုံးမှုနှင့် ပျက်ဆီးမှုအတွက်ဖြစ်စေ အစီရင်ခံစာတွင် တင်ပြထားသည့်အတိုင်း မကျေလည်မှုများကို လက်ခံ ဖြေရှင်းပေးသည့်စနစ် လုပ်ငန်းစဉ်အတိုင်း အချိန်နှင့်တစ်ပြေးညီ ဆောင်ရွက်ပါမည်။
အခန်း ၁၀	စီမံကိန်းသည် ဇယား ၁၀.၂-၁ နှင့် အပိုဒ်ခွဲ ၁၀.၃ တွင် ဖော်ပြထားသည့် ကတိခံဝန်ချက်များနှင့် အကြံပြုချက်များအတိုင်း တစ်သွေမသိမ်း တိကျစွာ လိုက်နာဆောင်ရွက်ပါမည်။

အနှစ်ချုပ်ဆိုရသော် အဆိုပြုတင်ပြထားသော တွံတေးတူးမြောင်းဘက်စုံဖွံ့ဖြိုးတိုးတက်ရေး စီမံကိန်း၏ ဆောက်လုပ်ရေးနှင့်လုပ်ငန်းလည်ပတ်စဉ်ကာလတစ်လျှောက်လုံးတွင် ဖြစ်နိုင်ချေရှိသည့် သက်ဆိုင်ရာ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေး နှင့် လူမှုရေးရာဆုံးရှုံးမှုများအတွက် စီမံကိန်းပိုင်ရှင်ဖြစ်သော (DWIR) အနေဖြင့် လူမှုရေးရာနှင့် ပြန်လည်နေရာချထားရေးဆောင်ရွက်မှုအစီအစဉ်များအား တာဝန်ယူ တာဝန်ခံမှုအပြည့်ဖြင့် အကောင်အထည်ဖော်ဆောင်မည် ဖြစ်ပါသည်။ ဆောက်လုပ်ရေးလုပ်ငန်းပြီးစီးပါက စီမံကိန်းအနေဖြင့် ဆောက်လုပ်ရေးကာလတွင် ခံစားခဲ့ရသော ထိခိုက်မှုများလုံးဝပျောက်သွားနိုင်လောက်သည့် ကောင်းကျိုးသုခများ ခံစားရဖွယ် ရှိပါသည်။

CHAPTER 1: CONTEXT OF THE PROJECT

1.1 Introduction

According to the Environmental Impact Assessment Procedure (2015), an EIA report has to be prepared in a professional manner and in accordance with the procedures and any applicable guidelines issued or adopted by MONREC.

In compliance with Article 63 of the EIA Procedure (2015), the project proponent has prepared the EIA report either in the Myanmar language or in English language with an accompanying, Executive Summary in the Myanmar language, with the following content:

- 1) Executive Summary
- 2) Introduction: Context of the Project
- 3) Policy, Legal and Institutional Framework
- 4) Project Description and Alternative selection
- 5) Description of the Surrounding Environment
- 6) Impact and Risk Assessment and Mitigation Measures
- 7) Cumulative Impact Assessment
- 8) Environmental Management Plan
- 9) Public Consultation and Disclosures
- 10) Grievance Redress Mechanism
- 11) Conclusions and Recommendations

1.2 Background of the Project

The Twante (Twantay) Canal is an artificial waterway connected between the Ayeyawrady delta area and the Yangon River in Myanmar, which had been completed by British Government in 1883 over the length of 34 km. Over a century, the Twante (Twantay) Canal was changed and improved by shortcutting, widening and deepening, reverting, etc. However, due to the lack of regular maintenance, the canal waterway became irregular and associated facilities (such as banks etc.) were marred over time by local erosion and deposition. This is threatening safe and smooth ship navigation. Aware of the necessity of systematical improvement and management of the Twante (Twantay) Canal, the Ministry of Transport and Communications (MOTC), 2012, instructed the Directorate of Water Resources and Improvement of River Systems (DWIR) under the MOTC to deliberate how to effectively improve the Twante (Twantay) Canal and to systematically manage it with foreign aids.

In this context, feasibility study on the Twante (Twantay) Canal Integrated Management Project in Yangon, Myanmar was conducted in November 2015 by Directorate of Water Resources and Improvement of River Systems (DWIR) of MOTC with the technical support of the ISAN Corporation, funded by the Government of the Republic of Korea. The Twante (Twantay) Canal Improvement Project is composed of two phases: The first phase of Channel training and Flood embankment; and the second phase of developing multi-purpose barrages. This EIA report covers only the first phase. The detailed design, component, geographical coverage and financing schemes for the second phase shall be planned in the future.

The first stage of implementation of the Twante (Twantay) Canal Improvement Project ("the Project" hereafter) will be carried out by the ODA loan of Economic Development Cooperation Fund (EDCF) from the Government of the Republic of Korea. The Project is expected to benefit local community in

the region and people using the canal by providing safe navigating environment, smooth flow of cargos, bank protection, flood protection and development in tourism.

1.3 Outline of the Project and Project Components

1.3.1 Objectives of the Project

This report is prepared for the Twante (Twantay) Canal, the main inland transport waterway which connects the Yangon River to Ayeyarwady Delta, the largest granary of Myanmar. The Project aims to provide security to the waterway transport, by speeding up the flow of goods, and consequently boost economic development by securing a more robust waterway transport and logistics, halting floods and protecting the area from collapsing riverbanks. Once completed, the Project is also expected to boost tourism in the region and generate job opportunities in associated industries.

This report is prepared in compliance with Myanmar's Environmental Impact Assessment Procedure (2015) and the EDCF Safeguard Policy (2016), required standards from the Export-Import Bank of Korea, the official executing body of the EDCF and the financial sponsor of the Project.:-

The proposed Project, i.e. the Twante (Twantay) Canal Improvement Project, is designed to address the current river erosion and frequent floods that hamper the steady and safe use of inland waterways, and negatively affecting the lives of residents near the canal. It is necessary to improve the condition of canal to ensure development of the region through enhancing the inland water transport capacity and safety along the canal. In addition, flood protection facility to protect the shore and prevent flood-induced inundations will be established.

1.3.2 Project Components

The Project is composed of the following two components:

Component 1 - Channel Training - Embankment construction (5.88km) and Bed erosion protection construction (A= 55,500 m²)

Component 2 - Flood protection- Embankment construction for flood protection (3 sections, 39.5 km)

1.3.3 Project Area

The project area, part of the Twante Canal (between 0 mile and 6.5 mile) and part of the yangon river(the right bank of a river) is located in the Yangon South District of Yangon Region. The geographical coverage of the area is part of the Dala Township, SeikkyiKhanaungto Township, Kyimyindaing Township and Twante Township (see in Figure 1.2-1 below).




Figure 1.3-1 General Layout Plan of Twante (Twantay) Canal

1.3.4 Project Period

DWIR under MOTC will be the Executive Agency for the Project and also be responsible for overall project monitoring and progress reporting including schedules, budgets, staff and other requirements to the EDCF. Since the Draft Final Report of the ESIA baseline study was submitted to DWIR in December 2017, the approval process of the Project implementation including social and environmental assessment has progressed in due course of Myanmar. The loan negotiations are expected with loan effectiveness in 2015. The Project will be implemented over a period of 6 years between 2019 and 2024. The project implementation schedule is shown in Figure 1.3-2.

Description	2015	2016-2019	2020	2021	2022	2023	2024
Project Preparation							
• Assistance of Financing (Loan Nego.)							
Consulting Service							
• F/S on Phase 2							
• Detailed Design for Phase 1							
• Tender Services							
• Construction Supervision							
Construction							
• Component 1							
Bank Protection							
Bed Scour Prevention							
• Component 2							
Khanaungto Section							
Dala Section							
Twante Section							

Figure 1.3-2: Project Implementation Schedule

1.4 Project Proponent and EIA Team

1.4.1 Objectives of the Proposal and Process

The primary objective of this EIA report is to define the study area, area of influence, time boundaries, project phases and stakeholders under the applicable regulations and standards to identify environmental and social impacts (including biophysical, social and health impacts). For this reason, potential significant environmental impacts of the Project have been identified throughout the primary survey data and secondary information from relevant reference sources. Regarding the collection of primary data, baseline environmental data relating to physical, biological and socio-economic sources were collected by direct observation and surveys that are mentioned in Chapter 4. The secondary data was gathered from published reports and literature from the internet and other sources such as the data from State/Regional Government bodies, relevant ministries and research institutions.

1.4.2 Project Proponent

The project proponent is the Directorate of Water Resources and Improvement of River Systems (DWIR) under the MOTC.

1.4.2.1 Project Proponent Information

Proponent Name:	Directorate of Water Resources and Improvement of River Systems(DWIR), Ministry of Transport and Communications(MOTC)		Company Registration Number by DICA(if any):	
Contact name of Proponent:	Director General, DWIR			
Proponent`s address for correspondence:	No-400, Lower Pazundaung Road, Yangon Myanmar			
Telephone(fixed/mobile):	+95-1-292961(office)	Fax: +95-4-290230	E-mail address:	lwinoocaphtun@gmail.com

Waterways Department was organized and founded in 1972 by combining Dredging and River Conservancy sections of Department of Marine Administration and parts of Hydrographic Surveying section of Port Corporation under the Ministry of Transport and Communication. In 1999, the Department was extended and reorganized as the DWIR. The DWIR has been expanded and reorganized with the increase of international attention, aids, and investment on water resources in Myanmar (see **Figure 1.4-1**).




Figure 1.4-1: Organizational Structure of DWIR

1.4.3 M ESIA Preparation Team

The field studies have been carried out by Resource and Environment Myanmar (REM) team, with vast experiences in conducting EIA projects in Myanmar. The project phases have been scoped in Pre-construction, Construction, and Operation phases for identification and evaluation of impacts based on their magnitudes, duration, extent and intensity with the required mitigation measures to reduce the impacts to be within the acceptable limits.

1.4.3.1 Resource & Environment Myanmar Ltd. (REM)

REM is located in the city of Yangon, Myanmar. As a leading resources and environment consulting firm, REM has current or former faculty members of Yangon University as its experts and they are specialized in environment, society and earth resources management and other related subjects. Its predecessor was a research team founded in 1998 within the University of Yangon of which the members were ecologists, social economists, geologists, doctors, economists, and data management staff. In 2003, an environmental impact assessment team was established. After five years of cooperation in several projects with the scientists from various disciplines of University of Yangon (such as environmental data collection, oilfield development evaluation, construction of offshore oil and gas production base, beach resorts and onshore gas pipelines, etc.), the Resource and Environment Myanmar was registered in 2008 under the current laws and regulations in Myanmar. REM provides systematic services for a variety of major infrastructure projects under the request.

So far REM has conducted environmental impact assessment, social and health impact evaluation for private sector or government-led projects. In addition, the company also delivers geotechnical engineering, geological and hydrogeological surveys, and soil investigations, geological hazard assessments (potential landslide risk figure, seismic hazard assessment, and flood risk map).

REM currently has nine research groups, including ecology, plants, soil and water, social investigation, cultural heritage, public health, risk, information management and atmospheric research, a total of 33 experts and has been certified for ISO9001:2008 No. 686750.

Team Leader of the Study Team				
Name(Sur name, Given name)	Registration / License No. by ECD (if applied)	Organization	Contact details	Area of expertise
U ZawNaingOo	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel : +95 9 73013448 Mobile : +95 9 976886587 Email: zawnaingoo@enviromyanmar.net	ESIA / ESMMP

Members of the team (Except the team leader)

Name(Surname, Given name)	Registration / License No. by ECD (if applied)	Organization	Contact details	Area of expertise
U Win Naing Tun	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Resettlement Action Plan, Cultural Heritage
DawKhinOhnmarHtwe	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Stakeholder Engagement Plan and Public Consultation
Ms. Jerry JH Kim	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448 +95 9976654118(Myanmar)	Socio Economy
UThura Aung	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Geology and Soil, Waste Management
U Soe Yu Htun	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Meteorology, Modelling for Air Quality
DawPhyuPhyuShein	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Socio Economy, Facilitation of Meeting
Daw Nan ThazinOo	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Socio Economy, Facilitation of Meeting
DawNaingNaing Win	Certificate for Transitional Consultant Registration No. 0025 (See in Appendix)	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
U ThetNaing Aung	Certificate for Transitional Consultant Registration No. 0025	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township.	Ecology and Biodiversity

	(See in Appendix)		Tel: +959 261328891	
U MyatKoKo Hein	Certificate for Transitional Consultant Registration No. 0025 (See in Appendix)	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
Daw Than ThanHtay	Certificate for Transitional Consultant Registration No. 0025 (See in Appendix)	Sustainable Environment Myanmar Co., Ltd.	No. 503, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +959 261328891	Ecology and Biodiversity
DawPhyoeK haingZar Wint	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Water Pollution Control
U Ngwe Moe	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Risk Assessment and Hazard Management
DawLaiLai Win	Certificate for Transitional Consultant Registration No. 0002 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Environmental Impact Assessment and Reporting
Daw Chit Hsu San	Certificate for Transitional Consultant Registration No. 0117 (See in Appendix)	Resource & Environment Myanmar Co., Ltd.	No. 702, Building B, Delta Plaza Compound, Shwegondaing Road, Bahan Township. Tel: +95 9 73013448	Legal Expert

1.4.3.2 EDCF Environmental and Social Impact Assessment Team

EDCF Environmental and Social Impact Assessment Team is counterpart consultants hired by the Export-Import Bank of Korea to assist the successful completion of the EIA exercises, particularly in compliance with the EDCF Safeguard Policy. The Team is a consortium of ISAN Corporation (as project manager), YOOSHIN ENGINEERING Corporation (in charge of environmental impact assessment), and GAIA CONSULT Inc. (in charge of social impact assessment and Framework Resettlement Action Plan development).

No.	Name	Firm	Field	Remarks
1	Mr. Kang, Yoonmin	ISAN	ESIA	ESIA Team Leader
2	Mr. Yun, Daeil	ISAN	EIA	Director
3	Mr. Nam, Teaho	ISAN	EIA	General Manager
4	Mr. Jeon, Kyungyoel	ISAN	EIA	Director
5	Mr. Joung, Wookyoung	ISAN	EIA	Director
6	Mr. Kim, Seongwoon	ISAN	EIA	General Manager
7	Mr. Lee, Sanghoon	YOOSHIN	EIA	Director

8	Mr. Kim, Hyunmoo	YOOSHIN	EIA	General Manager
9	Mr. Kim, Sungho	YOOSHIN	EIA	General Manager
10	Mr. Lee, Hwajung	YOOSHIN	EIA	General Manager
11	Mr. Kim, Byungsun	YOOSHIN	EIA	General Manager
12	Ms. Lee, Eunyoung	GAIA	SIA & Framework RAP	CEO & Social Team Leader
13	Ms. Lee, Juhyun	GAIA	SIA & Framework RAP	General Manager
14	Mr. Im, Uijin	GAIA	SIA & Framework RAP	General Manager
15	Mr. Kim, Jongwook	GAIA	SIA & Framework RAP	General Manager

1.5 Expected Effects of the Proposed Project

It is expected that the proposed project will offer the foundation of further social and economic development in Myanmar. Securing the safe ship navigation through channel training will attract traders to transport by inland waterway with an increase in the volume of freight by inland waterway. If transportation needs increase with economic development and conversion from other transport modalities in the region, the toll revenue is expected to rise, too.. Bank protection in channel training will prevent land loss and this will improve the safety from flooding in the adjacent residential and farmland area.

The widespread area around the Twante (Twantay) Canal in the southwest region of Yangon has been annually inundated due to the tidal flood. The flood prevention component of the Project covers four Township areas - i.e., Seikkyi Khanaungto, Dala, Kyinmyindaing and Twante (Twantay) Township respectively. Completion of the proposed project will ensure the safety of the subject inland area from the flood inundation and erosion damages. In turn, this will improve the living environment in the subject inland area, which will cause the increase in investment flow into the city. The Project will boost local economy by creating employment opportunities related to the project activities and generating associated income. In addition, it is expected that the Project will boost service sector industry such as retails, wholesale, catering services lodging and real estate business in the region, a second round booster of the local economy and local government tax revenue generation.

The project is expected to reduce the unpredictable erosion or flood damages and required compensation for the livelihood restoration. In this way, the project will facilitate the improvement of urban resources and infrastructure management and provide Yangon citizens with better services. These improved circumstances are expected to attract further foreign investment to Yangon Region. As a result, it is expected the proposed project will lead to overall positive environmental and social impacts with qualitative improvement in the lives of communities; especially in the poorer area and enhancement of industry and commerce of the beneficiary townships in Yangon Region providing residents and their future generations with safer and more reliable environment.

For the construction, the project requires land acquisition and involuntary resettlement. The impacts as such would need to be minimized and handled sensitively through effective environmental and

social management plans.

1.6 Implementation Framework of the ESIA

1.6.1. Categorization of the Project: Subject to EIA

The Project consists of 1) COMPONENT 1: Channel Training - Embankment construction (5.88km) and, Bed erosion protection construction (A= 55,500 m²) and;
2) COMPONENT 2: Flood protection- Embankment construction for flood protection (3 sections, 39.5 km) including access roads. This requires the EIA as per Categorization of Economic Activities for Assessment Purposes of the EIA Procedure (29th December 2015).

1.6.2 Project Implementation Schedules and ESIA Implementation Schedules

Project implementation schedule was established with reference to similar projects in Korea and Myanmar, construction quantities, and climate conditions (dry and wet seasons) in the Project site. A total of 6 years is required for the Project including 3 months for Consultant selection, 9 months for detailed design and tender service, and 60 months for construction and supervision as seen in **Table 1.6-1**, showing the annual investment plan based on construction quantities.

Table 1.6-1: Project Implementation Schedule

Activities	Year1				Year2				Year3				Year4				Year5				Year6			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Selection of Consultant & Detailed Design																								
Bidding																								
Land Acquisition & Compensation																								
Contractor Selection																								
Construction & Supervision																								

ESIA implementation schedules are as follows:

The ESIA tasks have been conducted jointly by REM and the EDCF ESIA Team according to the planned schedule to complete within 14 months (original 8 months and additional 6 months) of time which was mentioned in the commencement, with the following three steps:

The first step was to establish an overall EIA implementation plan through preliminary survey and submit the Project Proposal as required by Myanmar EIA Procedure (Screening stage).

The second step was to investigate a scoping (including stakeholder analysis) and submit scoping and TOR to MONREC for its review and approval. The first round of public consultation was carried out on 20th and 21st September 2018, in order to disclose project information and seek public consultation. TOR for EIA for the proposed Project was approved by MONREC on 8th May 2019 and the Team investigated and drafted ESIA report for submission to the project proponent (DWIR). A second round of public consultation was conducted on 26-29th January 2019 including project information disclosure through direct consultation with key local stakeholders including affected communities.

While the last stage of the EIA procedure includes the Project Proponent's submission of the EIA to

MONREC-ECD for review and final approval, the EDCF EIA Team shall not be engaged in this process due to the time limit of the EIA project allocated by the Export-Import Bank of Korea.

Table 1.6-2: ESIA Implementation Schedule

Step	Main Task	Process Plan (12 month)															
		M 1	M 2	M 3	M 4	M 5	M 6	M 7	M 8	M 9	M 10	M 11	M 12	M 13	M 14	M 15	M 16
1	Establishing evaluation plan through preliminary survey	■	■	■	■												
	Project proposal Submission				■	■	■										
2	Scoping investigation (Stakeholder Analysis)					■	■	■									
	Information disclosure & public consultation (1st)							■									
	Scoping and TOR writing and submission						■	■	■								
	Scoping and TOR confirmation (MONREC)													■			
3	ESIA investigation							■	■	■	■						
	Information disclosure & public consultation (2nd)									■							
	Drafting ESIA report													■	■		
4	ESIA Report Submission, Review and Approval (MONREC)														■	■	■

CHAPTER 2: OVERVIEW OF POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK

2.1 Overview of Myanmar Policies, Legislation and Institutions Concerning Environmental Management during Development Project Implementation and Environmental Impact Assessment

Myanmar's major environmental policies, laws and regulations are as follows:

- ✓ Environmental Policy (1994)
- ✓ Environmental Conservation Law (2012)
- ✓ Environmental Conservation Rules (2014)
- ✓ Environmental Impact Assessment Procedure (2015)
- ✓ Environmental Quality (Emission) Guidelines (2015)
- ✓ Other existing social related laws and regulations

(Source: MONREC-ECD, 2016)

EIA for the proposed Twante (Twantay) Canal Development Project will be conducted in compliance with the Myanmar Environmental Conservation Law (ECL, 2012) and the Myanmar Environmental Conservation Rules (ECR, 2014). ECR provides the regulatory guidance to implement the ECL, where all the government and public development projects shall undergo the required procedures of the EIA as prescribed by the relevant Ministry (i.e. MONREC).

In 2015, a new Myanmar EIA Procedure has been adopted with strengthened procedural requirements in conducting the EIA.

As the proposed Project is financed by the EDCF, the EDCF Safeguard Policy¹ shall be another guideline by which the EIA process and content should abide.

In addition, a number of national and regional environmental (of Yangon Region) and sector-specific laws and regulations of Myanmar shall be complied with in carrying out the EIA, as illustrated in the sections below:

2.2 Institutional Framework on Environmental Management

2.2.1 National Environmental Conservation Committee (NECC)

A National Commission for Environmental Affairs (NCEA) was established in 1990 which was reorganized into the National Environmental Conservation Committee (NECC) in April 2011. The roles of the NECC include, among others: "To supervise and oversee rehabilitation activities in relevant areas based on the magnitude and intensity of impacts caused by government projects and activities or commercial and private activities," and "Prescribe National Environmental Policy and other environmental related policies with approval of the President."² The NECC functions at the national level and developed sub-committees at sub-national (state & division) levels per relevant TOR. The Committee is chaired by the head (Union Minister) of the MONREC and committee members are composed of deputy ministers of the relevant ministries.

¹For the full text of the Policy, see: <https://www.edcfkorea.go.kr/site/homepage/menu/viewMenu?menuid=005001006003>.

² For more details of the responsibilities and functions of the NECC, see: <http://www.myanmar-redd.org/mm/redd-myanmar/management-structure/national-environmental-conservation-and-climate-change-central-committee-neccccc>

2.2.2 National Environmental Conservation and Climate Change Committee (NECCCC)

In June 2016, the Myanmar government set up the National Environmental Conservation and Climate Change Committee (NECCCC) at the highest level of the government, chaired by the vice president and supported by six sub-committees, with an aim to address and provide the adaptable actions for climate change impacts in Myanmar.



Source: MONREC-ECD Presentation slides (2016)³


Figure 2.2-1 Environmental Institutions of Myanmar

2.2.3 Ministry of Natural Resources and Environmental Conservation (MONREC)

The “Ministry of Natural Resources and Environmental Conservation (MONREC)” was founded by the merger between former “Ministry of Environmental Conservation and Forest (MOECAF)”, and former “Ministry of Mines (MOM)” when the new Myanmar Government was launched in 2016. Since then, MONREC has been the central governmental body of Myanmar for taking on administration of Environmental Management and Environmental Impact Assessment (EIA) procedures in Myanmar.

The Environmental Conservation Department (ECD) of the MONREC is to take the responsibility for the environmental conservation and management as well as EIA procedures in Myanmar which consists of five sub-divisions as shown in Figure 2.2-2.

³ <https://www.ifc.org/wps/wcm/connect/c6592ac2-bee6-4094-87ca-ea5229227b39/SEA+Kick+off+meeting.pdf?MOD=AJPERES>



Source: Environmental Conservation Department

Figure 2.2-2 Organization Chart of Environmental Conservation Department (ECD) within MONREC

2.3. Other Relevant Legislations Related to EIA and Environmental Management of the Project

The Project proponent will follow and comply with the following laws and regulation of Myanmar for the development of the Twante (Twantay) Canal Project.

2.3.1 The Constitution of the Union of Myanmar (2008)

The Constitution of the Union of Myanmar is the supreme law of the country and includes provisions stipulating the responsibility of protecting the environment in Myanmar. Such provisions of Articles 37, 42 and 390 are quoted as below for reference:

Article 37

- (a) The Union is the ultimate owner of all lands and all-natural resources above and below the ground, above and beneath the water and in the atmosphere in the Union;
- (b) The Union shall enact necessary law to supervise extraction and utilization of State-owned natural resources by economics forces;

Article 42

The Union shall protect and conserve natural environment.

Article 390

Every citizen has the duty to assist the Union in carrying out the following matters:

- (a) preservation and safeguarding of cultural heritage;
- (b) environmental conservation;
- (c) striving for development of human resources and
- (d) protection and preservation of public property

These three Articles in the Constitution provide a basis for legalizing and institutionalizing environmental health impact assessment and social impact assessment.

2.3.2 Environmental Policy (1994)

To achieve harmony and balance between socio-economic, natural resources and environment through the integration of environmental considerations into the development process, enhancing the quality of the life of all its citizens

2.3.3 National Land Use Policy (2016)

- a) To promote sustainable land use management and protection of cultural heritage areas, environment, and natural resources for the interest of all people in the country;
- b) To strengthen land tenure security for the livelihood improvement and food security of all people in both urban and rural areas of the country;
- c) To recognize and protect customary land tenure rights and procedures of the ethnic nationalities;
- d) To develop transparent, fair, affordable and independent dispute resolution mechanisms in accordance with rule of law;
- e) To promote people centered development in land resources and accountable land use administration in order to support the equitable economic development of the country;
- f) To develop a National Land Law in order to implement the above objectives of National Land Use Policy.

2.3.4 Environmental Conservation Law (2012)

The Pyidaungsu Hluttaw (Assembly of Union) enacted this law by Law No. 9 of 2012 on 30 March 2012. The legal mechanism for ESHIA (Environmental, Social, Health Impact Assessment) has been addressed in this law. This law was enacted with the objectives as follows:

- a. To implement the Myanmar National Environmental Policy;
- b. To lay down the basic principles and give guidance for systematic integration of environmental conservation matters in the sustainable development process;
- c. To emerge a healthy and clean environment and conserve natural and cultural heritage for the benefit of present and future generations;
- d. To reclaim ecosystems as may be possible which are starting to degenerate and disappear;
- e. To manage degradation or loss of natural resources and enable sustainable and beneficial use of resources;

- f. To promote public awareness and enable educational cooperation to raise awareness on environment;
- g. To promote international, regional and bilateral cooperation in the matters of environmental conservation;
- h. To cooperate with Government Departments, Government Organizations, International Organizations, non-government organizations and individuals in matters of environmental conservation.

The following articles are particularly relevant to ESHIA requirements and this project:

Article 7 of Chapter 4 mentions the need for SIA and ESIA for any project operated by the government, organizations, or individuals.

The duties and authority the Ministry holds in relation to the environmental conservation are as follows:

- a) To specify categories and classes of hazardous wastes generated from the production and use of chemicals or other hazardous substances in carrying out industry, agriculture, mineral production, sanitation and other activities;
- b) To prescribe categories of hazardous substances that may affect the environment significantly at present or in the long run;
- c) To promote and carry out the establishment of necessary factories and stations for the treatment of solid wastes, effluents and emissions which contain toxic and hazardous substances;
- d) To prescribe the terms and conditions relating to effluent treatment in industrial estates and other necessary places and buildings and emissions from machine, vehicles and mechanisms;
- e) To provide and carry out a system of ESIA and SIA as to whether or not a project or activity to be undertaken by any Government department, organization or person may cause a significant impact on the environment; To manage and ensure that the polluters compensate for environmental impact; organizations benefiting from and exploiting natural environment contribute fund; businesses exploring, trading, and utilizing natural resources contribute a part of their profit to environmental conservation work.

Also, in this law, Article 14 and Article 15 are related to waste disposal in accordance with environmental standards:

Article 14. A person causing a point source of pollution shall treat, emit drainage and deposit the substances which cause pollution in the environment in accord with stipulated environmental quality standards.

Article 15. The owner or occupier of any business, material or place which causes a point source of pollution shall install or use an on-site facility or controlling equipment in order to monitor, control manage, reduce or eliminate environmental pollution. If it is impracticable, it shall be arranged to dispose the wastes in accord with environmentally sound methods.

- a) is responsible to carry out by contributing the stipulated cash or kind in the relevant combined scheme for the environmental conservation including the management and treatment of waste;
- b) is responsible to carry out by contributing the stipulated cash or kind in the relevant combined scheme for the environmental conservation including the management and treatment of waste;
- c) shall contribute the stipulated users' charge s or management fees for the environmental conservation according to the relevant industrial estate, SEZ and business organization
- d) shall comply with the directives issued for environmental conservation according to the relevant industrial estate, SEZ or business."

2.3.5 Environmental Conservation Rules (2014)

The Ministry of Environmental Conservation and Forestry, empowered by sub-section (a) of section 42 of the Environmental Conservation Law, issued this rule by No.50 of 2014 on the date of 5 June 2014.

In the Environmental Conservation Rules, concerning Environmental Impact Assessment, it has been stated as:

- a) **Rule 51:** The Ministry shall assign duty to the Department for enabling to adopt and carry out the environmental impact assessment system.
- b) **Rule 52:** The Ministry shall determine the categories of plan, business or activity which shall carry out environmental impact assessment
- c) **Rule 53:** The Ministry shall to scrutinize whether or not it is necessary to conduct environmental impact assessment, determine the proposed plans, businesses or activities which do not include in stipulation under rule 52
- d) **Rule 56:** The person who carries out any project, business or activity shall arrange and carry out for conducting the environmental impact assessment for any project, business or activity by a qualified third person or organization accepted by the Ministry.
- e) **Rule 58:** The Ministry shall form the Environmental Impact Assessment Report Review Body with the experts from the relevant Government departments, Government organizations.
- f) **Rule 61:** The Ministry may approve and reply to the ESIA report or IEE or EMP with the guidance of the Committee
 - a. **Rule 69:**
 - (i) Any person shall not emit, cause to emit, dispose, and cause to dispose, pile and cause to pile, by any means, the pollutants and the hazardous waste or hazardous material stipulated by notification under the Law and any of these rules at any place which may affect the public directly or indirectly.
 - (ii) Any person shall not carry out to damage the ecosystem and the natural environment which is changing due to such system, except for carrying out with the permission of the Ministry for the interest of the people.

The following are summaries of the key natural and social environmental laws in Myanmar that seem relevant to the Project.

2.3.6 Environmental Impact Assessment Procedure (2015) ("EIA Procedure 2015)

The EIA procedure, issued on 29th December 2015, defines the requirements for the EIA and states that: *“An EIA investigation shall consider all biological, physical, social, economic, health, cultural and visual-components of the environment, together with all pertinent legal matters relating to the environment (including land use, resources use, and ownership of and rights to land and other resources) that may be affected by the Project during all project phases including pre-construction, construction, operation, decommissioning, closure, and post-closure; and shall identify and assess all Adverse impacts and risks that potentially could arise from the project.*

Article 7 – This Procedure does not address specific matters in relation to resettlement. Projects involving resettlement shall additionally comply with separate procedures issued by responsible ministries, and in the absence of such procedures all such Projects shall adhere to international best practice on Involuntary Resettlement.”

Three different steps are foreseen for the EIA process which are described in the following sections:


- screening phase;
- scoping phase; and
- EIA Investigation and Report Preparation

1) Screening Phase

The screening process unfolds as shown in the Figure below. MONREC is empowered to have the exclusive authority to define the screening criteria for a project.

Guidance is provided as to which projects or activities should carry out an Initial Environmental Examination (IEE) or EIA, as presented in the Annex to the law. If, as a result of that determination, an IEE or an EIA is required, then the proponent of the project or activity has to prepare, obtain approval for, and implement an appropriate Environmental Management Plan (EMP) in respect of the proposed project or activity. Any appeal from such determination must be made in accordance with the EIA Procedure.

The Annex shows for each type of economic activity, the criteria for selection of whether IEE or EIA apply to the proposed economic activity. The MONREC determines whether the project is an IEE type project, or an EIA type project or if it is exempted from undertaking any environmental assessment.



Source: Environmental Impact Assessment Procedure, 2015

Figure 2.3-1 EIA Process Screening Phase

The Project Proponent might be required to submit a project proposal (completed in accordance with MONREC's guidelines) to the Environmental Conservation department of MONREC for screening.

Within 15 days from receiving the complete project proposal, the MONREC shall determine the required type of environmental assessment (EIA, IEE, or none) and shall inform the Project Proponent

in writing about its determination. In addition, the MONREC can change the status of an IEE Type Project to be an EIA Type Project if any of the above additional factors are relevant in this sense.

2) Scoping Phase


All EIA type projects are required to undergo the Scoping Phase. The project proponent shall be responsible to ensure that the Scoping and the preparation of the Term of Reference (TOR) for the EIA report are undertaken in a professional manner and in accordance with any applicable guidelines issued or adopted by the MONREC. The scoping shall, in respect to the proposed project:

- define the study area, AoI, time boundaries, project phases, and potential stakeholders;
- start the process of understanding the applicable regulations and standards, and their context for project design and completion of the EIA;
- make a provisional identification of environmental, social and, if any, health impacts, focusing in particular on the environmental, social and health issues that need to be addressed in subsequent EIA studies;
- provide an indication of the required baseline data and information and methods to obtain them (although there is no need to actually collect any data at this stage);
- provide an opportunity for consultants, relevant authorities, project developers, interested and affected parties to express their views and concerns regarding the proposal before an EIA proceeds;
- enable an efficient and comprehensive assessment process that saves time, resources, costs and delays; and
- identify potentially affected communities and other stakeholders with an interest in the project.

As part of the scoping, the project proponent shall ensure that the following public consultation and participation process is carried out.

- disclose information about the proposed project to the public and civil society through local media, including by means of the prominent posting of legible sign boards and advertising boards at the Project Site which are visible to the public; and
- arrange the required complement of consultation meetings as advised by the MONREC, with local communities, potentially PAPs, local authorities, community-based organizations, and civil society.

The project proponent shall prepare a scoping report and TOR for the EIA investigations and submit the completed Scoping Report and TOR to the MONREC for review and approval. The Scoping process is shown in the following Figure.



Source: Environmental Impact Assessment Procedure, 2015

Figure 2.3-2 EIA Scoping Process

3) EIA Investigation and Report Preparation

The Project Proponent has to ensure that the EIA investigation properly addresses all adverse impacts and is undertaken in accordance with the approved TOR. The EIA investigation shall consider all biological, physical, social, economic, health, cultural and visual components of the environment, to get her with all pertinent legal matters relating to the environment (including land use, resources use, and ownership of and rights to land and other resources) that may be affected by the Project during all project phases, including pre-construction, construction, operation, decommissioning, closure, and post-closure; and shall identify and assess all adverse impacts and risks for environment, social and, if relevant, health that potentially could arise from the Project.

According to the Chapter 1: Title and Definition/ Article 2. of the EIA Procedure, “(h) [...] social impacts include involuntary resettlement and relating to indigenous people.” as such the procedure requires. The Chapter 5: Environmental Impact Assessment/Article 59 of the EIA Procedure stipulates that the Project Proponent is obliged to use, comply with and refer to applicable national and international standards adopted by the Union Government and/or the Ministry, or, in the absence of relevant national or adopted international standards, such standards as may be agreed with the Ministry.


Land acquisition, requires the finalization of the detailed design, based on which Detailed Measurement of Study (DMS) is carried out. Actual land acquisition and compensation takes place when the inventorization of the loss of assets are finalized based on the results of the DMS and extensive consultations with the public and the affected households and communities. Thus, at the

later stage, separate procedures related to this process shall be issued by responsible ministries. In the absence of such procedures all such Projects shall adhere to international practice on involuntary resettlement and indigenous people.

The EIA Report shall consider the views, concerns, and perceptions of stakeholders, communities and individuals that could be affected by the Project or who otherwise have an interest in the Project. The EIA should include the results of public consultations and negotiations with the affected populations on the environmental and social issues. Public concerns should also be taken into account in assessing impacts, designing mitigation measures, and selecting monitoring parameters. After completing all investigations and public consultation and participation processes required for EIA Type Projects, the Project Proponent shall submit the EIA Report to the MONREC in both digital and hard copy, together with the required service fee.

The MONREC shall within 10 days after submission disclose the EIA Report to civil society, PAPs, concerned government organizations, and other interested stakeholders. The MONREC shall submit the EIA Report to the EIA Report Review Body for comment and recommendations and also arrange for public consultation meetings at national and State/Regional/local levels where the Project Proponent shall present the EIA Report. All received comments and recommendations, including those of the EIA Report Review Board, will be collected and reviewed by the MONREC prior to making a final decision on approval of the EIA Report.

The MONREC shall deliver its final decision within 90 days from the receipt of the EIA Report. All costs incurred in completing to the EIA Report disclosure and review, including the public participation process, shall be borne by the Project Proponent. Upon completion of its review of the EIA Report, the MONREC will issue an Environmental Compliance Certificate (ECC) or inform the Project Proponent of its decision to reject the EIA Report and publicly disclose its decision. The proposed flow chart covering the EIA review process is shown in the following Figure.



Source: Environmental Impact Assessment Procedure, 2015

Figure 2.3-3 EIA Review and Approval within the Myanmar EIA Process

In conclusion, the IEE and EIA approval process can be summarized as reported in the following Table.

Table 2.3-1 IEE and EIA approval process in Myanmar

EIA Process	Duration
IEE/EIA/NON Proposal Screening	15 days
IEE Process	
- Approval of IEE experts	7 days
- IEE report preparation	-
- IEE report approval	60 days
EIA Process	
- Approval of EIA experts	7 days
- Developing EIA scoping report and TOR	-
- Scoping report and TOR approval	15 days
- Investigation/preparing EIA report	-
- EIA report approval	90 days

Source: Environmental Impact Assessment Procedure, 2015

2.4 Environmental Framework

2.4.1 Water Environment

The Conservation of Water Resources and Rivers Law (2006)

The aims of this law are as follows: (a) to conserve and protect the water resources and river system for the beneficial utilization of the public; (b) to enable smooth and safe waterways navigation along rivers and creeks; (c) to contribute to the development of the state economy through improving water resources and river system; and (d) to protect environmental impact.

However, this law is under the jurisdiction of the Ministry of Transport. This law focuses on transportation safety and its development. However, it lacks actual numerical criterion for natural environment.

Underground Water Act (1930)

The underground water act enacted on the date of 21st June in 1930 whereas it is expedient to conserve and protect underground sources of water supply in the Union of Burma. This act prohibits sinking of a tube for the purpose of obtaining underground water except under and in accordance with the terms of a license granted by the water officer. Township Officer or sub-divisional officer had power to close a license tube after exercising jurisdiction over the local area concerned and the expense of such closure shall be recoverable from the owner of the tube as if it were an arrear of land-revenue.

Canal Act (1905)

The Burma Canal Act was enacted by the Authority of the Government of the Union of Burma in 1905, and amended by Burma Act in 1914, 1924, 1928, and 1934, which has the aim to use and control for public purposes the water of all rivers and streams flowing in natural channels and of all lakes and other natural collections of water, and to control and undertake in whole or in part the maintenance of any work designed for irrigation, drainage, navigation or protection against floods or erosion. Canal Act has components enacted as below:

- 1) Application of water for public purposes,

- 2) Construction and maintenance of works,
- 3) Supply of water,
- 4) Water rates,
- 5) Village canal and village drainage works,
- 6) Canal navigation and drainage,
- 7) Obtaining labor for canals and drainage works,
- 8) Jurisdiction, offences and penalties, and
- 9) Supplementary provisions.

All river facilities such as bank protection, flood embankment, etc. proposed by the Project for smooth inland navigation and flood protection of Twante Canal shall be complied with the Canal Act.

Embankment Act (1905)

The Burma Embankment Act was enacted by the Authority of the Government of the Union of Burma in 1905, and amended by Burma Act in 1923, and 1931, in which the embankment is defined as any embankment constructed for the purpose of excluding, regulating or retaining water, and includes all earthen walls, dams, canals, drains, piers, groins, sluices, buildings, water-gauges, bench-marks and other works subsidiary to any such embankment. Embankment Act stipulates clauses regarding embankment and embankment works such as duties of Embankment-officer, obtaining labor and material, payment and compensation, offences and penalties, etc.

Rules to regulate the navigation of the Twante (Twantay) Canal

Revenue Department (Separate Revenue Branch) Notification No.55, dated the 25-2-1935 as subsequently amended by notifications Nos. 157,162,353,313,6,162 and 437, dated the 10-7-35,17-7-35 ,8-12-37,7-10-38,61-40 and 28-10-40 respectively.

These rules are supplementary to the rules made under the Inland Steam Vessels Act, 1917, which will continue to govern all matters for which the rules do not specially provide.

Without the written permission of the Divisional canal officer, no vessel shall navigate the Twante (Twantay) Canal whose capacity exceeds 400 tons or whose dimensions exceed the following limits; -

Length 170 feet.

Breadth 50 feet.

Draught 8 feet 6 inches.

All cargo boats, and other under oars or sail shall keep out of the way of steam or motor vessels and avoid tacking across their bows so close as to cause the steam or motor vessel to maneuver to avoid collision.

No vessel shall proceed through the Canal at a greater speed than 8 miles per hour against the current and 12 miles per hour with current or at slack water, both speed being relative to the ground.

- (i) During construction or survey warning flags by day and lights by night may be displayed at suitable positions upstream and downstream, and no vessel shall pass or attempt to pass such warning signals so long as they remain hoisted.
- (ii) When the warning signals are lowered traffic may proceed dead-slow.

The Divisional Canal Officer shall have power to prohibit the loading or unloading of passengers for cargo. No person shall place any bamboo, pole, fishing stake, fishing net, or obstruction in the canal. Any canal Officer may remove or destroy any such obstruction forthwith.

2.4.2 Forestry/Biodiversity

The Protection of Wildlife and Wild Plants and Conservation of Natural Areas Law (1994)

The objectives of this law are to implement the Government policy for wildlife protection and natural areas conservation, to carry out in accordance with the relevant International Conventions; to protect endangered species of wildlife and their natural habitats; to contribute to the development of research on natural science; and to protect wildlife by the establishment of zoological/botanical gardens. It prescribes the formation of the committee for protection of wildlife and natural areas with its function and duties and the determination of natural areas and endangered species of wild animal that are subject to protection.

The Protection of Wildlife and Natural Areas Law, 1994

The State Law and Order Restoration Council had enacted the Protection of wildlife and Natural Areas Law on 8th June, 1994.

The objectives of this Law are as follows:

- a) to implement the Government policy for wildlife protection;
- b) to implement the Government policy for natural areas conservation;
- c) to carry out in accordance with the International Conventions acceded by the State in respect of the protection and conservation of wildlife, ecosystems and migratory birds;
- d) to protect endangered species of wildlife and their natural habitats.

National Biodiversity Strategy and Action Plan (NBSAP) The National Biodiversity Strategy and Action Plan (NBSAP) of Myanmar was adopted by the Cabinet on 03 May 2012. The strategy contains 10 strategic directions as followings:

- Strengthening conservation of priority sites;
- Mainstreaming biodiversity into other policy sectors;
- Implementing focused conservation actions for priority species;
- Supporting local Non-Governmental Organization (NGOs) and academic institutions;
- Creating capacity to coordinate conservation investment in Myanmar;
- Scaling up implementation of in-situ and ex-situ conservation of agriculture, livestock and fisheries biodiversity and genetic resource management;
- Expediting the process of implementing the national bio-safety framework;
- Promoting the initiative to manage IAS;
- Facilitating the legislative process of environmental protection and environmental impact assessment; and
- Enhancing communication, education and public awareness on biodiversity conservation.

2.4.3 Cultural Heritages

The Protection and Preservation of Cultural Heritage Regions Law(1998, amended in 2009)

- a) The State Peace and Development Council Law enacted this law by Law No. 9/ 98 on the date of the 10th September 1998. The article 21 (c) prescribes that the proponent shall request the prior permission from the Department to carry out building road, constructing bridge, irrigation canal, embankment or extending the same and the article 23 of the said law described that no person shall plough and cultivate or carry out any activity which may cause damage to the cultural heritage within the boundary notified by

the Department in the cultural heritage region. The Ministry of Religious Affairs and Culture, with the approval of the Government, may issue notification for the protection of cultural heritage areas are categorized as ancient monumental zone and ancient site zone. This law established with the objectives of: to implement the protection and preservation policy with respect to perpetuation of cultural heritage that has existed for many years;

- b) to protect and preserve the cultural heritage regions and the cultural heritage therein so as not to deteriorate due to natural disaster or man-made destruction;
- c) to uplift hereditary pride and to cause dynamism of patriotic spirit of citizens by protecting and preserving the cultural heritage regions;
- d) to promote public awareness and will as to the high value of the protection and preservation of the cultural heritage regions;
- e) to protect the cultural heritage regions from destruction;
- f) to carry out protection and preservation of the cultural heritage regions in conformity with the International Convention approved by the State.

The Ministry of Religious Affairs and Culture prescribes the screening procedure of the cultural heritages in case any development project is prepared: A project proponent is required to screen the areas 90 feet (27.4 meter) radius from the limit of the construction sites, according to Annex (a): the general provisions for the cultural heritage region, the Protection and Preservation of Cultural Heritage Regions Rules (2011).

The Protection and Preservation of Antique Objects Law (2015)

The objectives of this law are to implement the policy of protection and preservation for the perpetuation of antique objects; to protect and preserve antique objects so as not to deteriorate due to natural disaster or man-made destruction; to uplift hereditary pride and to cause dynamism of patriotic spirit by protection and preservation of antique objects; to have public awareness of the high value of antique objects; and to carry out in respect of protection and preservation of antique objects in conformity with the International Convention and Regional Agreement ratified by the State. This law repeals the Antiquity Act of 1957. The Section 12 of this Law prescribes that the person who finds any object with no owner or custodian, he shall promptly inform the relevant Ward or Village-Tract Administrator if he knows or it seems reasonable to assume that the said object is an antique object.

According to the sub-section 13 (a) of the Law stipulates the following: if the information is received under section 12, the Ward or Village- Tract Administrator shall keep the said object as may be necessary and shall forward the information to the relevant Township Administrative Office within 14 days. The Township Administrator shall promptly carry out the necessities and inform the Department within 7 days from the date on which the information is received. Also, the Department shall inspect whether it is a real antique object or not and keep or cause to keep as may be necessary in accord with the stipulations when the information is received under sub-section (a).

The Antique Objects Act, 1957 is hereby repealed by this Law.

2.4.4 Health Standards for Project with Health Impacts

The Public Health Law (1972)

The Union Revolutionary Council enacted this law by No 1/1972 on the date of the 12th January 1972. It is concerning with protection of people's health by controlling the quality and cleanliness of food, drugs, environmental sanitation, epidemic diseases and regulation of private clinics. This law established with the objectives of:

- to create a more healthful environment
- to provide the facilities and trained professionals to prevent and treat disease,
- to educate people to protect themselves
- to improve their conditions

Section-2:

This section covered communicable disease prevention and environmental sanitation to protect public health and to enhance public health not only by prohibiting harmful activities or conditions, but also by providing preventive and rehabilitative services to advance the health of the people. Regarding environmental sanitation, it is included that

- a. limited control of the disposal of human and other wastes
- b. concerns for water purity and the hygiene of housing
- c. limited interest in food and milk sanitation,
- d. incipient school health controls, and very little else.

The recently enacted rules require ESIA study for large projects according to the rules of the Ministry of Environmental Conservation and Forestry. Although the law does not specifically define legislation for ESIA's, the following investments are prohibited under this law:

- a. Business which can affect the traditional culture Business which can affect the traditional culture and customs of the national races within the Union;
- b. Business which can affect public's environment, causing noise in the residing area;
- c. Business which can affect public health;
- d. Business which can cause damage to the natural environment and ecosystem;
- e. Business which can affect the land and marine animals, trees, flowers, crops, antique heritage, resources;
- f. Business which can bring the hazardous or poisonous waste into the Union;
- g. The factory which produce or the business which use hazardous chemicals under international agreements

The Prevention and Control of Communicable Diseases Law (1995, revised in 2011)

This law describes functions and responsibilities of health personnel and citizens in relation to prevention and control of communicable diseases. It also describes measures to be taken in relation to environmental sanitation, reporting and control of outbreaks of epidemics and penalties for those failing to comply. The law also authorizes the Ministry of Health to issue rules and procedures when necessary with approval of the government.

In case of the communicable disease outbreaks in the course of the project implementation, the project proponent will follow these guidelines in the said law:

9. The head of the household or any member of the household shall report immediately to the nearest health department or hospital when any of the following events occur:-

- (a) rat fall
- (b) outbreak of a Principal Epidemic Disease;
- (c) outbreak of a Notifiable Disease.

10. Traditional medicine practitioners, health assistants and doctors shall report immediately to the nearest health department or hospital if a case of Principal Epidemic Disease or Notifiable Disease is found during practice.

Occupational Safety and Health Law (2012)

The objectives of this law are as follows:

- 1) To support the development of the State's economy through the development of production by ensuring better security in social life and healthcare for the workers who are major productive force of the State by the collective guarantee of the employer, worker and the State;
- 2)) For the public to enjoy better security in social life and medical care by affecting their insurance voluntarily to raise public confidence up on the social security scheme by providing benefits which are commensurate with the realities;
- 3) To have the right to draw back some of the contributions paid by the employers and the workers as savings, in accord with the stipulations;
- 4) To obtain the right to continued medical treatment, family assistance benefit, invalidity benefit, superannuation benefit, survivors' benefit, unemployment benefit, the right to residency and ownership of housing after retirement in addition to health care and pecuniary benefit for sickness, maternity, death, employment injury of the workers.

It prescribes that all employers shall formulate an occupational safety and health management system which must be suitable and applicable to the nature of the industry to which his/her workplace belongs and submit it to the Department at least 30 days before opening the business.

The employers also shall form a workplace safety and health committee, reflecting the nature of the industry, in accordance with the prescribed requirements, with an equal number of representatives from workers and employers in every industry where the number of workers working is not fewer than the amount of the workers prescribed by the Ministry, with the intention of achieving safe and healthy workplaces.

Natural Disaster Management Law 2013

PyidaungsuHluttaw (Assembly of the Union) enacted this Law by No.21/2013, 31July 2013.

The objectives of this Law are as follows:

- a. To implement natural disaster management programmes systematically and expeditiously in order to reduce disaster risks;
- b. To form the National Committee and Local Bodies in order to implement natural disaster management programmes systematically and expeditiously;
- c. To coordinate with national and international government departments and organizations, social organizations, other non-government 3 organizations or international organizations and regional organizations in carrying out natural disaster management activities;
- d. To conserve and restore the environment affected by natural disasters;
- e To provide health, education, social and livelihood programmes in order to bring about better living conditions for victims.

Appropriate disaster reduction and management plan would need to be drafted as part of the environmental and social management plan.

2.5 Legal and Policy Framework on the Land Acquisitions and Resettlement

2.5.1 Relevant Policies, laws and regulations

Relevant laws and regulations related to land tenure, land use, land acquisition, compensation of assets and losses in Myanmar are summarized in Table 2.5-1.

Table 2.5-1 Relevant Laws and Regulations on Land Acquisition and Resettlement

Policy, Law and Regulation	Description
Land Acquisition Act No. 1/1894	<ul style="list-style-type: none"> The Act is still the legal basis for land acquisition which is consideration for calculating a suitable amount of compensation is to be made as quickly as possible for affected people when their land is acquired by the government. Government has authority to acquire the land under this Act not only for public purpose but also for business reasons for the companies at that time.
Forest Law 8/92	<ul style="list-style-type: none"> The law includes the classification of type of land belonging to Forestry Department. The law supports conservation, sustainable forestry and socio-economic benefits. In addition, the law decentralizes forest management to some degree and encourages the private sector and community participation in forest management
Union Government Notification No. 39/2011	<ul style="list-style-type: none"> On the application of right to use land owned by government, government departments, organizations, and citizens.
Myanmar Special Economic Zone Law, 2011	<ul style="list-style-type: none"> The developer shall bear the expenses of transferring and compensation of houses, buildings, farms and gardens, orchards/ fields, plantation on land permitted by the Central Body if these are required to be transferred
Farmland Law 11/2012	<ul style="list-style-type: none"> The law introduces right to use the land to farmers through land use certificate and acquiring the farmland for other purpose
Farmland Rules 62/2012	<ul style="list-style-type: none"> The Rules detail the eligibility of farmer or organization for the process of acquiring land use certificate, the role and responsibility of farm land committee in various level and the application process of land use certificate. And regulating the requirement of indemnity and compensation to the affected person when it comes to the case of confiscating farms in the interests of nation.
Vacant, Fallow & Virgin Lands Management Law 10/2012	<ul style="list-style-type: none"> Stipulation of claiming unused land to usable in form of agriculture, livestock, mining & government allowable other purpose.
Vacant, Fallow & Virgin Lands Management Rules 1/2012	<ul style="list-style-type: none"> The Rules introduce the process of application and approval of the unused land for various purposes;
National Land Use Policy (2016)	<ul style="list-style-type: none"> The most updated guidance notes on land acquisition, but no procedures or laws have been defined.
Draft Guidelines on Public Participation in Myanmar's EIA Processes (2017)	<ul style="list-style-type: none"> This is a draft version issued by MONREC on 31 May 2017 Provide more specific guidelines conducting public consultations related to EIA procedures. While not yet officially adopted, the EIA team was encouraged to refer to it as in draft version.
Transfer of Property Act (1882)	<ul style="list-style-type: none"> Property of any kind may be transferred, except as otherwise provided by this Act or by any other law for the time being in force. Transfer of property may be made without writing in every case in which a writing is not expressly required by law.
Land and Revenue	<ul style="list-style-type: none"> This Act extends to Lower Burma and the Thayetmyo District of Upper

Policy, Law and Regulation	Description
Act (1879)	<p>Burma</p> <ul style="list-style-type: none"> The President of the Union may, by notification, except any area from the operation of this Act. <p>Nothing contained in this Part shall be applied to the following:</p> <ol style="list-style-type: none"> Land included in any forest constituted a “reserved forest” under the law for the time being in force; Land included in any fishery demarcated under the Fisheries Act; The soil of any public road, canal, drain or embankment; Land included within the limits of any town; Land appropriated to the dwelling-places of any town or village; Land included in any military cantonment; Land included in any civil station;
The Lower Burma Town and Village Land Act (1899)	<ul style="list-style-type: none"> This Act extends to Lower Burma and the Thayetmyo District of Upper Burama The provisions of this Act shall apply only to land in towns and villages. A landholder’s right in respect of any land shall cease if the landholder abandons the land for two years continuously
The Partition Act (1893)	<ul style="list-style-type: none"> Nothing herein contained shall be deemed to affect any local law providing for the partition of immoveable property paying revenue to Government.
The Registration Act (1909)	<ul style="list-style-type: none"> The President of the Union shall appoint an officer to be the Inspector-General of Registration; Any Inspector-General may hold simultaneously any other office under the Government.
Procedures conferring the Right to Cultivate Land (1991)	<ul style="list-style-type: none"> The Central Committee for the Management of Culturable Land, Fallow land and waste land may grant to citizens for agriculture and livestock breeding purposes the right to cultivate/right to utilize culturable land, fallow land and waste land up to the extent mentioned below: <ol style="list-style-type: none"> Agriculture Livestock, Poultry Farming and Aquaculture <p>If an application is submitted by organization consisting of foreigners for the right to cultivate/ right to utilize land, the matter is to be referred to the Foreign Investment Commission</p>

Source: Government of Myanmar and EIA Team

2.5.2 Overview of Legal System on Land Acquisition and Resettlement of Myanmar

Even though relevant laws and regulations in Myanmar listed in Table 2-1, it can be evaluated that currently there is no law comprehensively stipulating land acquisition and resettlement regulations in Myanmar except EIA Notification (2015) of which Article No. 7 stipulates as follows.


- Article 7; EIA Procedure does not address specific matters in relation to resettlement. Projects involving resettlement shall additionally comply with separate procedures issued by responsible ministries, and in the absence of such procedures all such, Projects shall adhere to international best practice on Involuntary Resettlement (as accepted by international financial institutions including the World Bank Group and Asian Development Bank) on Involuntary Resettlement and Indigenous Peoples.

Therefore, the Project will also need to be consistent with international lender’s safeguards policies, specifically World Bank OP/BP 4.12 on Involuntary Resettlement and OP/BP 4.10 on Indigenous Peoples as well as ADB's Safeguard Policy Statements on the related issues, in addition to the EDCF Safeguard Policy. EDCF Safeguard Policy also requires the Project Proponent to refer to the

international practices, in case the national legislation and regulations are less stringent (Art. 18 of the Safeguard Policy⁴).

2.5.3 Institutional Framework on Land Acquisition and Involuntary Resettlement in Myanmar

On 27, September 2018, Land Compensation and Resettlement Negotiation Committee was formed at each of the four affected Townships. The members of each Committee are composed of 9-13 persons (seen in Appendix 2-1).



⁴" 18. A proposed project must comply with the borrowing country's environmental and social requirements, and may refer to internationally recognized standards, when appropriate. If the relevant requirements of the borrower's country regulations and laws are more stringent than the requirements of the EDCF Safeguard Policy or internationally recognized standards, it is required that the project may comply with more stringent requirements."

2.5.4 Steps of Farm Land to use for Public Purpose

In order to acquire farm land to use for public purpose, two main steps are required as follows.

- First: the project owner has to get approval from a Settlement and Land Record Department under Ministry of Agriculture and Irrigation at relevant township for conversion of land from agricultural land to other purposes.
- Second: the project owner has to set compensation price in consulting with a compensation committee organized by General Administration Department (GAD) at relevant Township.

2.6 International Conventions, Treaties and Agreements

Myanmar has also made commitments to the following international agreements and protocols on environmental, social, safety and occupational issues as shown in the Table 2.6-1.

Table 2.6-1: International Environmental Convention/Protocol/Agreement

<i>No</i>	<i>International Environmental Convention/Protocol/Agreement</i>	<i>Date of Signature</i>	<i>Date of Rectification</i>	<i>Date of Member</i>	<i>Cabinet Approval Date</i>
1	Plant Protection Agreement for the South-East Asia and the Pacific Region, Rome, 1956		4-11-1959 (Adherence)	4-11-1959	
2	Treaty Banning Nuclear Weapons Test in the Atmosphere in Outer Space and Under Water, Moscow, 1963	14-08-1963	15-11-1963 (rectification)		
3	Treaty on the Prohibition of the Emplacement of Nuclear Weapons and other Weapons of Mass Destruction on the Sea-Bed and Ocean Floor and in the Subsoil there of, London, Moscow, Washington, 1971	11-02-1971			
4	Convention on the Prohibition of the Development, Production and Stockpiling of Bacteriological (Biological) and Toxin Weapons, and on their Destruction, London, Moscow, Washington, 1972	10-04-1972			
5	International Convention for the Prevention of Pollution from Ships, London, 1973	(Accession)	undertakes to give effect to this Convention under para 1 & 2 of Article 1 of the Protocol of 1978		
6	Protocol of 1978 Relating to the International Convention for the Prevention of Pollution from Ships, London, 1973		04-8-1988 (Accession)	Except for Annexes III, IV and V of the Convention	
7	United Nations Convention on the Law of the Sea, Montego Bay, 1982	10-12-1982	21-05-1996 (Ratification)		

8	United Nations Framework Convention on Climate Change, New York, 1992 (UNFCCC)	11-06-1992	25-11-1994 (Ratification)		41/94 (09-11-1994)
9	Convention on Biological Diversity, Rio de Janeiro, 1992	11-06-1992	25-11-1994 (Ratification)		41/94 (09-11-1994)
10	Treaty on the Non-Proliferation of Nuclear Weapons, London, Moscow, Washington, 1968		02-12-1992(Accession)		
11	Convention on the Prohibition of the Development, Production, Stockpiling and Use of Chemical Weapons and their Destruction, Paris, 1993	14-1-1993			
12	International Tropical Timber Agreement (ITTA), Geneva, 1994	06-07-1995	31-1-1996 (Rectification)		
13	Vienna Convention for the Protection of the Ozone Layer, Vienna, 1985		24-11-1993 (Rectification)	22-2-1994	46/93
14	Montreal Protocol on Substances that Deplete the Ozone Layer, Montreal, 1987		24-11-1993 (Rectification)	22-2-1994	46/93
15	London Amendment to the Montreal Protocol on Substances that Deplete the Ozone Layer, London, 1990		24-11-1993 (Rectification)	22-2-1994	46/93
16	The Convention for the Protection of the World Culture and Natural Heritage, Paris, 1972		29-4-1994 (Acceptance)		6/94
17	ICAO ANNEX 16 Annex to the Convention on International Civil Aviation Environmental Protection Vol. 1 Aircraft Noise	Accession			
18	ICAO ANNEX 16 Annex to the Convention on International Civil Aviation Environmental Protection Vol. II Aircraft Engine Emission	Accession			
19	Treaty on Principles Governing the Activities of States in the Exploration and Use of Outer Space Including the Moon and Other Celestial Bodies Outer Space Treaty), London, Moscow, Washington, 1967	22-5-1967	18-3-1970 (Rectification)		
20	Agreement on the Networks of Aquaculture Centres in Asia and the Pacific, Bangkok, 1988		22-5-1990 (Accession)		
21	South East Asia Nuclear Weapon Free Zone Treaty, Bangkok, 1995	15-12-1995	16-7-1996 (Rectification)		
22	United Nations Convention to Combat Desertification in Those Countries Experiencing Serious Drought and / or Desertification,		02-01-1997(Accession)	02-04-1997	40/96 (4-12-96)

	Particularly in Africa, Paris, 1994 (UNCCD)				
23	Convention on International Trade in Endangered Species of Wild Fauna and Flora, Washington, D.C., 1973; and this convention as amended in Bonn, Germany, 1979 (CITES)		13-6-1997 (Accession)	11-09-1997	17/97 (30-4-97)
24	Agreement Relating to the Implementation of Part XI of the United Nations Convention on the Law of the Sea of 10 December 1982, New York, 1994		21-5-1996 (Accession)		
25	Agreement to Promote Compliance with International Conservation and Management Measures by Fishing Vessels on the High Seas, Rome, 1973		8-9-1994(Acceptance)		
26	ASEAN Agreement on the Conservation of Nature and Nature Resources, Kuala Lumpur, 1985	16-10-1997			
27	Cartagena Protocol on Biosafety, Cartagena, 2000	11-05-2001			13/2001 (22-03-2001)
28	ASEAN Agreement on Transboundary Haze Pollution	10-06-2002	13-3-2003 (Rectification)		7/2003 (27-02-2003)
29	International Treaty on Plant Genetic Resources for Food and Agriculture, 2001		04-12-2004(Rectification)	29-6-2004	
30	Kyoto Protocol to the Convention on Climate Change, Kyoto, 1997		13-8-2003(Accession)		26/2003 (16-07-2003)
31	Stockholm Convention on Persistent Organic Pollutants (POPs), 2001		18-4-2004 (Accession)	18-7-2004	14/2004 (01-04-2004)

2.7 Legal and Regulatory Framework of Development, Planning and Management for Yangon City

2.7.1 The State Level – The Constitution of Myanmar

The State Constitution of the Republic of the Union of Myanmar was ratified and promulgated by the National Referendum held in May 2011. In the Constitution some of the provisions related to the urban planning and land management are summarized as follows:

- The Union is the ultimate owner of all lands and natural resources in the area. (Section 37)
- Citizens are given the right for private property. (Section 37);
- The Union guarantees the right to ownership and the use of property. (Section 372);
- Every citizen has the duty to assist the Union in preserving and safeguarding the cultural

heritage, conserving the environment, striving for the development of human resources, and protecting and preserving the public property. (Section 390).

2.7.2 Yangon City Development Committee

The present city authority, the YCDC, which was established to promote development projects in Yangon region in accordance with the City of Yangon Development Law of 14 May 1990, is an independent body, bestowed with wide powers and authority. Under the provisions of this Act, the YCDC may establish policies, guidelines, supervision and implementation based on the following duties and responsibilities:

- Drawing and implementing land policies, administration of lands, developing and enforcing planning controls, protection of heritage buildings, regulation of construction sites
- Construction and maintenance of parks, gardens, playgrounds, recreation centers
- Promoting events and exhibitions to enhance the work of YCDC
- Providing parking spaces for vehicles and reducing traffic congestion
- Construction, maintenance, upgrading and administration of markets
- Regulation, control and healthcare for animals and pets, including the inspection of meat and fishery markets and supervision of slaughterhouses
- Practice of environmental protection and waste management, including collection and treatment of waste, management of landfills, prevention of water and air pollution
- Regulate and issue licenses for ferryboats and supervision of ferry businesses
- Licensing and regulating trading warehouses and pawn shops
- Ensuring the safety of the citizens through prevention of natural disasters and management of the fire services
- Issue licenses regarding slow moving vehicles such as tricycle rickshaws
- Providing water supply and sanitary systems
- Supervision of cemeteries and incinerators, and overseeing the land use of cemetery compounds
- Other beneficial municipal work such as environmental services

The primary duties of the City Committee are such as street-lighting, water supply, garbage disposal, maintenance of parks and gardens, markets, slaughterhouses. Additional powers vested in the Committee by virtue of the Yangon City Development Law authorize territorial limits of the city, to operate city development works independently with its own funds, to assess and levy its own taxes, to utilize the funds currency derived from the lease of its own lands and premises for development works and to take loans and grants from the Government or from foreign organizations on its own responsibility. The organizational chart of YCDC is shown **Figure 2.7-1**.




Figure 2.7-1: Organizational Chart of YCDC

The YCDC, under the relevant City Development Laws has functions including drawing up civil projects and developing new towns, administering land in accordance with existing laws, constructing, maintaining and demolishing buildings, demolishing and resettlement of squatter houses, squatter buildings and squatter wards, carrying out environmental conservation work and other duties potentially involving land acquisition.

Regarding compensation the YCDC stipulates that in the event of damaging the neighboring building or any part of the building, while carrying out the construction work with the committee's permission, the sufferer shall protest to the committee. In connection with the protest, the committee shall make inquiry immediately and if it is found to be true, the committee shall fix and pay the compensation to the sufferer after liaising with the construction work permit holder. The sufferer shall apply to the court of law concerned to get the compensation according to the existing law, if the compensation fixed by the committee is not accepted both parties or the committee is unable to fix the compensation.

2.7.3 City of Yangon Development Law (1990)

In 14 May 1990, the City of Yangon Development Law formally established the present incarnation of YCDC, delegating wide responsibilities to this body, including city planning, land administration, tax collection, and development. The Committee's duties stipulated in this law can be summarized as below:

- 1) Preparation of civil projects and establishment of new towns within the limits of the City of Yangon Municipality,
- 2) Administration of lands within the limits of the City of Yangon Municipality,
- 3) Determining only the population which should be allowed to settle properly in the City of Yangon,
- 4) Construction, repairing and demolition of buildings, demolition and re-settlement of squatter huts, squatter buildings and squatter wards,
- 5) Construction of roads, bridges and maintenance thereof,

- 6) Stipulation of conditions for traffic and parking of vehicles and slow-moving vehicles,
- 7) Construction of gardens, parks, playgrounds and recreation centers and maintenance thereof,
- 8) Carrying out works for lighting of roads and water supply,
- 9) Construction of reservoirs and pipelines and maintenance thereof,
- 10) Carrying out works for sanitation and public health,
- 11) Construction, maintenance and administration of markets,
- 12) Stipulation of conditions in respect of roadside stalls, and
- 13) Carrying out precautionary measures against fire.

The Law also gives YCDC the following powers:

(Section9):

- 1) Demarcation and re-demarcation of the territorial limit of the City of Yangon Municipality;
- 2) Having the right to operate works independently with funds owned by the Committee;
- 3) Prescribing, revising, assessing and collecting duties and taxes and their rates relating to development works, in accordance with the existing laws;
- 4) Having the right to apply the foreign currency derived from the lease of buildings, lease of lands or by other means, for development works;
- 5) Having the right to carry out works contributing to city development by making contacts with local and foreign organizations and with local and foreign individuals;
- 6) Having the right to take loans and grants from the Government or from foreign organizations on its own responsibility;
- 7) Having the right to carry out works by forming sub-committees for work;
- 8) Arranging modern methods and systems in order to carry out development works more effectively;
- 9) Exercising the powers conferred under the City of Yangon Municipal Act, rules and byelaws;
- 10) Exercising the powers conferred from time to time by the Chairman of the State Law and Order Restoration Council

Moreover, the Section 10 stipulates that establishment of new towns and administration of town lands within Yangon city shall be authorized by YCDC, despite anything contained in the existing City of Yangon Municipal Act, State Housing and Town and Country Development Board Act and other existing laws, and powers in respect of formulation and implementation of civil projects.

2.7.4 City of Yangon Municipal Act (1922)

This Act extends to the City of Yangon only: Provided that the President of the Union may, by notification, extend this Act or any part to any other local area in the Union of Burma.

The duty of carrying out the provisions of this Act shall, subject to the conditions and limitations herein after prescribed, be vested in a body to be called “The Municipal Corporation of the City of Rangoon”; and such body shall be a body corporate and have perpetual succession and a common seal and shall by the said name sue and be sued.

2.8 Environmental Quality Standards

Ministry of Natural Resources and Environmental Conservation, in exercise of the power conferred by sub-section (b) of section 42 of the 2012 Environmental Conservation Law (ECL), the National Environmental Quality (Emission) Guidelines were issued on December, 2015.

These Guidelines have been excerpted from the International Finance Corporation (IFC) Environmental Health and Safety (EHS) Guidelines, which provide technical guidance on good international industry pollution prevention practice for application in developing countries. The Guidelines are generally considered to be achievable in new facilities by existing technology at reasonable costs. Application of these Guidelines to existing facilities may involve the establishment of site-specific targets, with an appropriate timetable for achieving them.

Emissions Guidelines shall apply to any project subject to EIA Procedure, as adopted by the Ministry, in order to protect the environment and to control pollution in the Republic of the Union of Myanmar. These Guidelines specifically apply to all project types listed in the EIA Procedure under 'Categorization of Economic Activities for Assessment Purposes' which sets out projects that are subject to EIA, IEE, or EMP.

1) Air Emission

Projects with significant sources of air emissions, and significant potential impacts to ambient air quality, should prevent or minimize impacts by ensuring that: (i) emissions do not result in pollutant concentrations that reach or exceed ambient quality guidelines and standards, or in their absence the current World Health Organization (WHO) Air Quality Guidelines; and (ii) emissions do not contribute a significant portion to the attainment of relevant ambient air quality guidelines or standards (i.e. not exceeding 25 percent of the applicable air quality standards) to allow additional, future sustainable development in the same airshed (Source: National Environmental Quality (Emission) Guidelines, 2015).

Table 2.8-1 Ambient quality guidelines

Parameter	Averaging Period	Guideline Value $\mu\text{g}/\text{m}^3$
Nitrogen dioxide	1-year	40
	1-hour	200
Ozone	8-hour daily maximum	100
Particulate matter PM10 ^a	1-year	20
	24-hour	50
Particulate matter PM2.5 ^b	1-year	10
	24-hour	25
Sulfur dioxide	24-hour	20
	10-minute	500

^a Particulate matter 10 micrometers or less in diameter

^b Particulate matter 2.5 micrometers or less in diameter

Source: National Environmental Quality (Emission) Guidelines, 2015

2) Wastewater

This guideline applies to projects that have either direct or indirect discharge of process wastewater, wastewater from utility operations or storm water to the environment. It is also applicable to industrial discharges to sanitary sewers that discharge to the environment without any treatment. Process wastewater may include contaminated wastewater from utility operations, storm water, and sanitary sewage. Projects with the potential to generate process wastewater, sanitary (domestic) sewage, or storm water should incorporate the necessary precautions to avoid, minimize, and control adverse impacts to human health, safety or the environment.

**Table 2.8-2: Wastewater, Storm Water Runoff, Effluent and Sanitary Discharges
(General Application)³**

Parameter	Unit	Guideline Value
5-day Biochemical oxygen demand	mg/l	50
Ammonia	mg/l	10
Arsenic	mg/l	0.1
Cadmium	mg/l	0.1
Chemical oxygen demand	mg/l	250
Chlorine (total residual)	mg/l	0.2
Chromium (hexavalent)	mg/l	0.1
Chromium (total)	mg/l	0.5
Copper	mg/l	0.5
Cyanide (free)	mg/l	0.1
Cyanide (total)	mg/l	1
Fluoride	mg/l	20
Heavy metals (total)	mg/l	10
Iron	mg/l	3.5
Lead	mg/l	0.1
Mercury	mg/l	0.01
Nickel	mg/l	0.5
Oil and grease	mg/l	10
pH	S.U. ^a	6-9
Phenols	mg/l	0.5
Selenium	mg/l	0.1
Silver	mg/l	0.5
Sulphide	mg/l	1
Temperature increase	°C	<3 ^b
Total coliform bacteria	100 ml	400
Total phosphorus	mg/l	2
Total suspended solids	mg/l	50
Zinc	mg/l	2

^a Standard unit

^b At the edge of a scientifically established mixing zone which takes into account ambient water quality, receiving water use, potential receptors and assimilative capacity; when the zone is not defined, use 100 meters from the point of discharge

Note; 3 Pollution prevention and abatement handbook. 1998. Toward cleaner production. World Bank Group in collaboration with United Nations Environment Programme and the United Nations Industrial Development Organization. Source: National Environmental Quality (Emission) Guidelines, 2015

3) Noise Level

Noise prevention and mitigation measures should be applied where predicted or measured noise impacts from a project facility or operations exceed the applicable noise level guideline at the most sensitive point of reception. Noise impacts should not exceed the levels presented below, or result in a maximum increase in background levels of three decibels at the nearest receptor location off-site.

Table 2.8-3 Target Noise Level

Receptor	One Hour LAeq (dBA)	
	Daytime 07:00 – 22:00	Nighttime 22:00 – 07:00
Residential, institutional, educational	55	45
Industrial, commercial	70	70

Source: National Environmental Quality (Emission) Guidelines, 2015

2.9 Environmental Requirements for the Project

The Project shall satisfy both requirements of EDCF Safeguard Policy and EIA Notification (2015) of MONREC as mentioned in Section 2.3.6.

2.9.1 Requirement of the EDCF Safeguard Policy

Project Category by the EDCF Safeguard Policy

Requirement of the EDCF Safeguard Policy are dependent on “project categorization” of projects, which is stipulated in the Safeguard Policy. Currently, “Twante (Twantay) Canal Improvement Project” (the Project) has been classified as “Category A”, the project which is likely to have significant adverse environmental and social impacts that are irreversible, diverse, or unprecedented by the EDCF Safeguard Policy.

The Category A project will require to conduct ESIA.

- **Screening**

The borrower shall complete a screening form for categorization during the initial stages of project preparation and submit it to the Export-Import Bank of Korea as early as possible or at least before submission of the loan application.

- **ESIA and IESE**

The borrowers shall conduct ESIA for Category A projects and IESE for Category B projects. ESIA and IESE shall include ESMP. Major considerations of ESMP include: i) mitigation of adverse impacts to the extent of “no significant impacts to third parties”, ii) the polluters-pay principle and iii) precautionary principles.

The borrower shall prepare RP, if the proposed project will have involuntary resettlement impacts. If the proposed project is likely to have a direct or indirect impact on indigenous communities, the borrower is required to prepare IPP in a way that fosters respect for cultural traditions.

- **Monitoring**

The borrower shall monitor environmental and social impacts and implementation of ESMP (and RP or IPP, if applicable). The level of monitoring activities shall commensurate with project risks and impacts.

- **Information disclosure**

The Export-Import Bank of Korea requires the borrower to ensure that relevant environmental and social information is made available public for transparent decision-making. Information disclosure helps affected communities and other concerned stakeholders to assess and understand the risks, impacts, and opportunities with the project.

- **Consultation and Participation**

The borrower shall identify concerned stakeholders and develop communication mechanisms to facilitate dialogue among relevant stakeholders. The borrower will also develop and implement a participation mechanism tailored to the characteristics and interests of the affected people. The participation mechanism may include special measures to enable meaningful participation of vulnerable groups.

- **Local Grievance Redress Mechanism**

The borrower shall establish and maintain a grievance redress mechanism to receive and facilitate resolution of affected peoples' concerns and grievances about the borrower's environmental and

social performance at the project level. It should address affected people's concerns and complaints shortly, using an understandable and transparent process that is gender responsive, culturally appropriate, and readily accessible to most of the segments of the affected people.

2.9.2 Requirements for the Project by EIA Notification (2015) of Myanmar

(1) Project Categorization

Based on Annex 1 in EIA Procedures, 2015 "Categorization of Economic Activities for Assessment Purposes" of EIA Notification (2015), this type of project is classified as "River Channel Conservation (Surface water and water volume control)" of Type of Economic Activity (See Appendix A).

(2) Project Scope

The EIA of the proposed project is conducted by the Directorate of Water Resources and Improvement of River Systems (DWIR) of the Ministry of Transport and Communications of the Union of Myanmar with consultancy of the REM (qualified EIA company with MONREC registration) and the EDCF EIA Team (the ISAN Consortium) from the Republic of Korea. The Project aims to provide safe navigation, smooth flow of cargos, bank protection, flood protection and development in tourism. This scoping paper is submitted as a requirement of the EIA Procedure, 2015.

(3) Requirements for Project

In accordance with EIA Notification (2015) and the project components, it is recognized that the Project is subject to an EIA study and is required to obtain an ECC from ECD at MONREC.

Namely, the proponent for EIA for the Project is Directorate of Water Resources and Improvement of River Systems (DWIR) of the Ministry of Transport and Communications of the Union of Myanmar. Two rounds of public Consultations with stakeholders (Stakeholder Meetings) are also required to be initiated and implemented by DWIR.

As referred to above, all requirements for the project to satisfy both sets of standards (of Myanmar and EDCF Safeguard Policy) can be summarized in Table 2.9-1.

Table 2.9-1: All Environmental Requirements for the Project

Requirement	EIA Procedure (2015)	EDCF Safeguard Policy	Requirement for both standards
EIA Report	Yes (Project is categorized as Waste Management)	Yes (ESIA is required for the Project)	Yes
ECC	Yes (EIA is required for the Project)	Yes (ECC is to be obtained for the Project, if host country's national legislation requires so.)	Yes
RP (Resettlement Plan)	Yes (Art 7: reference to the international standards in the absence of the regulations issued by the relevant ministries, such as WBG policies etc.)	Yes (Appendix 5) (Households, land and business activity in existing ROW in Canal)	Yes

	(Households, land and business activity in existing ROW in Canal)		
Stakeholder Meetings (SHM)	Yes	Yes	Yes
Environmental Monitoring	Yes	Yes	Yes
Others (such as IPP, Public consultation, Cultural heritage and GRM)	<p>IPP - if required</p> <p>Public consultations - If required per screening</p> <p>Cultural heritage - Yes</p> <p>GRM - Not mentioned in Myanmar EIA procedure</p>	<p>IPP- If required</p> <p>Public consultations - Yes</p> <p>Cultural heritage - Yes</p> <p>GRM - Yes</p>	<p>The proposed project does not trigger indigenous peoples issue - IPP is not required</p> <p>Both public consultations and GRM mechanism settings are included as part of the ESIA.</p>

Source: REM Survey Team and ISAN Consortium ES Team

CHAPTER 3: PROJECT DESCRIPTION AND ALTERNATIVE ANALYSIS

3.1 Descriptions of the Proposed Project

3.1.1 Main Components

The Twante (Twantay) Canal Improvement Project was designed to address the current river erosion and frequent flooding which is hampering the steady and safe use of inland waterways, negatively affecting the lives of residents near the canal. It is necessary to improve the condition of the canal to ensure development of the region through enhancing the inland water transport capacity and safety along the canal. In addition, flood protection facility which protects the shore and prevents flood-induced inundations will be established.

The Twante (Twantay) Canal Improvement Project is composed of two phases: The first phase is on channel training and flood embankment. The second phase aims to development of multi-purpose barrages. This EIA report only covers the first phase. The detailed design, component, geographical coverage and financing schemes for the second phase shall be planned in the future.

Project components at Phase 1 comprise of measures to resolve urgent and serious problems such as bed and bank erosion and flood damages. Channel training measures are designed to reduce the flow velocity due to the tidal flow and to stabilize the flow field in the Twante (Twantay) Canal whereas flood embankment measures are to maintain the water level below the designed flood level during the largest spring tide. This project component will ensure less physical, social, and environmental damages due to bed and bank erosion and flood and protect lives, properties, and livelihood of affected persons.

The Project is composed of the following two components:

Component 1- Channel Training – Embankment construction (5.88km) and Bed erosion protection construction ($A= 55,500 \text{ m}^2$)

Component 2- Flood protection- Embankment construction for flood protection (3 sections, 39.5 km)

The location map of the project component phase 1 is shown in Figure 3.1-1.




Figure 3.1-1: Location Map of Proposed Project Components at Phase 1

3.1.1.1 Component 1: Channel Training

Component 1 consists of two sub-components: 1.1-Bank Protection and 1.2 -Bed Scour Prevention as shown in **Figure 3.1-2**. The main purpose of Sub-Component 1.1-Bank Protection is to mitigate channel contraction reducing the flow velocity and erosion risk near 0mile junction. Major work items include:

- 1) Removal of 4 groynes on both sides at 0.5 mile,
- 2) Improvement of the channel alignment near 0.5 mile, and
- 3) Installation of the bank protection near 0-mile junction area (L=5,880m).



Figure 3.1-2: Location Map of Component 1

Sub-component 1.1 was designated to protect the bank from erosion due to tidal flows near 0-mile junction and to regulate the velocity field. Particularly, it aims to reduce the maximum flow velocity at 0.5 mile, that is, the maximum velocity of 2.37 m/s decreases to 1.19 m/s during the flood tide while the maximum velocity of 3.23 m/s decreases to 1.46 m/s during the ebb tide. It is encouraged that this sub-component affects negligibly the flow field at 3.5 mile inducing 3~4% increase of flow velocity as shown in **Table 3.1-1** below. However, it is noticeable that there is potential of bed change near the junction at 0 mile showing low velocity field near the junction of the Khanaungto Creek, recapping that multi-purpose barrages at Phase 2 are required as permanent measure against the bed change. Based on the soil investigation results near the Project site, it was found that the Twante (Twantay) Canal is on the weak foundation and so the following factors shall be considered for the design of the bank protection:

- 1) Weight reduction using lightweight materials,
- 2) Soil improvement by replacement, and
- 3) Frame formation by piling.

Basically, the original silty soil is required to be replaced by sandy soil for stability of the bank

protection, which was considered for the design in the Study. The bank protection proposed in the Study consists of slope protection and toe protection. First, the slope protection is to protect the bank erosion from tractive force of tidal flow and wave action from shipping and its type can be classified into hard and flexible surface types. The hard surface type may cover the bank using bricks, concrete blocks, cement grouted rocks, etc. while the flexible surface type may use gabion mattress, hand-placed, dry rubble facing, dumped riprap, Reno mattress, etc. Main features of slope protection type can be compared as seen in **Table 3.1-2**. As seen in the table, each type has both strong and weak points and with regard to weak foundation of the Project site, the rip-rap type was found to be unsuitable for slope protection, thus the other two types, i.e. environmental block and gabion mattress, were considered in the Study.

Table 3.1-1: Summary of Flow Velocity Distribution at 0 and 3.5 Miles

Division			Original	Case1	Case2	Case3	Case4	Case5	Case6	Case7
Flood Tide	0.5 mile	Max	2.37	1.19	1.93	1.66	1.24	1.03	1.74	1.06
		Avg	1.53	1.14	1.60	1.37	1.18	0.99	1.46	1.01
		Min.	0.93	1.04	1.05	0.85	1.07	0.91	0.89	0.92
	3.5 mile	Max	1.43	1.46	1.40	1.28	1.48	1.26	1.28	1.26
		Avg	1.25	1.29	1.24	1.12	1.31	1.12	1.12	1.12
		Min.	1.00	1.06	1.02	0.91	1.07	0.93	0.91	0.93
Ebb Tide	0.5 mile	Max	3.23	1.46	3.49	3.13	1.50	1.47	3.47	1.51
		Avg	1.80	1.19	2.03	1.81	1.24	1.18	2.01	1.24
		Min.	0.66	0.80	0.92	0.64	0.87	0.79	0.70	0.86
	3.5 mile	Max	1.55	1.63	1.53	1.56	1.62	1.63	1.55	1.63
		Avg	1.38	1.43	1.37	1.38	1.42	1.43	1.37	1.43
		Min.	0.76	0.85	0.87	0.76	0.84	0.85	0.76	0.85

Source: Feasibility study on Twante Canal Integrated Management Project in Yangon, Myanmar, Final Report, October 2014

Table 3.1-2: Main Features of Major Slope Protection Type

Evaluation Items	Rip-rap	Environmental Block	Gabion Mattress	Remarks
1. Strength	+++	+++	+++	
2. Weight (light)	+	++	++	Key
3. Flexibility	+++	+	++	
4. Economical View	++	++	++	
5. Landscape	++	+++	++	

Note) +++: excellent, ++: fair, +: poor


Source: Feasibility study on Twante Canal Integrated Management Project in Yangon, Myanmar, Final Report, October 2014

The toe protection serves as the foundation of slope protection against falling down of the back-fill and slope covering materials preventing from scouring at the foundation of slope protection. In general, dumping rip-rap, gabion box or piling with filling stones is applicable for the toe protection, which was considered for the design in the Study. Two types of bank protection are proposed as seen in **Table 3.1-3** and **Figure 3.1-3**.


Table 3.1-3: Structures of Bank Protection Type

Division	Type 1	Type 2	Remarks
Slope Protection	<ul style="list-style-type: none"> Environmental block Geotextile Sand replacement 1:2 slope 	<ul style="list-style-type: none"> Gabion mattress Geotextile Sand replacement 1:2 slope 	
Toe Protection	<ul style="list-style-type: none"> Gabion box Sand and rubble Piling 	<ul style="list-style-type: none"> Gabion box Sand and rubble Piling 	
Bottom Protection	<ul style="list-style-type: none"> Stone pouch 	<ul style="list-style-type: none"> Stone pouch 	

Photographs



(a) Type 1




(b) Type 2

Figure 3.1-3: Typical Section of Bank Protection

The main purpose of Sub-Component 1.2 Bed Scour Prevention is to mitigate irregularity in flow depth and to regulate the streamwise flow field near 0 mile junction raising the minimum bed level from El.-27.6m to El.-15.0m. In principal, the deep pool near 0 mile junction will be filled with sand materials and the channel bed can be armored by rip-rap, gabion mattress, concrete block, etc. for scouring prevention whose dimension can be determined based on the flow characteristics.

Referring to HEC11 from U.S. Department of Transportation Federal Highway Administration, and the Design Guidelines by the Ministry of Land, Infrastructure and Transport (MOLIT) of Republic of Korea, the armoring countermeasures are designated as shown in **Table 3.1-4**. In the Study, the main features for each countermeasure were seriously reviewed and finally the stone gabion with fiber pocket was adopted for bed armoring in the Project as shown in **Figure 3.1-4**.

Table 3.1-4: Main Features of Armoring Countermeasures

Division	Riprap	Stone Gabion (wire)	Stone Gabion (fiber)
Requirements	<ul style="list-style-type: none"> • Riprap size (0.3 m) • Thickness (0.5 m) 	<ul style="list-style-type: none"> • Riprap size (80~150 mm) • Thickness (0.3 m) 	<ul style="list-style-type: none"> • Riprap size (80~150 mm) • Thickness (0.3 m)
Constructability	<ul style="list-style-type: none"> • Difficult to acquire stone materials • Non-uniform size • Not easy for laying 	<ul style="list-style-type: none"> • Easy to acquire stone materials (recycled) • Regular • Not easy for laying 	<ul style="list-style-type: none"> • Easy to acquire stone materials (recycled) • Regular • Easy for laying
Maintenance	<ul style="list-style-type: none"> • Loss of materials 	<ul style="list-style-type: none"> • No loss of materials • Not flexible • Corrosion of wire mesh 	<ul style="list-style-type: none"> • No loss of materials • Proper for soft ground (flexible) • No corrosion of fiber
Cost	• US\$ 54 per m ³	• US\$ 98 per m ³	• US\$ 136 per m ³
Photographs			
Adoption	X	X	O




Figure 3.1-4: Typical Section of Bed Scour Protection

3.1.1.2 Component 2: Flood Embankment

The main purpose of this component is to maintain water level below the flood level during the largest spring tide in Seikkyi Khanaungto, Dala, and Twante (Twantay) Townships. This component is divided into four sub-components according to the sections (Dala Section, Seikkyi Khanaungto Section, Kyimyindaing Section and Twante (Twantay) Section) as shown in **Figure 3.1-5**. Major work item is to embank along canals with drainage facility and concrete pavement as shown in **Figure 3.1-6**.

In the FS study, the levee crest was designed to be 1.5m higher than high water level considering the freeboard covering concrete pavement for traffic. The crest with the width of at least 7m was set up for two-laned road. For slope protection, seeding mattress and sodding were designed on the river and land sides, respectively, and the slope is adjustable from 1:2 to 1:3 according to the density of residential area land use. It was found from the site investigation that the dense residential area approximately corresponds with the bank protection site by Component 1. Based on design criteria and preliminary design as described above, the typical cross-sections are section by section presented in **Figure 3.1-7** and the work quantities for Phase 1: Channel Training and Flood Embankment are estimated as seen in **Table 3.1-5**.



Figure 3.1-5: Location Map of Component 2







Figure 3.1-6: Typical Section of Flood Embankment



(a) 0 mile



(b) K0



(c) 2 mile

Figure 3.1-7: Cross-sectional Maps of Project Components

Table 3.1-5: Work Quantities for Project Components

Work Items	Description	Units	Quantity	Remarks
Component 1. Channel Training				
1.1 Bank Protection				
• Removal of Groynes	Near 0.5 mile	LS	1	
• Bank Protection	Near 0 mile junction	m	5,880	
1.2 Bed Scour Prevention				
• Stone Gabion	El.-15.3 ~ -15.0m	m ³	16,000	
• Sandbag	El.-27.6 ~ -15.3m	m ³	224,000	
Component 2. Flood Embankment				
2.1 Khanaungto Section				
	L=11.5km			
• Embankment	W=7.0m, H=2.0m	m ³	300,000	
• Slope Protection	Both sides (Sodding)	m	23,000	
• Concrete Pavement	W=7.0m, T=0.2m	m	11,500	
• Drainage Facility		m	11,500	
2.2 Dala Section				
	L=12.2km			
• Embankment	W=7.0m, H=2.0m	m ³	320,000	
• Slope Protection	Both sides (Sodding)	m	24,400	
• Concrete Pavement	W=7.0m, T=0.2m	m	12,200	
• Drainage Facility		m	12,200	
2.3 Twante Section				
	L=15.8km			
• Embankment	W=7.0m, H=2.0m	m ³	410,000	
• Slope Protection	Both sides (Sodding)	m	31,600	
• Concrete Pavement	W=7.0m, T=0.2m	m	15,800	
• Drainage Facility		m	15,800	

3.1.2 Implementation Schedules

Project implementation schedule was established in consideration of past similar projects from the Republic of Korea and Myanmar, construction quantities, climate conditions (dry and wet seasons) in the Project site. Total 6 years are required for the Project including 3 months for Consultant selection, 9 months for detailed design and tender service, and 60 months for construction and supervision as seen in **Figure 3.1-8** and **Table 3.1-6** shows the annual investment plan based on construction quantities.

Activities	Year1				Year2				Year3				Year4				Year5				Year6			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Selection of Consultant & Detailed Design	■	■	■																					
Bidding			■	■	■																			
Land Acquisition & Compensation		■	■	■	■																			
Contractor Selection				■	■																			
Construction & Supervision					■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■

Figure 3.1-8: Project Implementation Schedule

Table 3.1-6: Annual Investment Plan

Items		Annual Investment (1,000 US\$)						Total
		1 st Year	2 nd Year	3 rd Year	4 th Year	5 th Year	6 th Year	
EDCF	1. Direct Construction Cost	-	7,618	13,121	13,808	12,856	5,503	52,906
	2. Consulting Services	1,813	1,189	736	538	453	792	5,521
	3. Direct Investment (1+2)	1,813	8,807	13,857	14,346	13,309	6,295	58,427
	4. Contingencies	1	185	754	869	910	93	2,812
	5. Service Charge	2	9	14	15	14	7	61
	Subtotal	1,816	9,001	14,625	15,230	14,233	6,395	61,300
Myanmar	1. Commercial Tax	276	2,645	-	-	-	-	2,921
	2. Customs	-	105	-	-	-	-	105
	3. Project Management Cost	35	76	139	145	135	57	587
	4. Compensation	3,247	1,082	-	-	-	-	4,329
	Subtotal	3,558	3,908	139	145	135	57	7,942
Total		5,374	12,909	14,764	15,375	14,368	6,452	69,242

3.2 Project Executing Agency

Waterways Department was organized and founded in 1972 by combining Dredging and River Conservancy sections of Department of Marine Administration and parts of Hydrographic Surveying section of Port Corporation under the Ministry of Transport and Communication. In 1999 the Department was extended and reorganized as the DWIR. DWIR has then been expanded and reorganized again with the increase of international attention, aids, and investment on water resources in Myanmar (see **Figure 3.2-1**).




Figure 3.2-1: Organizational Structure of DWIR

DWIR has already implemented river training works in the Twante Canal, which are small-scaled works financed by the Myanmar Government. Recently, the DWIR commenced to implement the AIRBM (the Ayeyarwady Integrated River Basin Management) Project, which is a unique ODA project related to water resources and inland navigation as shown in **Table 3.2-1**.

Table 3.2-1: ODA Project/Program by DWIR

Project	Funding Sources	Project Cost (US\$ million)	Location	Period
AIRBM	WB	100.0	Midstream of Ayeyarwady River (Mandalay~Nyaung Oo)	March 2015 to March 2020

3.3 Project Alternatives

Alternative analysis is important as it guides the project to identify ways in a timely manner to accomplish the project's purposes in the most technically robust, efficient and cost-effective manner. From EIA perspective, alternatives are sought to avoid or minimize environmental impacts.

3.3.1 Analysis of the Alternatives: 'Action' vs. 'No action' Scenarios

Environmental and socio-economic considerations of both the 'Action (of the proposed project)' and 'No Action' Options are put in comparison as below. In addition to two technical options of including and excluding a Diversion Channel are also reviewed far below (seen in Table 3.3-1).

Table 3.3-1: Analysis of the Alternatives: 'Action' vs. 'No action' Scenarios

Expected Impacts	'Action' Scenario (of the Proposed Project)	'No action' (Status quo) Scenario	Remarks
Environmental	<ul style="list-style-type: none"> Temporary negative influences on the environment are expected to occur by execution of a project such as: <ul style="list-style-type: none"> dust generation, noise pollution, sediment discharge, and damage to the ecosystem of the waterside are expected to occur. 	<ul style="list-style-type: none"> Short-term environmental changes do not occur if the project is not to take place. Currently, erosion, sedimentation, and scour are constantly occurring, which can cause serious safety problems if we do not conduct project. 	<p>These are temporary effects and expected to be stabilized at the operational stage once the construction is completed.</p> <p>During the construction period, an effective environmental impact management plan (EMP) need to be set in place to minimize the environmental impacts.</p>
Social	<ul style="list-style-type: none"> Active flood prevention measures of the project can save lives and cause less damages to the livelihood of the communities located adjacent the Twante Canal, after the completion of construction. 	<ul style="list-style-type: none"> No disturbance in livelihood of the community near the project area during construction (e.g. no temporary/permanent loss of land, inconvenience of movements, longer commuting time, etc.). 	<p>The overall social welfare of the adjacent communities in "No Action" Scenario is expected to be lesser than the "Action" scenario in mid- and long-term.</p>

	<ul style="list-style-type: none"> ● Bed scouring prevention measures of the project will also reduce the traffic accidents along the canal while increasing the stability and safety of the inland water transport, after the completion of construction. ● Fishing activities and inland water transport (freight, regular passenger boat as well as tourist boats, etc.) may be disturbed to a certain degree during the construction but the effects are expected to be marginal in scale and only temporary. 	<ul style="list-style-type: none"> ● The historic trends indicate that the bank erosion, sedimentation and scouring of the bottom of the canal is becoming speedier: With no timely prevention, the social costs of the lost lives due to safety accidents in inland water transportation and consequent welfare loss would disproportionally aggravate. ● Fishing activities and inland water transport (freight, regular passenger boat as well as tourist boats etc.) would not be disturbed but maintain the current level of traffic volume in short term. However, due to the worsening sedimentation and aggravating bed scouring problem, the traffic volume will decrease, and fishing activities may also be affected in a longer term. 	<p>Expected negative social impacts on the affected communities during construction could be minimized or offset through effective impact management and compensation measures.</p> <p>(Detailed impacts and mitigation measures are to be included in Chapter 6.)</p>
Economic	<ul style="list-style-type: none"> ● Immediate and direct economic loss may occur due to the land and property losses and damages due to construction to directly affected persons and households. ● Other types of interruptions of business of temporary nature, due to the agricultural land loss and (temporary or permanent) halt of the shipyard operations along the canal would occur. ● Transport Cost Reduction by using inland water transport ● Prevented yearly land loss due to bank erosion along the Twante Canal leading to economic gain (estimated to be 1,115 sqm per annum in Twante Township, Seikkyi Khanaungto Township, Kyimyindaing Township and Dala township, 	<ul style="list-style-type: none"> ● No disturbance of livelihood of the community near the project area during construction (e.g. no temporary/permanent loss of land, loss of jobs (e.g. temporary fishery halting or relocation of the fishing and other Twante canal-related economic activities etc.). ● In the longer term, however, worsening sedimentation, bed scouring, deteriorating bank conditions leading to a higher risk of safety, inland transport accidents, flooding damages, loss of land and other types of losses, will result in ever increasing economic losses. 	<p>Mid- and long-term economic benefits is estimated to outweigh the short-term costs the project host community would pay during construction.</p> <p>Expected negative economic impacts on the affected communities during construction could be minimized or offset through effective impact management and compensation measures.</p>

	<p>respectively, worthy of US\$ 0.225 million yearly after the construction completion)</p> <ul style="list-style-type: none"> ● Increased efficiency and economic gains of the inland water transport users and industry due to safer and faster movement. ● With the New Town Development Plan in Twante and Seikkyi Khanaungto Township, as part of 2040 Greater Yangon Strategic Urban Development Plan (SUDP), the economic return from the prevented land loss through prevention of the bank erosion and flooding is expected to be even higher in the region over time. 		
--	---	--	--

3.3.2 Analysis of Technical Alternatives

Various technical alternatives to mitigate the risks of bank erosion and tidal floods have been proposed, particularly engineering interventions for bank and bed protection around 0-mile section have been established as a main component of the proposed project.

In this technical review, the optimal engineering intervention to ensure stability of the canal bank and river bed effectively and flood prevention has been proposed after comparing several proposed types of measures in various aspects. The proposed optimal measure is expected to maximize the Project effects.

A. Review on bank protection

The soil investigations along the project area found that the Twante canal has poor(soft) ground conditions, so the following considerations should be taken into account for bank protection design:

- Use of light materials for bank protection, respectively
- Improvement of soil conditions through replacing the material (cohesive soil → sandy soil)
- Adoption of pile for foundation of bank protection

Bank protection has been designed to prevent erosion and scouring caused by the ebb and flow of ocean tides and the wave by ship transportation. The advantages and disadvantages of each type of proposed bank protection measure are presented in Table 3.3-3. Considering poor(soft) ground conditions along the project area, bank protection measures by environmental blocks and gabion mattresses are considered more appropriate than riprap type protection.

Table 3.3-2: Characteristics of Proposed Bank Protection Types

Evaluation Criteria	Alternative 1 (riprap)	Alternative 2 (Environment Block)	Alternative 3 (Gabion mattress)	remark
1. Strength	+++	+++	+++	
2. Weight	+	++	++	key consideration
3. Flexibility	+++	+	++	
4. Cost-effectiveness	++	++	++	
5. Aesthetic impression	++	+++	++	
Recommendation		○	○	

Ref.) +++: Excellent; ++: Good; +: Poor

The toe protection for the canal bank is designed to support the foundation of the slope protection and prevent bank sliding and erosion of the slope protection foundation. In general, gabion mattress, riprap, and pile foundation can be employed for toe protection. As shown in Table 3.3-3 and Figure 3.3-2, two types of toe protection have been proposed.

Table 3.3-3: Structural Review on Bank Protection Alternatives




Item	Alternative 2 (Environment Block)	Alternative 3 (Gabion mattress)	Remark
Slope protection	Environment Block Geotextile Sand replacement 1:2 slope	Gabion mattress Geotextile Sand replacement 1:2 slope	
Toe protection	Gabion box Sand and Gravel Pile foundation	Gabion box Sand and Gravel Pile foundation	
Bed protection works	Gabion mattress	Gabion mattress	

Sample Photo			
--------------	---	--	--

Bed protection works have been proposed to elevate the existing scoured canal bed from El.-27.6 m up to El.-15.0 m to reduce erosion risks by the eddy of tidal flows at the 0-mile section by filling with sandbags and covering with gabion mattress.

In the F/S conducted previously, the bed protection design has been implemented based on the numerical modeling with HEC-11 model (Department of Transportation's Federal Highway Administration, USA) and the design standards of Ministry of Land, Infrastructure and Transport of Korea (Refer to Table 3.3-4, as a result fiber-gabion has been employed for bed protection measure as shown in Figure 3.3-1.)

Table 3.3-4: Characteristics of Proposed Bed Protection Types

Evaluation Criteria	Riprap	Gabions (Iron)	Gabions (Fiber)
Material Requirements	<ul style="list-style-type: none"> • Riprap size (0.3m) • Thickness (0.5m) 	<ul style="list-style-type: none"> • Riprap size(80~150mm) • Thickness (0.3m) 	<ul style="list-style-type: none"> • Riprap size(80~150mm) • Thickness (0.3m)
Construction Aspects	<ul style="list-style-type: none"> • Difficult to obtain materials • Inconsistent in size • Difficult to settle down 	<ul style="list-style-type: none"> • Easy to obtain materials (recycling) • Consistent in size • Easy to settle 	<ul style="list-style-type: none"> • Easy to obtain materials (recycling) • Consistent in size • Easy to settle
Maintenance	<ul style="list-style-type: none"> • Material loss 	<ul style="list-style-type: none"> • No material loss • Non-flexible • Corrosion 	<ul style="list-style-type: none"> • No material loss • Non-flexible (poor ground) • No corrosion
Cost	• US\$54/m³	• US\$98/m³	• US\$136/m³
Sample Photo			
Recommendation			○




Figure 3.3-1: Typical Section of Bed Protection Work

B. Review on Freeboard of Flood Embankment

The freeboard of the proposed flood embankment has been identified to be 1.5m considering that the main factor in determining the freeboard of flood embankment prevents flood discharge from the basin despite tidal flows and uncertainties in site and climatic conditions, through close consultation with the project implementation agency (DWIR).

Key uncertainties in freeboard design are 1) rise of sea levels due to climate change and 2) wave due to ship navigation.

The 5th Impact Assessment Report (2013) published by the Intergovernmental Panel on Climate Change (IPCC) under the UN forecasts that the sea level near project area (Bangol Bay) will rise by 50cm in the target year of 2070.

Based on the existing technical analysis and the regulations for ship navigation in Myanmar, the height of probable ship wave in the canal is estimated at 20cm.

The width of the levee of flood embankment is designed to be 7m to comply with river design criteria of Korea. The embankment is designed for a two-lane road for local residents and maintenance purpose.

In the F/S conducted previously, the designed slope of 1:2 for bank protection and 1:3 for flood embankment have been employed considering site conditions and technical analysis on bank stability. As the project area has respectively short flood duration (about 1 to 2 hours) and the design flood level is about 0.5m higher than the existing bank, the design bank slope of 1:2 is considered appropriate.

- (River Design Criteria of Korea) Design bank slope is recommended to be at least 1:3 to ensure stability of the riverbank. However, the design slope of 1:2 or steeper slope can be employed considering site conditions as long as the bank stability is ensured through detailed surveys and investigations.




Figure 3.3-2: Sea Level Rise Trend Curve by Major Coastal Points (IPCC, 2013)

CHAPTER 4: DESCRIPTIONS OF THE SURROUNDING ENVIRONMENT

4.1 Setting the Study Limits

The area of influence (AOI) for this project will be designated based on the following project components.

- Component 1 - Channel Training
 - 1.1 - Bank Protection
 - 1.2 - Bed Scour Prevention
- Component 2 - Flood Embankment
 - 2.1 - Khanaungto Section
 - 2.2 - Dala section
 - 2.3 - Twante (Twantay) Section
 - 2.4. - Kyimyindaing Section

The Ayeyarwady Delta is located in the southern part of the middle plains of Myanmar. It consists of three regions: Yangon, Ayeyarwady, and part of the Bago region. The Ayeyarwady Division is where the Ayeyarwady (local name Irrawaddy) River splits into many streams and drains into the Andaman Sea. On the southern and western sides of the Ayeyarwady Division is the Andaman Sea and Bay of Bengal. The Gulf of Martaban also lies to the east of the division. The Project site is located in the Twante (Twantay) Township, Dala Township, Kyimyindaing Township and SeikkyiKhanaungto Township of Yangon South District, Yangon Region.

4.1.1 Study Boundaries of the EIA

■ Temporal Boundary for Environmental (biophysical & ecological) Impact Assessment

The Twante Canal is a semi-permanent facility. The main objective of the proposed Project is to provide sustainable and systematic measures for the Twante Canal improvement in Myanmar in order to secure safe inland water navigation, protect residential and farmland areas from bank erosion and flood damages, and provide fresh water and water-friendly space.

The biophysical impact during the de-commissioning, closure and post-closure phases are expected to be minimal or insignificant.

In the construction phase, the environmental impacts are expected to occur on the atmospheric environment, water environment, noise and vibration, waste treatment, and flora and fauna due to construction equipment operation. In the operation phase, positive changes are expected, such as prevention of eco system damage caused by the annual inundations, stabilization of topographic changes, and recovery of water quality by canal operation. Thus, the temporary boundaries of this ESIA will be divided into, pre-construction, construction and operation phases to examine their impacts on the environment.

The following table indicates more details of the expected environmental (i.e. biophysical and ecological) impacts during construction and operation periods:

Table 4.1-1: Temporary Boundaries of the Assessment of Environmental (Biophysical & Ecological) Impacts

Temporary Boundaries		Environmental Impacts	Remark
Construction	Atmospheric environment	<ul style="list-style-type: none"> ◦Construction dust arising from the dust generating activities and air emissions from construction vehicles ◦Temporary increase of fugitive dust due to excavation and backfilling 	
	Water environment	◦Civil construction work such as bank protection, bed scour and embankment may affect Twante canal water quality through arising sedimentation during construction phase	
	Topographic change	◦The potential impacts to ground conditions such as geology and soils associated with construction of the Project is considered	
	Noise and vibration	◦Temporary noise and vibration impacts may arise during construction due to site clearance and ground works mainly related to excavation, and delivery and movement of materials and equipment	
	Waste treatment	<ul style="list-style-type: none"> ◦Wastes will be generated during the construction such as waste oils and solid waste etc. ◦Excavation spoil associated with site clearance ◦Concrete and concrete washings from concrete batching plants required for the construction ◦Waste oil and lubricants from vehicle maintenance and repair ◦Domestic waste including glass, plastics, paper in construction camp 	
	Flora and fauna	<ul style="list-style-type: none"> ◦Decrease habitat of flora and fauna due to construction embankment, bank protection ◦Affection on river and canal ecosystem as fish, terrestrial invertebrates during bed scour prevention in Yangon river and Twante Canal construction. ◦Temporary habitat loss of the project site during movement of temporary facilities during construction ◦Permanent loss of habitat and disturbance to surrounding habitats to the embankment project site ◦Localized changes in air quality resulting from construction activities and increased vehicle movements through the area 	
Operation	Water environment	◦Water quality recovery through canal operation	
	Topographic change	◦Stabilization of the slope and shore at the construction site	
	Flora and fauna	<ul style="list-style-type: none"> ◦Restoration of damaged important sorts of vegetation and tree (esp. Mangrove tree) during construction ◦The project impacts on those canal projects can be considered to be of negligible for operation phase 	

■ Spatial boundary for environmental (biophysical & ecological) impact assessment

The spatial boundaries of the assessment of the environmental (biophysical) impacts can be divided into direct and indirect impact zones. Direct impacts generated by construction activities will incur dust generation, noise and vibration generation, turbidity generation due to soil leakage, and changes

in habitat of flora and fauna in the area. Indirect impacts such as dust generation and soil leakage due to construction vehicle movements are expected to affect nearby areas.

Therefore, the direct potential impact areas on the project site is set to 200m from the edge of embankment site considering relatively small earth working size compared with other infrastructure projects such as road, urban development etc., and the indirect influence range is set to 500m. This project aims to improve the existing canal, and there will be few hydrological, and environmental negative impacts on the wide area including Ayarwaddy by operating the project.




Figure 4.1-1: Map of Area of Environmental Influence (AoI) of the Proposed Project


■ Temporal Boundary for Social Impact Assessment

Land acquisition and potential involuntary relocation as well as other income and livelihood loss would occur mainly during pre-construction (preparation) and construction stage. Direct/indirect impacts other than land acquisition and involuntary resettlement (such as income and livelihood improvements, safer living environments during flooding seasons and less inland water transport safety accidents) will occur mainly during and after the construction (i.e. operation) stage over a diversity of social aspects, both in positive and negative fashions. Thus, the temporal scope for the social impact assessment shall cover pre-construction, construction and operation phases.

■ Spatial boundary for direct social impact assessment - Land acquisition and Involuntary Resettlement

Direct impacts include land acquisition (both public and private-owned land) for construction and temporary or permanent access road building. Right-of-ways of the embankment and other canal improvement works are designated to be as follows:

- ① **Area 1:** ROW in Twante Section and Dala Section- Areas along, adjacent to Twante Canal, within 30 meter (Tentatively supposed 30-meter ROW before confirming AoI) from the limit of the construction site (canal improvement and embankments)



- ② **Area 2:** ROW in SeikkyiKhanungto Section: As of May 2015, it was reported that there are 29 officially registered shipyards located along the Twante canal in SeikkyiKhanungto Township (DWIR Data-2015-2016). The area is reported to cover 2,190 acres (8,962,616 sqm). The assessment based on the field study during the ESIA exercise indicates that there are about 40 registered shipyard operations as of Dec 2018. Final number of the shipyards that are to be affected would need to be confirmed later. In order to minimize the impacts on the shipyard business during the construction, it was agreed that the ROW in Kanaungto Township would be tentatively be drawn outskirt from the limits of the shipyard area inward to the landside, not cross-cutting the existing facilities. (The exact alignment of the ROW

shall be determined later.)



■ **Spatial boundary for other types of direct and indirect social impact assessment**

Area 3: ROW in Yangon River(MPA in charge, Kanungto, Dala, and Kyimyindaing Section) : ROW is tentative supposed to 30 meter from the limit of the construction site of embankments.



- Spatial boundary for social impact assessment in Yangon River Section MPA in charge (1)



■ **Spatial boundary for social impact assessment in Yangon River Section MPA in charge (2)**

In addition, geographical scopes are set for study along the administrative boundaries of the affected four Townships (Twante, Dala, SeikkyiKhanaungto and Kyimingdaing) for the social impacts such as:

- **Long-term income and livelihood and general improvement of living condition (including traffic, health and sanitation conditions etc):** While the primary beneficiaries of the project would be the inland water transport industry and the residents along the canal, the spill-over and ripple effects are expected to reach the broader community including the other residents of the affected Township. Thus, the study would include the residents of all the four affected Township as secondary level of beneficiaries and include them in the study as part of stakeholder engagement.
- **Temporary disturbance of shipyard operation businesses in SeikkyiKhanaungto Township:** The study assumes that the owners and the employees of the shipyard business in SeikkyiKhanaungto Township as part of the SeikkyiKhanaungto Township business community, regardless of their actual residential locations. Special consideration shall be given to reflect their particular concerns and socio-economic baseline conditions through the survey design and the arrangement of a focused group discussion (FGD).
- **Temporary disturbance of fishery and inland water transport business during construction:** The study assumes that the affected persons and households engaged in the fishery and inland water transport business (e.g. mini passenger boats (mini bus type business with the vessel capacity of about 20 passengers and taxi type boats (small engine boats hosting max. less than 5 passengers) and associated business holders as part of the business community of the four affected Township, regardless of their actual residential locations. Special consideration shall be given to reflect their particular concerns and socio-economic

baseline conditions through the survey design and the arrangement of targeted interviews.

The following figure shows the Administrative Boundaries of the Four Affected Townships (Twante Township, SeikkyiKhanaungto Township, Kyimyindaing Township and Dala Township).



Figure 4.1-2: The Administrative Boundaries of the Four Affected Townships (Twante, SeikkyiKhanaungto, Dala and Kyimyindaing)

4.2 Methodology and Objectives

4.2.1 Environmental Quality Survey

Investigation of the key environmental quality status and trends will be conducted in key origins and receptors that would be affected by the project implementation. The environmental quality survey points are presented in Table 4.2-1 and Figure 4.2-1 below. Among the items of this survey, baseline values of air quality, water quality, noise level, and vibration are being confirmed through laboratory analysis and field survey.

Sampling and analysis of ambient air pollutants was conducted by referring to the recommendation of United States Environmental Protection Agency (U.S. EPA). The Haz-Scanner Environmental Perimeter Air Station (EPAS) was used to collect ambient air monitoring data. The characteristics of the instrument are:



- Portable direct reading
- Configure up to 14 simultaneous air measurements including U.S. EPA criteria air pollutants
- Standard configuration measures PM2.5, PM10 or TSP particulates, CO, NO, NO₂, SO₂, temperature, and relative humidity
- Wind parameters are also measured by Haz-scanner EPAS and the required data are analyzed by using the WRPLOT View of AERMOD View (ver. 7.0) in which calm wind is defined below 0.5 m/s.

Table 4.2-1: Sampling and Analysis Method for Air Quality

No.	Parameter	Analysis Method
1	Sulfur dioxide (SO ₂)	On site reading
2	Carbon monoxide (CO)	On site reading
3	Nitrogen dioxides (NO ₂)	On site reading
4	Particle matter 2.5 (PM 2.5)	On site reading
5	Particle matter 10 (PM10)	On site reading
6	Nitric Oxide	On site reading
7	Relative Humidity	On site reading
8	Temperature	On site reading
9	Wind Speed	On site reading
10	Wind Direction	On site reading

Source: REM Survey (Resource & Environment Myanmar Co., Ltd), 2018

Monitoring Instrument for Air Quality

No.	Instrument	Brand & Model	Measurement/ Parameter	
1.	Environmental Perimeter Air Monitoring System	HAZ-SCANNER EPAS	CO, NO ₂ , NO, SO ₂ , PM (2.5), PM (10), VOCs, Relative Humidity, Temperature, Wind Speed, Wind Direction	 

Measurement of environmental sound level was conducted by referring to the recommendation of International Organization for Standardization (ISO), i.e. ISO 1996-1:2003 and ISO 1996-2:2007. The instrumentation used for noise quality survey is shown in the following Table 4.2-2. Noise meter was set up to record the log as ten minutes' intervals during an hour for one consecutive day.

Table 4.2-2: Instrumentation for Noise Survey

Instrumentation	Description
Sound level meter	Sound level meter with SD Card, Model SL-4023SD



Figure 4.2-1: Lutron Sound Level Meter

Measurement of environmental vibration level was conducted by referring to the recommendation of International Organization for Standardization (ISO), i.e. ISO 1996-1:2003 and ISO 1996-2:2007. The instrumentation used for vibration level survey is shown in the following Table 4.2-3. Vibration meter was set up to record the log as ten minutes' intervals during an hour for one consecutive day.

Table 4.2-3: Instrumentation for noise survey

Instrumentation	Description
Vibration meter	Rion VM55 with SD Card



Table 4.2-4: Baseline Environmental Quality Survey Points

Survey Items	Number and Sampling location	Parameters	Sampling Method
Air Quality Measurement	4 locations (_TBD)	PM10, PM2.5, SO ₂ , NO ₂ , CO, wind Speed, & Weather condition, Temperature, Wind, wind directions	24hr measurement for each sampling point
Noise Quality Measurement	4 locations(_TBD)	Noise Level	Measurement in the Morning, afternoon, evening, and night for each sampling point
Vibration measurement	4 locations(_TBD)	Vibration Level	Measurement in the Morning, afternoon, evening, and night for each sampling point
Water Quality Measurement (Surface Water)	6 locations(_TBD)	Water Temperature, pH, DO, Turbidity, BOD, COD, T-N, T-P, TSS, Total Coliform Bacteria(TCB), Oil & Grease, Total Chromium, Cu, Zn, Pb, Cd, Mercury, Arsenic, NH ₄ -N, Cr (VI), Ni, NO ₃ -N, Fe, CN, Salinity	One time water sampling for each sampling point
Water Quality Measurement (Ground Water)	1 location (TBD)	Water Temperature, pH, DO, Turbidity, BOD, COD, T-N, T-P, TSS, Total Coliform Bacteria(TCB), Oil & Grease, Total Chromium, Cu, Zn, Pb, Cd, Mercury, Arsenic, NH ₄ -N, Cr (VI), Ni, NO ₃ -N, Fe, CN, Salinity	One time water sampling for each sampling point




Figure 4.2-2: Environmental Quality Survey Points

4.2.2 Biodiversity Survey

A Global Positioning System will be used to navigate and mark coordinates between sample plots around the study area. Field observation will also be conducted in and around the project area. During the field survey period, plotless sampling method will be used. Plotless sampling methods are based on the random selection of points within a particular survey area. In addition, all trees, shrubs, plants and cultivated crops were recorded and listed. Identification of plants and animal species was conducted by assistances of skilled local people. The identified species and families were translated to scientific name with assistance of a checklist of trees, shrubs, herbs and climbers of Myanmar.

As part of this study, a desktop study was carried out of publicly available scientific publications to investigate the ecology and biodiversity of the project AOI. A site visit was undertaken where the different biodiversity features, habitat, vegetation and landscape units present at the site were identified and mapped in the field.

This included generating a fine-scale vegetation map for the site which identified and mapped the different plant communities present. Walk-through-surveys were conducted across the site and all plant and animal species observed were recorded. Searches for listed and protected plant species at the site were conducted and the location of all listed plant species observed was recorded using a GPS. Active searches for reptiles and amphibians were also conducted within habitats likely to be important for such species. The impact assessment phase will involve the determination of the nature of likely impacts of the development and recommendations on mitigation.

The following information will be collected.

- Forest: Type of Forest, Phase of development, distribution, existing and future use, presence of fragile or exceptional forests
- Flora species and their habitats: Abundance, distribution, diversity, Rare, endangered or vulnerable species, wetlands, Riparian vegetation, species of social economic, cultural or scientific interest (i.e NTFP)
- Fauna species and their habitats (Mammalians, reptiles, amphibians, aves, fish); - Abundance, distribution, diversity, Migration, Rare, endangered or vulnerable species, species of social, economic, cultural or scientific interest (i.e NTFP)

4.2.3 Socioeconomic Study

The ESIA team will engage key local stakeholders including the affected communities through quantitative and qualitative baseline study, focus group discussions and other participatory exercise as follows:

- Data collection including acquirement of the location maps with updated demarcation of the household and land use/ownership type within the AOI at Township GAD level
 - Individual household interviews (Questionnaire-based household survey)
 - Focused group discussions (FGD) of particular interest groups among the project affected people, including: Shipyard business community and farming community among the affected households
 - Consultation meetings with other key stakeholders including relevant government agencies (including MONREC-ECD, MPA, IWTD)
 - Data analysis including data entry, data cleaning, data processing, recording, feedback to key project staffs
- a. Secondary Data Collection:** Baseline data gathered from the regional government (YRG) and other appropriate government and public organizations, academics and other experts in

relevant fields, etc. The secondary data sources included reports, field documents, monographs, information leaflets/booklets, manuals, written order and instruction, statement of the government organization, among others.

- b. **Primary data Collection:** Primary data collection through direct observations, interviews, individual/target group consultation (FGDs) to collect and verify the socio-economic conditions (demography/residence), economic status (by age, sex, education, occupation, ethnical group and income, expenditure, loan and household assets and poverty status). The survey tools and methodologies considered was developed by the Local consultant (REM) and reviewed by the Isan consortium before implementation. The study also reflected the comments and concerns in the ESIA raised by the survey respondents, participants in FGDs, interviews and other consultation activities (including the public consultation workshops).
- c. **A questionnaire-based survey for socio-economic conditions** was carried out during field surveys. 353 households in total responded to the survey (about 13% sampling of the expected project affected households (2,697 households) from each of the four affected Township sections (i.e. Dala, Twante, Kyimyindaing and SeikkyiKhanaungto). Male respondents were 125 in total (35%) while the female respondents 228 (65%). Swedness of the gender representation is judged due to the fact that the survey was conducted through household visits during weekdays.
- d. The socio-economic survey covered the following items:

Section/Title	Contents
A. Household Characteristics	<ul style="list-style-type: none"> •Primary information on survey respondents and households (name, gender, ethnicity, age etc.)
B. Income, Expenditure, and Lifestyles	<ul style="list-style-type: none"> •Average income and major income source •Recent increase in income and its reason •Average expenditure status •Key areas of spending by household •Frequency of fishing on the Twante canal and the Yangong river
C. Asset and Properties C.1. Land and Structure for Residence C.2. Land and Structure for Economic Activities	<ul style="list-style-type: none"> •Land ownership status •Status of housing conditions •Status of economic activities in the land •Information on potentially affected land/structure (type, size, materials of housing units etc.) •Status of asset and properties (livestock, boat, home appliances, vehicles etc.)
D. Access to Utilities, Basic Social Infrastructure	<ul style="list-style-type: none"> •Drinking water supply and sanitation •Sewage and waste management •Power supply and main source of energy •Medical and health status •Status of education facilities such as schools

	<ul style="list-style-type: none"> •Status of religious and cultural facilities
E. Impacts on Ecosystems and Communities	<ul style="list-style-type: none"> •Expected environmental and social impact (Impact on water resources, religious and cultural facilities etc.) •Positive/Negative environmental-social impact before and after construction •Expected impact on vulnerable groups
F. Perceptions and Expectations	<ul style="list-style-type: none"> •Project perception and level of project info awareness •Source of project information •Level of expectations and concerns about the positive/negative impact of the project •Feedback collections regarding the project

4.3 Public Administration and Planning

Country Profile: Union of Myanmar

Myanmar is located as a potential land bridge between South and Southeast Asia. The total land area is 676,578 sq. km. It stretches for 936 km from east to west and 2051 km from north to south. At present, the total population of Myanmar is 54.4 million, and the 2014 Census revealed that the population is 51.48 million; the population density is 76 per square kilometer, and just under 30% of the population lives in urban areas.

Myanmar is a union of 135 ethnic groups with their own languages and dialects. The eight major national ethnic races are: Kachin, Kayah, Kayin, Chin, Mon, Bamar, Rakhine, and Shan. According to the administration of Myanmar, the country consists of 7 regions, 7 states, 1 union territory, 5 self-administered zones, and 1 self-administered division. The **regions** are: Ayeyarwady, Bago, Magway, Mandalay, Sagaing, Tanintharyi and Yangon. The **States** are: Chin, Kachin, Kayin, Kayah, Mon, Rakhine and Shan. The new capital city is Naypyidaw since November 2005 and other two large cities are Yangon and Mandalay.


Administrative Structure

Regions where mainly Barmans resides have the same status with states where mainly ethnic minorities reside. A region or a state is consisted of districts; and a district basically is consisted of villages, words, towns, andvillage-tracts. The administrative divisions and area of the country are shown in Table 4.3-1.



Figure 4.3-1: Map of Myanmar

The lowest levels of government offices are generally located in the townships. These in turn report to the government offices at the district and region levels. The regions are governed by a Chief Minister appointed by the President, who in turn is supported by a unicameral legislative assembly.



(Source: Ministry of National Planning and Economic Development and Ministry of Construction)

Figure 4.3-2: Myanmar Administrative Structure

Table 4.3-1: Area and Administrative Unit by Region and State of Myanmar

	Area (km ²)	District	Township	City/Town	Ward	Village Tract	Village
Union	676,578.00	74	330	442	3,301	13,588	63,798
Ayeyarwady	35,136.05	6	26	43	292	1,920	11,910
Bago	39,403.00	4	28	51	325	1,410	6,441
Chin	36,017.58	3	9	15	46	469	1,363
Kachin	89,038.58	4	18	30	160	596	2,547
Kayah	11,731.10	2	7	8	37	74	56
Kayin	30,381.67	4	7	18	86	376	2,097
Magway	44,818.96	5	25	30	184	1,535	4,781
Mandalay	29,954.33	7	28	28	271	1,415	4,779
Mon	12,296.19	2	10	16	100	368	1,153
Rakhine	36,776.72	5	17	26	170	1,035	3,738
Sagaing	94,621.07	10	37	46	238	1,754	6,000
Shan	155,795.72	13	55	85	505	1,566	14,334
Tanintharyi	43,343.34	3	10	17	87	264	1,228
Yangon	10,170.89	4	45	21	743	619	2,126
Naypyidaw	7,067.50	2	8	8	57	187	795

(Source: Socio-Economic Atlas of Myanmar, 2017)

The region assemblies can legislate on matters of land revenue, municipal taxes on buildings and land as well as the sales, lease and other matters involving property of the region or state. On the other hand, revenues from the exploitation of the natural resources of a region or state are to be paid to the Union Fund and not the region or State Fund. The Union Government does not need an approval from state or regional governments for large scale investments in their local jurisdictions, although they must be informed, and their views are sought as part of the evolving ESIA process and on foreign lease of land in their respective areas.

4.3.1 Socioeconomic Profile

The region and the township level information pertaining to the socio-economic profile of the country are limited and the baseline review has been undertaken on the basis of the limited secondary information available from reliable sources.

Myanmar's economy is diversified. The service sector has been growing steadily in the last few years, and now account for over 38 percent of GDP. The share of agriculture has been declining and represents 36 percent of GDP. Finally, industry(manufacturing) sector contributes the remaining 26 percent of GDP. The following table shows the economic facts of Myanmar.

Table 4.3-2: Myanmar Economy Profile

Surface Area	676,578 km ²
Population	51.48 million (2014 Census)
Population density	76/km ²
Percentage of urban population	30% (2014 Cencus)
Nominal GDP	USD 69.32 Billion (estimated of 2018: Trading Economics)
GDP per capita	USD 1484.20 (estimated of 2018: Trading Economics)
Percentage of employment by industry	Agriculture: 36% Industry: 26% Services: 38% (estimated of 2018: Trading Economics)
Economic growth rate	6.4% (2018: IMF)

4.3.2 Local Governments and Spatial Planning System

In three major cities, Naypyidaw, Yangon, and Mandalay, have respective City Development Committees which serve for the duties of city governments in other countries. Planning system for national policy, as of December 2012, is under consideration to be established among the present administration which began in 2011. The following two systems are expected to be established:

1. National Comprehensive Development Plan System (short- and long-term plans centered by economic and sectoral plans) which will be governed by Ministry of National Planning and Economic Development and
2. National Spatial Development Plan System which will be governed by Ministry of Construction.

There also is an intention to integrate both systems. Table 4.3-3 shows the planning systems expected to be established at national, region/state, and township level.

Table 4.3-3: Expected Planning Systems to be Established

	Spatial Plan	Socio-economic Development Plan
National level	National Spatial Development Plan	National Comprehensive Develop Plan (Long-Term Twenty-Year Plan)
		Short-Term Five-Year Plan
Region/State level	Regional Spatial Development Plan	National Comprehensive Development Plan (Regional Plan)
Township level	Spatial Development Plan for Township	-

(Source: Ministry of National Planning and Economic Development and Ministry of Construction)

Table 4.3-4 shows the major authorities relating to spatial policy.

Table 4.3-4: Major Authorities Relating to Spatial Policy

Program Name or Administrative Field	Organization
National Comprehensive Development Plan (Long-Term Twenty-Year Plan)	Ministry of National Planning and Economic Development
Short-Term Five-Year Plan	
National Spatial Development Plan	Ministry of Construction
Comprehensive Development Plan for Yangon Region	Government of Yangon Region
Strategic Urban Development Plan of the Greater Yangon	

(Source: Ministry of National Planning and Economic Development and Ministry of Construction)

4.3.3 Socioeconomic Planning System at the National Level (National Long-Term Plan and Short-Term Plan)

The current socioeconomic planning system of Myanmar consists of National Long-Term Plan (the current plan is the thirty-year plan targeting at 2001/02-2030/31) and Short-Term Five-Year Plan (targeting at every five years of the Long-Term Plan).

As of December 2012, marking a decade from the establishment of current Long-Term Plan (thirty-year plan), the planning system for national spatial policy is expected to be fully revised as a twenty-year plan (National Comprehensive Development Plan) for the remaining 20 years targeting at 2030/31. Preparation of the plan is carried out by the Ministry of National Planning and Economic Development. The planning process is to be consulted by United Nations Development Program (UNDP) and advice to it for keeping the viewpoint of urban environment is to be given by United Nations Human Settlements Program. The structure of the plan is roughly determined to be divided into several parts, Part 1 of which will be setting out macro framework including economic development targets, while Part 2 will be the sectoral plans for each of the 16 policy fields, at the same time plans such as regional (regions/states) plan and development plan for specific areas are expected to be included..

Sectoral plans are to be discussed among related ministries and regional plans similarly are to be discussed at township level, followed by drafting process by each region/state and organizing process by Ministry of National Planning and Economic Development. Finally, they are submitted to National Planning Committee. Then they will be put to deliberation at the national assembly.

On the other hand, as for short-term plan, after the 1st Plan which was a four-year plan targeting at 1992/93 - 1995/96, the 2nd Plan starting from 1996/97 through to the 4th Plan were five-year plans. 2011/ 12 - 2015/16 corresponds to the planning period of a five-year plan, but for 2011/12 and 2012/13 only plans for single year were approved at the national assembly and the plan for remaining three years has both possibilities of being a three-year plan or a set of single-year plans. The Myanmar government also established Myanmar Sustainable Development Plan (2018-2030).


Spatial Planning System at the National Level

Currently, the basic act for physical plans in Myanmar is National Housing Town and Country Development Act legislated in 1951. Provisions of this old act no longer matches the situation nowadays so that Ministry of Construction, having jurisdiction over this act, proceeded drafting of the National Spatial Development Planning Act.

The contents of the newly drafted the National Spatial Development Planning Act, as of December 2012, includes: spatial planning policy for three spatial levels (national, regional (region/state) and township), land use regulations, and development permission criteria. It proposes to give roles to districts, which are at the administrative level between region/state and township, of putting township plans together. Ministry of Construction also has a vision of integrating the of Spatial Planning system with the system of National Comprehensive Development Plan which Ministry of National Planning and Economic Development is establishing.

4.3.4 Development Plan for Greater Yangon

The establishment of Development Plan for Greater Yangon (Master Plan) for 39 townships targeting at the year 2040 has been progressed under the cooperation program provided by Japan International Cooperation Agency (JICA) taking Yangon Regional Government and Yangon City Development Committee (YCDC) as partners. The master plan has been established in 2018. Due to the lack of expert staff for urban planning in local governments, urban plans of local governments in Myanmar have been prepared by MOC.



(Source: Ministry of Construction)

Figure 4.3-3: Housing Development Plan 2040 for Greater Yangon (by Ministry of Construction)

4.3.5 Growth Areas and Economic Corridors

Growth areas and economic corridors are attracting attention as a key growth driver of the national economy of Myanmar. The Ministry of National planning and Economic Development (MNPED) expressed intention to place special economic zones (SEZ) with focus on the growth areas.

4.4 Legally Protected National, Regional or State Areas, Protected areas and Parks

Conservation of nature and biodiversity is an ingrained habit of most people in Myanmar to conserve biodiversity; the Government enacted the Protection of Wildlife, Wild plants and Conservation of Natural Area Law in 1994. There are at present 40 protected areas in Myanmar including wildlife and bird sanctuaries, national parks, and nature reserves. As of March 2014, 38 areas, covering 5.61% of total country's land area, have been established as protected areas. Another seven areas (1.19%) have been proposed for future PA designation; this would result in PAs covering 6.81% of total land area.

Table 4.4-1: Establishment of Protected Areas in Myanmar

No.	Status of Notification	Number	Total Area (km ²)	% of Total Land Area
1	Notified Protected Areas	38	38029.23	5.61
2	Proposed Protected Areas	7	8062.89	1.19
	Total	45	46092.13	6.81

Source: International Union for Conservation of Nature (IUCN) 2013

Table 4.4-2: Protected Areas and their Locations in Myanmar

No.	Site Name	General Location
1	Pidaung Wildlife Sanctuary	Kachin State
2	Shwe-U-Daung Wildlife Sanctuary	Mandalay Region
2	Shwe-U-Daung Wildlife Sanctuary	Shan State
3	Pyin-O-Lwin Bird Sanctuary	Mandalay Region
4	Moscov Islands Wildlife Sanctuary	Tanintharyi Region
5	Kahilu Wildlife Sanctuary	Karen State
6	Taunggyi Bird Sanctuary	Shan State
7	Mulayit Wildlife Sanctuary	Karen State
8	Wethikan Bird Sanctuary	Magway Region
9	Shwese-taw Wildlife Sanctuary	Magway Region
10	Chatthin Wildlife Sanctuary	Sagaing Region
11	Kelatha Wildlife Sanctuary	Mon State
12	Thamihla Kyun Wildlife Sanctuary	Ayeyar-wady Region
13	Htamanthi Wildlife Sanctuary	Sagaing Region
14	Minwuntaung Wildlife Sanctuary	Sagaing Region
15	Hlawga Park	Yangon Region
16	Inlay Wetland Bird Sanctuary	Shan State
17	Moeyongyi Wetland Bird Sanctuary	Bago Region
18	Alaungdaw Kathapa National Park	Sagaing Region
19	Popa Mountain Park	Mandalay Region
20	Meinmahla Kyun Wildlife Sanctuary	Ayeyarwady Region
21	Lampi Island Marine N. Park	Tanintharyi Region
22	Hkakaborazi National Park	Kachin State
23	Loimwe Protected Area	Shan State
24	Parsar Protected Area	Shan State
25	Natmataung National Park	Chin State
26	Lawkananda Wildlife Sanctuary	Mandalay Region

27	IndawgyiWetlandWildlifeSanctuary	KachinState
28	KyaikhtiyoeWildlifeSanctuary	MonState
29	MinsontaungWildlifeSanctuary	MandalayRegion
30	HukaungValleyWildlifeSanctuary	KachinState
31	KyaukPanTaungWildlifeSanctuary	ChinState
32	HponkanraziWildlifeSanctuary	KachinState
33	RakhineYomaElephantRange	RakhineState
34	Panlaung-pyadalinCaveWildlifeSanctuary	ShanState
35	MaharmyaingWildlifeSanctuary	SagaingRegion
36	LenyaNationalPark	TanintharyRegion
37	TanintharyNationalPark	TanintharyRegion
38	BumhpabumWildlifeSanctuary	KachinState
39	HukaungValleyWildlifeSanctuary(extension)	KachinState
40	TaninthayiNatureReserve	TaninthayiRegion

Source: International Unionfor Conservation of Nature (IUCN) 2013


The nearest Protected Area to the Project is the Hlawga Wildlife Prak located to the north of Yangon city. It is around 20km distance from project areas and located upper Yangon River, therefore, it is unlikely that the Park biophysical environment would be affected by the implementation of the Proposed Project.

4.4.1 HlawgaWildlife Park

The nearest National Park of the proposed project site is the Hlawga National Park. It is also known as Hlawga Wildlife Park (Figure 4.4-1). The Hlawga Wildlife Park with an area of 1542 acres (624 ha) has a fenced core area of 808 acres (327 ha). It is situated in Mingaladon Township of Yangon Division, northern part of Yangon City. The eastern part of the park is bordered by the Yangon Pyay road, the southern part by Hlawga forest reserve, the western part by paddy fields and the northern part by Pe-Nwe-Gone Village.



Figure 4.4-1: Hlawga Wildlife Park



The Hlawga Wildlife Park has key environmental resources such as Eld's Deer, Sambar Deer, Barking Deer, Hog Deer and migratory birds. The habitat's characteristic is the combination of evergreen forest (typical), Mixed deciduous forest (lower) and swamp forest.

4.4.2 Urban Greenery Area

The urban greenery areas include parks and garden areas of Yangon city. The Kandawgyi garden is a well-known greenery area, which can also be defined as public space. Parks and gardens are covered with natural and man-made vegetation. The commonly known greenery areas are Kandawgyi garden, Inya Lake greenery area. Inya Lake lies a few miles north of the Shwedagone pagoda. Inya Lake and Kan DawGyi Lake have 37 acres (15 ha) and 150 acres (61 ha) respectively.




Figure: 4.4-4: Location of the Inya Lake

4.4.3 Threatened Species

A total of 3 animal species and 2 plant species have been recorded as threatened species among the 380 recorded species in greater Yangon area (Table 4.4-3 and 4.4-4). Indian flap shell turtle *Lissemys punctata* and yellow tortoise *Indotestudo elongata* are exploited for local consumption and for the export to China, which cause the decline of their populations in natural habitats. Burmese Python *Python molurus bivittatus* become vulnerable species mainly due to habitat loss and human activities. The plant species *Dipterocarpus alatus* and *Hopea odorata* are overharvested in the country for local use and for export as well. All these threatened species are also protected by forest law in Myanmar.

Table 4.4-3: Animal Species Recorded as Threatened Species in Yangon Region during the Period from September 2012 to November 2012

No.	Scientific name	Common name	Family	IUCN, 2018
1	<i>Lissemys punctata</i>	Indian flap shell turtle	Trionychidae	Least Concerned
2	<i>Indotestudo elongata</i>	Yellow tortoise	Testudinidae	Vulnerable
3	<i>Python molurus bivittatus</i>	Burmese Python	Boidae	Vulnerable

Table 4.4-4: Flora Species Recorded as Threatened Species in Yangon Region during the Period from September 2012 to November 2012

No.	Scientific Name	Common Name	Family	Habit	IUCN Red List
1	<i>Dipterocarpus alatus</i>	Kanyin-phyu	Dipterocarpaceae	T	Vulnerable
2	<i>Hopea odorata</i>	Thin-gan	Dipterocarpaceae	T	Vulnerable

There are no endemic animal and plant species that are identified as globally threatened as of January 2018.

4.5 Physical Components

4.5.1 Climate and Meteorology

Yangon has a tropical monsoon climate and it is characterized by strong monsoon influences, has a considerable amount of sunlight, a high rate of rainfall, and high humidity. There are three well-defined seasons: Summer, 'rainy season' and 'cool (and dry) season'. Summer months are from March to Mid-May; heavy rain falls from Mid-May to the end of October (the 'rainy season') and the cool season starts in November up to the end of February. The Yangon Region features a lengthy rainy season from May through October where a substantial amount of rainfall (2837mm) is received; and a dry season from November through April, where little rainfall is seen (120mm).

Representative observatories for the Project area were screened based on the list for rainfall observatories from Department of Meteorology and Hydrology (DMH): The Kaba-Aye Station was found to be located relatively close to the Project area. (Figure 4.5-1 and Table 4.5-2).



Figure 4.5-1: Location Map of Meteorological Stations

Table 4.5-1: Summary of Meteorological Station: Kaba-Aye

Station	Coordinates ¹⁾		Data Availability			
	Latitude	Longitude	Rainfall	Temperature	Humidity	Evaporation
Kaba-Aye	N 16° E 46'	N 96° E 10'	1994 ~ 2013	2004 ~ 2013	2004 ~ 2013	1990 ~ 2013

1) GCS WGS 1984

For the proposed project, the Kaba-Aye station is suitable to use the climatic data due to the proximity of the location to the Project Site. To identify climatic conditions around the Project area, meteorological data such as precipitation, temperature, relative humidity, and evaporation are collected from the DMH.

As shown in Tables 4.5-2 and 4.5-3, mean monthly rainfall at Kaba-Aye station was calculated using daily data from 1994 to 2013, while monthly temperature and mean monthly relative humidity were calculated using daily data from 2004 to 2013, and mean monthly evaporation was calculated using daily for, 1990 to 2013.

There are three distinct seasons around the Yangon Region including project site. The cool (and dry) season (from November to February) measured at the Kaba-Aye Station, indicates the mean monthly temperatures of between 24.8°C and 27.6°C. The summer (hot and dry) season (start from March to Mid-May) has mean monthly temperatures between 28.8°C and 30.5°C. The rainy season (between mid-May and October) has average temperature between 26.4°C and 28.5°C.

Mean monthly rainfall during rainy season (from Mid-May to October) recorded at Kaba-Aye Station is occupying 96% of total amount (2957mm), with mean monthly relative humidity over 80% as shown in Table 4.5-4. As shown in Table 4.5-5, the mean monthly evaporation during summer (hot and dry) season in March in April) are 5.0mm and 5.5mm, respectively, having the highest range of

values around the year.

Table 4.5-2: Monthly Temperature at Kaba-Aye Station (2004-2013)

Division	Month / Temperature (°C)											
	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.
Min.	22.2	24.5	26.1	27.7	24.8	24.7	24.4	24.3	24.7	25.2	24.9	22.3
Max.	26.8	29.4	30.7	32.3	31.5	29.1	28.6	28.5	28.9	29.5	29.7	27.8
Mean	24.8	26.8	28.8	30.5	28.5	27.0	26.4	26.4	26.8	27.8	27.6	24.9

Table 4.5-3: Mean Monthly Rainfall at Kaba-Aye Station (1994-2013)

Division	Month / Rainfall (mm)												
	Total	Jan.	Feb.	Mar	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.
Mean	2,957	3	1	23	49	392	574	605	582	470	214	36	8

Table 4.5-4: Mean Monthly Relative Humidity at Kaba-Aye Station (2004-2013)


Division	Month / Relative Humidity (%)												
	Jan.	Feb.	Mar.	Apr	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.	Yearly Average
Mean	70.2	64.3	65.7	65.6	81.5	89.4	91.3	91.5	90.3	84.6	76.9	73.4	78.7

Table 4.5-5: Mean Monthly Evaporation at Kaba-Aye Station (1990-2013)

Division	Month / Evaporation (mm)											
	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.
Mean	3.5	4.3	5.0	5.5	4.0	2.4	2.1	2.1	2.6	3.3	3.8	3.5

4.5.2 Topography

According to the Digital Elevation Model (DEM) shown in Figure 4.5-2, topographical condition around the Twante (Twantay) Canal is characterized by typical feature of delta plain. The aerial distribution of ground levels is range from El. 0 m to El. 5 m which cover 626km² and occupy 87% of total area.



Source: 1:50,000 DEM of Survey Department. The following figure shows the Administrative Boundaries of the Four Affected Townships (Twante, SeikkyiKhanaungto, Kyimyindaing and Dala)

Figure 4.5-2: Distribution Map of Ground Level for Southern part of Project Area

4.5.3 Geology and Seismicity

Regional geomorphic features of the entire area of the project site includes ridges and deltaic lands lying south of the PeguYoma between the SittaungRiver on the east and the Irrawaddy River on the west. According to the geological map shown in Figure 4.5-3, three stratigraphic units are encountered in the southern district of Yangon Region. The encountered stratigraphic units are described as follows:

Stratigraphic Unit	Geological Age
Recent Alluvium	- Quaternary
Upper Pegu Group and marine, brackish and terrestrial equivalents	- Miocene
Irrawaddy Group and its equivalents	- Miocene - Pliocene

The Alluvial deposit is widely occupied by the entire project area. It was deposited on recent times (Quaternary) and thus it blankets the delta area Figure 4.5-2. It occupies areas which are affected by tidal action. It is estimated to be about 15m thick with variations according to depositional environments. This formation consists essentially of yellowish grey, brownish grey silts and clays. It also contains some organic matter such as decomposed wood. Traces of sands found scattered throughout the deposits.





Figure 4.5-3: Geological Map of Southern District of Yangon Region

Based on the seismicity and the records of the previous considerably high magnitude earthquakes, Yangon Region can be assumed as low to medium seismicity region. Some of the large earthquakes that caused the considerable damages to some buildings and some casualties in and around Yangon Region can be recognized in the past records, e.g. the magnitude 7.3, earthquake that struck on May 5, 1930 and December 3, 1930 earthquake with the same magnitude. The former earthquake, well-known Bago earthquake, caused 50 deaths and great damages in Yangon while 500 casualties were resulted in Bago. The other significant earthquakes are Yangon earthquakes of September 10, 1927 and December 17, 1927. These events also resulted in a certain amount of damage in Yangon. All of these events and their consequences, and the rapid growth of population and various sorts of structures alarm to conduct the seismic hazard analysis for this region and the seismic hazard assessment was therefore performed applying the probabilistic way (Figure 4.5-4).




Note: Blue colour shows the Yangon Region.

Figure 4.5-4: The Seismicity of Myanmar (Data Source – ISC earthquake catalog, 2009)

The seismic hazard maps (peak ground acceleration (PGA) at the periods of 0.2s and 1.0s in rock condition) for Yangon Region are depicted in Figure 4.5-5 and Figure 4.5-6. The PGA map predictable in 10% probability of exceedance in 50 years is illustrated in Figure 4.5-5. In this recurrence interval, the maximum seismic hazard zone comprises the eastern portion of Yangon Region with value of $> 0.5g$, while the minimum hazard areas are in western portion and the eastern margin with the value of $< 0.2g$.


The probabilistic seismic hazard map of PGA for 2% probability of exceedance in 50 years is shown in Figure 4.2-6. The maximum PGA is $> 0.9g$ which also comprises of the eastern portion of Yangon

Region as in the hazard distribution of 10% probability of exceedance in 50 years, especially along the areas lie along the Sagaing Fault. The minimum seismic hazard zones can be observed in the western part of the Yangon Region with PGA value of $< 0.2g$, whereas the Project area is also situated.



Source: Probabilistic seismic hazard map of Yangon Region, Myo Thant, 2012 ASEAN Engineering Journal, vol.3 no., 2.

Figure 4.5-5: Probabilistic Seismic Hazard (PGA) Map of Yangon Region with 10% Probability of Exceedance in 50 Years



Source: Probabilistic Seismic Hazard Map of Yangon Region, Myo Thant, 2012ASEAN Engineering Journal, vol.3 no., 2.


Figure 4.5-6: Probabilistic Seismic Hazard (PGA) Map of Yangon Region with 2% Probability of Exceedance in 50 Years

4.5.4 Soil

There are four main types of soil are found in the entire project area and southern part of Yangon Region. They are:

- Meadow & Meadow Alluvial soil
- Lateritic Soil
- Saline Swampy & Meadow Gley Soil
- Dune Forest and Beach Sand

Only Meadow Alluvial soils occupy the entire project area as shown in Figure 4.5-7. About 90% of these soils are composed of silt and clay, but humus content varies from place to place. These soils are favorable for paddy cultivation. The main problem, however, is poor drainage and waterlogged conditions. These soils are usually found in lowlands under impeded drainage. In rainy season, they are covered with flood water. Because of the high content of clay, these soils become very dry and cracked in the dry season. Moreover, the soils with long periods of moisture content may contain large amount of aluminum and soluble iron, sulphur and manganese by chemical process and can be toxic to plants. The humus content is high and usually deficient in phosphorus and potassium. Rice and jute can be grown on these soils after the floods recede. On-going comprehensive soil studies are essential to the successful management of contamination areas.



Source: Data from the Land Use Division, Myanmar 2006

Figure 4.5-7: Soil Map of Yangon Area

4.5.5 Natural Hazards

‘Hazard Profile of Myanmar’ prepared by five Government Ministries and Departments in Myanmar and four non-government agencies in July 2009, describes nine types of disasters in Myanmar: 1) Cyclone, 2) Drought/Dry zone, 3) Earthquake, 4) Fire, 5) Floods, 6) Forest Fire, 7) Land slide, 8) Storm, and 9) Tsunami. Among them, “Cyclone” is the potential natural hazard for the study are and discussed as follows.

Cyclones that originate in the Bay of Bengal generally move westward heading for India and then turn towards Bangladesh and Myanmar. Severe cyclones tend to occur either during the pre-monsoon season from April to May or post-monsoon season from October to November.

Cyclones have three destructive forces, namely: i) storm surge, ii) heavy rainfall and iii) strong winds. According to ‘Hazard Profile of Myanmar’, 1,248 tropical storms formed in the Bay of Bengal during the period from 1887 to 2005, of which 80 storms (6.4% of the total) hit the Myanmar coast. In all, 12 cyclones caused severe damage in Myanmar mainly due to the accompanying storm surge, and the maximum death or missing toll was 138,373 caused by Cyclone Nargis in May 2008.

Cyclone Nargis also hit Greater Yangon and flood water spread on a number of Townships around Yangon City. Most of the inundated area during Cyclone Nargis are Dala, Twantay, Htantabin and Hlegu areas.

4.5.6 Hydrologic Conditions

There are two hydrological stations near the Project area such as Maubin Station located in the Toe River and Pyay Station (Given that it is rather distant from the Project Area geographically, it is the only station which could measure the hydrological condition of the Toe River, whose stream also flow into the TwanteCanal.) located in the Ayeyarwady River as shown in Figure4.2-8. In order to calculate inflow discharge from upstream of the Toe River and Yangon River, hydrologic data on flow discharge of Maubin Station and Pyay Station were used. The general information of the two hydrological stations is described in Table 4.5-6.

Table 4.5-6: Summary of the Hydrological Stations: Maubin and Pyay

Station	Coordinates ¹⁾		Data Availability	
	Latitude	Longitude	Flow Discharge	Water Level
Maubin	N 16° 47'	E 95° 39'	1997 ~ 2013	1995 ~ 2013
Pyay	N 18° 49'	E 95° 13'	1966 ~ 1986	-

1) GCS WGS 1984




Figure 4.5-8: Location Map of Hydrological Stations

Based on the discharge distribution related with the Twante Canal, data of flow discharge were collected at both Maubin Station and Pyay Station. For Maubin Station, daily discharge data for 17 years from 1997 to 2013 were directly collected from DMH while for Pyay Station daily discharge data for 21 years from 1966 to 1986 referring to Irrawaddy and Lower Chindwin Rivers Study (1988) were used.

Using data of daily flow discharge at two stations, general statistics were estimated as shown in Table 4.5-7.

Table 4.5-7: General Statistics of Flow Discharge at Major Stations

Station	Flow Discharge (m ³ /s)				Remarks
	Avg.	Max.	Min.	Rainy ¹⁾	
Pyay	11,951	40,849	2,114	21,878	Ayeyarwady River
Maubin	6,157	13,415	3,649	7,903	Toe River
Twante Junction (Toe River)	5,172	11,269	3,065	6,639	
Twante Junction (Yangon River)	1,500	5,129	265	2,747	

1) Averaged during the rainy season from the middle of May to the middle of October

4.5.7 Environmental Quality

4.5.7.1 Air Quality

Survey Item

The parameters for air quality survey were SO₂, NO₂, NO, CO, PM_{2.5}, and PM₁₀.

Survey Location

The monitoring locations of air quality, noise and vibration are shown in Table 4.5-8 and Figure 4.5-8.

Table 4.5-8: Location of Air Quality, Noise and Vibration Survey

Monitoring Location	GPS Coordinates	Description
AQNV1: Pyawbwelay village, Twante Township	16°44'42.88"N 96° 5'32.99"E	It is located within the small grass ground, beside the Dala-Twante car road. It is situated southern part of village and approximately 300 m south of the Project ROW.
AQNV2: Targyi ward, Dala Township, Yangon Region	16°45'13.89"N 96° 7'12.62"E	The sampling location is beside the Dala – Twante Car Road surrounded by orchard village. Approximately 130-meter south of Project ROW.
AQNV3: General Administration Office compound, Seikkyikhanaungto Township, Yangon Region	16°45'19.58"N 96° 6'40.46"E	Monitoring station set in the middle of the township; Approximately 205 m north of Project ROW.
AQNV4: Basic High School compound of Ngasin village, Kyinmyindaing Township, Yangon Region	16°47'13.72"N 96° 6'47.00"E	Monitoring station set at the east portion of Ngasin village near the main Yangon River; Approximately 30 m west of the Project ROW.



Figure 4.5-9: Location Map of Air Quality, Noise and Vibration Survey

Survey Period

The environmental quality survey duration is shown in the following table 4.5-9.

Table 4.5-9: Survey Duration for Air Quality, Noise and Vibration

Sampling Point	Period
AQNV1	28 th - 29 th September, 2018
AQNV2	29 th - 30 th September, 2018
AQNV3	30 th September- 1 st October, 2018
AQNV4	20 th - 21 st October, 2018

Source: EIA Study Team

Figure 4.5-10 shows the air quality, noise and vibration monitoring locations and site activities photos.






Figure 4.5-10: Location of Air Quality, Noise and Vibration Survey

Survey Method

Sampling and analysis of ambient air quality were conducted by referring to the recommendation of the United States Environmental Protection Agency (U.S. EPA). The Haz-Scanner Environmental Perimeter Air Station (EPAS) was used to collect ambient air survey data. Sampling rate or air quality data were measured automatically every 1 minute and directly read and recorded onsite for measured parameters as shown in Table 4.5-3. The recorded wind data are analyzed by using the WRPLOT View of AERMOD View (ver. 7.0) in which calm wind is defined below 0.5 m/s.

Table 4.5-10: Sampling and Analysis Method for Air Quality

No.	Parameter	Analysis Method
1	Sulfur dioxide (SO ₂)	On site reading
2	Nitrogen dioxide (NO ₂)	On site reading
3	Nitrogen monoxide (NO)	On site reading
4	Carbon monoxide (CO)	On site reading
5	Particulate matter 2.5 (PM _{2.5})	On site reading
6	Particulate matter 10 (PM ₁₀)	On site reading
7	Temperature	On site reading
8	Humidity	On site reading
9	Wind speed and direction	On site reading

Source: EIA Study Team

Survey Result

(a) Ambient air quality

Results of ambient air quality measured are presented in Table 4.5-11 and hourly results are shown in Appendix. Comparing with the target value of (National Environmental Quality (Emission) Guideline, 2015), the concentration of all pollutants complied with the standard, except concentration of SO₂ at three locations exceeded the target value. It is assumed that emission from vehicles at those three locations caused the high concentration of SO₂.

Table 4.5-11: Ambient Air Quality

Sampling. No	Time	CO	NO ₂	NO	PM _{2.5}	PM ₁₀	SO ₂	Temp.	RH
	hours	µg/m ³	µg/m ³	µg/m ³	µg/m ³	µg/m ³	µg/m ³	Deg. C	%
AQNV1	24hr	173.59	54.74	0.03	2.84	7.07	26.74	29.24	83.02
AQNV2		356.43	44.08	0.03	2.87	9.58	47.04	27.47	85.40
AQNV3		215.55	48.84	0.04	2.79	7.06	26.19	26.85	85.74
AQNV4		219.00	71.73	0.01	2.68	7.25	17.66	26.00	87.15
Guideline value		-	-	-	25	50	20	-	-

(a) Ambient Air Quality

According to the wind rose analysis, average wind speed and prevailing wind direction of each sampling points are summarized in Table 4.5-12. Wind rose diagram of each sampling point are presented in Figure 4.5-11 to 4.5-14.

Table 4.5-12: Result of Wind Speed and Direction

Sampling Point	Average Speed (m/s)	Prevailing direction	Calm wind (%)
AQNV1	0.15	W	79.17
AQNV2	0.14	E	79.17
AQNV3	0.13	WSW	87.5
AQNV4	0.54	E	54.17




Figure 4.5-11: Wind Rose Diagram of AQNV-1




Figure 4.5-12: Wind Rose Diagram of AQNV-2




Figure 4.5-13: Wind Rose Diagram of AQNV-3




Figure 4.5-14: Wind Rose Diagram of AQNV-4

4.5.7.2 Noise and Vibration

Survey Item

The noise and vibration level survey items are shown in following table.

Table 4.5-13: Survey Parameters for Noise and Vibration Level

No.	Item	Parameter
1	Noise	A-weighted loudness equivalent (L_{Aeq})
2	Vibration	Vibration level (L_{veq})

Source: EIA Study Team

Survey Location

Survey location are as same as air quality survey and described in Table 5.5-1.

Survey Period

The survey duration is also shown in Table 5.5-2.

Survey Method

Measurement of noise and vibration level was conducted by referring to the recommendation of International Organization for Standardization (ISO), i.e. ISO 1996-1:2003 and ISO 1996-2:2007. The instrumentation used for noise and vibration level survey is shown in the following Table 5.5-14.

Table 4.5-14: Instrument for Measurement of Noise and Vibration Level

Parameter	Instrument	Model	Manufacture
Noise	Sound level meter	SL-4023SD	Lutron
Vibration	Vibration level meter	VM-55	Rion Co. Ltd. (Japan)

Source: EIA Study Team

The instrument used for noise measurement was set at the height of 1.2 m. A-weighted loudness equivalent level was measured automatically every 10 minutes and recorded in a memory card. One-hour L_{Aeq} was calculated by using the following array formula.

$$10 * \text{LOG}_{10} (\text{AVERAGE} (10^{((\text{RANGE})/10)}))$$

The vibration instrument used was the VM-55 Vibration Level Meter accompanied by a 3-axis accelerometer which was placed on solid soil ground near the roads. Vertical vibration (Z axis), L_v , was hourly measured and recorded. L_v (dB) vibration levels were recorded as $L_{v,max}$, $L_{v,min}$, L_{v5} , L_{v10} , L_{v50} , L_{v90} , L_{v95} , and L_{veq} . L_{v10} was the vibration level used in accordance with referred standard.

Survey Result

(1) Noise Level

Equivalent noise level (L_{Aeq}) are presented in Table 4.5-14. The noise levels at all station are higher than the “Residential, Institutional, Educational” of National Environmental Quality (Emission) Guideline, 2015. Because of the high traffic condition at all stations, daytime noise levels at all station are higher than the target value of National Environmental Quality (Emission) Guideline. The background noise level recorded in all noise survey station is close to the industrial, commercial setting of National Environmental Quality (Emission) Guideline, 2015. The hourly noise level of all survey stations is presented in Appendix.

Table 4.5-15: Equivalent Noise Level (L_{Aeq})

Survey Point	Equivalent Noise Level (L_{Aeq} , dB)	
	Daytime (7:00 AM - 10:00 PM)	Night Time (10:00 PM - 7:00 AM)
AQNV1	74	64
AQNV2	79	66
AQNV3	72	58
AQNV4	71	70
Guideline Value (Residential, institutional, Educational)	55	45
Guideline Value (Industrial, commercial)	70	70

(2) Vibration Level

Vibration level (L_{v10}) are presented in Table 4.5-16 and hourly value is shown in Appendix. There is no standard for vibration level in Myanmar so the vibration levels are compared with “road side level of residential area” of Japan standard. Comparing with the target value, both daytime and nighttime vibration level at all stations are complied with target value.

Table 4.5-16: Vibration Level

Survey Point	Vibration Level (L_{v10} , dB)	
	Daytime (7:00 AM - 10:00 PM)	Nighttime (10:00 PM - 7:00 AM)
AQNV1	46	40
AQNV2	43	37
AQNV3	37	34
AQNV4	36	29
Target Value	65	60

4.5.7.3 Water Quality***Survey Item***

Total of 6 surface water and one groundwater samples were collected during September and December 2018. The location of surface water sampling points is in Kanaungto Creek, Twante Canal and Yangon River, and one ground water was collected in Seikkyi Khanaungto Township. The analyzed parameter is shown in Table 4.5-17.

Table 4.5-17: Parameter for Surface Water Quality Survey

No.	Item	Analysis Method	Water Quality	
			Surface Water	Ground Water
1	Temperature	HI7609829-1 Sensor	✓	✓
2	pH	HI7609829-1 Sensor	✓	✓
3	Dissolved Oxygen (DO)	HI7609829-2 Sensor	✓	✓
4	Salinity	HI7609829-2 Sensor	✓	
5	Turbidity	HI7609829-4 Sensor	✓	✓
6	Total Dissolved Solid	HI7609829-4 Sensor		✓
7	Ammonia	APHA-AWWA-WEF Method		✓
8	Ammonium-Nitrogen	APHA-AWWA-WEF Method	✓	
9	Arsenic	AAS – Graphite Hydride Method	✓	

10	BOD ₅	5210B. 5 Days BOD Test	✓	✓
11	COD	Close Reflux, Titrimetric Method	✓	✓
12	Cadmium	APHA-AWWA-WEF Method	✓	
13	Chromium (hexavalent)	AAS – Graphite Furnace Method	✓	
14	Chromium (total)	AAS – Graphite Furnace Method	✓	
15	Copper	AAS – Graphite Furnace Method	✓	
16	Cyanide	APHA-AWWA-WEF Method	✓	✓
17	Fluoride	APHA-AWWA-WEF Method		✓
18	Iron	AAS – Graphite Furnace Method	✓	
19	Lead	APHA-AWWA-WEF Method	✓	
20	Mercury	APHA-AWWA-WEF Method	✓	
21	Nickel	APHA-AWWA-WEF Method	✓	
22	Nitrate-Nitrogen	APHA-AWWA-WEF Method	✓	✓
23	Oil & Grease	APHA-AWWA-WEF Method	✓	✓
24	Sulfate	APHA-AWWA-WEF Method		✓
25	Sulfide	APHA-AWWA-WEF Method		✓
26	Suspended Solids	Gravimetric Method	✓	✓
27	Total Hardness	APHA-AWWA-WEF Method		✓
28	Total Nitrogen	APHA-AWWA-WEF Method	✓	
29	Total Organic	APHA-AWWA-WEF Method		✓
30	Total Phosphorus	APHA-AWWA-WEF Method	✓	
31	Zinc	AAS – Graphite Furnace Method	✓	
32	Total Coliform	APHA-AWWA-WEF Method	✓	✓

Source: EIA Study Team

Survey Location

The brief description of surface water point is presented in table 4.5-18. The detail of the sampling point is described as below. The sampling activities are shown in Figure 4.5-15 to Figure 4.5-22.

Table 4.5-18: Sampling and Survey Points of Surface Water Quality

Monitoring Location and Period of Sampling	GPS Coordinates	Description of Sampling Points
SW1 – Kanaungto Creek Low tide: 30 September 2018 High tide: 09 December 2018	16°45'30.34"N 96° 6'39.59"E	The sampling point is closed to the south bank of Kanaungto Creek; it is entering into the Twente Canal. The width of Kanaungto creek is 160 meters where SW1 is sampled. The stream is utilized for fishing and transportation purpose.
SW2 – Twante Canal Low tide: 30 September 2018 High tide: 09 December 2018	16°44'39.67"N 96° 3'42.63"E	It is generally flowing from west to east. The width of Twante Canal is about 400 meters. Approximately 7.5 km from Yangon River. The canal is utilized for transportation purpose.
SW3 - Twante Canal Low tide: 30 September 2018 High tide: 09 December 2018	16°45'13.55"N 96° 6'54.03"E	The sampling location is middle of the canal and it is generally flowing from west to east. The width of Twante Canal is about 190 meters where SW3 is sampled. The sampling point is located about 0.7 km far from Yangon River.

SW4 - Twante Canal Low tide: 30 September 2018 High tide: 09 December 2018	16°45'51.32"N 96° 7'40.80"E	The sampling location is middle of the canal and it is generally flowing from west to east. The width of Twante Canal is about 460 meters where SW4 is sampled. The sampling point is located about 2.4 km far from Yangon River.
SW5 - Downstream of Yangon River Low tide: 30 September 2018 High tide: 09 December 2018	16°46'1.99"N 96° 8'57.90"E	The width of Yangon River is about 720 meters where SW5 is sampled. The sampling point is located about 300 m far from western bank of Yangon River. Yangon River is mainly utilized for transportation and fishing purpose.
SW6 - Upstream of Yangon River Low tide: 30 September 2018 High tide: 09 December 2018	16°46'42.22"N 96° 7'4.86"E	The width of Yangon River is about 570 meters where SW6 is sampled. The sampling point is located about 250 m far from western bank of Yangon River. Yangon River is mainly utilized for transportation and fishing purpose.
GW1- Groundwater Sampling	16°45'22.42"N 96 6'29.06"E	The ground water sample was taken from tube well and the depth of the tube well is about 40 m. The water from tube well is used as domestic purpose and not utilized as drinking water.




Figure 4.5-15: Location of Surface Water Sampling



Figure 4.5-16: Surface Water Sampling at SW1



Figure 4.5-17: Surface Water Sampling at SW2



Figure 4.5-18: Surface Water Sampling at SW3



Figure 4.5-19: Surface Water Sampling at SW4



Figure 4.5-20: Surface Water Sampling at SW5



Figure 4.5-21: Surface Water Sampling at SW6



Figure 4.5-22: Ground Water Sampling at GW1

Survey Period

The sampling and measuring of the surface water during ebb tide was conducted on 30, September 2018 as well as during flood tide on 16, December 2018. Ground water sampling was conducted on 5 December 2018.

Survey Method

Water samples were taken by Alpha horizontal water sampler and collected in plastic and sterilized glass sample containers. All sampling was in strict accordance with recognized standard procedures. The parameters as pH, temperature, dissolved oxygen (DO) and electrical conductivity (EC), including the odor and color in visual analyzing were measured at each site concurrently with sample collection. According to the Laboratory standard, some samples were preserved using the chemicals. All samples were kept in iced boxes and were transported to the laboratory.

Table 4.5-19: Field Equipment for Surface Water Quality Survey

No.	Equipment	Model/Serial No.	Manufacturer
1	Multi parameter for water quality	SmarTROLL MP SN-346054	In-Situ Inc.
2	Multi Parameters for water quality	HI 9829	HANNA
3	Alpha Bottle (Water Sampler)	Wildco P/N-1120-G45	Wildlife Supply Company®

Source: EIA Study Team

Water samples were sent to REM-UAE Laboratory in Yangon, UAE Thailand and SGS Thailand for laboratory analysis.

Survey Result

Results of surface water quality survey are shown in following table.

Table 4.5-20: Survey Results of Surface Water Quality (ebb tide in September 2018)

No.	Item	Unit	SW1	SW2	SW3	SW4	SW5	SW6
1	Temperature (water)	°C	27.54	27.49	29.82	27.61	30.05	31.59
2	pH	-	8.73	8.22	8.21	8.10	8.31	8.29
3	Dissolved Oxygen (DO)	mg/l	5.25	4.84	4.36	5.02	5.23	4.27
4	Salinity	psu	1.0	1.3	1.5	1.5	2.2	2.0
5	Turbidity	FNU	439	458	463	475	521	528

6	Ammonium-Nitrogen	mg/l	0.09	0.16	0.12	<0.02	0.09	0.10
7	Arsenic	mg/l	0.001	0.0021	0.0009	0.0006	ND	0.0003
8	BOD5	mg/l	1.5	1.7	2.5	1.6	1.7	1.4
9	COD	mg/l	46.1	49.2	55.5	49.2	52.3	57.1
10	Cadmium	mg/l	ND	ND	ND	ND	ND	ND
11	Chromium (hexavalent)	mg/l	ND	ND	ND	ND	ND	ND
12	Chromium (total)	mg/l	ND	0.025	ND	ND	ND	ND
13	Copper	mg/l	0.008	0.012	0.005	0.004	0.004	0.004
14	Cyanide	mg/l	ND	ND	ND	ND	ND	ND
15	Iron	mg/l	8.46	15.1	16.2	5.69	5.76	3.21
16	Lead	mg/l	ND	ND	ND	ND	ND	ND
17	Mercury	mg/l	ND	0.0002	0.0004	0.0002	0.0003	0.0002
18	Nickel	mg/l	0.026	0.05	0.018	0.02	0.019	0.006
19	Nitrate-Nitrogen	mg/l	0.09	0.06	0.09	0.07	0.07	0.09
20	Oil & Grease	mg/l	ND	3	4	3	ND	3
21	Suspended Solids	mg/l	231	27.3	366	341	309	230
22	Total Nitrogen	mg/l	0.56	0.61	0.67	0.59	0.63	0.41
23	Total Phosphorus	mg/l	0.05	0.05	0.1	0.05	0.05	0.07
24	Zinc	mg/l	0.014	0.028	0.009	ND	ND	0.007
25	Total Coliform	MPN/100ml	>160,000	54,000	160,000	92,000	35,000	>160,000

ND: Non-Detectable

Table 4.5-21: Survey Results of Surface Water Quality (Flood Tide in December2018)

No.	Item	Unit	SW1	SW2	SW3	SW4	SW5	SW6
1	Temperature (water)	°C	26.52	26.59	27.07	27.15	28.30	28.70
2	pH	-	7.39	7.41	7.18	7.16	7.15	7.17
3	Dissolved Oxygen (DO)	mg/l	5.57	6.05	5.49	5.65	5.49	5.56
4	Salinity	psu	1.2	1.4	1.8	2.0	2.5	2.3
5	Turbidity	FNU	355	209	696	635	549	510
6	Ammonium-Nitrogen	mg/l	0.15	0.16	0.16	0.14	0.24	0.16
7	Arsenic	mg/l	ND	ND	0.0028	0.0018	0.002	0.0015
8	BOD5	mg/l	ND	ND	1.0	1.2	1.3	ND
9	COD	mg/l	38.3	39.9	35.1	38.3	41.5	38.5
10	Cadmium	mg/l	ND	ND	ND	ND	ND	ND
11	Chromium (hexavalent)	mg/l	ND	ND	ND	ND	ND	ND
12	Chromium (total)	mg/l	ND	ND	ND	ND	ND	ND
13	Copper	mg/l	ND	ND	0.008	0.005	0.003	0.005
14	Cyanide	mg/l	ND	ND	ND	ND	ND	ND
15	Iron	mg/l	3.02	4.3	16.8	12.3	9.94	11.0
16	Lead	mg/l	ND	ND	ND	ND	ND	ND
17	Mercury	mg/l	0.0003	0.0002	0.0005	0.0005	0.0004	0.0002
18	Nickel	mg/l	0.005	0.014	0.042	0.036	0.029	0.032
19	Nitrate-Nitrogen	mg/l	0.09	0.11	0.14	0.18	0.16	0.16
20	Oil & Grease	mg/l	4	4	3	3	3	4
21	Suspended Solids	mg/l	157	79.6	335	248	197	191
22	Total Nitrogen	mg/l	0.83	1.05	0.14	1.14	1.08	1.10
23	Total Phosphorus	mg/l	ND	0.01	0.01	ND	0.02	0.01

24	Zinc	mg/l	ND	ND	0.023	0.016	0.012	0.014
25	Total Coliform	MPN/100m 1	1,100	>160,000	35,00 0	54,000	>160,00 0	54,000

ND: Non-Detectable

Table 4.5-22: Survey Results of Ground Water Quality

No.	Item	Unit	GW
1	Transparency	-	High
2	Depth	m	40
3	Temperature	°C	24.43
4	pH	-	6.19
5	Dissolved Oxygen (DO)	mg/l	2.3
6	Turbidity	FNU	96
7	Total Dissolved Solid	ppm	3318.2
8	Ammonia	mg/l	0.5
9	BOD ₅	mg/l	1.2
10	COD	mg/l	ND
11	Cyanide	mg/l	ND
12	Fluoride	mg/l	0.29
13	Nitrate-Nitrogen	mg/l	36.4
14	Oil & Grease	mg/l	30
15	Sulfate	mg/l	164
16	Sulfide	mg/l	ND
17	Suspended Solids	mg/l	23.6
18	Total Hardness	mg/l	313
19	Total Organic	mg/l	4.42
20	Total Coliform	MPN/100ml	7.8

ND: Non-Detectable

4.6 Biological Components

A Global Positioning System will be used to navigate and mark coordinates between sample plots around the study area. Field observation will also be conducted in and around the project area. During the field survey period, plotless sampling method will be used. Plotless sampling methods are based on the random selection of points within a particular survey area. In addition, all trees, shrubs, plants and cultivated crops were recorded and listed. Identification of plants and animal species was conducted by assistances of skilled local people. The identified species and families were translated to scientific name with assistance of a checklist of trees, shrubs, herbs and climbers of Myanmar.

As part of this study, a desktop study was carried out of publicly available scientific publications to investigate the ecology and biodiversity of the project AOI. A site visit was undertaken where the different biodiversity features, habitat, vegetation and landscape units present at the site were identified and mapped in the field.

This included generating a fine-scale vegetation map for the site which identified and mapped the different plant communities present. Walk-through-surveys were conducted across the site and all plant and animal species observed were recorded. Searches for listed and protected plant species at the site were conducted and the location of all listed plant species observed was recorded using a GPS. Active searches for reptiles and amphibians were also conducted within habitats likely to be important for such species. The impact assessment phase will involve the determination of the nature of likely impacts of the development and recommendations on mitigation.

The biodiversity survey had been carried out during 13 October to 17 October 2018. The survey areas are within ROW (30m from the shoreline) and buffer zone (200m from the shoreline) along the Twante canal, Khanaungto creek and western bank of Yangon River near Kyimyindaing.

The following information were collected during the biodiversity field survey.

- Forest: Type of Forest, Phase of development, distribution, existing and future use, presence of fragile or exceptional forests
- Flora species and their habitats: Abundance, distribution, diversity, Rare, endangered or vulnerable species, wetlands, Riparian vegetation, species of social economic, cultural or scientific interest (i.e NTFP)
- Fauna species and their habitats (Mammalians, reptiles, amphibians, aves, fish); - Abundance, distribution, diversity, Migration, Rare, endangered or vulnerable species, species of social, economic, cultural or scientific interest (i.e NTFP)

Vegetation Cover

In Yangon area, the vegetation cover consists of a mosaic of semi-evergreen, moist mixed deciduous, lower mixed deciduous and swamp/mangrove forests. Common trees include *Aporosa sp.*, *Pterpermumsemiagittatum*, *Eugenia megacarpa*, *Rauvolfia*, *aphiorrhizoides*, *Microcos*, *spaniculata*, *Markhamia*, *stipulata* and *Casia* sp. etc. *Eupatorium sp.*, *Miliusa*, *roxburghiana*, *Connarus*, *monocarpus* and *Jasminum sessiliflorum*.

The field survey identified the vegetation cover with bamboo and shrub land, cultivated land, mangrove and riverbank vegetation. The shrub lands with small woody trees are more abundant in the area. Some woody trees in fragmented forest areas are low in population density and frequency.

As present bamboo with sparsely grow small tree species and shrub species naturally replaced the area. The patches of small woody trees block still exist as habitat blocks. These remaining habitat blocks should be protected, and restoration of forest should be carried out by any mean.

Some extent of the trees was found in/around the residential area and mangroves were found along the river side and some parts of the canal bank. The natural vegetation grow in Twante Township were Thayet, Malaka, Padauk, Htan, Ohn, Peine, Kokko, Magyi, Tama and Zi. And the natural vegetation grows in Seikgyi-Khanaungto were Lamu, Khaya and Dani.



Cultivated Plants



Survey Activities



Mangrove Species Dani



Mangrove Species Lamu

Flora species and their habitat

Within the ROW and buffer zone area, there are two major habitat types were observed namely (1) agricultural land and (2) Mangrove forest and some extent of cultivated trees. There is not any intact forest within the ROW and buffer zone area. Habitat Map of the ROW and buffer zone area of Twante canal is shown in the following figure (Figure 4.6-1). Most of the mangroves along the canal area are planted by the DWIR for riverbank protection.




Figure 4.6-1: Habitat Map of the Project ROW and Indirect Impact Zone

The present survey identified and recorded 76 plants species within the ROW and buffer area as in the direct and indirect impact zone. There is one plant species (Htan) listed in IUCN Globally Threatened Red List (2018-2) but this species is not included in Myanmar IUCN Red List (Plant Species of IUCN Red List in Myanmar announced by Forest Department).

Based on the information of IUCN organization, this species is endemic to Madagascar. The major threats of this species in Madagascar is the loss of habitat due to expanding agriculture and increasing fire frequency. A major part of the population in Maevatanana is located in town now. The plant is also exploited for food. It would probably also qualify for listing as Endangered and further fieldwork is required to determine the true area of occupancy and number of locations of this species. But this species can be found abundantly in Central Region of Myanmar.

List of Floral species

There were 76 plant species identified within the ROW of Twante canal, Khanaungto creek and western bank of Yangon River, near Kyimyindaing. List of identified plant species recorded were presented in the following table.

Table 4.6-1: List of Floral Species

No.	Family Name	Scientific Name	Common Name	Habitat	Distribution	IUCN Status
1	Acanthaceae	<i>Acanthus ebracteatus</i>	Khaya	Shrub	Ayeyarwady, Rakhine, Taninthayi	LC
2	Amaranthaceae	<i>Alternanthera nodiflora</i>	Kanaphaw	Herb	Yangon, Mandalay, Taninthayi	LC
3	Anacardiaceae	<i>Mangifera indica</i>	Thayet	Tree	Wide	NE
4	Anacardiaceae	<i>Anacardium occidentale</i>	Thiho-thayet	Tree	Cultivated	NE
5	Annonaceae	<i>Annona squamosa</i>	Awzar	Small Tree	Cultivated	NE
6	Apocynaceae	<i>Carissa carandas</i>	Khan	Small Tree	Cultivated	NE
7	Araceae	<i>Areca catechu</i>	Kunthi-pin	Small Tree	Cultivated	NE
8	Areaceae	<i>Nypa fruticans</i>	Dani	Tree	Ayeyarwady	LC
9	Arecaceae	<i>Borassus flabellifer</i>	Htan	Tree	Bago, Mandalay, Sagaing, Taninthayi	NE
10	Arecaceae	<i>Cocas nucifera</i>	Ohn	Tree	Cultivated	NE
11	Arecaceae	<i>Caryota mitis</i>	Minbaw	Tree	Ayeyarwady, Bago, Kayah, Mon, Rskhine, Shan, Taninthayi, Yangon	NE
12	Asclepiadaceae	<i>Calotropis procera</i>	Mayo	Shrub	Magway, Mandalay, Sagaing, Shan	NE
13	Asteraceae	<i>Chromolaena odorata</i>	Bizat	Shrub	Wide	NE
14	Balsaminaceae	<i>Impatiens balsamina</i>	Dan-pan	Herb	Cultivated	NE
15	Bignoniaceae	<i>Oroxylum indica</i>	Kyaung-sha	Tree	Wide	NE
16	Bignoniaceae	<i>Millingtonia hortensis</i>	Egayit	Tree	Wide	NE
17	Bignoniaceae	<i>Dolichandrone serrulata</i>	Tha-khut	Tree	Wide	NE

18	Bombacaceae	<i>Bombax ceiba</i>	Letpan	Tree	Wide	NE
19	Caesalpinaceae	<i>Delonixrigia</i>	Sein-ban-gyi	Tree	Cultivated	NE
20	Caesalpinaceae	<i>Caesalpinia pulcherrima</i>	Seinban-gale	Small Tree	Cultivated	NE
21	Caesalpinaceae	<i>Senna siamea</i>	Mezali	Tree	Reported from Myanmar	NE
22	Caesalpinaceae	<i>Tamarindus indica</i>	Magyi	Tree	Cultivated	NE
23	Caesalpinaceae	<i>Bauhinia acuminata</i>	Swe-daw	Small Tree	Wide	LC
24	Cannaceae	<i>Canna indica</i>	Budatharana	Herb	Cultivated	NE
25	Caricaceae	<i>Carica papaya</i>	Thinbaw	Small Tree	Cultivated	DD
26	Casuarinaceae	<i>Casuarina equisetifolia</i>	Pinle-kabwe	Tree	Cultivated	NE
27	Combretaceae	<i>Terminalia catappa</i>	Banda	Tree	Cultivated	NE
28	Convolvulaceae	<i>Ipomoea batatas</i>	Kazun	Climber/ Creeper	Cultivated	NE
29	Convolvulaceae	<i>Ipomoea carnea</i>	La-thar-pan	Climber/ Creeper	Yangon	NE
30	Cucurbitaceae	<i>Cephalandra indica</i>	Kinmon	Climber/ Creeper	Ayeyarwady, Kayin, Mandalay, Mon, Yangon	NE
31	Ebenaceae	<i>Diospyros burmanica</i>	Te	Tree	Bago, Mandalay	NE
32	Euphorbiaceae	<i>Flueggea virosa</i>	Chin ya	Small Tree	Wide	NE
33	Euphorbiaceae	<i>Emblia officinalis</i>	Zi-phyu	Tree	Wide	NE
34	Euphorbiaceae	<i>Cephalocroton discolor</i>	Pilaw-pinan-u-ywethla	Tree	Cultivated	NE
35	Euphorbiaceae	<i>Phyllanthus niruri</i>	Kyet-tha-hin	Shrub	Wide	NE
36	Fabaceae	<i>Mucuna pruriens</i>	Khwele-ya	Climber/ Creeper	Bago, Chin, Kayin, Mandalay, Sagaing, Shan, Yangon	NE
37	Fabaceae	<i>Pterocarpus macrocarpus</i>	Padauk	Tree	Bago, Mandalay, Sagaing, Taninthayi	NE
38	Fabaceae	<i>Sesbania grandiflora</i>	Paukpan-byu	Small Tree	Cultivated	NE
39	Fabaceae	<i>Butea frondosa</i>	Pauk	Tree	Reported from Myanmar	NE
40	Fabaceae	<i>Erythrina fusca</i>	Kathit	Tree	Ayeyarwady, Bago, Yangon	NE
41	Lecythidaceae	<i>Barringtonia acutangula</i>	Ye-kyi	Tree	Wide	NE
42	Lythraceae	<i>Lagerstromia speciosa</i>	Pyinma	Tree	Reported from Myanmar	NE
43	Lythraceae	<i>Duabanga grandiflora</i>	Ma-u-lettan	Herb	Kachin, Sagaing	NE
44	Lythraceae	<i>Ammannia baccifera</i>	Kanyut	Herb	Bago, Mandalay,	LC

					Yangon	
45	Meliaceae	<i>Azadirachta indica</i>	Tama	Tree	Wide	NE
46	Mimosaceae	<i>Mimosa pudica</i>	Htikayon	Herb	Wide	NE
47	Mimosaceae	<i>Albizia lebbek</i>	Kokko	Tree	Reported from Myanmar	NE
48	Mimosaceae	<i>Leucaena leucocephala</i>	Bawsagaing	Tree	Mandalay, Sagaing, Yangon	NE
49	Mimosaceae	<i>Pithecellobium dulce</i>	Kala-magyi	Tree	Magway, Mandalay	NE
50	Mimosaceae	<i>Acacia auriculiformis</i>	Malaysia-padauk	Small Tree	Cultivated	LC
51	Mimosaceae	<i>Xylocarpus</i>	Pyin-ka-do	Tree	Wide	NE
52	Moraceae	<i>Streblus asper</i>	Okhne	Small Tree	Bago, Sagaing, Taninthayi	NE
53	Moraceae	<i>Artocarpus heterophyllus</i>	Peinne	Tree	Cultivated	NE
54	Moraceae	<i>Ficus religiosa</i>	Bawdi-nyaung	Tree	Cultivated	NE
55	Moraceae	<i>Ficus obtusifolia</i>	Nyaung-gyat	Tree	Wide	NE
56	Moraceae	<i>Ficus glomerata</i>	Ye-thapan	Tree	Bago, Kachin, Mandalay, Yangon	NE
57	Moraceae	<i>Ficus obtusifolia</i>	Nyaung-gyat	Tree	Wide	NE
58	Moringaceae	<i>Moringa oleifera</i>	Dan-da-lun	Tree	Cultivated	NE
59	Musaceae	<i>Musa sapientum</i>	Nget-pyaw	Herb	Cultivated	NE
60	Myrtaceae	<i>Eucalyptus camaldulensis</i>	U-ca-lit	Tree	Cultivated	NE
61	Myrtaceae	<i>Eugenia praetermissa</i>	Thabye	Tree	Ayeyarwady, Sagaing, Taninthayi	NE
62	Poaceae	<i>Cynodon dactylon</i>	Mye-sa-myet	Grass	Wide	NE
63	Poaceae	<i>Bambusa vulgaris</i>	Shwe-wa	Bamboo	Cultivated	NE
64	Poaceae	<i>Mnesithea striata</i>	Kaing	Grass	Reported from Myanmar	NE
65	Poaceae	<i>Arundo donax</i>	Kyu	Grass	Reported from Myanmar	LC
66	Poaceae	<i>Dendrocalamus longispatus</i>	Waya	Bamboo	Bago, Mandalay, Mon, Rakhine, Shan, Taninthayi, Yangon	NE
67	Poaceae	<i>Dendrocalamus longispatus</i>	Wanet	Bamboo	Bago, Mandalay, Mon, Rakhine, Shan, Taninthayi, Yangon	NE
68	Pontederiaceae	<i>Monochoria vaginalis</i>	Beda	Aquatic	Taninthayi, Yangon	LC
69	Rhamnaceae	<i>Ziziphus jujuba</i>	Zi	Tree	Cultivated	NE
70	Rubiaceae	<i>Morinda angustifolia</i>	Yeyo	Small Tree	Wide	NE
71	Rutaceae	<i>Aegle marmelos</i>	Okshit	Tree	Bago, Chin, Kachin, Kayin, Magway, Sagaing, Shan, Taninthayi, Yangon	NE

72	Sapindaceae	<i>Aryteralittoralis</i>	Lamu	Small Tree	Kachin, Mon, Sagaing, Taninthayi	LR/LC
73	Solanaceae	<i>Solanum indicum</i>	Khayan-kazaw	Shrub	Bago, Mandalay, Shan, Yangon	NE
74	Steruliaceae	<i>Scaphiumscaphigerum</i>	Mohbin	Tree	Mon, Taninthayi	NE
75	Tiliaceae	<i>Microcospaniculata</i>	Mya-yar	Small Tree	Ayeyarwady, Bago, Mandalay, Mon, Taninthayi	NE
76	Vitaceae	<i>Cayratia trifolia</i>	Taw-sabyit	Climber/ Creeper	Bago, Mandalay, Yangon, Unknown	NE

NE = Not Evaluated

DD = Data Deficit

LR/LC = Lower Risk/Least Concerned

Fauna species and their habitat

Habitat of fauna species were found within ROW, along riverbank, mangrove, agricultural land and in some residential area. Total of 5 wildlife groups of fauna were collected in the Twante canal area consist of mammals, birds, insects, Herpet and Fish.

(i) Birds

A total of 55 bird species were recorded in the survey area. Members of the Family Ardeidae included Little egret (*Egretta garzetta*), Intermediate Egret (*Mesophoyx intermedia*) and Great Egret (*Ardea alba*), and Chinese pond heron (*Ardeolabacchus*) were found near the water body and recorded as water bird species. Apart from the bird species of family Ardeidae, other bird species such as Black-Capped Kingfisher (*Halcyon pileate*), White-throated Kingfisher (*Halcyon smyrnensis*), Common Kingfisher (*Alcedo atthis*) from family Alcedinidae and White-breasted Waterhen (*Amaurornis phoenicurus*) from family Rallidae were also recorded as water birds. The birds of prey species were Black kite (*Milvus migrans govinda*) and Brahminy kite (*Haliastur indus*). The bird species such as Spotted Dove (*Streptopelia chinensis*), Indian roller (*Coracias benghalensis*), Barn swallow (*Hirundo rustica*), and Common myna (*Acridothera tristis*) were recorded as common species in the survey area. Member of the family Cisticolidae included Plain prinia (*Prinia flaxiventris*), Zitting cisticola (*Cisticola juncidis*) and the members of Estrildidae included Scaly-breasted Munia (*Lonchura punctulata*) and White-rump Munia (*Lonchura striata*) were found in agriculture land and recorded as grass bird species. One Endemic species of Ayeyarwady Bulbul (*Pyconotus blanfordi*) were also observed in that area.

Table 4.6-2: List of Bird Species

No	Scientific Name	Common Name	Family	IUCN Status	Remark
1	<i>Dendrocygna javanica</i>	Lesser Whistling-duck	Anatinae	LC	
2	<i>Butorides striata</i>	Little Heron	Ardeidae	LC	
3	<i>Egretta garzetta</i>	Little Egret	Ardeidae	LC	
4	<i>Mesophoyx intermedia</i>	Intermediate Egret	Ardeidae	LC	
5	<i>Ardea alba</i>	Great Egret	Ardeidae	LC	
6	<i>Ardeolabacchus</i>	Chinese pond-heron	Ardeidae	LC	
7	<i>Nycticorax nycticorax</i>	Black-crowned night-heron	Ardeidae	LC	
8	<i>Tringahypoleucos</i>	Common Sandpiper	Scolopacidae	LC	
9	<i>Milvus migrans govinda</i>	Black kite	Accipitridae	LC	

10	<i>Haliasturindus</i>	Brahminy kite	Accipitridae	LC	
11	<i>Amaurornisphoenicurus</i>	White-breasted Waterhen	Rallidae	LC	
12	<i>Centropussinensis</i>	Greater Coucal	Cuculidae	LC	
13	<i>Coracias benghalensis</i>	Indian Roller	Coraciidae	LC	
14	<i>Halcyon pileata</i>	Black-Capped Kingfisher	Alcedinidae	LC	
15	<i>Halcyon smyrnensis</i>	White-throated Kingfisher	Alcedinidae	LC	
16	<i>Alcedoatthis</i>	Common Kingfisher	Alcedinidae	LC	
17	<i>Megalaimahaemacephala</i>	Coppersmith Barbet	Ramphastidae	LC	
18	<i>Jynxstorquilla</i>	Eurasian Wryneck	Picidae	LC	
19	<i>Meropsorientalis</i>	Little green bee-eater	Meropidae	LC	
20	<i>PsittaculaKrameri</i>	Rose-ringed Parakeet	Psittadae	LC	
21	<i>Rhipiduraalbicollis</i>	White-throated Fantail	Rhipiduridae	LC	
22	<i>Cypsiurusbalasiensis</i>	Asian Palm-Swift	Apodidae	LC	
23	<i>Streptopeliachinensis</i>	Spotted Dove	Columbidae	LC	
24	<i>Streptopeliatranquebarica</i>	Red collared Dove	Columbidae	LC	
25	<i>Columba livia</i>	Rock Pigeon	Columbidae	LC	
26	<i>Laniuscristatus</i>	Brown Shrike	Laniidae	LC	
27	<i>Vanellus indicus</i>	Red-wattled Lapwing	Charadriidae	LC	
28	<i>Corvussplendens</i>	House Crow	Corvidae	LC	
29	<i>Corvusmacrorhynchos</i>	Large-billed Crow	Corvidae	LC	
30	<i>Hirundorustica</i>	Barn Swallow	Hirundinidae	LC	
31	<i>Artamusfuscus</i>	Ashy Woodswallow	Artimidae	LC	
32	<i>Aegithinatiphia</i>	Common Iora	Aegithinae	LC	
33	<i>Dicrurusmacrocerus</i>	Black Drongo	Dicruridae	LC	
34	<i>Copsychussaularis</i>	Oriental Magpie-robin	Muscicapidae	LC	
35	<i>Pyconotuscafer</i>	Red-vented Bulbul	Pycnonotidae	LC	
36	<i>Pycnonotusjocosus</i>	Red-whiskered Bulbul	Pycnonotidae	LC	
37	<i>Pyconotusblanfordi</i>	Ayeyarwady Bulbul	Pycnonotidae	LC	Endemic
38	<i>Acridotherestrictis</i>	Common Myna	Sturnidae	LC	
39	<i>Acridotheresfuscus</i>	Jungle Myna	Sturnidae	LC	
40	<i>Sturnus burmnicus</i>	Vinous –breasted Myna	Sturnidae	LC	
41	<i>Phylloscopusfuscatus</i>	Dusky Warbler	Phylloscopidae	LC	
42	<i>Priniaflaxiventris</i>	Plain prinia	Cisticolidae	LC	
43	<i>Orthotomussutorius</i>	Common Tailorbird	Sylviidae	LC	
44	<i>Dicaeumcruentatum</i>	Scarlet-backed Flowerpecker	Dicaeidae	LC	
45	<i>Saxicola caprata</i>	Pied Bushchat	Muscicapidae	LC	
46	<i>Saxicola maurus</i>	Siberian stonechat	Muscicapidae	LC	
47	<i>Priniaflaxiventris</i>	Plain prinia	Cisticolidae	LC	
48	<i>Orthotomussutorius</i>	Common Tailorbird	Sylviidae	LC	
49	<i>Lonchurapunctulata</i>	Scaly-breasted Munia	Estrildidae	LC	
50	<i>Lonchurastrata</i>	White-rump Munia	Estrildidae	LC	
51	<i>Passer domesticus</i>	House Sparrow	Passeridae	LC	
52	<i>Passer montanus</i>	Eurasian Tree-sparrow	Passeridae	LC	
53	<i>Cisticola juncidis</i>	Zitting cisticola	Cisticolidae	LC	

54	<i>Motacilla alba</i>	White wagtail	Motacillidae	LC	
55	<i>Ploceus philippinus</i>	Baya weaver	Ploceidae	LC	

LC = Least Concerned



Common Sandpiper (*Tringahypoleucos*)



Brown Shrike (*Lanius cristatus*)



White-rump Munia (*Lonchura striata*)



Black-Capped Kingfisher (*Halcyon pileata*)



Oriental Magpie-robin (*Copsychus saularis*)



Jungle Myna (*Acridotheres fuscus*)

Figure 4.6-2: Bird Species Recorded from Study Area

(ii) Mammals

During the survey period a total of 5 mammal species belonging to 5 genera were recorded through observation and interviewed in the project area. According to the Villagers, the following the mammal species recognized as conservation interest that were found within the forest habitat of the study area. They were Small Indian Civet, Small Asian Mongoose, Crab eating Mongoose, Common Palm Civet, House Shrew that were recorded by interviewed survey from local people.

Although a total of these 5 species of mammal were interview information. According to the IUCN red List (2018), there was no threatened species and no endemic species in this area.

Table 4.6-3: List of Mammal Species

No	Scientific Name	Common Name	Family Name	Observed	Interviewed	IUCN Status
1	<i>Suncus murinus</i>	House Shrew	soricidae		√	LC
2	<i>Viverricula indica</i>	Small Indian Civet	Viverridae		√	LC
3	<i>Paradoxurus hermaphroditus</i>	Common Palm Civet	Viverridae		√	LC
4	<i>Herpestes sura</i>	Crab eating Mongoose	Herpestidae		√	LC
5	<i>Herpestes javanicus</i>	Small Indian Mongoose	Herpestidae		√	LC

LC = Least Concerned

(iii) Herpet

During the field survey, 10 amphibians and reptile species were recorded within the Study Area through interviewed and observation. Six species were observed, and four species were recorded by interviewed from local people who live in and near the survey area. They included 1 frog, 1 Skink, 1 Gecko, 3 lizards and 4 snakes. The families of frog were one species in families Hylidae. The families of lizard were three species in families Agamidae and the families of snake were two species in families Colubridae and one species in families Elapidae and one species in families Viperidae. The families of Skink were one species in families Scincidae. The families of Gecko are one species in families Gekkonidae. According to the IUCN Red List of threatened species (2018), there was no threatened species and no endemic species in this survey area.

Table 4.6-4: List of Herpet Species

No	Scientific Name	Common Name	Family Name	Observed	Interviewed	IUCN Status
1	<i>Calotes Versicolor</i>	Garden Fence Lizard	Agamidae	√		NE
2	<i>Calotes Mystaleus</i>	Blue forest Lizard	Agamidae	√		NE
3	<i>Calotes semma</i>	Forest crested lizard	Agamidae	√		NE
4	<i>Sphenomorphus maculatus</i>	Streamside Skink	Scincidae	√		NE
5	<i>Hemidactylus frenatus</i>	Spiny-tailed House Gecko	Gekkonidae	√		LC
6	<i>Ptyas mucosa</i>	Indian Rat Snake	Colubridae		√	NE
7	<i>Daboia russelii</i>	Russell's Viper	Viperidae		√	LC
8	<i>Bungarus fasciatus</i>	Banded Krait	Elapidae		√	LC
9	<i>Xenochrophis piscator</i>	Chequered Keelback Water Snake	Colubridae	√		NE
10	<i>Polypedates leucomystax</i>	Common Flying Frog	Hylidae	√		NE

NE = Not Evaluated

LC = Least Concerned



Common Flying Frog



Spiny-tailed House Gecko



Garden fence Lizard



Streamside Skink



Forest crested lizard

Figure 4.6-3: HerpetSpecies Recorded from Study Area

(iv) Fish

Field surveys and interviews survey with local fishermen who lived near the study area were conducted during the collection of the specimens. Fishing activities are mostly traditional method. Fishermen were interviewed with regard to fishery process. A total of 23 species distributed in 10 families were identified and recorded from Twante Canal, Khanaungto River and Yangon River. The most occurrence species are *Otolithoides pama*, *Pangasius pangasius*, *Polynemus paradiseus* and

Tenualosailisha. The dominant Family is Cyprinidae. According to the IUCN Red List (2018-1), one species was near threatened species: *Osteobramabelangeri* (NT), other were least concerned and not evaluated. There was no endemic species in this area.

According to the spatial distribution data of IUCN organization, the range of spatial distribution of Near Threatened species is far away from the project area. However, rivers connect with each other due to fact that this species can be found in this area. The extinction of this species mainly in Manipur was due to construction of dams, habitat degradation and introduction invasive species which caused fragmentation. Threats to this species in Myanmar are unknown and this species is not included in Myanmar Protected species.



Source: IUCN.org

Table 4.6-5: List of Fish Species

No	Scientific Name	Common Name	Family	IUCN Status
1	<i>Notopterusnotopterus</i>	Grey feather back	Notopteridae	LC
2	<i>Gudusiavariegata</i>	Burmese River Shad	Clupeidae	LC
3	<i>Tenualosailisha</i>	Hilsa	Clupeidae	LC
4	<i>Catlacatla</i>	Catla	Cyprinidae	LC
5	<i>Cirrhinusmrigala</i>	Mrigal	Cyprinidae	LC
6	<i>Labeoboga</i>	<i>Boga labeo</i>	Cyprinidae	LC
7	<i>Labeocalabasu</i>	Carp	Cyprinidae	LC
8	<i>Labeorohita</i>	Rohu	Cyprinidae	LC
9	<i>Labeomicrophthalmus</i>	Murree labeo	Cyprinidae	LC
10	<i>Labeostoliczkae</i>	Minor Carp	Cyprinidae	LC
11	<i>Osteobramabelangeri</i>	Manipur Osterobrama	Cyprinidae	NT
12	<i>Osteobramacunma</i>	Cunmaosteobrma	Cyprinidae	LC
13	<i>Puntius chola</i>	Swamp barb, chola barb	Cyprinidae	LC
14	<i>Puntius ticto</i>	Ticto barb	Cyprinidae	LC
15	<i>Amblypharyngodonmola</i>	Molacarplet	Cyprinidae	LC
16	<i>Channaorientalis</i>	Asiatic snakehead	Channidae	LC

17	<i>Tetraodon cutcutia</i>	Ocellated pufferfish	Tetraodontidae	LC
18	<i>Latescalcarifer</i>	Seabass	Latidae	LC
19	<i>Pangasius pangasius</i>	Pangas Catfish	Pangasiidae	LC
20	<i>Otolithoides pama</i>	Croaker	Sciaenidae	NE
21	<i>Polynemus paradiseus</i>	Indian salmon	Polynemidae	LC
22	<i>Eleutheronema tetradactylum</i>	King fish	Polynemidae	LC
23	<i>Macrobrachium malcolmsonii</i>	Monsoon River Prawn	Palaemonidae	LC

NE = Not Evaluated

LC = Least Concerned

NT = Near Threatened



Tenulosailisha



Polynemus paradiseus



Otolithoides pama



Labeorohita



Amblypharyngodon mola



Channa orientalis

Figure 4.6-4: Fish Species Recorded from Study Area

(v) Butterfly

Butterfly Species belonging to 22 species in 16 genera, and 5 families were recorded during the survey period. According to baseline data, 8 species of Pieridae and Nymphalidae, 3 species of Hesperidae and 2 species of Papilionidae and the remaining are Lycaenidae. And then there was no endemic species in this area.

Table 4.6-6: List of Butterfly Species

No.	Species Name	Common Name	Family Name	IUCN Status
1	<i>Pailiopolytes</i>	Common Mormon	Papilionidae	NE
2	<i>Pachliopta aristolochiae</i>	Common Rose	Papilionidae	NE
3	<i>Catopsilia pomona</i>	Lemon Emigrant	Pieridae	NE
4	<i>Catopsilia pyranthe</i>	Mottle Emigrant	Pieridae	NE
5	<i>Appias libythea</i>	Striped Albatross	Pieridae	NE
6	<i>Delias hyparete</i>	Painted Jezebel	Pieridae	NE
7	<i>Hebomoia glaucippe</i>	Great Orange-Tip	Pieridae	NE
8	<i>Eurema andersonii</i>	Anderson Grass Yellow	Pieridae	NE
9	<i>Eurema hecabe</i>	Common Grass Yellow	Pieridae	NE
10	<i>Eurema brigitta</i>	No Branded Grass Yellow	Pieridae	NE
11	<i>Danaus genutia</i>	Common Tiger	Nymphalidae	NE
12	<i>Danaus melanippus</i>	White Tiger	Nymphalidae	NE
13	<i>Ideopsis vulgaris</i>	Blue Glassy Tiger	Nymphalidae	NE
14	<i>Cethosia penthesilea</i>	Plain Lacewing	Nymphalidae	NE
15	<i>Euploea core</i>	Common Crow	Nymphalidae	LC
16	<i>Hypolimnas bolina</i>	Great Eggfly	Nymphalidae	NE
17	<i>Junonia almanac</i>	Peacock Pansy	Nymphalidae	LC
18	<i>Junonia atlites</i>	Grey Pansy	Nymphalidae	NE
19	<i>Curetis aronias</i>	Sumatran Sunbeam	Lycaenidae	NE
20	<i>Borbocinnara</i>	Formosan Swift	Hesperiidae	NE
21	<i>Caltois brunnea</i>	Dark Branded Swift	Hesperiidae	NE
22	<i>Matapa aria</i>	Common Redeye	Hesperiidae	NE

NE = Not Evaluated

LC = Least Concerned

	
<i>Pachlioptaaristolochiae</i> (Common Rose)	<i>Euremaandersonii</i> (Anderson Grass Yellow)
	
<i>Deliashyparete</i> (Painted Jezebel)	<i>Euploea core</i> (Common Crow)
	
<i>Junonia almanac</i> (Peacock Pansy)	<i>Junoniaatlites</i> (Grey Pansy)
	
<i>Danaus genutia</i> (Common Tiger)	<i>Danaus melanippus</i> (White Tiger)

Figure 4.6-5: Butterfly Species Recorded from Study Area

(vi) Dragonfly

5 species 5 genera of dragonfly species were collected in the survey area. All species were belonging in family Libellulidae and all were Least Concerned. There were no threatened species and no endemic species in the survey area.

Table 4.6-7: List of Dragonfly Species

No.	Species Name	Common Name	Family Name	IUCN Status
1	<i>Diplacodestrivialis</i>	Ground Skimmer	Libellulidae	LC
2	<i>Brachythemiscontaminata</i>	Ditch Jewel	Libellulidae	LC
3	<i>Orthetrumsabina</i>	Green Marsh Hawk	Libellulidae	LC
4	<i>Crocothemisservilia</i>	Scarlet Skimmer	Libellulidae	LC
5	<i>Neurothemistullia</i>	Pied Paddy Skimmer	Libellulidae	LC

LC = Least Concerned



***Brachythemiscontaminata* (Ditch Jewel)**



***Diplacodestrivialis* (Ground Skimmer)**



***Orthetrumsabina* (Green Marsh Hawk)**



***Crocothemisservilia* (Scarlet Skimmer)**



Neurothemistullia (Pied Paddy Skimmer)

Figure 4.6-6: Dragonfly Species Recorded from Study Area

4.6.1 Description of Valued or Sensitive Environmental Areas and Habitats

Mangrove

Mangrove forest was found along the Twante canal and bank of Khanaungto Creek and Western bank of Yangon River (See in Figure 4.6-7). The species of mangrove observed in the project area are listed in the Table 4.6-1. Mangrove can be found in low altitude coastal and sub-coastal areas along river valleys and across watersheds. A mangrove is a tree, shrub, palm or ground fern, generally exceeding one half meter in height that normally grows above mean sea level in the intertidal zone of marine coastal environments and estuarine margins. A mangrove is also the tidal habitat comprising such trees and shrubs.



Figure 4.6-7: Mangroves

Table 4.6-8: List of Mangrove Species in Study Area

No.	Scientific Name	Family Name	Vanicular Name	Habit
1	<i>Acanthus ilicifolius</i> L.	Acanthaceae	Khaya	S
2	<i>Nypafruticans</i> Wurm	Arecaceae	Dani	ST
3	<i>Sonneratiacaseolaris</i> (L.) Engl.	Sonneratiaceae	Lamu	T

T- Tree

ST- Small tree

S- Shrub

4.6.2 Species of Economic Value

Flora

During the field survey period of Twante canal project, five economically important plant species were collected. Among them, two merchantable hardwood species such as Pyin-ka-do and Padauk are included in Hardwood Group 1 which is extracted from Myanmar Timber Enterprise (MTE) and the rest of species such as Dani, Wanet and Nget-pyaw sold only in local.

Fauna

During the field survey period of Twante canal project, six economically important aquatic species such as Hilsa, Seabass, Pangas Catfish, Croaker, Indian salmon and Monsoon River Prawn were collected, and the rest species of fauna were not collected as economically important species.

4.7 Infrastructure Facilities

4.7.1 Social Infrastructures

Table 4.7-1 indicates major social infrastructure facilities in the affected four townships.

Table 4.7-1: Social Infrastructures in the Affected Townships

Name of Township	Hotel	Lodging House	Beach/Recreation Zone	Bank	Market	News & Media Printing House	Hospital	Clinic
Twente	0	0	0	3	1	3	3	0
Dala	0	10	0	1	3	18	3	3
SeikkyiKhan aungto	0	0	0	3	1	3	3	0
Kyimyindain g	3	2	0	15	4	3	107	3

(1) Housing conditions

Nationwide the majority (85.5%) of the population in Myanmar is living in the residence of their own ownership as of 2014 (See Table 4.7-2 below). The conditions of housing units are important characteristics which indicate the quality of life of the population. Table 4.7-3 indicates that the significant proportion of household's walls is made of bamboo (more than half of the population nationwide and more than 30% in Yangon Region). In rural areas this proportion is much higher than in urban areas. The proportion of households with walls made of wood at the Union level ranks second at 21.6 percent of the total. In contrast, the housing materials in Yangon Region has higher portion of modern building materials such as concrete, tiles and bricks. Most households live in housing units

where roofs are made of corrugated sheets at the Union level (61.5%), followed by dhani, (32.9%). There were more housing units with roofs made of corrugated sheets than dhani in urban areas.

Table 4.7-2: Proportion of Households by Housing Ownership in Myanmar

I. Myanmar Union (Nationwide) Unit (%)					
Total Households	Owner	Renter	Provided free	Government Quarter	Other
10,877,832	85.5	7.4	2.5	3.3	1.3

Source: Census Report, 2014

Table 4.7-3 shows the proportion of material for housing unit in Myanmar and Yangon region.

Table 4.7-3: Proportion of Material for Housing Unit in Myanmar and Yangon Region

	Union of Myanmar			Yangon Region		
Conventional Households	10,877,832			1,582,944		
Material for housing	Wall	Floor	Roof	Wall	Floor	Roof
Dhani/Thetke ¹ /In leaf	9.5	-	32.9	9.2	-	17.8
Bamboo	51.2	25.1	2.2	31.8	15.6	0.2
Earth	0.2	7.9	-	Less than 0.1	0.5	-
Wood	21.6	50.8	0.1	24.0	52.0	0.2
Corrugated sheet	0.5	-	61.5	1.5	-	76.3
Tile/Brick/Concrete	15.9	15.2	2.2	32.0	30.7	5.2
Other	1.1	1.0	1.1	1.5	1.2	0.3

Four Affected Townships

The following table 4.7-4 and 4.7-5 show different type of housing types and materials of housing units in studied four Townships. The majority of households in Twente Township are living in bamboo houses (53.5%) followed by in wooden houses (35.1%).

The majority of the households in Dala and SeikkyiKhanaungto Township are living in wooden houses (50.0% and 66.7% respectively) followed by in bamboo houses (40.1% and 29.1% respectively).

The majority of the households in Kyimyindaing Township are living in apartment/ condominium (37.0%) followed by households in wooden houses (33.7%).

Table 4.7-4: Type of Housing Unit in Study Townships

Residence	Total	Apartment/ Condominium	Bungalow/ Brickhouse	Semi-paccahouse	Wooden house	Bamboo	Hut 2-3 years	Hut 1 year	Other
Twente	51,602	0.4	3.2	4.2	35.1	53.5	2.2	1.2	0.2
Dala	37,912	1.1	1.7	3.4	50.0	40.1	1.3	1.4	1.1
SeikkyiKhanaungto	7,729	0.3	0.6	2.4	66.7	29.1	0.4	0.4	0.2
Kyimyindaing	23,062	37.0	6.6	7.3	33.7	13.3	0.3	0.1	1.8

¹ Dhani : *Nypa fruticans* (*Areaceae*) and Thetke : *Erinthus ravenae*, (*Poaceae*) are naturally growing plants which are used as construction materials, especially for roof and wall, that are very common traditional in rural area of Myanmar.




Table 4.7-5: Proportion of Material for Housing Unit in Study Townships

Townships	Twente			Dala			Sekikyikhanaungto			Kyimyindaing		
Convention al	51,602			37,912			7,729			23,062		
Material for housing	Wall	Floor	Roof	Wall	Floor	Roof	Wall	Floor	Roof	Wall	Floor	Roof
Dhani/Theke/In leaf	36.4	-	47.6	22.4	-	32.1	19.3	-	19.0	20.1	-	9.2
Bamboo	35.7	39.0	0.1	37.2	32.5	0.2	43.	23.5	0.1	5.3	10.4	<0.1
Earth	<0.1	0.6		0.1	0.4	-	0.1	0.2	-	<0.1	0.2	-
Wood	19.4	52.4	0.1	30.8	61.1	0.1	25.	72.6	0.2	20.8	41.8	0.2
Corrugated sheet	0.3	-	51.6	2.5	-	66.8	6.2		80.3	2.4	-	82.7
Tile/Brick/Concrete	7.4	7.3	0.4	5.6	5.0	0.6	2.9	2.9	0.2	50.4	46.3	7.8
Other	0.8	0.7	0.2	1.4	1.0	0.2	2.4	0.8	0.2	1.0	1.3	0.1

(2) Electricity

Electricity and Energy

In Myanmar, about 70% of the population is reliant on firewood for cooking (Table 4.7-6). This practice is contributing to the increasing rates of deforestation seen within the country. Some households use electricity and charcoal in cooking.

Table 4.7-6: Access to Energy

Source	Cooking	Source	Lighting
Electricity	16.4%	Electricity	32.4%
LPG	0.4%	Kerosene	8.1%
Kerosene	0.2%	Candle	20.7%
Biogas	0.3%	Battery	17.0%
Firewood	69.2%	Generator	9.3%
Charcoal	11.8%	Water mill	1.6%
Coal	0.3%	Solar system	8.7%
Other	1.4%	Other	2.2%




Figure 4.7-1: Main Source of Energy for Cooking in Myanmar




Figure 4.7-2: Main Source of Energy for Lighting in Myanmar

In terms of lighting, a range of sources are available. Figure 4.7-2 indicates that the most commonly used are electricity, candle, and batteries. The access to electricity is likely to become easier in the future given the investment that the Myanmar government is making in the power sector; a number of new power plants are being developed in order to provide an increasing number of people with electricity.

Table 4.7-7 shows the number of conventional households by main source of lighting in Twente, Dala, SeikkyiKhanaungto and Kyimyindaing townships according to the result of the census in 2014. Around 85.3%, 76.4%, 48.2%, and 16.4 % of households use electricity in Kyimyindaing, SeikkyiKhanaungto, Dala and Twente townships, respectively, marking significant differences across the Townships.

Table 4.7-7: Conventional Households by Main Source of Lighting

Townships	Total	Electricity	Kerosene	Candle	Battery	Generator (Private)	Water Mill (Private)	Solar System / Energy	Other
Twente	51,602	8,446	13,080	8,745	15,203	3,391	26	2,673	38
(%)	100	16.4	25.3	16.9	29.5	6.6	0.1	5.2	0.1
Dala	37,912	18,270	1,138	3,887	7,571	6,202	87	645	112
(%)	100	48.2	3.0	10.3	20.0	16.4	0.2	1.7	0.3
SeikkyiKhanaungto		5,905	*	1,345	426	*	-	*	*
(%)	100	76.4	0.2	17.4	5.5	0.2	-	0.2	0.2
Kyimyindaing	23,062	19,669	24	750	2,154	84	-	*	*
(%)	100	85.3	0.1	3.3	10.9	0.4	-	<0.1	0.1

Note: * Less than 20

Energy

Electricity is a common energy in all townships except Twente Township where only 35% can access to electricity. Highest electrification rate among the four Township is in Kyimyindaing, marking as high as 96% of the electrification rate, followed by SeikkyiKhanagunto (88%) and Dala (77%). The results indicate the dire need for electrification in Twente Township. The reasons in electricity problem are reported to be: frequent cut of electricity, low voltage and irregular voltage.

Table 4.7.8: Electricity (%)

Township	Yes	No
Twente	35	65
Dala	77	23
SeikkyiKhanagunto	88	12
Kyimyindaing	96	4




Figure 4.7-3: Electricity (%)

Most of the respondents use electricity for cooking. About 80% of people in Kyimyindaing Township use electricity for cooking. Charcoal and firewood are another source of fuel for cooking. There are no uses of gas and fuel oil in the project area.

(3) Source of Water

The studied townships's the source of drinking water and non-drinking water are shown in Table 4.7-8 and 4.7-9.

Table 4.7-9: Source of Drinking Water in the Four Affected Townships

Township	Source of Water	Tap Water/ Piped	Tube Well, Borehole	Protected Well/ Spring	Bottled / Purifier Water	Total Improved Water Sources	Unprotected well/spring	Pool/Pond/ Lake	River/Stream/Canal	Waterfall/ Rainwater	Other	Total Unimproved Water Sources
Twente	Number	41	15,204	4,928	320	20,493	3,668	22,400	4,919	82	40	31,109
	(%)	0.1	29.5	9.5	0.6	39.7	7.1	43.4	9.5	0.2	0.1	60.3
Dala	Number	642	87	41	2,196	2,966	47	32,379	22	2,171	327	34,946
	(%)	1.7	0.2	0.1	5.8	7.8	0.1	85.4	0.1	5.7	0.9	92.2
SeikkyiKha naungto	Number	*	*	*	246	253	*	7,104	-	69	301	7,476
	(%)	<0.1	0.1	<0.1	3.2	3.3	<0.1	91.9	-	0.9	3.9	96.7
Kyimyindaing	Number	1,206	5,744	23	8,769	15,742	41	5,425	*	*	1,842	7,320
	(%)	5.2	25.0	0.1	38.0	68.3	0.2	23.5	<0.1	>0.1	8.0	31.7

(Source: Department of Population, Ministry of Immigration and Population, “The 2014 Myanmar Population and Housing Census—The Union Report-Census Report Volume 2” May 2015)

(Note: * Less than 20)

Table 4.7-10: Source of Non-Drinking Water in the Four Studied Townships

Townships	Source of Non-Drinking Water	Tap Water/ Piped	Tube Well, Borehole	Protected Well/Spring	Unprotected Well/ Spring	Pool/Pond/ Lake	River/Stream/Canal	Waterfall/ Rainwater	Bottled/ purifier water	Other
Twente	Number	41	19,197	3,004	3,74	16,80	8,747	*	*	37
	(%)	0.137	37.2	5.8	7.3	32.5	17.0	<0.1	<0.1	0.1
Dala	Number	3,870	1,128	194	55	32,52	42	51	*	33
	(%)	10.2	3.0	0.5	0.1	85.8	0.1	0.1	<0.1	0.1
Seikkyi Khanau ngto	Number	*	54	*	*	7,648	*	*	*	-
	(%)	0.1	0.7	0.1	0.1	99.0	0.1	<0.1	0.1	-
Kyimyindaing	Number	909	17,569	58	45	4,397	*	-	28	44
	(%)	3.9	76.2	0.3	0.2	19.1	0.1	-	0.1	0.2

(Source: Department of Population, Ministry of Immigration and Population “The 2014 Myanmar Population and Housing Census—The Union Report-Census Report Volume 2” May 2015)

(Note: * Less than 20)

In our household survey, most of the respondents from Dala Township depended on bottled water (31%) and pond and lake (51%). Piped water (25%) is only available in Dala Township. Some respondents from Dala, SeikkyiKhanau ngto and Twente Township depend on tube wells (14%) and common taps (3%). The survey respondents in Kyimindaing and Dala had relatively higher level of

accessability to drinking water (with 78% and 71% respectively) than those in Twente and Dala (48% and 34% respectively). (See Figure 4.7-4). There is a possiblity that the condition of the drinking water accessability has changes since the 2015 stats survey.

Table 4.7-11: Access to Drinking Water (%)

Township	Yes	No	Don't know
Twente	48	39	13
Dala	71	29	0
SeikkylKhanaungto	34	63	3
Kyimyindaing	78	13	9




Figure 4.7-4: Use of Drinking Water Problem (%)

4.7.2 Information and Communication Infrastructure

4.7.3 Waste Management

In Myanmar, it is anticipated that approximately 0.45 kilograms of waste is produced per capita per day (Glawe et al. n.d.). This includes organic waste, commercial waste and paper and plastic waste.

It is estimated that nearly 65% of the waste generated is organic waste. This is attributed to the size of the agricultural sector, as the agricultural sector largely generates organs waste.

In most major cities – such as Yangon – household waste is collected and disposed of for a small fee. However, outside major cities, waste disposal is typically the responsibility of the household. In both instances, solid waste is often disposed of at open dump sites, in other words uncontrolled sites. In a small number of cases, composting and recycling is carried out.

The followig Table presents the proportion of the households in Myanmar by ownership of selected informaion and communication items such as: radio, televisionset, mobilephone, landline telephone, computer, internet-at-home divided by urban/rural areas.

Table 4.7-12: Proportion of households by Ownership of Selected Information and Communication Items

	Total	Radio (%)	Television (%)	Landline phone	Mobile phone	Computer	Internet at home	% with none of the items	% with all of the items
UNION	10,877,832	35.5	49.5	4.8	32.9	3.5	6.2	30.3	0.5
Urban	3,049,433	27.2	75.8	9.4	63.5	10.2	17	14.8	1.5
Rural	7,828,399	38.8	39.2	3.1	21	0.8	2	36.4	0.1

4.7.4 Transportation

In terms of roads, most urban areas in Myanmar are accessible only by road. However, nearly half of all roads are not passable during the monsoon season (World Bank 2015) – limiting access to key areas within the country.

Myanmar has three main highways or corridors running north-south, as follows:

- Yangon-Mandalay Road – The road passes through major cities in central Myanmar such as Bago, Thungoo, Pyinmana, Naypyidaw, and Meikhtila ;
- Yangon-Pyay Road – This road runs west of the Pegu Range ; and
- Western Union Highway – The road connects urban areas west of the Ayeyarwaddy River, but is still largely under construction.

[Transport infrastructure in Myanmar]

Myanmar's roadways received the government's attention in the 90's, but not many improvements have been made. Approximately 12 percent of the roads are paved with an overwhelming majority being made of gravel (about 2/3). The remaining roads are not easily accessible by cars, but by jeeps or ox carts.

The railways aren't much better, since there are from the time of British rule (and government owned and run). There are about 2,000 miles of track, but they don't connect with railways outside of Myanmar, only with major cities within the country.

The major mode of transportation for passengers or for carrying cargo is the use of the inland waterways. There are about 8,000 miles of rivers and canals with 2,000 miles of it navigable for large commercial boats. Considering the fact that most of the major cities in Myanmar are near water, this isn't surprising.

There is an airline in Myanmar (Myanmar Airways) that is owned by the government and does have international service to a few countries/cities. Joint ventures with companies in Singapore have brought about the modernization of domestic flights. There are other airlines (international carriers) who provide flights directly to Mandalay and Bagan.

[Transport vehicle ownership]

Table 4.7-11 4.7-1 2 present information on the ownership of household transportation assets (bicycles, motorcycles, cars/trucks/vans, etc.) such as at the Union level and by urban and rural areas:

Table 4.7-12: Conventional households by Ownership of Transportation Items, Myanmar, Yangon Region and Study Townships

Region/District/Township	Conventional households	Car/Truck/Van	Motorcycle/Moped	Bicycle	4-Wheel tractor	Cane/Boat	Motorboat	Cart(bullock)
Union of Myanmar	10,877,832	3.1	38.7	35.9	2.5	3.9	2.2	21.6
Yangon Region	1,582,944	7.8	13.6	46.2	1.2	1.2	1.0	4.8
Twente Township	51,602	1.0	19.9	31.8	1.9	5.8	6.6	6.0
Dala Township	37,912	1.0	17.7	42.4	1.6	1.2	1.7	6.2
Seikkyi Khanaung Township	7,729	0.5	8.3	45.7	0.2	2.9	0.5	0.7
Kyimyindaing Township	23,062	12.8	3.8	15.7	0.1	2.6	0.5	0.8

(Source: Census Report, 2014)

4.7.4.1 Transportation of Twente Township

Inland Water Transportation especially water and highway facilities in Twente Township is as shown table 4.7-14 and 4.7-15.

Table 4.7-14: Water Transport at Twente Township

No.	Name of Waterway	Within Township		Mile	Number of Jetty	
		From	To		Port	Other
1	Twente- Kayinachaung	Twente	Kayinachaung	7	1	-
2	Twente- Twentewa	Twente	Twentewa	6	1	-
3	Twente- Tanphyuzayaat	Twente	Tanphyuzayaat	7	1	-
4	Twente-Yangon	Twente	Yangon	17	1	-
				37	4	-

Source: General Administrative Department, 2017

Table 4.7-15: Highway Facilities at Twente

No.	Name of Highway	Within Township		Mile
		From	To	
1	Twente-Hlaingtaryar	Twente	Hlaingtaryar	22
2	Twente-Dala	Twente	Dala	17
3	Twente-Payargyi	Twente	Payargyi	10
4	Twente-Yaykyaw	Twente	Yaykyaw	6
5	Twente-Maopin	Twente	Maopin	30
				85

Source: General Administrative Department, 2017

4.7.4.2 Transportation of Dala Township



Figure 4.7-3: Transportation map of study Townships

Figure 4.7-3 shows the transportation map of study townships.

Inland Water Transportation especially water and highway facilities in Dala Township is as shown table 4.7-16 and 4.7-17.

Table 4.7-16: Water Transport at Dala

No.	Name of Waterways	Within Township		Mile	Number of Jetty	
		From	To		Jetty	Other
1	Dala-Yangon	-	-	0.5	1	
2	Tamata	-	-	0.5	-	1
3	Kamaraung	-	-	0.5	-	1
4	Talyat	-	-	0.5	-	1
5	Yaykan	-	-	0.5	-	1
6	Kamarkatwe	-	-	0.5	-	1
7	Satmay	-	-	0.5	-	1
8	Kamarkasit	-	-	0.5	-	1
9	Mawsat	-	-	0.5	-	1
10	Kaungsu	-	-	0.5	-	1
11	Sarparchaung	-	-	0.5	-	1
12	Nyeinchan	-	-	0.5	-	1
	Total	-	-	-	1	11

Source: General Administrative Department, 2017

Table 4.7-17: Highway Facilities at Dala Township

No.	Name of Highway	Within Township		Mile
		From	From	
1	Dala-Danote	Dala	Danote	14

Source: General Administrative Department, 2017

4.7.4.3 Transportation of SeikyiKhanaungto Township

Inland Water Transportation especially water in SeikkyiKhanaungto Township is as shown in Table 4.7-18.

Table 4.7-18: Water Transport at SeikyiKhanaungto Township

No.	Name of Waterways	Within Township		Mile	Number of Jetty	
		From	To		Port	Other
1	Twente Canal-Kanaungto creek	Seikkyi	Tax office	3	2	6

Source: General Administrative Department, 2017

4.7.4.4 Transportation of Kyimyindaing Township

Inland Water Transportation and highway facilities in Kyimyindaing Township is as shown table 4.7-19.

Table 4.7-19: Highway Facilities at Kyimyindaing Township

No.	Name of Highway	Mile	Type
1	Upeer/Lower Kyimyingdaine Road	3	Tar
2	Hlaing river	2.9	Port
3	Hantharwady-Pan Hlaing	2.9	Railway station

Source: General Administrative Department, 2017

4.7.5 Traffic Accident Trends:

4.7.5.1 Safety and Stability of Inland Water Transport

DWIR from the table below it appears that the comparative safety level of Yangon river water transport is not higher than those of the other major rivers in Myanmar (Please see the Table 4.7-20 below.)

Table 4.7-21: Yearly Vessel Accidents in Myanmar's Inland Waterways

Fiscal Year	Number of Accidents in Inland Waterways									Number of Accidents
	Ayeyarwaddy River	Chindwin River	Thanlwin River	Ataran River	Delta Waterways	Twante Canal	Pun Hlaing River	Ngamoeyek Creek	Yangon River	
2004	9	6	1	1	3	2	1	0	0	23
2005	7	6	0	0	0	5	0	0	0	18
2006	2	3	0	0	3	4	0	0	0	12
2007	8	3	0	0	0	7	1	0	0	19
2008	5	1	1	0	1	5	2	0	0	15
2009	8	1	0	0	2	2	0	0	0	13
2010	4	2	0	0	0	3	1	1	0	12
2011	10	1	0	0	1	1	1	1	1	16
2012	8	2	0	0	1	4	0	0	0	15
2013	6	12	1	0	0	0	1	1	0	21
1 April-30 June 2014	2	0	0	0	0	0	0	1	0	3
Total	69	37	3	1	12	33	7	4	1	167

Source: Directorate of Water Resources and Improvement of River Systems.

During the last 14 years, from 2004 to 2018, the number of 34 accidents in total were recorded within the project region, especially Twante canal and Kanaungto creek area. According to the records, there was no occurrence of accident in 2013 and 2014. Accidents most commonly include by attacking with one another, the anchored vehicles in the middle of water and sometimes with the bollard at the jetty. Sometimes the accidents are caused by weak strength of water vehicles which can make seeping of the water into the vehicles while anchoring at the berth or sometimes by anchoring for long time. and then sank underwater and some are due to by lack of awareness to avoid overloading of the goods on the ships and one of them is found by fire in one shipyard in Kanaungto creek in 2008.

The following table shows the records of accident of shipwreck and other inland water transport accident in Twante Canal in the last 14 years:

Table 4.7-20: Records of the Inland Water Transport Accidents from 2004 to 2018 in the Project Region

No.	Year	Accident /Location	Human Casualties (Number)
1	2004	Twante Canal (Near 1.0 mile)	None
2		Twante canal (at the point of A Kauk Sa Khan)	2 Lost
3	2005	Twante Canal (4 mile)	None
4		Twante Canal (3.25-mile, Lat Pan Gone Village)	None
5	2006	Twante Canal (Above 7 mile)	None
6		Twante Canal (3.75 mile)	None
7		Twante Canal (3.5 mile)	None
8		Kanaungto Creek	None
9		Twante Canal (Near 11 mile)	None
10		Twante Canal (Lat Pan Gone Village)	None
11	2007	Twante Canal (12 mile)	None
12		Twante Canal (0 mile)	2
13		Twante Canal (between 19.5 mile and 20 mile)	10
14		Twante Canal (4.5 mile)	None
15		Twante Canal (3.5 mile)	1+ 2 Lost

16		Twante Canal (14.5 mile)	None
17	2008	Twante Canal (4.5 mile)	None
18		Kanaungto Creek (Tha-nin-thar-ri shipyard)	None
19		Twante Canal (3.25 mile)	None
20		Twante Canal (3.5 mile, Lat Pan Gone, A Kauk Sa Khan)	None
21		Twante Canal	None
22	2009	Twante Canal (Near 5 mile)	None
23		Twante Canal (12.5 mile)	None
24		Twante Canal	4
25		Twante Canal (0.5 mile)	None
26	2010	Twante Canal (21 mile)	1 + 3 (Lost)
27	2011	Twante Canal (10.5 mile)	
28	2012	Twante Canal (4 mile)	1
29		Kanaungto Creek	None
30		Junction of Twante Canal and Toe River	1 Lost
31	2013	Twante Canal (Near 9.5 mile)	None
32	2016	Twante Canal (4 mile)	None
33		Kanaungto Creek	None
34	2018	Kanaungto Creek	None

(Source: Directorate of Water Resources and Improvement of River Systems-DWIR)

Positive social impacts would be mainly enhanced safety and stability of inland water transport along the Twante Canal area. Safety accidents due to rapid flows at some points of the canal would be reduced and the flood-related disasters and accidents would be mitigated. Enhanced safety of the inland water transport in Twante Canal will primarily benefits the regular/frequent users of the transport such as commuters crossing the canal on regular basis as well as the inland transport operators. In principles all the uses of the inland water transport in the canal will be beneficiaries. Population living along the canal have been most vulnerable to the damages and disasters related to the regular flooding in the canal. They vulnerability to the disaster is expected to be reduced to a certain extent.

[Road Transport]

The table below presents the traffic accidents in Myanmar increased between 2013 and 2014. The overall number of accidents, injuries and fatalities in 2014 were 1,081,818,621 and 3,064 respectively. For Yangon Region, the statistics in 2014 are 3,241 and 425, respectively. (Table 4.7-13)

Table 4.7-13: Road Traffic Accidents by States and Regions in Myanmar (2013-2014)

No.	State/ Region	2014 January to October			2013 January to October		
		Accident	Injury	Fatality	Accident	Injury	Fatality
1.	Naypyitaw	279	472	143	306	450	172
2.	Kachin	352	507	136	259	445	109
3.	Kayah	102	140	33	95	150	20
4.	Kayin	313	629	96	294	537	62
5.	Chin	69	146	30	57	109	24
6.	Sagaing	1241	2302	312	530	881	144
7.	Tanintharyi	252	406	97	316	624	76
8.	Bago	1163	2193	340	1208	2108	288
9.	Magway	923	2060	221	785	1610	179
10.	Mandalay	1116	1960	354	988	1603	300

11.	Mon	434	712	193	456	723	203
12.	Rakhine	263	465	76	215	334	69
13.	Yangon	2295	3231	425	2177	3210	324
14.	Shan	401	742	137	341	665	106
15.	Shan (Lasio)	307	402	169	235	396	84
16.	Shan (Kyaington)	137	287	73	139	257	65
17.	Ayeyarwaddy	1171	1967	229	875	1627	190
	Total	10818	18621	3064	9276	15729	2415

The road accident records in Township level are not available.

4.8 Socio-Economic Components

4.8.1 Location of the Project Area

Myanmar is located in Southeast Asia. The country is bordered to the east by Thailand and Laos, to the north by China and to the west by India. Myanmar has a lengthy coastline that extends for approximately 2400 km along the Andaman Sea and Bay of Bengal. (Figure 4.8-1)

There are a number of mountain ranges and river systems, which run north to south through the country- creating natural divisions. This includes the Ayeyarwaddy River, which is the largest river system in Myanmar. It starts in the Himalayas and empties into the Bay of Bengal and accommodates about 70% of the country's population and transports 40% of its commerce.

There are three distinct seasons in Myanmar. The cold and dry season runs from November to February, while the hot season is March and April, and the rainy season extends from May to October. During the rainy season monsoons can occur, causing flooding and landslides.

Myanmar is split into number of States and Regions (sometimes also referred to as Division), which are further divided into Township for administrative or governance purposes.



Figure 4.8-1: Map of Republic of the Union of Myanmar

The Project area is located in the Twente, Dala, SeikkyiKanaungti and Kyimyindaing townships in the Yangon Western District, Yangon Region. Twente Township (also known as Twente Township) is a township in the Yangon Region of Myanmar. It is located west across the Hlaing River from the city of Yangon. Twente Township is between North Latitude 16° 33" and East Longitude 96° 58". The total area is 279.09 square miles. It adjoins Kyimyindaing Township, SatekyiKhanaungto Township and Dala Township in east, Kawmu Township in South, Maubin Township and Nyaung Tone Township in West and HtanTabin and Hlaing Tar Yar Township in North. It has an area of 279.09 square miles. It has the longest man made canal in Myanmar is Twente canal and it is also a shortcut waterway to Ayeyarwaddy river to Yangon river which divides Twente Township with its length of 35 km and there is one bridge that spans the canal is called Twente bridge. The 220 villages of Twente Township are organized into 65 village tracts and 8 urban wards. Twente Township is well known for its pottery activities handled by a few families since several generations. It is also area of fish farming in Yangon region (seen in Figure 4.8-2).




Figure 4.8-2: Map of the Twente Township

Dala Township is located at the South of Yangon. Between North Latitudes $16^{\circ} 20''$ and $16^{\circ} 32''$ and between East longitude $96^{\circ} 16''$ and $96^{\circ} 18''$ and the area coverage is about 86.51 square mile and on the southern bank of Yangon River across from downtown of Yangon. The township, made up of 23 wards and 23 village track (including 50 villages), is bounded by the Yangon River in the north and east, the Twente Canal in the west, and Twente Township in the south. There are 7 miles from east to west and 10 miles from south to north. There are Yangon River in the eastern, Kawmhu Township in the South. In the western, there is Twente Township and Yangon River in the North (Figure 4.8-3).



Figure 4.8-3 (a): Map of Dala Township




Figure 4.8-3 (b): Map of DalaTown

SeikkyiKhanaungto Township is located on the southwestern bank of Yangon River across from downtown Yangon. The township comprises eight wards, and is bounded by the Yangon River in the north, the Twente Canal in the east, and Twente Township in the south and west. The township is still largely rural and undeveloped mainly because it still lacks a bridge across the Yangon River to downtown. It is located between North latitude 16° 45" and 16° 48", from east to west is mile and south to north is 2.3 mile. In eastern, there are Yangon River and Dala Township, Twente Township in east, Kawmu Township in West, Twente Township and Dala Township in South and in north bordering with Yangon River and Kyimyindaing Township. It has an area of 3.04 square miles (Figure 4.8-4).




Figure 4.8-4 (a): Map of SeikkyiKhanaungto Township




Figure 4.8-4(b): Map of SeikkyiKhaungto Town

Kyimyindaing Township is located on the western part of Yangon. Kyimyindaing Township is located between $16^{\circ} 46' 51''$ N, $16^{\circ} 49' 45''$ N and $96^{\circ} 6' 75''$ E, $96^{\circ} 7' 48''$ E. There are 2 miles from east to north and 2.08 miles from south to north. The total square mile of township is 4.808.

It adjoins Sanchaung Township in eastern and being border with Alone Township and SeikkyiKhaunaungto Township in southern. In northern, there are border with Kamaryut Township and Hlaingtaryar Township.

Kyimyindaing Township is situated above sea level of 35 feet. Kyimyindaing Township is fewer in river and creeks. Most of the creek is flowing from north to south. The famous river in township is Hlaing River (Yangon River) and flow through the center of the township form north to south. In the east, there is Pun Hlaing river and flowing from west to east through Yangon River. In summer, Yangon River in water become saltwater and not available to drink and also cannot use for Agricultural. Pun Hlaing River is only about 3 feet in depth of water and cannot pass boats (Figure 4.8-5).




Figure 4.8-5: Map of Kyimyindaing Township

4.8.2 Socioeconomic Profile

4.8.2.1 Demography

As of 2017, it was estimated that the population of Myanmar was approximately 54.67 million, with an annual growth rate of approximately 1% (CIA 2015). The population in the Mandalay Region is estimated to be 6.2 million, making it the second largest region in the country in terms of population, after Yangon Region, which has a population of approximately 7.3million.

4.8.2.1.1 Population of Myanmar

Table 4.8-1 indicates population and its annual average growth rate in the census years (1973, 1983 & 2014). The population of Myanmar increased at the rate of 0.89% per annum between 2003 and 2014. During 40 years from 1973 to 2014, population of Myanmar had almost doubled from 29 million to 51 million. The growth rate is getting lower from 2.0 during 1973-1983 to 0.89% in 2014.

Distribution of population among regions/states is indicated in Table 4.8-2. Percentage of population distribution did not change much in all regions and states during 1973 and 2014. Comparing the proportion of the population by State and Region, Yangon Region ranks as the largest number. Ayeyarwaddy and Mandalay Regions had a higher population than Yangon Region in the 1983 and 1973 censuses. Until 2014, the percentage share of population had increased in Shan, Kachin, Kayah, Kayin, and Rakhine States and Tanintharyi Region. Kayah and Chin still remain the States with the least proportion of the population. Percentage share of population had decreased in Chin and Mon States and Sagaing, Bago, Magway, Mandalay, and Ayeyarwaddy Regions. From 2014 to 2016, proportion of population distribution slightly changed in all regions and states.

Table 4.8-1: Population and Annual Average Growth Rate in Census Years

Year	1973	1983	2014
Total Population	28,921,226	35,306,913	51,486,253
Annual Average Growth Rate (%)	2.0	2.0	0.89

Source: Myanmar Statistical Yearbook, 2017

Table 4.8-2: Population Distribution among Regions/States

Regions/States	Proportion of the Total Population			
	1973	1983	2014	2016
UNION	100	100	100	100
Kachin	2.6	2.6	3.3	3.4
Kayah	0.4	0.5	0.6	0.57
Kayin	3.0	3.0	3.1	3.0
Chin	1.1	1.0	0.9	0.95
Sagaing	10.8	10.9	10.3	10.3
Tanintharyi	2.5	2.6	2.7	2.74
Bago	11.0	10.8	9.5	9.28
Magway	9.1	9.2	7.6	7.45
Mandalay	12.7	13.0	12.0	11.96
Mon	4.5	4.8	4.0	3.82
Rakhine	5.9	5.8	6.2	6.2
Yangon	11.0	11.2	14.3	14.67
Shan	11.0	10.5	11.3	11.52
Ayeyawady	14.4	14.1	12.0	11.84
Nay Pyi Taw	-	-	2.3	2.3

(Note: Provinces do not exist at that time in blank cells.)

(Source: Myanmar Statistical Yearbook, 2017)

According to Myanmar Statistical Yearbook 2017, the estimated population (2016-2017) of Myanmar was 52 million and the sex ratio (the number of males per 100 females) was 92.66. In the proportion of people, the age group of 15-59 years was 62.44%. The crude birth rate per 1000 person was 20.2% and the crude death rate was 9.1%. In terms of population distribution, 70% of total population lived in rural areas and 30 % live in urban areas.

4.8.2.1.2 Population of Yangon Region

The total population of Yangon Region represents 14.3 percent of the total population of Myanmar. In terms of the proportion of the total population, the population of Yangon Region has increased from 11.2 percent in 1983 to 14.3 percent in 2014. Table 4.8-3 shows the proportion of each State and Region to the total population in the country. The total population of Yangon Region is the highest in size when compared with other States and Regions in the country, followed by Ayeyarwaddy and Mandalay Regions.

Since 1973, the population of Yangon Region has increased from 3,190,359 to 3,965,916 in the 1983 Census and 7,360,703 in the census of 2014. The population of Yangon Region has increased by about 85 percent between the 1983 and the 2014 census.

Table 4.8-3: Population of Myanmar and Yangon Region in Census Years

	1973	1983	2014
Union of Myanmar	28,921,226	35,306,913	51,486,253
Yangon Region	3,190,359	3,973,626	7,360,703

Source: Myanmar Statistical Yearbook, 2017

Table 4.8-4 indicates that the total population of Yangon Region was 7.36 million and the sex ratio (the number of males per 100 females) was 91.4 which is lower than that of the Union. Comparing the population density by State and Region, Yangon has the highest density (716.3 per km²) and the population density of Union is 76.1 persons per square kilometer (km²).

Table 4.8-4: Population Estimates, Growth Rate and Density

	Population			Annual Average Growth Rate	Sex Ratio (the number of males per 100 females)	Population Density (/km ²)
	Total	Male	Female			
Union of Myanmar	51,486,253	24,824,586	26,661,667	0.88*	93.1	76.1
Yangon Region	7,360,703	3,516,403	3,844,300	2.18*	91.4	716.3

(Source: a. The Union Report: Census Report Volume 2, May 2015)

(*b. Myanmar Statistical Yearbook, 2017)

4.8.2.1.3 Population of Twente, Dala, SeikkyiKhanaungto, and Kyimyindaing Township

The lack of publicly available demographic data for 2018 at township level is a major impediment to detailed analysis. The extensive, annually collected, demographic data is not readily available for 2018 and the last countrywide data shared is for 2014. Figure 4.8-6 shows the population of Twente, Dala, SeikkyiKhanaungto, Kyimyindaing townships.




Figure 4.8-6: Population Map for Study Townships

Table 4.8-5 shows the population by sex, annual growth rate and population density of Twente, Dala, SeikkyiKhanaungto and Kyimyindaing Townships. It indicates that the population of females exceeds the population of males in Twente, Dala, and Kyimyindaing Townships. In terms of sex ratio, the township Twente and Dala have the highest sex ratio in the region at 96 males per 100 females. The lowest sex ratio of the population is 89 males per 100 females which is lower than that of Nationwide and Yangon Region.

Table 4.8-5 and Figure 4.8-7 provide that the annual population growth rate in Twente Township as 1.36% which is higher than nationwide annual growth rate of 0.88%. Kyimyindaing Township has the lowest annual growth rate at 0.30 which is lower than the national growth rate. In all the four affected Townships, the annual population growth rate is lower than the average in Yangon Region.

Table 4.8-5: Population by Sex, Annual Growth Rate, and Population Density of the Four Affected Townships

	Population					
	Total	Male	Female	Annual Average Growth Rate	Sex Ratio (the number of males per 100 females)	Population Density (/km ²)
Twente	226,836	111,251	115,585	1.36*	96	312.9
Dala	172,857	84,671	88,186	0.75*	96	771.5
Seikkyi Khanaungto	34,003	17,068	16,935	0.78*	101	4,313.3
Kyimyindaing	111,514	52,627	58,887	0.30*	89	8,955.4

Source: a. Census Report, 2014,

b. * General Administrative Department, 2017




Figure 4.8-7: Annual Average Growth Rate

[Work Population by Township]

Twente Township

The proportion of productive working population between 15 to 64 years of age in Twente Township is 65.4 per cent. The proportions of children aged 14 and below together with the proportion of the elderly aged 65 and over are less than the working age group population. Fewer proportions of children and elderly reduce the dependency of those age groups on the working age population. The birth rate has been noticeably declining in Twente Township since the last 10 years.

Dala Township

The proportion of productive working population between 15 to 64 years of age in Dala Township is 66.8 per cent. The proportions of children aged 14 and below together with the proportion of the elderly aged 65 and over are less than the proportion of the working age group population. Fewer proportions of children and elderly reduce the dependency of those age groups on the working age population. *Seikkyi Khanaungto Township*

The proportion of productive working population between 15 to 64 years of age in Seikkyi Khanaungto Township is 65.9 per cent. The proportion of children aged 14 and below together with the proportion of the elderly aged 65 and over are less than the proportion of the working age group population. *Kyimyindaing Township*

The proportion of productive working population between 15 to 64 years of age in Kyimyindaing Township is 71.9 per cent. The proportions of children aged 14 and below together with the proportion of the elderly aged 65 and over are less than the proportion of the working age group population.

[Age Group Breakdown by Township]

The following Table 4.8-6 provides population by age group. All the four affected Townships are characterized by a positive sex ratio, with more women than men.

Table 4.8-6: Population by Age Group and Gender of Townships

Township	Above 18 years old			Under 18 years old			Total		
	Male	Female	Total	Male	Female	Total	Male	Female	Total
Twente	74702	78700	153402	37169	37282	74551	111871	116082	227953
Dala	50278	53258	103536	24903	26124	51027	75181	79382	154563
SeikkyiKhannaungto	6652	6588	13240	10111	10593	20704	16763	17181	33944
Kyimyindaing	35234	41255	76489	12040	12758	24798	47274	54013	101287

Source: General Administrative Department, 2017

[Conventional Households by Sex and Size]

Table 4.8-7 shows population and number of conventional households by sex, by mean household size in study Townships. In Twente Township, there are more females than males with 96 males per 100 females. The majority of the people in the Township live in rural areas with only (19.0%) living in urban areas. The population density of Twente Township is 313 persons per square kilometers. There are 4.3 persons living in each household in Twente Township. This is slightly lower than the Union average.

In Dala Township, there are more females than males with 96 males per 100 females. The majority of the people in the Township live in urban areas with (69.1%). The population density of Dala Township is 772 persons per square kilometers. There are 4.5 persons living in each household in Dala Township. This is slightly higher than that of the Union average.

In SeikkyiKhanaungto Township, there are more males than females with 101 males per 100 females. Considering that the natural birth rates indicates slightly more female birth than male (for biological reason), excedence of the male popuolation over female in this township indicates that that the inbound (economic) migration of the male popluation into the township, presumably related to the shipyard operations. All the people in the Township live in urban areas. The population density of SeikkyiKhanaungto Township is 4,313 persons per square kilometers. There are 4.3 persons living in each household in SeikkyiKhanaungto Township. This is slightly lower than the Union average.

In Kyimyindaing Township, there are more females than males with 89 males per 100 females. The entire population in the Township lives in urban areas. The population density of Kyimyindaing Township is 8,955 persons per square kilometers. There are 4.6 persons living in each household in

Kyimyindaing Township. This is slightly higher than to the Union average.

According to the census report, the average size of conventional households in Myanmar at the time of the 2014 Census was 4.4 persons. There were 10,877,832 conventional households in Myanmar at the time of the census. The number of persons enumerated in conventional households was 47,929,999, representing 95.3 percent of the population. The remaining 2,349,901 persons were living in institutional households.

As of 2014, it was recorded that there are total 51,602 households in Twente; 37,912 households in Dala; 7,729 households in SeikkyiKanaungto, and; 23,062 households in Kyimyindaing Township respectively. Twente has only 19% households that are residing in urban area. The urbanalization rate is highest in SeikkyKanaunto and Kyimyingdaing with 100% of the households are residing in urban area.

Table 4.8-7: Population and Number of Conventional Households by Sex, by Average Household Size in the Four Affected Townships

Township	Population in Conventional Households			Gender ratio (male/female: %)	Household	Average No. of Person in Household	Percentage of Urban Population	Ward	Village Tract	Village
	Total	Urban	Rural							
Twente	221,372	41,543	179,829	96	51,602	4.3	19%	8	65	234
Dala	170,363	117,577	52,786	96	37,912	4.5	69.1%	23	23	54
Seikkyi Kanaungto	33,251	33,251	-	101	7,729	4.3	100%	9	-	-
Kyimyindaing	106,702	106,702	-	89	23,062	4.6	100%	22	-	-

(Source: Yangon Region, Census Report, 2014)

Table 4.8-8: Demographic Profile of the Village/Ward in Survey Areas

Township	Study Ward/Village	Respondents			Sampling Ratio (Out of the expected project affectedhouseholdsof the Township) (%)
		Male	Female	Total	-
Twente	1. Pathein 2. Sat Ka Lay 3. Thar Si 4. Sat San 5. PyawBwal Lay	57 (52%)	36 (48%)	93 (100%)	38.9% (93/239)
Dala	1. Hmaw Set 2. KyaungSu 3. Tar Gyi	16 (21%)	61 (79%)	77 (100%)	13.4% (77/575)
SeikkyiKhanaungto	1. U Tun Oh 2. Pan Pin Chaung 3. Samar Du War 4. ThaKhin Ba 5. Thaug 6. Ka Naungto (east) 7. Seikkyi (west) 8. Seikkyi (east)	45 (28%)	115 (72%)	160 (100%)	16.5% (160/972)
Kyimyindaing	1. Seik Kyi 2. U Myar 3. Nga Zin	7 (30%)	16 (70%)	23 (100%)	7.1% (23/323)
Total	-	125 (35%)	228 (65%)	353 (100%)	16.74% (353/2,109)

(Source: Household Survey, 2018)

The respondents were divided into four broad age groups, those less than 18 years (Minors), 19-35 years (Young adults), 36-50 years (Mature adults), and over 50 years (Elders). Figure 4.8-9 shows that Population by broad age groups in study Townships.

Table 4.8-9: Age Group of Respondents (%)

Township	Minors (18 years)	Young adults (19-35)	Mature Adults (36-50)	Elders (>50)
Twente	2%	42%	41%	15%
Dala	1%	19%	38%	42%
Seikkyi Khanaungto	0%	19%	37%	44%
Kyimyindaing	0%	45%	35%	30%




Figure 4.8-9: Respondent Composition by Age Groups in the Four Studied Townships

The following table shows that the majority of survey participants were family members, while 25 %, 35 %, 22 %, and 23 % of respondents were head of households in Twante, Dala, SeikkyiKhanaungto, and Kyimyindaing Township respectively.

Table 4.8-10: Respondent Percentage

Township	Head of household (%)	Family member (%)	Total
Twente	25	75	100
Dala	35	65	100
SeikkyiKhanaungto	22	78	100
Kyimyindaing	23	77	100

Source: ESIA Team's Household Survey, 2018

[Duration of Residence among Survey Respondents]

The following table indicates the duration of living in current location. 195 out of total 353 respondents (55%) reported to have lived in their current location more than 25 years while 27 respondents (7.5%) reported to live less than five years. In general, in all the four townships, the residents are long stayers in their respective locations.

Table 4.8-11: Duration of Living in the Location (Total respondents: 353 HHs)

Township	<5years	5-15 years	16-25 years	>25 years
Twente	7	11	14	61
Dala	7	16	19	35
SeikkyiKhanaungto	12	25	35	88
Kyimyindaing	1	7	4	11
Total	27 (7.6%)	59 (16.7%)	72 (20.4%)	195 (55.2%)

[Property Ownership Types of the Survey Respondents]

The survey asked respondents about the ownership status of their current residence. The survey results are shown in Table 4.8-12. Most of the households (323 out of 353 respondents, 91.5%) reported that they own their home, while 20 respondents (5.6%) rent and seven respondents neither own their home nor pay rent. Three respondents replied that their homes were provided by their employers. While verification by the documentary evidence is required, it is surmised that the majority of the respondents are owners of their residential land or the housing structure or both.

Table 4.8-12: Ownership Status of Respondents' Current Residence (Total respondents: 353 HHs)

Township	Owner	Renter	Provided by employer	Other	I don't know
Twente	93	0	0	0	0
Dala	68	3	1	5	0
SeikkyiKhanaungto	142	14	2	2	0
Kyimyindaing	20	3	0	0	0
Total	323 (91.5%)	20 (5.7%)	3 (0.8%)	7 (2%)	0

Source: Household Survey, 2018

[Debt Status of the Survey Respondents]

The survey also asked respondents about their debt status. It was found that about half of the respondents have a type of debt.

Table 4.8-13: Household Debt (%)

Township	Yes	No
Twente	44%	54%
Dala	51%	49%
SeikkyiKhanaungto	53%	47%
Kyimyindaing	52%	48%

Source: Household Survey, 2018

4.8.3 Poverty

In Myanmar, poverty has steadily declined since early 2000s. Myanmar is in a transition from a centrally planned economy to a market-oriented economy. This has been supported by a reform program launched by the government in 2011. Household expenditure, on average, has been increased by 15% over the past decade, enhancing the living standards of Myanmar people. This can be shown in various well-being indicators, such as sales of consumer goods. For example, more than 42% of households had motorcycles in 2015, about 4 times more than that in 2009.² Still, 37% of the population lives near or below the national poverty line in 2015, which means that a large portion of people continue to remain vulnerable to poverty. The country's gross domestic product (GDP) was estimated to be \$56.8 billion in 2014, approximately \$1,505 of the GDP per capital – one of the lowest in Southeast Asia (World Bank 2015).

² The World Bank (2017) Myanmar Poverty Assessment

The situation is generally worse in rural regions, with 38.8% of its population in 2015 are categorized as poor, whereas only 14.5% of those in towns and cities was regarded as poor in the same year. Sectoral growth figures can explain reasons why rural poverty had been alleviated at a slower pace. Manufacturing and service sector were more rapidly grown than agricultural industry during the same period.³ The same pattern applies in the four affected townships: Dala and Twente Township, with a level of rural population still residing, marks the less socio-economic development level compared with 100% urbanized Seikkyi Kanaungto and Kyimintine Township. With the advancement of the SUDP and Yangon City Development Plan, the former Township are expected to mark visible socio-economic development with higher income levels with rapid urbanization in the future.

Households in poverty tend to make their livings through agriculture, in most cases either as laborers or as small farmers. Even when they are farming, most of them do not have their own lands. Besides, poor people are likely to be distant from the formal economy, including public credit services or market transactions. They are also less likely to be highly educated, both household heads and working age members. All of these factors are closely correlated with low incomes, not allowing them to escape from poverty.

4.8.4 Gender

4.8.4.1 Legal Framework on Gender Issues⁴

Gender and women-related laws and national policies of Myanmar are as follows:

Table 4.8-14: Major Laws and National Policies on Gender Issues

No,	Laws and policies	Year	Key contents on gender issues
1	Constitution	1947, 2008 (amended)	State gender equality and women's rights
2	Suppression of Prostitution Act	1949 1998 (amended)	Stipulate prostitution as illegal
3	Basic Rights and Duties of Workers	1964	6-week maternal leave for female workers
4	Myanmar Maternal and Child Protection Act	1990	Enhancement of maternal and child health by establishing networks among villages (wards) and townships
5	Nursing and Delivery Act	1990	Protect mothers and children through prevention of illegal childbirth
6	National Strategic Plan for the Advancement of Women 2013-2022, NSPAW	2013	Suggest 12 priorities for women's advancement and plans for each agenda, including ways of basic research and study, establishment of budgets and policies, and public awareness.

³The World Bank (2017) Myanmar Poverty Assessment

⁴ADB, UNDP, UNFPA, and UN Women (2016) Gender equality and women's rights in Myanmar: A situation analysis and KOICA (2014) Gender situation of Myanmar

4.8.4.2 Current Gender Situation and Inequality

[Economic and social situations of Myanmar women⁵]

In relation to the proposed project, the following are issues of our attention:

• **Health and sanitation:** The Myanmar government has recently increased investments in public services, including water and sanitation. This is of importance because management of such public services is essential for women's health enhancement. Its first advantage is to reduce an incidence of water-borne diseases of women who could be more likely to be vulnerable, given their high dependence in daily lives on water, both underground and potable, and sanitation. During the construction along the canal and the Yangon river, preventing the water contamination is of pivotal importance which may directly affect the public health of the adjacent population, especially of women and children.

• **Small businesses near rivers or canals:** Although works and businesses of the fishery have traditionally been dominated by males, especially for large-scaled ones in offshore and deep-seas, women have carved a niche of the fishery industry by engaging in inland water fisheries, including aquaculture and small-scale fishery, in addition to the sale of fish they have caught. This linkage to the fishery industry has provided women, not just with job opportunities, but also practical ways of supporting their families by providing protein nutrition (subsistence fishery) as well. Given the improvement river bank facilities along the canal and the Yangon River, it is possible that especially the women population in small scale fishery and associated economic activities may benefit.

• **Participation in petty trading:** For most Myanmar women who want to find economic opportunities, petty trading is a good and easy option to be taken. For example, they can offer drink or catering service on the street and near construction sites (temporal). Female merchants from poor households tend to utilize informal mobile peddlers, because they find it hard to obtain permanent places or to have large-scale businesses. The proposed project may generate petty business opportunities during the construction period (street peddlers, catering services etc.), boosting temporarily local economy, especially run by women.

• **Public transport improvement benefit women more:** Most women in Myanmar do neither have their own cars, nor driving licenses, which means that only few of them are able to drive. Instead, they use public transport to conduct their diverse household and productive responsibilities. Therefore, women's mobility would be largely relying on the general conditions of public transportation, such as safety, frequency, and affordability. They could have lots of advantages if the quality of small public transport is improved and diversified, including inland water transports and minibuses. While further study is necessary it is possible that the improvement of inland water transport may benefit women, who commute for business/economic activities across the canal/river to the CBD.

Some other aspects of gender equality in Myanmar are summarised as below:

[Gender inequality inside the Myanmar society⁶] Although women's rights are guaranteed by the Constitution and Dhammathat (Buddhism Customary law), Myanmar has a low level of political representativeness (the ratio of high level governmental officers and Parliament members), largely

⁵ADB, UNDP, UNFPA, and UN Women (2016) Gender equality and women's rights in Myanmar: A situation analysis and KOICA (2014) Gender situation of Myanmar

⁶ADB, UNDP, UNFPA, and UN Women (2016) Gender equality and women's rights in Myanmar: A situation analysis and KOICA (2014) Gender situation of Myanmar

because of the male chauvinism and the preference for male offspring. Men and women are in most cases making decisions together on participation in activities in their community, property purchasing and religious activities. However, such decisions are usually determined by physical conditions, social structure and norms. This tendency also affects roles and division of labor. While men play a major role in farming and have more political interest, women roles are dominant in daily livelihood and children's education. Women in Myanmar has been in many cases marginalized from access to practical ownership of land, capital and other forms of productive assets. The cultural stereotype that women cannot be farmers has been reinforced for a long time with lack of land ownership and legally or institutionally certified rights. This has further marginalized them throughout the various economic and social aspects of the whole society. While carrying out projects or programs, therefore, legal and institutional supports are necessary to guarantee the rights for women to be provided benefits during land acquisition and compensation. Thus, it is recommended that the project proponent set up measures to ensure that the women's access to the compensation and welfare benefits are not captured by their male family members based on the cultural customs. As for the sexual harassments, in spite of the report procedure, silence and unpunishment tendency of the Burmese society has brought about a low reporting ratio, which has rendered most cases resolved through private agreement. Human Development Index (HDI): 148th / Gender Inequality Index (GII): 106th (Year of 2017)⁷

[Future opportunities⁸] With all these limitations, however, women have high potential mainly on the basis of the growing ratio of higher education completion.

Table 4.8-15: Gender Breakdown of Higher Education Students, by Level (2012)

Course	Male	Female	% of female students	Total
Undergraduates	201,762	296,725	59	498,487
MA/MSc qualifying	156	915	87	1,041
Postgraduate diploma	473	1,309	73	1,782
Master's degree	1,315	5,473	80	6,788
Masters of research	69	407	85	476
PhD	429	1,858	81	2,287
Total	204,204	306,687	60	510,891

In particular, more women have been entering into the engineering sector, such as construction for infrastructure, which has been dominated by male workers. Among civil engineering students in the Yangon Technological University, about 90% of them was women in 2013. Moreover, female students in architecture department in the same school were 4 times more than men. It is recommended that the project proponent ensures to secure a certain quota in hiring the engineers from local population for construction. Furthermore, as mentioned above, the Myanmar government has increased investment in public services and infrastructure, especially electricity supply in rural regions, water and sanitation, roads and transports, and time-saving appliances for household chores. As a


⁷UNDP (2018) Human Development Indices and Indicators, 2018 Statistical Update

⁸ADB, UNDP, UNFPA, and UN Women (2016) Gender equality and women's rights in Myanmar: A situation analysis and KOICA (2014) Gender situation of Myanmar

result of reducing the burden of domestic works, women can have more time and energy to be educated and to be connected to markets, which increase their income as well as social status in the long term.

4.8.5. Ethnicity and Religion

The country is ethnically diverse and there are at least 108 ethnolinguistic groups in Myanmar. The Bamar accounts for around 68% of the population, following by the Shan (10%), Kayin (7%), and Rakhine (4%).



Source: Yangon Region, Southern District Report, 2017

Figure 4.8-10: Proportion of the Population by Religion in Myanmar and Yangon Region

Myanmar is a predominantly Buddhist country as shown in Figure 4.8-10 and Table 4.8-14. As for the distribution spread of religion, Buddhism comprises of 87.9%, Christianity 6.2%, Islam 4.3%, Hinduism 0.5%, Animist 0.8%, and others (include no religion) 0.3% at national level.

In Yangon Region, the most people believe in Buddhism with a small percent of Christian, Islam and Hinduism as shown in Figure 4.8-10. In Yangon Region, it is 91.0% Buddhist, 3.2% Christian, 4.7% Islam, 1.0% Hindu, 0.1% other religion, and less than 0.1% each for Animist and those with no religion respectively.

Table 4.8-16: Proportion of the Population by Religion in Myanmar and Yangon Region

Region	Buddhism	Christianity	Islam	Hinduism	Animist	Other and No Religion	Total
Union of Myanmar	45,185,449	3,172,479	2,237,495	252,763	408,045	230,022	51,486,253
%	87.9	6.2	4.3	0.5	0.8	0.3	100
Yangon	6,697,673	232,249	345,612	75,474	512	9183	7,360,703
%	91.0	3.2	4.7	1.0	*	0.1	100

Source: Myanmar Statistical Yearbook, 2017

Note: * Less than 0.1%

As can be seen from the following Table 4.8-17, the majority of the people who live in the four affected Townships are Bamar, followed by Kayin, Mon, and Rakhine people.

Table 4.8-17: Proportion of Population by Ethnicity in the Four Affected Townships

Race	Population							
	Twente	%	Dala	%	SeikkyiKhan aungto	%	Kyimyindaing	%
Kachin	-	-	3	*	-	-	164	0.16
Kayar	-	-	-	*	-	-	7	-
Kayin	52216	22.9	1826	1.2	113	0.3	1528	1.5
Chin	8	*	32	*	3	*	251	0.2
Mon	22	*	105	0.1	212	0.6	357	0.4
Bamar	172977	75.9	148170	95.9	32745	96.5	98176	96.9
Rakhine	131	0.1	421	0.3	57	0.2	418	0.4
Shan	297	0.1	6	*	-	-	200	0.2
China	18	*	-	-	18	0.1	71	0.1
Indian	31	*	66	*	20	0.1	89	0.1
Pakistan	-	-	2	*	4	*	-	-
Bangladeshi	-	-	-		3	*	-	-
Other	2253	1	3932	2.5	769	2.3	186	0.2
Total	227953		154563		33944		101287	

(Source: General Administrative Department, 2017Note: * Less than 0.1%)

The different kinds of religion present in Twente, Dala, SeikkyiKhanaungto and Kyinmyindaing townships are shown in Table 4.8-18. More than 75% of the people living in these Study Townships are Buddhists. There is more Christianity living in Twente Township than in the other Townships.

Table 4.8-18: Percentage of the Population by Religion in the Four Affected Townships

Township		Buddhism	Christianity	Islam	Hinduism	Total
Twente	Population	181769	43882	1635	667	227953
	%	79.7	19.3	0.7	0.3	100
Dala	Population	138767	2782	6283	6731	154563
	%	89.8	1.8	4.1	4.3	100
SeikkyiKhanaungto	Population	32213	85	460	1186	33944
	%	94.9	0.2	1.4	3.5	100
Kyimyindaing	Population	98905	1862	285	235	101287
	%	97.6	1.8	0.3	0.2	100

Source: General Administrative Department, 2017


Household Survey Results

In terms of ethnicity, majority of the respondents are Bamar while 13 respondents are Kayin (Table 4.8-19 and Figure 4.8-11).

Table 4.8-19: Respondents by Ethnicity in Study/Focus Areas

Township	Bamar	Mon	Shan	Kayin	Others
Twente	369	0	0	9	0
Dala	341	3	0	0	16
SeikkyiKhanaungto	714	1	0	4	0
Kyimyindaing	97	0	0	0	3
Total	1521	4	0	13	19

Source: Household Survey, 2018



Source: Household Survey, 2018

Figure 4.8-11: Respondents by Ethnicity in Study/Focus Areas

4.8.6 Education

Type of Schools

All basic education schools are under the supervision of the Ministry of Education. Table 4.8-20 indicates that in 2016-2017 academic years, Yangon Region has 2,217 schools, covering from primary schools to high schools including both government and private schools. In total there are 537,083 primary school students and 19,211 teachers. Different type of basic education schools in the four affected townships are shown in Table 4.8-21.

Table 4.8-20: Education Facilities in Myanmar and Yangon Region (2016-2017)

Regions	Universities	High School	Middle School	Primary School	Monasteries
Union of Myanmar	171	1972	2635	38197	1538
Yangon	430	235	292	2217	-
Private School in Yangon	438	123	9	28	-

(Source: Myanmar Statistical Yearbook, 2017)

Table 4.8-21 shows the education facilities in the four affected townships. Twente has eight state high schools, 22 state middle schools, 183 state primary schools, two preschools, and one monastery education center. There are no universities and colleges in Twente.

Dala has four state high schools, seven state middle schools, 53 state primary schools, three preschool and three monastery education centers.

SeikkyiKhanaungto has two state high schools, one state middle school, 14 state primary schools, and one preschool.

Kyimyindaing has seven state high schools, five state middle schools, 11 state primary schools, 13 preschools, and two monastery education centers.

There are no universities and colleges in those four townships.


The total population in study townships is 517,747 (the proportion of aged 15 and over is 374,622) and the number of educational facilities is 330, which means that the number of educational facilities is insufficient compared to the total population. In particular, with the exception of primary schools in Twente, the total number of educational facilities is 147, which means that more educational facilities are expected to be needed as a proportion of the population in study townships. In the case of SeikkyiKhanaungto and Kyimyindain, the proportion of children aged 14 and below who need basic education is 3,286 and 25,076 with the number of pre-schools, primary school and middle school in each townships 16 and 19.

Table 4.8-21: Basic Education Schools in Study Townships (2016-2017)

Township	No. of Universities/ Collage	No. of High School	No. of Middle School	No. of Primary School	No. of Pre School	Monastery Education School
Twente	0	8	22	183	2	1
Dala	0	4	7	53	3	3
SeikkyiKhanaungt	0	2	1	14	1	0
Kyimyindaing	0	7	5	11	13	2

(Source: General Administrative Department, 2017)

School Attendance



Source: Yangon Region, Southern District Report, 2017

Figure 4.8-12: School Attendances by Age in Union, Yangon Region and Study Townships

As can be seen in Figure 4.8-12, school attendance drops after age 11 in Twente (Twantay) Township. Compared to the Yangon Region, the school attendance in Twente Township is lower than that of Yangon Region at starting age 13 and markedly lower at 17 onwards.

School attendance in Dala Township drops after age 12. Compared to the Union, the school attendance in Dala Township is not much difference between the Union.

School attendance in SeikkyiKhanaungto Township drops starting from age 11. Compared to the Union, the school attendance in SeikkyiKhanaungto Township is lower after age 17.

School attendance in Kyimyindaing Township drops starting from age 12. Compared to the Union, the school attendance in Kyimyindaing Township is higher starting from age 14.

Literacy Rate

According to the Census Union Report, in Myanmar, out of 33.9 million people aged 15 years and over, 30.37 million were reported to be literate, representing a literacy rate of 89.5 percent. There are over 3.55 million people who are illiterate.

Table 4.8-22 indicates that in Myanmar, 88.9 % of people over 15 years of age are literate, but with disparities by age, gender, and geographic locations. According to Myanmar Living Conditions survey 2017; adult literacy is high among the working age population, with almost 9 out of 10 adults being literate at the national level.

	Literacy Rate		
Region and Township	Total	Male	Female
Union of Myanmar	89.2	92.8	85.6
Yangon	96.6	98.1	95.2

[illegible]

Figure 5.8-13: Literacy Rate in Yangon Region (aged 15 and over)

Table 4.8-23 provides that the literacy rate of adult in Twente, Dala, and Kyimyindaing Township are 100% while adult literacy rate in Seikkyi Khanaungto Township is 99.89%. All Study Townships have higher literacy rate than that of Yangon Region and national level.

Table 4.8-23: Adult Literacy Rate in the Four Study Townships

Township	Total Population	Population (15 and above)	Literates (15 and above)	Literacy Rate
Twente	227953	153402	153402	100
Dala	154563	114351	114351	100
SeikkyiKhanau ngto	33944	30658	30625	99.89
Kyimyindaing	101287	76211	76211	100

Source: General Administrative Department, 2017

Household Survey Results

The following table indicates that the literacy rate of respondents in Dala Township is 90% while the literacy rate of respondents in SeikkyiKhanaungto Township is 68%. The respondents in Twente, SeikkyiKhanaungto, and Kyimyindaing Township have lower literacy rate than that of national average (89.5 %).

Table 4.8-24: Respondents by Literacy Rate in Study/Focus Areas

Township	Literate (%)	Male (%)	Female (%)
Myanmar	89.5	-	-
Twente	88	45	43
Dala	90	48	42
SeikkyiKhanaungto	68	36	32
Kyimyindaing	81	41	40

(Source: Household Survey, 2018)

According to the household survey, the literacy rate of SeikkyiKhanaungto is 68 percent and that of Kyimyindain is 81 percent, which is lower than 88 percent in Twente and 90 percent in Dala. The average literacy rate of Myanmar is 89.5%. While further study is required to clarify the reason for visibly low rate of the reported literacy rates among the respondents in SeikkiKanaungto and Kyimyindain of our household survey, it is possible that adult family members may have been absent during the household survey due to their work outside - being 100% urban population there are no farmers whose presence at residence areas are more likely during the work days, that junior population may have responded.

4.8.7 Economic Profile

Economic activities

The Gross Domestic Product (GDP) in Myanmar was worth 69.32 billion US dollars in 2017. The GDP value of Myanmar represents 0.11 percent of the world economy. GDP in Myanmar averaged 33.05 USD Billion from 1998 until 2017, reaching an all-time high of 69.32 USD Billion in 2017 and a record low of 6.46 USD Billion in 1998 (Source: TRADINGECONOMIC.COM, WORLD BANK).

Income and Livelihood

Wages in Myanmar remain low; more than half of the population works in the agricultural, forestry and fishery sectors with average earnings 18% lower than the Union average salary. Males are

generally paid more than females; male daily wage earners are paid on average 47% more than females. The men are preferred as labours than women, despite the higher wage rate.

The following Table 4.8-26 indicates that the highest average individual annual income is estimated as 2,632,255.9 Kyats for Kyimyindaing Township and Dala Township has lowest average individual annual income.

Table 4.8-26: The Average Individual Annual Income Status of Study Townships (Unit: Kyat)

Township	2014-15	2015-16	2016-17
Twente	1,651,514	1,688,712	1,725,910
Dala	443,442	558,776	674,110
SeikkyiKanaungto	786,032	857,994	1,091,608
Kyinmyindaing	1,882,711.6	2,014,485.7	2,632,255.9

(Source: General Administrative Department, 2017)

Household Survey Results

As can be seen in the following table, most of the households (196 out of 353 households) reported an income of between 1,100,000-3,600,000 Kyats. Four households reported an income of less than 1,000,000 Kyats and 56 households reported an income of more than 6,000,000 Kyats.

Table 4.8-27: Annual Income of Survey Results (Total respondents: 353 HHs)

Income Rate				Unit: Kyat
Township	<1000000	1100000-3600000	3700000-6000000	>6000000
Twente	0	54	26	13
Dala	0	37	23	17
SeikkyiKhanaungto	3	90	43	24
Kyimyindaing	1	15	5	2
Total	4 (1.1%)	196 (55.5%)	97 (27.5%)	56 (15.9%)

Source: Household Survey, 2018

According to the household surveys, Table 5.8-28 indicates that 28 out of 353 households reported an annual expenditure of more than 5,000,000 Kyats while 201 households reported an annual expenditure between 1,000,000-3,000,000 Kyats.

Table 4.8-28: Annual Expenditure of Survey Results (Total Respondents: 353 HHs)

				Unit: Kyat
Township	<100000	100000-300000	310000-500000	>500000
Twente	2	61	27	3
Dala	0	43	20	14
SeikkyiKhanaungto	3	86	62	9
Kyimyindaing	1	11	9	2
Total	6 (1.7%)	201 (57%)	118 (33.4%)	28 (7.9%)

Source: Household Survey, 2018

In term of income sources, agriculture, including livestock and fishery is most important sector for Myanmar's economy. As can be seen from the following Table 4.8-29, the main sources of income in Study Townships are agriculture, fishery and official employment of the government.

Table 4.8-29: Existing Status of Local Livelihoods in Townships

Township	Working-age Population (aged 15+)	Government Staff (%)	Service Staff (%)	Agriculture (%)	Livestock (%)	Sales (%)	Trader (%)	Fishery (%)	Odd Job (%)	Other (%)
Twente	144013	2.1	4.5	50.1	0.1	3.7	1.5	28.0	9.0	1
Dala	177497	2.9	13.6	2.3	0.1	13.6	0.2	-	11.6	55.8
SeikkyiKanaungto	14613	3.4	6.0	0.4	0.3	10.5	0.4	59.5	-	19.5
Kyinmyindaing	76661	17.6	8.6	0.4	0.2	25.2	6.5	-	13.0	28.6

Source: General Administrative Department, 2017

4.8.8 Industry

Agriculture

Traditionally, Myanmar has been reliant on the agriculture sector (and to a lesser extent forestry and fishing). In fact, at one point, Myanmar was the world's largest exporter of rice.

Even with recent effort to diversify, the agricultural sector still accounts for approximately 37% of GDP (as of 2014), while the services sector accounts for 41.6% and the industrial sector accounts for 21.3% (CIA 2015).

It is estimated that, as of 2014, approximately 21.1 million people worked in the agricultural sector. This means that approximately 65.8% of the labour force is employed in the agricultural sector in Myanmar (FAO 2015). This includes a large number of people considered to be “landless” – who work as seasonal farm labourers and migrate to urban areas during non-planting and/ or harvesting times to find temporary employment. It also includes women – as women play a substantial role in crop production in farming households in Myanmar (in part because women are typically seen as responsible for meeting the food security needs of their families).

Approximately half of all agricultural land in Myanmar is devoted to cereal crops, such as rice. Other agricultural products include beans, sesame, groundnuts, sugarcane, and hardwood.

Livestock

In addition to crops, livestock rearing is another source of income in Myanmar. A variety of animals are raised, including duck, cattle, water buffalo, goats, sheep, chickens, and pigs. In 2013/2014, duck was the most commonly raised livestock, with 18.3 million, followed by cattle and chicken.

Forestry

Approximately 48% of Myanmar is covered by forest, which equates to an area of approximately 31773000ha. In 2011, the forestry sector contributed approximately 0.5% to GDP, and employed approximately 36000 people.

The dragging of logs is done mainly by elephants and, to a lesser extent, water buffalo. This process is referred to as skidding. The use of animals in log extraction is considered to have a lower impact on the environment than other methods.

In addition to the timber industry, many people in rural areas of Myanmar are dependent on forest products, especially for firewood and fodder for livestock. Often poorer farmers and agriculture labourers supplement their incomes by cutting wood for fuel.

Fisheries

The fishing industry contributes approximately 8% to GDP. The industry is separated into three components – inland fisheries, marine fisheries and aquaculture. The marine sector makes up approximately 52% of the industry, followed by inland fisheries (28%) and aquaculture (20%).

Island fisheries Myanmar are mostly associated with open water (e.g. riverine and estuarine systems) and flood plains. Inland water bodies, such as natural lakes, reservoirs, river systems and ponds, cover about 8.1 million hectares, of which 1.3 million hectares are permanent, while the remainder are seasonally inundated floodplains.

In 2008-2009, the total fish production in Myanmar was around 3542190 tons, of which 899430 tons was from inland fisheries. Common fishing techniques include drift net, gillnet, traps and pots, pole-and-line, stationary traps, and bamboo stake traps in the near shore of rivers.

The aquaculture industry is also prevalent in Myanmar and includes fin fish, crustaceans, and seaweed. At present, the aquaculture industry covers approximately 182315ha. This is broken downs as follows:

- Freshwater Fish : 89138ha ;
- Freshwater prawn: 4119ha;
- Marine shrimp (in ponds) : 88308 ha ; and
- Soft shell crab: 750 ha.

Fish constitutes approximately 75% of the animal protein consumed in Myanmar. It is anticipated that approximately 10-15% of monthly household expenditure for food is on fish products.

Economic Infrastructure by Township

Twente Township is located in Yangon region and is an economically developing township. Township local people tend to operate mainly for agriculture. In addition, has the breeding business. Twente Township can transport to other township by road, by water and waterway and good transportation. The main township's main products are rice and exported to other parts. The economic status, occupational status, income status and other social infrastructures are shown in Table 4.8-30.

Table 4.8-30: The Economic Facilities of Twente Township (as of April 2017)

No.	Name of Township	No. of factories	No. of Workshops	No. of Small scale/ domestic enterprises	Total
1	Twente	68	2 (car service centres)	55	125

Source: General Administrative Department, Twente Township (2017)

Dala Township located in Yangon region and is also the commercial city. The local people are mainly doing agriculture and services. The economic status, occupational status, income status and other social infrastructures are shown in Table 4.8-31.

Table4.8-31: The Economic Facilities of DalaTownship (as of March 2017)

No.	Name of Township	No. of factories	No. of Workshops	No. of Small scale/ domestic enterprises	Total
1	Dala	2	14 (Wet shipyards)	27	43

Source: General Administrative Department, Dala Township (2017)

SeikkyiKhanaungto is located in Yangon Township and that economic growth is slowing. Compared to other 3 townships in the project area, there were a smaller number of production industries in SeikkyiKhanaungto. Township local people mainly work agriculture and causal. Township only use transportation for water, if create for employment opportunities and services the residents could be living the high living standard and will be developed faster. The economic status, occupational status, income status and other social infrastructures are shown in Table 4.8-32.

Table 4.8-32: The Economic Facilities of SeikkyiKhanaungto Township (as of March 2017)

No.	Name of Township	No. of factories	No. of Workshops	No. of Small scale/ domestic enterprises	Total
1	SeikkyiKhanaungto	1	41 (Slipways)	63	105

Source: General Administrative Department, SeikkyiKhanaungto Township (2017)

Kyimyindaing is located in Yangon Township and is a commercial center. Township main economic is servicing. Township is also located on the intersection of the road and water access and good transportation. The economic status, occupational status, income status and other social infrastructures are shown in Table 4.8-33.

Table 4.8-33: The Economic Facilities of Kyimyindaing Township (as of April 2017)

No.	Name of Township	No. of factories	No. of Workshops	No. of Small scale/ domestic enterprises	Total
1	Kyimyindaing	2	6	16	24

Source: General Administrative Department, Kyimyindaing Township (2017)

4.8.9 Labor Force

In 2017, working age population (aged 15+) in Myanmar was 36.4 million and among them females constitute 54.3 percent while males, 45.7 percent. In terms of rural and urban areas, rural area covers 70.9 percent of working age population while urban area, 29.1 percent. It is noted that the younger the age group is, the higher percentage of the group occupy themselves in the economic activities in urban areas. (On the contrary the older the age group, the more likely that they engage in rural/agricultural activities.)

The labor force participation in urban and rural is somewhat close to working age population structure in urban and rural areas. In contrast, participation of females is lower although females are numerically higher in working age population.

For distribution of working population by attainment of education level for labor force, Predominant group was primary level graduates. Although there is a level of similarity between the distribution of males and females, the proportion of females is higher at the tertiary level. As regards to attaining a higher level of education, the proportion was skewed to the urban population.

As of 2017, the official unemployment rate was 4.0 % for the age of 15 to 64 nationwide. Although this rate is low, it is higher for younger ages (15-29) at the 7.7 %. The unemployment rate in Myanmar is low especially because the country does not have social security system and people had to take up job irrespective of their choice for their survival. Labor underutilization refers to mismatches between labor supply and demand leading to an unmet need of employment among the population (Myanmar Census Report, 2016).

**Table 4.8-34: Working Age Population/Labor Force and Labor Underutilization
by Age, Sex and Urban/Rural (2017)**

		Male	Female	Urban	Rural	Total
Working age population by age (million)		16,618	19,776	10,591	25,803	36,394
	15-24	4,115	4,513	2,408	6,220	8,628
	25-24	3,593	4,196	2,174	5,615	7,789
	35-44	3,230	3,733	2,030	4,933	6,963
	45-54	2,630	3,172	1,816	3,986	5,802
	55-64	1,800	2,284	1,185	2,899	4,084
	65+	1,250	1,878	978	2,150	3,128
Labor force by age (million)		12,955	9,434	6,241	16,148	22,389
	15-24	2,541	2,120	1,117	3,544	4,661
	25+	10,414	7,314	5,124	12,604	17,728
Labor force by education (%)	Less than primary	24.7	24.9	13.2	29.3	24.8
	Completed primary	59.6	55.2	53.7	59.4	57.8
	Completed secondary	9.3	7.8	14.3	6.6	8.7
	Tertiary	6.3	12.0	18.9	4.8	8.7
Labor force participation (%) by age		78.0	47.7	58.9	62.6	61.5
	15-24	61.7	47.0	46.4	57.0	54.0
	25+	83.3	47.9	62.6	64.4	63.9
Labor underutilization, aged 15+ (million)	Unemployment	197	280	170	307	477
	Unemployment rate (%)	1.5	3.0	2.7	1.9	2.1
Youth labor underutilization, Aged 15-24 (million)	Unemployment	99	132	84	147	231
	Unemployment rate (%)	3.9	6.2	7.5	4.1	5.0

Source: Myanmar Annual Labor Force Survey, 2017

In 2017, 48.8 percent of the employed persons were working in agriculture, forestry and fishing sector. It is followed by wholesale and retail trade (15.9%), manufacturing (10.8%), construction (5.5%), transportation and storage (4.7%), other service activities (4.5%) and education (3.0%). All other section accounts less than 3 percent. The occupations are skilled agriculture workers (34%), elementary occupations (25.1%), service and sales workers (16.9%) and craft and related trades workers (11.2%).

The informal employment is large and at the national level, informal employment is accounted 83 percent. Relatively, presence of formal employment is higher in urban areas than rural areas. For the gender perspective, the share of females in informal employment was much higher than that of that of males. At the national level, detailed breakdowns are shown in the table below:

Table 4.8-35: Employment by Age, Sex and Urban/Rural

		Male	Female	Urban	Rural	Total
Employment by economic sector (%)						
	Agriculture, forestry and fishery	51.6	44.9	9.3	63.9	48.8
	Wholesale and trade	10.9	23.0	31.2	10.1	15.9
	Manufacturing	8.7	13.7	17.4	8.3	10.8
	Construction	8.3	1.7	9.2	4.2	5.5
	Transportation and storage	7.7	0.4	9.3	2.9	4.7
	Education	1.3	5.4	5.1	2.2	3.0
	Accommodation and food service	1.4	2.3	3.4	1.2	1.8
	Mining and quarrying	1.7	0.5	0.8	1.4	1.2
	Other services	4.6	4.3	4.6	4.4	4.5
Employment by occupation (%)	Agricultural workers	36.6	30.4	7.3	44.2	34.0
	Elementary occupations	26.1	23.8	14.5	29.2	25.1
	Service and sales	11.6	24.3	33.1	10.6	16.9
	Craft and related trades workers	12.1	10.0	19.0	8.2	11.2
	Plant machine operators	8.1	1.5	9.8	3.6	5.3
	Managers	0.8	0.5	2.0	0.2	0.7
Employment by informal status (%)	Informal	77.4	90.7	78.7	84.6	83.0
	Formal	22.6	9.3	21.3	15.4	17.0
	Employment in the informal sector	58.9	62.1	55.7	62.0	60.2




Figure 4.8-14: Labour Force Participation Rate and Unemployment Rate in Twente Township

(Source: Myanmar Annual Labor Force Survey 2017)

Figure 4.8-14 shows the labour force participation rate and unemployment rate in Twente Township. Labour force participation rate for the population aged 15-64 in Twente Township is 68.5 per cent. The labour force participation rate of females is 49.8 percent and is much lower than that of their male counterparts which is 88.2 per cent. In Twente Township, labour force participation rate for the population aged 10-14 is 12.6 per cent.

The unemployment rate for those aged 15-64 in Twente Township is 3.5 per cent. There is not much difference between the unemployment rate for males (3.4%) and for females (3.6%). The unemployment rate for young females aged 15-24 is 7.7 percent.




Figure 4.8-15: Proportion of Employed Persons in Twente (by Occupation)

(Source: Myanmar Annual Labor Force Survey 2017)

Figure 4.8-15 shows the percentage of employed persons aged 15-64 by occupation by sex, national level, region level and Twente Township. In Twente Township, 35.8 per cent of the employed persons aged 15-64 are skilled agricultural, forestry and fishery workers and is the highest proportion, followed by 18.5 per cent in elementary occupations. Analysis by sex shows that 41.6 per cent of males and 26.2 per cent of females are skilled agricultural, forestry and fishery workers.

In Yangon Region, 10.1 per cent are skilled agricultural, forestry and fishery workers and 14.0 per cent are in elementary occupations.




Figure 4.8-16: Proportion of Employed Persons in Twente (by Industry)

(Source: Myanmar Annual Labor Force Survey 2017)

Figure 4.8-16 provides the percentage of employed persons' age 15-64 by industry in national, region level and Twente Township. The proportion of employed persons working in the industry of "Agriculture, forestry and fishing" is the highest with 46.5 per cent. The second highest industry is "Wholesale and retail trade; repair of motor vehicles and motorcycles" at 11.2 per cent. There are 54.1 per cent of males and 33.7 per cent of females working in "Agriculture, forestry and fishing" industry.

Dala Township




Figure 4.8-17: Labour Force Participation Rate and Unemployment Rate in Dala Township

(Source: Myanmar Annual Labor Force Survey 2017)

Figure 4.8-17 shows the labour force participation rate and unemployment rate in Dala Township. Labour force participation rate for the population aged 15-64 is 58.6 per cent. The labour force participation rate of females is 36.1 per cent and is obviously lower than that of their male counterparts which is 82.4 per cent. In Dala Township, labour force participation rate for the population aged 10-14 is 8.1 per cent.

The unemployment rate for those aged 15-64 in Dala Township is 7.8 per cent. There is difference between the unemployment rate for males (6.7%) and for females (10.0%). The unemployment rate for young females aged 15-24 is 19.7 per cent.




Figure 4.8-18: Proportion of Employed Persons in Dala (by Occupation)

Figure 4.8-18 provide the understanding of occupation by sex in Union, Yangon Region and Dala Township. 30.1 per cent of the employed persons aged 15-64 are services and sales workers and is the highest proportion, followed by 19.1 per cent in craft and related trades workers. Analysis by sex shows that 20.7 per cent of males and 50.7 per cent of females are services and sales workers. In Yangon Region, 23.7 per cent are services and sales workers and 22.9 per cent are craft and related trades workers.




Figure 4.8-19: Proportion of Employed Persons in Dala (by Industry)

Figure 4.8-19 provides the percentage of employed persons' age 15-64 by industry in Union, Yangon Region level and Dala Township. The proportion of employed persons working in the industry of "Wholesale and retail trade; repair of motor vehicles and motorcycles" is the highest with 22.0 per cent. The second highest industry is "Agriculture, forestry and fishing" at 16.3 per cent. There are 15.7 per cent of males and 35.8 per cent of females working in "Wholesale and retail trade; repair of motor vehicles and motorcycles" industry.

In Yangon Region, there are 15.8 per cent of employed population working in "Wholesale and retail trade; repair of motor vehicles and motorcycles" industry and 14.3 per cent in "Agriculture, forestry and fishing" industry.

SeikkyiKhanaungto Township




Figure 4.8-20: Labour Force Participation Rate and Unemployment Rate in SeikkyiKhanaungto Township

(Source: Myanmar Annual Labor Force Survey 2017)

Labour force participation rate for the population aged 15-64 in SeikkyiKhanaungto Township is 62.3 per cent. The labour force participation rate of females is 37.1 per cent and is much lower than that of their male counterparts which is 87.4 per cent. In SeikkyiKhanaungto Township, labour force participation rate for the population aged 10-14 is 7.1 per cent.

The unemployment rate for those aged 15-64 in SeikkyiKhanaungto Township is 4.6 per cent. There is not much difference between the unemployment rate for males (4.8%) and for females (4.2%). The unemployment rate for young females aged 15-24 is 9.8 per cent.




Figure 4.8-21: Proportion of Employed Persons in SeikkyiKhanaungto (by Occupation)

(Source: Myanmar Annual Labor Force Survey 2017)

In SeikkyiKhanaungto Township, 29.3 per cent of the employed persons aged 15-64 are in services and sales workers and is the highest proportion, followed by 27.6 per cent in craft and related trades

workers. Analysis by sex shows that 33.0 per cent of males and 54.8 per cent of females are craft and related trades workers and services and sales workers respectively.

In Yangon Region, 23.7 per cent are services and sales workers and 22.9 per cent are in craft and related trades workers.




Figure 4.8-22: Proportion of Employed Persons in SeikkyiKhanaungto (by Industry)

(Source: Myanmar Annual Labor Force Survey 2017)

In SeikkyiKhanaungto Township, the proportion of employed persons working in the industry of “Wholesale and retail trade; repair of motor vehicles and motorcycles” is the highest with 19.2 per cent. The second highest industry is “Construction” at 17.1 per cent. There are 12.3 per cent of males

and 34.6 per cent of females working in “Wholesale and retail trade; repair of motor vehicles and motorcycles” industry.

In Yangon Region, there are 15.8 per cent of employed population working in “Wholesale and retail trade; repair of motor vehicles and motorcycles” industry and 8.9 per cent in “Construction” industry.

Kyimyindaing Township




Figure 4.8-23: LabourForce Participation Rate and Unemployment Rate in Kyimyindaing Township

(Source: Myanmar Annual Labor Force Survey 2017)

Labour force participation rate for the population aged 15-64 in Kyimyindaing Township is 63.0 per cent. The labour force participation rate of females is 47.7 per cent and is much lower than that of their male counterparts which is 80.6 per cent. In Kyimyindaing Township, labour force participation rate for the population aged 10-14 is 8.3 per cent.

The unemployment rate for those aged 15-64 in Kyimyindaing Township is 4.6 per cent. There is difference between the unemployment rate for males (5.2%) and for females (3.7%). The unemployment rate for young females aged 15-24 is 9.0 per cent.




Figure 4.8-24: Proportion of Employed Persons in Kyimyindaing (by Occupation)

(Source: Myanmar Annual Labor Force Survey 2017)

In Kyimyindaing Township, 35.5 per cent of the employed persons aged 15-64 are services and sales workers and is the highest proportion, followed by 18.9 per cent in craft and related trades workers. Analysis by sex shows that 27.7 per cent of males and 46.4 per cent of females are services and sales workers.

In Yangon Region, 23.7 per cent are services and sales workers and 22.9 per cent are in craft and related trades workers.




Figure 4.8-25: Proportion of Employed Persons in Kyimyindaing (by Industry)

(Source: Myanmar Statistical Yearbook 2017)

In Kyimyindaing Township, the proportion of employed persons working in the industry of “Wholesale and retail trade; repair of motor vehicles and motorcycles” is the highest with 24.2 per cent. The second highest industry is “Accommodation and food service activities” at 19.6 per cent. There are 20.1 percent of males and 30.0 percent of females working in “Wholesale and retail trade; repair of motor vehicles and motorcycles” industry.

In Yangon Region, there are 15.8 percent of employed population working in “Wholesale and retail trade; repair of motor vehicles and motorcycles” industry and 9.3 percent in “Accommodation and food service activities” industry.

Household Survey Results

According to the household surveys, Table 4.8-35 indicates source of creditors of the respondents in study townships.

Table 4.8-35: Source of Creditors Surveyed

Township	Private Lender	Bank	Public Lender	Public Institutions	Others (Relative)
Twente	16	10	13	0	1
Dala	28	0	10	0	1
SeikkyiKhanaungto	60	1	5	1	0
Kyimyindaing	10	0	1	0	0

Source: Household Survey, 2018

4.8.10 Land Use Status

The Union of Myanmar has total land area of approximately 676,578 km² and its land use of arable land is 14.9%, permanent crops are 1.3%, and others are 83.8%. In Myanmar land is categorized as either 1) Agricultural land or 2) Non-agricultural land. Agricultural land refers to cultivable waste land at the disposal of the State and land which is occupied for the purposes of agriculture such as paddy (rice land), *ya* (dry land), *kaing* (alluvial land) and garden. Non-agricultural land refers to land that is not used for agricultural purposes. For example, forest land, grazing ground, road, town and village lands, etc. If agricultural land is not used for cultivation, all the buildings on agricultural land can be removed by authorities. Furthermore, whoever uses agricultural land for purposes other than the intended use, can be vacated and penalized under the 1963 Land Tenancy Law. In order to change the land title from 'agricultural land' into 'non-agricultural land' it is necessary to get the Land Use Permission, in accordance with the 1953 Land Nationalization Act, Article No 39. Act.

Types and Classes of Land in Myanmar

From an administrative point of view, land can be classified into the following eleven categories.

1. Freehold Land
2. Grant Land
3. Agricultural Land
4. Garden Land
5. Grazing Land
6. Cultivable Land, Fallow Land and Waste Land
7. Forest Land
8. Town Land
9. Village Land
10. Cantonments and
11. Monastery.

Zoning and Changing Land Use in Myanmar

Based on land use information, the District Land Use Committee may define the following zones and additional zones as necessary, in the proposed land use planning maps:

- a) Urban and rural development zone
- b) Agriculture zone
- c) Livestock breeding and fishery zone
- d) Protected area zone or national security zone
- e) Commercial zone, industrial zone or mining zone

- f) Grazing land zone and
- g) Forest zone.

Land Use Status in the Four Affected Townships


Land use status of the study townships are as shown Table 4.8-36. Large area is allocated for agricultural land in Twente, Dala and Kyinmyindaing Townships. The largest ratio of agricultural land in total area is 83.8 % in Dala Township, followed by 57.4 % in Kyimindaing Township, and 5.01 % in Twente Township. Apart from agricultural land, about 1~5 % of land is allocated for the residential area in Twente and Dala Township while 34.4 % and 42.6 % of land is allocated for the residential area in SekikyiKhanaungto and Kyimindaing Township respectively.

Table 4.8-36: Land use in the Study Townships

Townships	Total Area (Acres)	Agricultural Land (Acres)	Settlement Land (Acres)	Forest and Natural Area (Acres)	Industrial Land (Acres)	Unused Land (Acres)	Fallow (Acres)	Other (Acres)
Twente	236711	118523	3456	868	102	58462	1283	54017
	(%)	50.1	1.5	0.4	*	24.7	0.5	22.8
Dala	55368	46384	2696	-	340	5688	260	-
	(%)	83.8	4.9	-	0.6	10.3	0.5	-
SekikyiKhanaungto	1949.47	87	670.47	-	324	-	-	868
	(%)	4.5	34.4		16.6	-	-	44.5
Kyimindaing	3077	1767	1310	-	-	-	-	-
	(%)	57.4	42.6	-	-	-	-	-

Source: General Administrative Department, 2017

Note: * Less than 0.1%



<Reference map 1: Twente Township Township)



Myanmar Information Management Unit



Dala Township - Yangon Region



Map ID: MMU10404
Creation Date: 5 May 2016 A1
Projection/CRS: UTM/CRS84

Data Source:
BASE MAP: MMU Boundaries - WFP, modified by MMU 2006.
Landcover: LP SMLC - MCD12Q1 2011 A 3 SLP (Type1)
Place names: Ministry of Home Affairs (MOHA)
Reviewed by: MMU
Map produced by: MMU - E-mail: info@mmu.org
Website: www.mmui.org

Legend

Village
Type
Road
Railway

Street
Township Boundary
District Boundary
State Boundary
International Boundary
Non-Perennial Waterway/Interlocking
Perennial Waterway

Landcover
Crop and Irrigation
Forest
Wood Forest
Grassland
Shrubland

Stone tile
Urban Building
Bar/Land
Ricefield
Water

Village Name
Phone
Village Trust Name

Myanmar Information Management Unit (MIMU) is a common resource of the Myanmar Country Team (CT) providing information management services, including GIS mapping and analysis, to the humanitarian and development actors, both inside and outside of Myanmar.
NOTE: Due to the limited space of labels for villages, some village names will not be displayed on this map.
Copyright © Myanmar Information Management Unit 2016. May be used freely with attribution. For more information see <http://www.mimui.org/permissions>. This notice cannot be modified or removed.

<Reference Map 2: Dala Township>

4.8.11 Public Health Condition

The life expectancy in Myanmar is 65 years of age for men and 69 years of age for women (Table 4.8-37). Between 2000 and 2012, the life expectancy increased by 3 years for both males and females; however, during this same time the average increase in life expectancy in Myanmar's neighboring countries was 5 years (WHO 2016).

Table 4.8-37: Key Health Indicators

Indicator	Myanmar	Thailand	Laos
Total population (2016)	53 million	68 million	6.7 million
Life expectancy at birth (2016)	65 males 69 females	72 males 79 females	64 males 67 females
Total expenditure on health per capita (Int \$, 2014)	103	600	98
Total expenditure on health as % of GDP (2014)	2.3	4.1	1.9
Total fertility rate (2014)	2.29	-	-
Infant mortality rate (deaths per 1,00 live births) (2014)	62	-	-
Under five rate (deaths per 1,000 live births)	72	-	-

(Source: Health in Myanmar 2012)

Morbidity

Morbidity is the state of being in poor health and encompasses both acute and chronic diseases. Many of the leading causes of morbidity in Myanmar are associated with communicable diseases and pregnancy/ childbirth (Table 4.8-38).

Table 4.8-38: Leading Causes of Morbidity in Myanmar (2012)

No.	Causes	Percent
1	Other injuries of specified, unspecified and multiple body regions	10.0
2	Other complications of pregnancy and delivery	6.9
3	Single spontaneous delivery	6.0
4	Diarrhea and gastroenteritis of presumed infectious origin	5.8
5	Other viral diseases	3.8
6	Other pregnancies with abortive outcome	2.6
7	Gastritis and duodenitis	2.4
8	Malaria	2.4
9	Cataract and other disorders of lens	2.4
10	Other acute upper respiratory infections	2.0
11	Pneumonia	1.8
12	Other conditions originating in the perinatal period	1.7
13	Toxic effects of substance chiefly non-medicinal as to source	1.6
14	Fractures of other limb bones	1.5
15	Disease of appendix	1.5
	All other causes	47.6
	Total	100.0

Although not reflected in Table 5.39 considerable focus has been given to tuberculosis (TB) over the past few years as it is considered a major public health problem in Myanmar. In 2013, the estimated TB prevalence and incidence was 473 and 373 per 100,000 people respectively (WHO 2015). Although rates of TB are lower in the Mandalay Region than many other parts of the country, TB is

still an issue of concern (Table 4.8-39). To address the rates of TB, the Myanmar Government has established the National Tuberculosis Program, which focuses largely on improving detection.

Table 4.8-39: Diseases under Myanmar National Surveillance (2012)

Regions/ States	Diarrhea		Malaria		TB: sputum +ve		TB: sputum -ve		TB: Extra pulmonary	
	(1)	(2)	(1)	(2)	(1)	(2)	(1)	(2)	(1)	(2)
Kachin	916.3	0.4	2374.2	3.8	44	1.0	80.0	1.9	58.6	0.2
Kayah	1388.0	6.7	1858.6	0.7	12.0	0.0	26.2	0.7	5.6	0.0
Kayin	907.5	0.0	970.0	1.4	74.1	0.1	155.7	0.1	8.4	0.0
Chin	1803.1	5.4	2613.6	1.9	23.2	0.4	58.3	0.6	78.5	0.0
Sagaing	846.9	0.9	1085.6	1.6	46.7	0.3	55.0	0.4	36.0	0.1
Tanintharyi	862.3	0.3	2166.9	1.2	56.5	0.2	182.9	1.2	88.0	0.5
Bago	549.0	0.2	484.5	0.6	48.6	0.5	98.9	0.9	13.0	0.1
Magway	714.9	0.4	322.1	0.1	40.2	0.4	46.9	0.4	35.5	0.1
Mandalay	547.5	0.1	279.5	0.1	54.0	0.4	44.9	0.3	42.6	0.1
Mon	755.3	0.2	362.2	0.6	66.0	0.8	173.2	1.8	18.7	0.1
Rakhine	1150.4	0.4	1752.8	0.6	43.9	0.7	47.1	0.5	16.8	0.1
Yangon	255.0	0.4	25.4	0.0	109.4	0.6	114.6	0.6	36.4	0.1
Shan (S)	672.4	1.1	845.3	1.5	39.2	0.6	47.2	0.4	21.9	0.2
Shan (N)	697.0	1.4	934.6	1.1	63.1	0.1	58.5	0.3	70.1	0.0
Shan (E)	1015.1	0.5	209.5	0.0	101.7	0.7	160.9	0.2	37.6	0.0
Ayeyarwady	523.8	0.3	361.3	0.6	49.1	0.4	61.4	0.6	28.5	0.1
Naypyitaw	476.4	0.3	250.3	0.1	59.6	0.0	38.6	0.2	36.9	0.1
Union	670.5	0.5	686.0	0.7	58.0	0.5	78.6	0.6	33.7	0.1

Sources: Ministry of Health 2014

Note: (1) Number of cases per 100,000 populations. (2) Number of deaths per 100,000 populations.

Malaria is considered to be another health issue. The cities of Yangon and Mandalay and areas above 1000 meters in elevation are considered to be malaria-free, making malaria largely an issue in rural areas of the country, most notably in Bago, Kachin, kayah, kayin, Shan, and Tanintharyi. The issue is compounded by the increasing presence of the multi-drug resistant form of malaria, which is now widespread along much of the Myanmar-Thailand border.

Other vector borne diseases common in Myanmar include dengue fever and Chikungunya virus, which are spread by two species of daytime feeding mosquitoes- *Aedes aegypti* and *Aedes albopictus*. Unlike the mainly rural-dwelling mosquitoes that spread malaria, the *Aedes* mosquitoes thrive in cities as well as rural areas.

Mortality

Mortality is the measure of deaths per population over time and is a key indicator of population health. The leading cause of mortality in Myanmar is human immunodeficiency virus (HIV)/ acquired immune deficiency syndrome (AIDS) (a communicable disease) (Table 4.8-40).

Myanmar has one of the highest rates of HIV / AIDS infection in Southeast Asia. In 2017, the number of adult and children living with HIV in Myanmar was estimated to be around 220, 000; while an

estimated 6700 people died of AIDS in 2017 (UN AIDS 2018). There is often a correlation between TB and HIV/ AIDS – as TB, worldwide, is the leading of death in people living with HIV) This may change in the future; as recent data shows that rates of HIV/ AIDS have begun to decline.

Table 4.8-40: Leading Causes of Morality in Myanmar (2012)

No	Causes	Percent
1	Human immunodeficiency virus (HIV)/ acquired immune deficiency syndrome (AIDS)	6.6
2	Septicaemia	6.1
3	Other injuries of specified, unspecified and multiple body regions	5.4
4	Slow foetal growth, foetal malnutrition and disorders related to short gestation and low birth weight	4.6
5	Other disease of the liver	4.0
6	Other disease of respiratory system	3.7
7	Intrauterine hypoxia and birth asphyxia	3.4
8	Heart failure	3.3
9	Respiratory tuberculosis	3.2
10	Intracranial hemorrhage	2.9
11	Other Heart disease	2.8
12	Intracranial injury	2.7
13	Malaria	2.6
14	Pneumonia	2.6
15	Stroke, not specified as a hemorrhage or infraction	2.5
	All other causes	43.6
	Total	100.0

(Source: Ministry of Health 2014)

Although communicable diseases top the list of causes of mortality, there are a number of non-communicable diseases that also contribute. The World Health Organization estimated that in 2014 non-communicable diseases accounted for 59% of all deaths in Myanmar.

The trends in mortality and fertility indicate that Myanmar is currently in demographic transition – while the current population is young, Myanmar is moving slowly towards an ageing population (WHO 2014). This reflects broader global trends and will present new challenges for the health system.

Behavioral Factor

Behavioral factor, such as tobacco and alcohol use, diet patterns and physical activity, are often seen as being key determinations of health.

In Myanmar, most of the population abstains from consuming alcohol. The World Health Organization estimates that approximately 92.1 percent of the population (over 15 years of age) abstains from drinking alcohol. The rate of abstinence is considerably higher in Myanmar when compared to other nearby countries. (Table 4.8-41).

Table 4.8-41: Alcohol Use

Indicator	Population	Male	Female
Abstainers over past 12 months (15+)	92.1	87.6	96.2
Lifetime abstainers (15+)	84.1	91.1	76.5

Former drinks (15+)	8.0	11.1	5.2
Alcohol use disorders	1.5	2.7	0.5
Alcohol dependence	0.7	1.3	0.2

Healthcare Facilities

According to the Ministry of Health, in 2012, Myanmar had 987 public hospitals with a total of 54,503 beds. As of 2012, there were 28,077 doctors. This includes 11,460 doctors in the public sector and 16,617 doctors based in cooperative/ private sector (seen in Table 4.8-42 and 4.8-43).

Table 4.8-42: Health Facilities in Myanmar (2012)

Health Facilities	1988-1989	2007-2008	2008-2009	2009-2010	2010-2011	2011-2012
Hospitals (Public Sector)	631	839	8464	871	924	987
Total No of Hospital beds	25309	36949	38249	39060	43789	54503
No. of primary and secondary Health Centers	64	86	86	86	86	87
No. of Maternal and Child Health Centers	348	348	348	348	348	348
No. of Rural Health Centers	1337	1473	1481	1504	1558	1556
No. of school Health Centers	80	80	80	80	80	80
No. of Traditional Medicine Hospitals	2	14	14	14	14	14
No. of Traditional Medicine Clinics	89	237	237	237	237	237

(Source: Ministry of Health 2014)

Table 4.8-43: Health Personnel in Myanmar (2012)

Health Manpower	1988-1989	2007-2008	2008-2009	2009-2010	2010-2011	2011-2012
Total No. of Doctors	12268	21799	23740	24536	26435	28077
Public	4377	7976	9583	9728	10927	11460
Cooperative and private	7891	13823	14808	14808	15508	16617
Dental Surgeon	857	1867	2092	2308	2562	2770
Public	328	793	777	703	813	848

Table 4.8-44: Health Workforce in Myanmar (2012)

Health Manpower	1988-1989	2007-2008	2008-2009	2009-2010	2010-2011	2011-2012
Cooperative and private	529	1074	1315	1605	1749	1922
Nurse	8349	22027	22885	24242	25644	26928
Dental Nurse	96	177	244	262	287	316
Health Assistants	1238	1788	1822	1845	1899	1536
Lady Health Visitors	1557	3197	3238	3278	3344	3371
Midwives	8121	18098	18543	19051	19556	20044
Health Supervisor	1161	1973	2013	2174	2621	2330

Traditional Medicine Practitioners						
- Public	290	945	950	890	890	885
- Private	2500	5163	5397	5737	5737	5867

Access to Medical Services

Table 4.8-45: Medical Facilities Present in Yangon (2012)

Region	Hospital	Clinic
Yangon	84	2194

Source: General Administrative Department, Yangon Region

Table 4.8-46: Medical Facilities Present in the Four Study Townships (2012)

Township	Hospital	Clinic
Dala	3	24
Twante	2	31
Kyimyindaing	2	66
SeikgyiKhanaungto	1	-
Total	8	121

Source: General Administrative Department, Yangon Region

(*GAD interview indicates that there is one government hospital).

As of 2012 in Yangon region, there are 84 hospitals and 2,194 clinics that offer professional medical services in total. In township level, Twente has 2 hospitals and 31 clinics, Dala has 3 hospitals and 24 clinics, Kyimyindaing has 2 hospitals and 66 clinics and there is one hospital in Khanaungto. The total number of hospitals in four study townships is 8 and the number of clinics is 121, indicating that township residents have significantly less access to medical services compared to the number of medical facilities in city proper (such as CBD) in Yangon region. In particular, there is a lack of hospitals and clinics in Khanaungto, therefore local residents have to cross the canal to go to hospitals and medical facilities in other region in order to receive medical services.

Public Health Condition at Twente Township

The main health risks in Myanmar include limited clean drinking water and poor sanitation services. The poor living standards assist the spread of vector borne diseases (e.g. diarrhoea, cholera, influenza, malaria, dengue fever, yellow fever and tuberculosis). The sub-project on solid waste management will assist in addressing these health risks within the selected wards of the two townships.

Both townships have health facilities. Dala Township has three hospitals. One 25-bed hospital is located in the urban area, while two others with 16-bed capacity are located in Pyawbwe village tract and Yakhine Chaung village tract. Hlaing Tharyar has a 25-bed government hospital and a private Pan Hlaing Hospital.

Table 4.8-47: Health Facilities at Twente Township (as of April 2017)

No.	Name of Hospital	Government/Private	Total no. of bedstead
1	Twente Hospital	Government	50
2	Kayinchaung Hospital	Government	16
3	Kantiya Hospital	Government	16
			82

Source: General Administrative Department, Twente Township

The most common diseases in the Twante Township are shown in Table 4.8-48.

Table 4.8-48: Most Common Diseases at Twante Township

Type of Diseases									
Malaria		Diarrhea		TB		Dysentery		Hepatic	
Suffer	Death	Suffer	Death	Suffer	Death	Suffer	Death	Suffer	Death
2	-	1437	-	588	-	777	-	-	-

Source: General Administrative Department, 2017

Health Condition at Dala Township

Table 4.8-49: Health Facilities at Dala Township

No.	Name of Hospital	Government/Private	Total no. of bedstead
1	Township Hospital	Government	25
2	Pyawbwegyi Hospital	Government	16
3	Yakhinechaung Hospital	Government	16
	Total	Government	57

Source: General Administrative Department, 2017

Health Condition at SeikkyiKhanaungto Township

Table 4.8-50: Health facilities at SeikkyiKhanaungto Township

Name of Hospital	Government/Private	Total no of bedstead
Township Hospital	Government	25

Source: General Administrative Department, 2017

The most common diseases in the SeikkyiKhanaungto Township are shown.

Table 4.8-51: Most Common Disease at SeikkyiKhanaungto Township

Type of Diseases									
Malaria		Diarrhea		TB		Dysentery		Hepatic	
Suffer	Death	Suffer	Death	Suffer	Death	Suffer	Death	Suffer	Death
-	-	177	-	133	-	132	-	-	-

Source: General Administrative Department, 2017

Health Condition at Kyimyindaing Township

Table 4.8-52: Health facilities at Kyimyindaing Township

Name of Hospital	Government/Private	Total no of bedstead
Western District Hospital	Government	300
Bone Hospital	Government	300
Satsan Hospital	Government	16

Source: General Administrative Department, 2017

The most common diseases in the Kyimyingdaing Township are shown in Table 5.8-53.

Table 4.8-53: Most Common Disease at Kyimyingdaing Township

Type of Diseases									
Malaria		Diarrhea		TB		Dysentery		Hepatic	
Suffer	Death	Suffer	Death	Suffer	Death	Suffer	Death	Suffer	Death
-	-	122	-	121	-	16	-	-	-

Source: General Administrative Department, Kyimyingdaing Township

There are three government-owned hospitals in Twente township and among the major diseases are waterborne diseases such as diarrhea and dysentery, and respiratory diseases such as tuberculosis. Dala township also has three government-owned hospitals and according to GAD data provided, there has no available data of communicable disease outbreaks (HIV/AIDS). Khanaungto township has only one government hospital due to its small population compared to other townships and major diseases include diarrhea, tuberculosis and dysentery. Kyimyingdaing township has three government hospitals and major diseases include diarrhea and tuberculosis. The main causes of disease are lack of water purification facilities and poor hygiene environment, and it is estimated that the incidence of waterborne diseases such as diarrhea and dysentery is high. This is not only a problem for study townships: Over the past decade, the incidence of new tuberculosis has declined and access to safe water and sanitation facilities has increased in Myanmar. While the Myanmar government stepped forward to improve the overall access to the safe drinking water and sanitary facilities nationwide (See the figures below), but it is necessary to improve hygiene and the public health environment. During the construction, it is of high importance that the project proponent and the contractor ensure preventing of the deterioration of the water quality and sanitation level in relation to the construction activities.

* Tuberculosis incidence (per 100,000 people): 403 (2005) → 369 (2014)

* Accessible proportion of population to safe drinking water: 72.3% (2005) → 80.6% (2015)

* Accessible proportion of population to sanitary facilities: 69.4% (2005) → 79.6% (2015)

(Source: Myanmar national cooperation strategy)

4.12 Cultural Components

In Myanmar, some of the prominent physical cultural resources are associated with religion such as the temples and monasteries. There are 104 pagodas, 263 monasteries, 32 centres for nuns, and 11 Dhamma halls in Twente Township. Dala Township has 38 pagodas, 87 monasteries, seven centres for nuns, and 87 temples. SeikkyyiKhanaungto has 16 statues, 15 monasteries and 15 Dhamma halls. In Kyimyingdaing Township, there are one pagoda, eight statues, 21 monasteries and 24 chapels. Table 4.9-1 showed the existing religious buildings in the study townships.





Table 4.9-1: Religious Building in the Four Study Townships


Township	Pagoda	Statue	Temple	Monastery	Center for Nuns	Chapels
Twente	104	-	-	263	32	11
Dala	38	-	-	87	7	87
SeikkyyiKhanaungto	-	16	-	15	-	15
Kyimyingdaing	1	8	-	21	-	24

Source: General Administrative Department (2017)

All the identified items are pagoda complexes and monasteries. Most of these items are located within or in close proximity to human settlements. The study townships located within the cultural heritage areas (see in Table 4.9-2).

Table 4.9-2: List of Key Tangible Cultural Heritage Resources Identified within the Four Study Townships (2018)

Township	Tangible Cultural Heritage	Photograph
Twente	Shwesantaw Pagoda	
	Maungti Pagoda	
	PaukKhayawati Old Town	
Dala	Danote	

SeikkyiKhanaungto	New Pada Tha	
Kyimyindaing		No Cultural Heritage Resources

Most pagodas and monasteries in the four townships are small-sized and mainly for mundane religious lives of residents. None of them in the study area was designated as the cultural heritage by the concerned national governmental ministry as well as by the United Nations Educational, Scientific and Cultural Organization (UNESCO).

Among them, major cultural heritages in the scale aspect are shown in the table above. Although within townships of the project area, they are located outside from banks of the Twante canal or the Yangon river where the actual construction and improvement engineering works will be carried out, which would be likely to have no or only insignificant impacts by the project.

Nevertheless, with the progress of the project, unexpected environmental or social impacts could be on these cultural heritages. No matter when such impacts happen, if any, to a certain extent of possibly damaging these cultural heritages, all mitigation and management measures shall be conducted in accordance with EDCF safeguard policy and related Burmese laws, such as the protection and preservation of cultural heritage regions law, the Protection and Preservation of Ancient Monuments Law, and the Protection and Preservation of Antique Objects Law.

4.13 Landscape

The project site and its surrounding area are composed of plains and typical rural landscapes of urban neighborhood. The landscape assessment is to consider effects on the visual components arising from the proposed establishment of Twente Canal Development activities. The location of the project area (application site) was shown in Figures 4.10-1.

Component 1 - Channel Training

- 1.1 - Bank Protection
- 1.2 - Bed Scour Prevention

Component 1- Waterway maintenance- Shore protection – Embankment construction (5.88km) and Bed erosion protection construction (A= 55,500 m²)

Component 2- Flood protection- Embankment construction for flood protection (3 sections, 39.5 km)

- 2.1 - Khanaungto Section
- 2.2 - Dala section
- 2.3 - Twante (Twantay) Section
- 2.4. - Kyimyindaing Section




Figure 4.10-1: The Overall Project Area

4.13.1 Kyimyindaing Township

The line (**Tracking ----**) in the picture referred to the related project area for Kyimyindaing Township. The whole township area is plains and typically urbanized area as shown in Figure 4.10-2. However, the project area (AOI) was typically rural landscapes of urban neighborhood. The detailed map related with the project AOI was attached in Annex 4-1 of A3 size.



Figure 4.10-2: The Overall Cityscape of Kyimyindaing

4.13.2 SeikkyiKhanaungto Township

SeikkyiKhanaung township was a typical rural landscape and almost all the AOI area is within the proposed project area as shown in Figure 4.10-3. Actually, the whole township was likely a flood plains area. The map showing the detail information within the project area was attached in Annex 4-2 of A3 size.




Figure 4.10-3: The Overall Cityscape of SeikkyiKhanaungto

4.13.3 Dala Township

Dala township area is typically a rural landscape which comprised of inland water transportation facilities along with the Yangon River and Twente canal as shown in Figure 4.10-4. Detailed map within Project AOI will be attached in Annex 4-3 of A3 size.





Figure 4.10-4: The Overall Cityscape of Dala

4.13.4 Twente Township

The cityscape of Twente township was shown in Figure 4.10-5 and the proposed project area will be set up from the Twente bridge. Actually, the township area was totally escaped from the current project AOI. Detail map will be attached in Annex 4-4 of A3 size.




Figure 4.10-5: The Overall Cityscape of Twente

CHAPTER 5 IMPACT AND RISK ASSESSMENT AND MITIGATION MEASURES

5.1 Impact Assessment Methodology

The impact assessment process comprises a systematic approach for the evaluation of the project components and their associated activities throughout the project lifecycle. The assessment process mainly considers the followings (Ref: General Environmental Impact Assessment Guideline, 2017):¹

- Screening and Scoping;
- Baseline Information;
- Project Alternatives and Design;
- Key Issues and Selection of Valued Ecosystem Components
- Impact Assessment;
- Impacts Identification and Evaluation;
- Residual Impact Identification;
- Mitigation and Monitoring.

5.1.1 Scope of Assessment

Screening is the initial step of the assessment process to confirm the need of EIA/IEE/EMP type report by appraising the type of project and its associated activities throughout the project lifecycle in the context of its biophysical, socio-economic, policy and regulatory environments and also its given location, scale and planned project activities.

According to the description of Paragraph 24 in Chapter III of Environmental Impact Assessment Procedure, 2015, the proposed Twante Canal Improvement Project is an EIA type project, which should be taken account of applicable national legislations and international treaties and conventions that the Myanmar government ratified because of its multiple components which are characterized by a high risk of significant, adverse environmental or social impacts.²

Scoping is a preliminary level of the assessment process to anticipate the “interactions” between project activities and environmental “receptors”. It mainly considers on the assessment of key environmental and social issues. A mixture of scientific judgments of experienced experts and the qualification and/or numerical analysis such as emission and discharge modeling are used to scope out the activities and/or events.

Since the scoping is conducted before the detailed field investigation is made, for this proposed project, the information from the reconnaissance activities carried out by the study team with preliminary assessment checklist/matrix was used to determine which are the most critical issues to study and will involve community participation to some degree based on preliminary site studies and expert judgments. After the scoping, the EIA was prepared with the following objectives :

- To identify and evaluate environmental and social risks and impacts of the project.

¹General Environmental Impact Assessment Guideline, The Republic of The Union of Myanmar, Ministry of Natural Resources and Environmental Conservation, September 2017.

²Environmental Impact Assessment Procedure, The Government of the Republic of the Union of Myanmar Ministry of Environmental Conservation and Forestry Notification No. / 2015.

- To adopt a mitigation hierarchy to anticipate and avoid, or where avoidance is not possible, minimize, and, where residual impacts remain, compensate/offset for risks and impacts to workers, Affected Communities, and the environment.
- To promote improved environmental and social performance of clients through the effective use of management systems.
- To ensure that grievances from Affected Communities and external communications from other stakeholders are responded to and managed appropriately.
- To promote and provide means for adequate engagement with Affected Communities throughout the project cycle on issues that could potentially affect them and to ensure that relevant environmental and social information is disclosed and disseminated.

ESIA is regarded as a decision-making tool which provides the information needed to manage to allow full consideration of environmental interests likely to have significant environmental and social impacts. The ESIA report details how the project will affect the environment and whether alternative (including no project option) should be considered in a more sustainable manner.

Based on the findings and results of these reviews, investigations and consultations, the key environmental and social impacts of the project activities were preliminarily identified in the scoping process. A scoping matrix has been developed to support this assessment and to enable the identification of interactions in a consistent way. Scoping report with suggested TOR has been submitted to the MONREC by DWIR on 14th November 2018.

In the review of the submitted Scoping and TOR, the MONREC issued its opinions on 20 December 2018 as follows:

- Utilities and amount of resource that will be used to implement the proposed project
- Source of water and usage of electricity for the construction phase
- Alternative plan for social environment in ways that will reduce impacts in project design, technology and tools.
- Affected people and the project which will accommodate about Graveness Mechanism
- Wastewater and solid waste management.
- General budget for the Environmental Management Plan

The EIA Team together with the project proponent (DWIR) revised the Scoping and TOR accordingly and submitted again to MONREC in February 2019. Final approval of the Scoping paper and the TOR has been issued on 08 May 2019 with the following suggestions:

- a) Based on the scoping report and TOR, to prepare an EIA report in the compliance with EIA procedure (2015) following the articles of 60, 61, 62, 63 and 65.
- b) The Project Proponent shall issue a letter of endorsement in a format prescribed in Article 62 of EIA procedure (2015) with the authorized signature
- c) To submit and get approval from the concerned Ministry (MONERC) after preparation of the report accordingly
- d) To choose the officially registered supplier for construction materials and resources
- e) To include resettlement action plan for the affected persons from the proposed project including loss of land, magnitude, type of lands, number of affected houses and livelihood restoration plans in the assessment report

f) To update the EIA report with the additional analysis and survey results of environmental and social impact assessment in the project area

(For final TOR approved by the MONREC, pls see the Annex 5-1 of this report.)

5.1.2 Geographical Scope and Study Area Boundaries

The potential Area of Influence (AoI) for the project was determined to identify potential interactions between the project activities in the AoI and the impacts that could result from these interactions. Later on, impact assessment focuses on those issues that are most important for design, alternatives and stakeholder interests.

The AoI for the Twante (Twantay) Canal Project consists of the following aspects:

- Bank protection
- Bed scour prevention
- Flood embankment

Area of influence (AOI) was determined based on the project components and key environmental and social sensitive areas such as wetlands and through consultations with DWIR and other key stakeholders.

Area of Influence (AOI) of Environmental and Social Impacts Assessment

The affected area of the proposed project (the Twante Canal Improvement Project) was supposed to have both direct and indirect impacts. Direct impacts will be considered as the canal embankment and road construction area within 30 m ROW along the canal. Considerations for indirect impacts are within 200 m and 500 m from ROW along with canal in the project area.

The events will include the frequency rates of the surrounding environmental receivers, including human and natural environments, such as noise, nuisances and others from construction activities, etc.




Figure 5.1-1: Distribution Map of Ground Level for Southern part of Project Area³



Figure 5.1-2: Area of Influence (AOI) for Environmental Impact Assessment


Area of Influence (AOI) of social impacts has been considered as two distinctive zones such as direct impact zone and indirect impact zone. Direct Impact Zone has been defined in the area where loss of physical assets (land, structures and other types of properties etc.) are likely to be affected and need to be compensated (and some of them subject to physical relocation due to the loss of their residential

³Source: 1:50,000 DEM of Survey Department. The following figure shows the Administrative Boundaries of the Four Affected Townships (Twante Township, Seikkyi Khanaungto Township, Kyimyindaing Township and Dala Township)

area). Indirect Impact Area are defined as the areas where other types of impacts are occurring such as (temporary or permanent) disturbance of movements, noise and dust during construction etc. The direct impact zone (i.e. right-of-way (ROW)) has been established as follows:

Direct impacts include land acquisition (both public and private-owned land) for construction and temporary or permanent access road building. Right-of-ways of the embankment and other canal improvement works are designated to be as follows:

- ① **Area 1:** ROW in Twante Section and Dala Section- Areas along, adjacent to Twante Canal, within 30 meter (Tentatively supposed 30-meter ROW before confirming AoI) from the limit of the construction site (canal improvement and embankments)



- ② **Area 2:** ROW in SeikkyiKhanungto Section: As of May 2015, it was reported that there are 29 officially registered shipyards located along the Twante canal in SeikkyiKhanungto Township (DWIR Data-2015-2016). The area is reported to cover 2,190 acres (8,962,616 sqm). In order to minimize the impacts on the shipyard business during the construction, ROW is to be drawn outskirt from the limits of the shipyard area inward to the landside, not cross-cutting the existing facilities. (The exact alignment of the ROW shall be determined later.)



B . Spatial boundary for other types of direct and indirect social impact assessment

Area 3: ROW in Yangon River(MPA in charge, Kanungto, Dala, and Kyimyindaing Section) : ROW is tentatively supposed to 30meter from the limit of the construction site of embankments.



C. Spatial boundary for social impact assessment in Yangon River Section MPA in charge (1)



D. Spatial boundary for social impact assessment in Yangon River Section MPA in charge (2)

In addition, geographical scopes are set for study along the administrative boundaries of the affected three Township for the social impacts such as:

- **Long-term income and livelihood and general improvement of living condition (including traffic, health and sanitation conditions etc):** While the primary beneficiaries of the project would be the inland water transport industry and the residents along the canal, the spill-over and ripple effects are expected to reach the broader community including the other residents of the affected Township. Thus the study would include the residents of the three affected Township as secondary level of beneficiaries and include them in the study as part of stakeholder engagement.
- **Temporary nuisances and disturbance in livelihood due to the noise generation, water and air and other pollution and construction-related waste generations:** While actual scope of influence may differ from item and item, the study suggest to lump the entire tboundaries of the affected four townships as the limits of this study for the convenience of assessment as well as due to the jurisdictional/administrative governance mechanism.
- **Temporary disturbance of shipyard operation businesses in SeikkyiKhanaungto Township:** The study assumes that the owners and the employees of the shipyard business in SeikkyiKhanaugto Township as part of the SeikkyiKhanaungto Township business community, regardless of their actual residential locations. Special consideration shall be given to reflect their particular concerns and socio-economic baseline conditions through the survey design and the arrangement of a focused group discussion (FGD).
- **Temporary disturbance of fishery and inland water transport business during construction:** The study assumes that the affected persons and households engaged in the fishery and inland water transport business (e.g. mini passenger boats (mini bus type business with the vessel capacity of about 20 passengers and taxi type boats (small engine boats hosting max. less than 5 passengers) and associated business holders as part of the business community of the three affected Township, regardless of their actual residential locations. Special consideration shall be given to reflect their

particular concerns and socio-economic baseline conditions through the survey design and the arrangement of targeted interviews.

The following figure shows the Administrative Boundaries of the Four Affected Townships (Twante Township, SeikkyiKhanaungto Township, Kyimyindaing Township and Dala Township).



Figure 4.1: The Administrative Boundaries of the Four Affected Townships (Twante, SeikkyiKhanaungto, Dala and Kyimyindaing)

5.1.3 Methodology for Significance Assessment of the Identified Impacts

Significance level of an identified impacts is a composite index of several factors, including magnitude, duration, extent and probability. The significance assessment for this study has adopted by the International Association of Impact Assessment-IAIA,2014, www.iaia.org.

5.1.3.1 Event Magnitude Rankings from those Affecting an Area

the magnitude for an event was determined on the following parameters, which are equally weighted, and ratings assigned as:

- 1 – Insignificant
- 2 – Small Changes: 0-10 m
- 3 – Moderate Changes: 10-50 m
- 4 – High Changes: 50-200 m
- 5 – Very High Changes: Greater than 200 m

5.1.3.2 Duration: Events Range Occurring from those Affecting an Area

- 1 – Up to 1 year;
- 2 – 2 to 5 years;
- 3 – 6 to 15 years;
- 4 – Life of Operation
- 5 – Post Closure

5.1.3.3 Extent: Degree/permanence of Disturbance

It includes concentration of an emission or discharge with respect to standards of acceptability that include applicable legislation and international guidance, its toxicity or potential for bioaccumulation, and its likely persistence in the environment. Degree/permanence of disturbance or physical impact (e.g. disturbance to species, loss of habitat or damage to cultural heritage). Ranges from:

- 1 – Limited to the site;
- 2 – Limited to the local area;
- 3 – Limited to the region;
- 4 – National
- 5 – International

However, the proposed project is noted that it would be a solution to support the waterway transport within the region by aligning of the bank in constantly permanent to secure safe inland water navigation, protect residential and farmland areas from bank erosion and flood damages, and provide fresh water and water-friendly space. Thus, it could be considered that the intensity of impacts related to the project activities will not be high and applicability on toxic emissions or discharges to lead the deteriorations of surrounding species, natural habitats or cultural heritage at the affected area.

However, when the construction starts, the construction activities will effect on water and air quality negatively from minor to a moderate level to concentrate contents by the excavation works and use of heavy vehicles and machines, etc.

5.1.3.4 Probability: Events Range of Occurrence from those Affecting an Area

- 1 – Very Improbable;
- 2 – Improbable;
- 3 – Probable;
- 4 – Highly Probable;
- 5 – Definitely;

The assessment of each impact is based on consideration of the magnitude, duration, spatial and frequency of activities which are going to be carried out during each phase of the project as well as on characteristics of the project site. The assessment is both quantitative and qualitative and the significance of each impact is classified into 5 categories overall. The following methodology will be applied to assess the environmental and social impacts of the project mainly on air, water, land, biodiversity, human beings and society. Each source of impact has been assessed by four parameters, magnitude, duration, extent and probability, and each assessment point has 5 scales as illustrated in the Table below:

Table 5.1-1: Impact Assessment Parameters and its Scale

Parameter	Scale				
	1	2	3	4	5
Magnitude (M)	Insignificant	small and will have no effect on environment	Moderate and will result in minor changes on environment	High and will result in significant changes on environment	Very high and will result in permanent changes on environment
Duration (D)	0- 1 year	2- 5 year	6- 15 year	Life of operation	Post Closure
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite

(Source: International Association of Impact Assessment-IAIA,2014,www.iaia.org)

Then, the significant Point (SP) is calculated by the following formula.

Significant Point (SP) = (Magnitude + Duration + Extent) * Probability

Impact Significance: Based on calculated significant point, impact significance can be categorized as follows:

Explanation


Significant Point (SP) = (Magnitude + Duration + Extent) * Probability

Table 5.1-2: Impact Significance

Significant Point (SP)	Impact Significance
<15	No impact (-)
15-29	Low impact (U)
30-44	Moderate significant (C)
45-59	High significant (B)
> 60	Very high significant (A)

(Source: International Association of Impact Assessment-IAIA, 2014, www.iaia.org)

Overall event magnitude is scored from low (15) to very high (>60) by adding the individual parameter scores:



Any impact classified as high and very high (B and A) is considered to be significant, where the impact is negative, requires additional mitigation. Impacts of negligible, low or moderate (U and C) are considered as being mitigated as far as practicable and necessary, and therefore, do not require further mitigation. Impacts can be positive or negative. Positive impact is signed as ‘+’ and negative impacts is signed as ‘-’.

5.2 Scope of Environmental Impact Assessment (Pre-construction, Construction, Operation and Disclosure Phases)

The environmental and social impacts due to the project-related activities in design (Pre-construction), construction and operation stage respectively. The scoping matrix displays project activities against potential environmental and social impacts, and potential interactions each project activity may have on the range of resources/ receptors within the Area of Influence for the project.

All of the impacts are expected to effect on 4 types of specific receptors, such as Biological receptors (routine or reliably predictable presence of any unique, threatened or protected species), human receptors (people who lost residential and/or commercial properties within the geographical area of anticipated impacts and people who are likely to suffer from air emission and noise disturbance from construction activities above the adopted standards), Physical/feature receptors (presence of feature such as state protected monument or potential for substantial damage or loss of physical integrity) and Atmosphere Soil, Ground Water and Surface Water Receptors (e.g. used extensively for agriculture and used as a public water supply).

5.2.1 Identification and Assessment of Physical Environmental Impacts

Valued Ecosystem Components (VECs) such as fundamental elements of the physical, biological or socio-economic environment, include the air, water, soil, terrain, vegetation, wildlife, fish, birds and land use, as well as the added contributed effects to same VECs from other past, present and future

projects or actions located in the same area.

The key VEC physical components include:

Atmosphere: climate conditions and trends, and extreme weather events and air-quality conditions.

Physiography and Geology: physiography such as landforms, elevations, relief and unique features; surficial geology including types and depths; and bedrock geology including types, location and depths.

Soils: soil types and characteristics, soil capabilities and limitations, and permafrost conditions.

Surface Water: watersheds and waterbodies characteristics, shoreline environment, and sources of potable water.

Groundwater: primarily local groundwater characteristics.

The selected criteria will be considered on the followings;

- Overall importance/value to people
- Regulatory requirements
- Potential for substantial Project effects
- Key for ecosystem function, such as star fishes, humming birds, sea otter, African elephants, etc.
- Umbrella indicator

5.2.2 Impact Assessment on Ambient Air Quality

During the construction phase, emissions of air pollutants at the project site are mainly associated to transportation (i.e. vehicle movement), earth works, foundation works, and construction and site clearance activities. Emissions during the construction of a building or road can be associated with land clearing, drilling, ground excavation, cut and fill operations (i.e., earth moving), and construction of a particular facility itself. These activities are expected to occur over for about 5 years along the canal.

Construction phase activities will generate the following main types of air emissions:

- combustion and exhaust emissions generated from the construction equipment, generators and vehicles from road transportation; and
- fugitive dust generated by earthworks including excavation, backfilling, grading, equipment movement, material piling, loading and unloading, and demolition of decommissioned buildings.

There are not emitted air pollution during operations. Therefore it is less affected in the air during operation phase and can be considered as negligible.

Construction operations account for a significant amount of greenhouse gas (GHG) and criteria air pollutants (CAP) (e.g. nitrogen oxide, carbon monoxide, particulate matter) emissions which are essential to reliably estimate the emissions from construction equipment, which account for the largest share for the total impacts of construction operations towards the implementation of environmentally sustainable construction operations.

Currently, the method widely used for quantifying construction emissions is based on US Environmental Protection Agency (EPA)'s NONROAD model (US EPA 2009b) or California Air Resources Board's OFFROAD model (CARB 2009).

5.2.2.1 Impact Estimation by Calculation using Emission Factors of Construction Equipment

Current practices and existing research to quantify construction emissions largely depend on the methodology and emission factors which are provided by NONROAD model or OFFROAD model. In those models, the amount of emissions from each piece of equipment is determined by the following equation (US EPA 2004a):

$$\text{Emissions(g)} = \text{Engine Power (hp)} * \text{Operating Hours (hrs)} * \text{Emission Factor (g/hp-hr)} * \text{Load Factor (1)}$$

Based on the details of equipment employed for the given task, emission factors for various duty cycle of each piece of construction equipment are calculated based on Lewis' model⁴ using the Equation -1.

⁴<https://pdfs.semanticscholar.org/4dc0/1dc3c7e5a162aff7cee83cd858ab2bc70df7.pdf>

Table 5.2-1: Emission Factors for Various Duty Cycle of Construction Equipment

Equipment Type	Duty Cycle	Operating Hours	Load Factor	Engine Power (hp)	Model	Emission Factors				
						HC (g/hr)	CO (g/hr)	NO _x (g/hr)	PM (g/hr)	CO ₂ (kg/hr)
Bulldozer	Rough Grade	88.83	0.59	410	CAT D9T (2 units)	130.09	270.01	806.53	5.56	55.13
	Stockpile					100.53	272.45	962.29	8.78	83.44
Off-Road Truck	Hauling	266.48	0.59	469	CAT 740 (6 units)	56.78	128.26	385.64	2.94	28.84
Excavator	Excavate Soil	44.41	0.59	453	Hitachi EX 750	126.94	341.57	1122.52	10.22	98.05
Grader	Resurfacing	11.10	0.59	259	CAT 14M	75.52	200.45	655.43	5.86	56.48

Table 5.2-2: Emissions from Various Construction Equipment

Equipment Type		Emissions				
		HC (g)	CO (g)	NO _x (g)	PM (g)	CO ₂ (kg)
Bulldozer	Rough Grade	6817.97	14151.14	42269.99	291.40	2889.35
	Stockpile	5268.75	14279.02	50433.33	460.16	4373.07

Off-Road Truck	Hauling	8927.13	20165.45	60631.55	462.24	4534.32
Excavator	Excavate Soil	3326.07	8949.78	29411.89	267.78	2569.10
Grader	Resurfacing	831.33	1312.75	4292.41	38.38	369.89
Total Emissions		24709.81	58858.14	187039.17	1519.96	14735.73

5.2.2.2 Impact Estimation by Direct Measurement Method

1) AQM and Dust Survey Methodology

The survey started with the initial site visits prior to the air quality monitoring to establish representative sites for air sampling. The background ambient air monitoring aims to cover up within 3 km radius of the proposed project site.

For the direct measurement at the project site, the Hazscanner TM EPAS wireless environmental perimeter air station was deployed to measure the selected air parameters. The instrument is factory calibrated with calibration Span check.

Calibration: Gravimetric reference NIST traceable- SAE fine dust –ISO12103-1.

Accuracy: $\pm 10\%$ to filter gravimetric SAE fine test dust.

The recorded wind data are analyzed by using the WRPLOT View of AERMOD View (ver. 7.0) in which calm wind is defined below 0.5 m/s.

Ambient air quality monitoring was conducted for (4) designated air quality monitoring locations based on the prevailing wind direction.

The proposed canal project will not directly affect the air emission during the operation stage. The construction phase air emissions will be related to road transportation, construction vehicles and fuel and oil used, however, the impacts will be temporary during only construction time.

2) AQM and Dust Sampling Locations

Baseline 24-hour average air pollutants levels at three air quality monitoring stations were established by conducting baseline 24-hour average monitoring.

Based on the prevailing wind directions of the proposed project site, the ambient air samples were collected from 4 locations.



Figure 5.2-1: Location Map of Air Quality, Noise and Vibration Survey

Table 5.2-3: Baseline Air Quality Sampling Points

Sampling Location	Duration	Coordinates	Description of Sampling Points	Prevailing direction	Average Speed (m/s)	Calm wind (%)
AQNV1	28-29 th Sep, 2018	16°44'42.88"N 96° 5'32.99"E	Beside of Dala-Twante road at Pyawbwe Tay Village, Twante township, Yangon Region	W	0.15	79.17
AQNV2	29-30 th Sep, 2018	16°45'13.89"N 96° 7'12.62"E	Beside of Dala-Twante road at Targyi ward, Dala township, Yangon region	E	0.14	79.17
AQNV3	30 th Sep – 1 st Oct, 2018	16°45'19.58"N 96° 6'40.46"E	At General Administration Office compound, Seikgyi kanaungto Township, Yangon region	WSW	0.13	87.5
AQNV4	20 th – 21 st Oct, 2018	16°47'13.72"N 96° 6'47.00"E	At High School compound of Ngasin village, Kyinmyindaing township, Yangon region	E	0.54	54.17

2) AQM Baseline Results

The findings present the baseline air quality measurements which were recorded simultaneously in terms of 24-hour average of Particulate Matters (PM₁₀, PM_{2.5}), Carbon Monoxide (CO), Sulphur Dioxide (SO₂) and Nitrogen Dioxide (NO₂) along with meteorology condition at the monitoring sites.

The averaged 24-hour air parameters at 4 locations are summarized as follows:

Table 5.2-4: Baseline Air Quality Results

Sampling. No	Time	CO	NO ₂	NO	PM _{2.5}	PM ₁₀	SO ₂	Temp.	RH
	hours	µg/m ³	µg/m ³	µg/m ³	µg/m ³	µg/m ³	µg/m ³	Deg. C	%
AQNV1	24hr	173.59	54.74	0.03	2.84	7.07	26.74	29.24	83.02
AQNV2		356.43	44.08	0.03	2.87	9.58	47.04	27.47	85.40
AQNV3		215.55	48.84	0.04	2.79	7.06	26.19	26.85	85.74
AQNV4		219.00	71.73	0.01	2.68	7.25	17.66	26.00	87.15
Myanmar Emission Guideline value		-	-	-	25	50	20	-	-

Source: REM Survey, 2018 (Twante Canal Project)

According to the surveying results on ambient air quality, all parameters hit the targets under emission guideline values (National Environmental Quality (Emission) Guideline, 2015) except SO₂, which incredibly exceed than the target guideline value at three sampling locations. Regarding the experiences of REM field surveyors, vehicle emissions would be one of the main possible reasons for such high emission of SO₂ at these locations.

SO₂ is known to contribute to acid deposition (dry and wet) resulting in subsequent damages to the ecosystem while about human health impacts from exposure to Sulphur dioxide concentrations, the main impact relates to repercussions induced on the respiratory system through inhalation since it does not accumulate in the body. Sulphur dioxide in ambient air mostly affects the elderly, children, and people with bronchial and asthmatic disorders (i.e. the most sensitive and vulnerable groups in the community).

Table 5.2-5: Impact Significance due to Atmospheric Emissions during Construction and Operation Phase

Source of Impact	<p>Description: Excavation & Foundation Work and Civil Construction - Temporary pollutant emissions from vehicles and on-site machinery during construction period.</p> <p>Dust (Particulate matters, PM₁₀ and PM_{2.5}) emissions is the most likely impact.</p> <p>SO₂ emission is likely from heavy vehicle uses for construction.</p> <p>Environmental Concern: Occupational health concern for construction workers and community health lived in the closed surroundings of the construction site are expected. SO₂ is known to contribute to acid deposition (dry and wet) resulting about human health impacts from exposure to Sulphur dioxide concentrations, the main impact relates to repercussions</p>
-------------------------	---

	induced on the respiratory system.				
Magnitude	Insignificant	small	Moderate	High	Very High
	Rationale: Dust emissions have been proven to have adverse impacts on human health. SO ₂ emission from heavy vehicle uses is also concerned due to its high level in baseline condition.				
Duration (D)	0- 1 year	2- 5 year	6- 15 year	Life of operation	Post Closure
	Rationale: The construction phase will take about 2-5 years in proposed plan. Impacts will be temporary associated with the construction phase.				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
	<p>Rationale: People in affected communities will only be exposed when equipment and vehicle are operating near communities.</p> <p>Dust is the most likely emission while construction phase, it's only at the specific site of living construction activities as a temporary impact for sensitive residents nearby the construction site.</p>				
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite
	Rationale: Impacts are expected to occur with high magnitude at the (specific) limited site by temporary and intermittent atmospheric emissions within the varied location during construction activities and the impact is likely to reversible within a short recovery time after construction.				
Significant Level	Magnitude (4) + Duration (2) + Extent (1) * Probability (3) = 21				Low impact (U)

5.2.2.3 Greenhouse Gases

There will be no relation to impact from greenhouse gas emissions from the project activity except temporary emissions from the contribution of the greenhouse gases, CO and CO₂ emission mainly from fossil fuel burning during construction, however, the impact result is temporary and negligible which could not cause any increment to exceed the existing magnitude.

5.2.2.4 Mitigation Measures for Atmospheric Emissions

Withstanding the potential of atmospheric emissions from construction and related activities the environmental impact of the project is high; the following mitigation measures will further reduce the impact of emissions, leading to insignificant impacts:

- Sprinkling of water on dust generating areas;
- Restricting the speed limits of vehicles during movement on unpaved roads;
- Covering of vehicles carrying loose soil/construction material;
- Applying preventive maintenance system;
- Checking vehicle and equipment inspection daily;
- Stopping dust generating activities in high wind;
- Applying good site practice and housekeeping;

- Turning off the engine while not in use;
- Optimizing construction schedule to minimize time that vehicles are in operation;
- Covering load-carrying platform properly when carrying earth/sand.

With the purpose to reduce the emissions of gaseous pollutants during the construction phase, the following mitigation measures and good practice have to be taken into account:

- vehicle engines and other machinery will be kept turned on only if necessary, avoiding any unnecessary emission;
- activities will be conducted trying to use the minimum required number of means at the same time;
- electric small-scale mechanization and technical tools will be used when available and feasible; and
- repair and maintenance of construction equipment and vehicles will be performed outside of the construction site by at specialized enterprises.

Concerning dust control methods and measures, the following actions are recommended to reduce the generation of dust:

- watering or increase of the moisture level of the open materials storage piles to reduce dust levels (especially during dry season);
- enclosure or covering of inactive piles to reduce wind erosion;
- loads in all trucks transporting dust-generating materials will be sprayed with water to suppress dust, as well as wheels of means moving inside and outside of the construction site;
- speed reduction for the means travelling inside the construction site; and
- stabilization and re-vegetation of cleared areas that are no longer needed as soon as practicable during construction.

5.2.3 Impact Assessment on Noise and Vibration

During the construction phase, noise is the worst impact as much as dust emissions for the receiving bodies due to construction activities and the impacts are inevitable for residents nearby the construction site due to the activities such as;

- Earthwork: the main noise sources are related to the use of equipment and earthwork machinery such as: bulldozers, excavators, loaders, various transport vehicles;
- Groundwork: the main noise sources are pile hammers and excavators. It has been noted that the pile hammers noise is characterized by an impulse noise;
- Structure installation: the main noise sources during the structure installation stage are a concrete mixer, vibrating machine, etc., and collision noise impact during the load and unload of materials and;
- Equipment installation: the main noise source during the equipment stage is the crane elevator.

Exposure to noise of high intensity for a long term will reduce hearing and labor productivity, and will cause fatigue, stress, and insomnia. Movement of heavy vehicles and some construction work will generate vibration and affect some unstable buildings. Exposure to noise of high intensity for a long term will reduce hearing and labor productivity, and will cause fatigue, stress, and insomnia.

5.2.3.1 Direct Measurement Method for Noise and Vibration

One of the worst impacts in the construction phase is dust or noise due to construction vehicles, and these impacts are caused mainly by carrying construction materials and negatively affect the health of both workers and residents inevitably.

Noise and vibration investigation sites during baseline survey are set up at:

- 1) AQVN 1: It is located beside the Dala-Twante car road, Pyawbwelay village, Twante Township, with a situation of southern part of the village within approximately 300 m south of the Project ROW.
- 2) AQVN 2: The sampling location is beside the Dala – Twante Car Road, Targyi ward, Dala Township, Yangon Region which is approximately 130-meter south of Project ROW.
- 3) AQNV 3: It is located at General Administration Office compound in the middle of Seikgyi Kanaungto Township, Yangon Region, approximately 205 m north of Project ROW.
- 4) AQNV 4: Basic High School compound of Ngasin village, Kyimyindaing Township, Yangon Region which is near the main Yangon River, approximately 30 km west of Project ROW.

5.2.3.2 Noise and Vibration Survey Methodology

Various noise scales have been introduced to describe, in a single number, the response of an average human being to a complex sound made up of various frequencies at different loudness levels. The most common and heavily favored of these scales is the **A weighted decibel dB (A)**.

Measurement of noise and vibration level was conducted by referring to the recommendation of International Organization for Standardization (ISO), i.e. ISO 1996-1:2003 and ISO 1996-2:2007. The instrumentation used for noise and vibration level survey is shown in the following Table 5.2-8.

Table 5.2-6: Instruments for Measurement of Noise and Vibration

Parameter	Instrument	Model	Manufacture
Noise (A-weighted loudness equivalent (L_{Aeq}))	Sound level meter	SL-4023SD	Lutron
Vibration (Vibration level (L_{Veq}))	Vibration level meter	VM-55	Rion Co. Ltd. (Japan)

For noise levels measured over a given period of time interval, it is possible to describe important features of noise using statistical quantities. This is calculated using the percent of the time certain noise levels are exceeded during the time interval. The notation for the statistical quantities of the noise levels are described below:

- L10 is noise level exceeded 10% of the time;
- L50 is noise level exceeded 50% of the time; and
- L90 is noise level exceeded 90% of the time.

The instrument used for noise measurement was set at the height of 1.2 m. A-weighted loudness equivalent level was measured automatically every 10 minutes and recorded in a memory card. One-hour L_{Aeq} was calculated by using the following array formula.

$$10 \cdot \text{LOG}_{10} (\text{AVERAGE} (10^{((\text{RANGE})/10)}))$$

The vibration instrument used was the VM-55 Vibration Level Meter accompanied by a 3-axis accelerometer which was placed on solid soil ground near the roads. Vertical vibration (Z axis), L_v , was hourly measured and recorded. L_v (dB) vibration levels were recorded as $L_{v,max}$, $L_{v,min}$, L_{v5} , L_{v10} , L_{v50} , L_{v90} , L_{v95} , and L_{veq} . L_{v10} was the vibration level used in accordance with referred standard.

5.2.3.3 Noise and Vibration Sampling Locations

Sampling locations were designed as 4 different sites which are as same as air quality survey shown in Figure 5.1-5. All location coordinates and description and so the survey periods are as baseline air quality as described in Table 5.1-3.

5.2.3.4 Noise and Vibration Baseline Results

Equivalent noise level (L_{Aeq}) and Vibration level (L_{v10}) are presented in Table 5.2-9.

Table 5.2-7: Equivalent Noise Level (L_{Aeq}) and Vibration Level (L_{v10})

Survey Point	Equivalent Noise Level (L_{Aeq} , dB)		Vibration Level (L_{v10})	
	Day-time (7:00 AM - 10:00 PM)	Night-time (10:00 PM - 7:00 AM)	Day-time (7:00 AM - 10:00 PM)	Night-time (10:00 PM - 7:00 AM)
AQNV1	74	64	46	40
AQNV2	79	66	43	37
AQNV3	72	58	37	34
AQNV4	71	70	36	29
Target Value (Industrial, commercial)	70	70	-	-
Target Value (Residential)	55	45	65	60

Source: REM Survey, 2018 (Twante Canal Project)

Note: The target value for Vibration is the Japan Standard for “road side level of residential area”.

According to the REM survey results, daytime and night-time noise levels are above the residential standards and the result is quite reasonable because the sampling locations are along the existing canal as the high commercial area with the high traffic issue at all stations.

Table 5.2-8: Impact Significance due to Noise and Vibration during Construction and Operation Phase

Source of Impact	<p>Description: Earth work: the use of equipment and earthwork machinery such as: bulldozers, excavators, loaders, various transport vehicles, Ground work: the use of pile hammers, and excavators and Equipment Installation: crane elevator.</p> <p>Vibration: Movement of heavy vehicles and some construction work will generate vibration and affect some unstable buildings.</p>
-------------------------	---

	Environmental Concern: Occupational health: along-term noise exposure will reduce hearing and labor productivity, and will cause fatigue, stress, and insomnia.				
Magnitude	Insignificant	small	Moderate	High	Very High
	Rationale: Noise generation is likely to impact on the occupational health of the construction workers and nearby communities by construction activities like earth work, ground work and equipment installations. High noise is expected where the baseline condition was already high without project activities. Movement of construction vehicles and transportation of materials are expected to seek during the construction activities.				
Duration (D)	0- 1 year	2- 5 year	6- 15 year	Life of operation	Post Closure
	Rationale: The construction phase will take about 2-5 years in proposed plan. Impacts will be temporary associated with the construction phase.				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
	Rationale: People in affected communities will only be disturbed by noise and vibration impacts when equipment and vehicle are operating near communities, especially piling and excavation activities and movement of heavy vehicles.				
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite
	Rationale: The communities are expected to suffer with high magnitude at the specific site with the high noise in baseline condition during the working hours of using noise generating vehicles and equipment and use of pile hammers. The vibration is expected to arise when moving the heavy vehicles for transportation of huge construction machinery and equipment. The impact will be terminated after the construction period and it has no relation with longer consequent sufferings.				
Significant Level	Magnitude (4) + Duration (2) + Extent (1) * Probability (4) = 28				Low impact (U)

5.2.3.5 Mitigation Measures for Reduction of Noise and Vibration

The protection, mitigation and monitoring measures are foreseen in order to minimize and reduce the impacts related to the noise emissions during the construction phase of the power plant are:

- to select adequate equipment (fit with noise mufflers);
- to minimize machinery and equipment unused conditions with engines in action;
- to maintain machinery and equipment in good conditions;
- to maintain an active community consultation and positive relations with local residents that will assist in alleviating concerns that might arise and resolve any potential noise complaints;
- to post warning signs within the vicinity of the impact and all personnel shall be provided with personal protective equipment. For example, workers operating equipment that generates noise should be equipped with the appropriate noise protection gear; and
- to restrict the construction activities that will generate disturbing sounds to normal working hours.

5.2.4 Impact Assessment on Water Quality

The potential impacts on water resources derived from the construction phase for the proposed project are mainly related to water consumption; and water quality modifications.

The water necessary for the construction activities and for feeding the worker camp will be taken from the nearby canal. Consequently, the assessment of impacts on the water environment is limited to the evaluation of:

- impacts on canal water availability and accessibility concerning the water needs to be requested by the Project, during the construction phase, and
- impacts on groundwater quality as a result of construction activities such as deep foundation and piling works, and discharges.

Potential sources of contamination of surface and groundwater quality are likely to include:

- construction and site clearance activities;
- wastewater discharge;
- piling operations for foundation; and
- accidental chemical or oil spill from the project operations (e.g.: refueling operations).

i) Wastewater Discharge

Potential water pollution would occur within the construction phase on canal water and it could cause by the discharged wastewater during the construction work at the project site.

During construction, wastewater would be discharged from the construction area as the result of rainfall on the construction unpaved areas. In any case, and in accordance to the protection, mitigation and monitoring measures to be taken into account during the construction phase (as discussed in the following mitigation measures), the potential surface and groundwater contamination caused by the construction phase would be well controlled and managed and would not cause any significant impact on surrounding and downstream area.

ii) Site Preparation Works

Site preparation works will comprise the levelling of the site, earthworks and the excavations for foundations, trenching and installation of underground services.

Both surface water and groundwater resources may be subjected to potential impacts related to accidental spillage or leakage.

iii) Accidental Events

Pollution of surface and/or groundwater may arise from accidental spills during construction (fuel, oils, grease, etc.). Both surface water and groundwater resources will be at risk during these construction activities from potential pollution caused by accidental spillage of fuels, lubricants, cement and wet concrete.

5.2.4.1 Water Survey Methodology

Construction of the bank protection, embankment, bank protection, and bed scour prevention for Seikgyi Khanungto, Dala, Kyimyindaing and Twante may cause impacts to the surface water in the project area during construction. The survey parameters are listed in Table 5.2-14. Ambient water quality was analyzed with the 25 parameters in totally at 6 designed sampling location.

1) Surface Water Sampling

Careful sample collection was conducted on 30th September 2018 by Alpha horizontal water sampler into the plastic and sterilized glass sample containers in strictly followed as accordance with recognized standard procedures. The parameters pH, temperature, dissolved oxygen (DO) and electrical conductivity (EC), including the odor and color in visually have been done on *in situ* analysis methods using the digital pH meter during the sampling period at each sampling site. Preservation of water samples was strictly followed according to the standard laboratory procedure by using chemicals at the freezing condition with the use of ice packs. Survey equipment, sampling containers and preservative methods were shown in Tables 5.2-9, 5.2-10 and 5.2-11.

Table 5.2-9: Field Equipment for Water Quality Survey

No.	Equipment	Manufacturer	Originate Country	Model
1	Multiparameter (water quality)	HANNA	USA	HI7609829 (with 3 sensors) 
2	SmarTROLL multi-parameter	In-situ Inc.	USA	
3	pH meter	HANNA	USA	HI 98129
4	Alpha Bottle (Water Sampler)	Wildlife Supply Company®	Indonesia	Wildco P/N-1120-G45
5	DO meter	HANNA	USA	

Table 5.2-10: Container and Preservation Method for Water Samples

No.	Parameter	Container	Volume (ml)	Preservation	Holding Time
1	BOD	PE	1,000	Cool 4±2 °C	48 Hours
2	COD	PE	500	Add H2SO4 to pH <2	28 Days
3	TSS	PE	1,000	Cool 4±2 °C	7 Days
4	TDS	PE	1,000	Cool 4±2 °C	7 Days
5	TCB	Glass	250	Cool 4±2 °C	24 Hours

6	Heavy Metals (Pb, As, Fe)	PE	1,000	Add HNO ₃ to pH <2	6 Months
7	Cyanide	PE	134	Add NaOH to pH >12	24 Hours

Table 5.2-11: Container and Preservation Method for Water Samples

No	Parameter	Container	Preservation
1	Oil and Grease	1000 ml glass bottle	Sulphuric acid, Refrigerate
2	BOD ₅ , COD	1000 ml glass bottle	Refrigerate
3	Heavy metals	1000 ml glass bottle	HNO ₃ , Refrigerate
4	Bacteria	1000 ml glass bottle (Sterilize)	Refrigerate
5	Others	2,800 ml plastic bottle	Refrigerate

2) Survey Methods and Parameters

REM team conducted surface water survey with the reliable analysis method as shown in Table 5.2-12, which were presented together with the survey parameters.

Table 5.2-12: Survey Parameters and Analysis Methods for Water Quality

No.	Item	Analysis Method	Water Quality
			Surface Water
1	Temperature	HI7609829-1 Sensor	✓
2	pH	HI7609829-1 Sensor	✓
3	Dissolved Oxygen (DO)	HI7609829-2 Sensor	✓
4	Salinity	HI7609829-2 Sensor	✓
5	Turbidity	HI7609829-4 Sensor	✓
6	Ammonium-Nitrogen	APHA-AWWA-WEF Method	✓
7	Arsenic	AAS – Graphite Hydride Method	✓
8	BOD ₅	5210B. 5 Days BOD Test	✓
9	COD	Close Reflux, Titrimetric Method	✓
10	Cadmium	APHA-AWWA-WEF Method	✓
11	Chromium (hexavalent)	AAS – Graphite Furnace Method	✓
12	Chromium (total)	AAS – Graphite Furnace Method	✓

13	Copper	AAS – Graphite Furnace Method	✓
14	Cyanide	APHA-AWWA-WEF Method	✓
15	Iron	AAS – Graphite Furnace Method	✓
16	Lead	APHA-AWWA-WEF Method	✓
17	Mercury	APHA-AWWA-WEF Method	✓
18	Nickel	APHA-AWWA-WEF Method	✓
19	Nitrate-Nitrogen	APHA-AWWA-WEF Method	✓
20	Oil & Grease	APHA-AWWA-WEF Method	✓
21	Suspended Solids	Gravimetric Method	✓
22	Total Nitrogen	APHA-AWWA-WEF Method	✓
23	Total Phosphorus	APHA-AWWA-WEF Method	✓
24	Zinc	AAS – Graphite Furnace Method	✓
25	Total Coliform	APHA-AWWA-WEF Method	✓

5.2.4.2 Sampling Locations for Surface Water Quality

The brief description of surface water point is presented in table 5.2-13. The detail of the sampling point is described as below and the points at the project site were presented in Figure 5.2-2. As shown in the figure, the surface water sampling locations covered enough for water samples of the whole project area. The coordinates and description of sampling points are as shown in the Table below.




Figure 5.2-2: Location Map of Surface Water Quality Survey

Table 5.1-13: Sampling and Survey Points of Surface Water Quality Survey

Category	Sampling Point	Coordinates	Description of Sampling Points
Surface Water	SW1	16°45'30.34"N 96° 6'39.59"E	At the Kanaungto creek
Surface Water	SW2	16°44'39.67"N 96° 3'42.63"E	Upstream of Twante cannal
Surface Water	SW3	16°45'13.55"N 96° 6'54.03"E	Midstream of Twante Canal
Surface Water	SW4	16°45'51.32"N 96° 7'40.80"E	Downstream of Twante Canal, near Yangon River
Surface Water	SW5	16°46'1.99"N 96° 8'57.90"E	Downstream of Yangon River
Surface Water	SW6	16°46'42.22"N 96° 7'4.86"E	Upstream of Yangon River

5.2.4.3 Surface Water Survey Results

Then the water samples were sent to REM-UAE Laboratory in Yangon, UAE Thailand and SGS Thailand with the proper handling and transportation methods for further laboratory analysis. The analysis results were presented in Table 5.2-14 below.

Table 5.2-14: Survey Results of Surface Water Quality

No.	Parameters	Unit	SW1	SW2	SW3	SW4	SW5	SW6	NEQG Target Value
1	Temperature	°C	27.54	27.49	29.82	27.61	30.05	31.59	-
2	pH	-	8.73	8.22	8.21	8.10	8.31	8.29	-
3	Dissolved Oxygen (DO)	mg/l	5.25	4.84	4.36	5.02	5.23	4.27	-
4	Salinity	psu	1.0	1.3	1.5	1.5	2.2	2.0	-
5	Turbidity	FNU	439	458	463	475	521	528	-
6	Ammonium- Nitrogen	mg/l	0.09	0.16	0.12	<0.02	0.09	0.10	-
7	Arsenic	mg/l	0.001	0.0021	0.0009	0.0006	ND	0.0003	-
8	BOD5	mg/l	1.5	1.7	2.5	1.6	1.7	1.4	-
9	COD	mg/l	46.1	49.2	55.5	49.2	52.3	57.1	-
10	Cadmium	mg/l	ND	ND	ND	ND	ND	ND	-
11	Chromium (hexavalent)	mg/l	ND	ND	ND	ND	ND	ND	-
12	Chromium (total)	mg/l	ND	0.025	ND	ND	ND	ND	-
13	Copper	mg/l	0.008	0.012	0.005	0.004	0.004	0.004	-
14	Cyanide	mg/l	ND	ND	ND	ND	ND	ND	-
15	Iron	mg/l	8.46	15.1	16.2	5.69	5.76	3.21	-
16	Lead	mg/l	ND	ND	ND	ND	ND	ND	-
17	Mercury	mg/l	ND	0.0002	0.0004	0.0002	0.0003	0.0002	-
18	Nickel	mg/l	0.026	0.05	0.018	0.02	0.019	0.006	-
19	Nitrate- Nitrogen	mg/l	0.09	0.06	0.09	0.07	0.07	0.09	-
20	Oil & Grease	mg/l	ND	3	4	3	ND	3	-
21	Suspended Solids	mg/l	231	27.3	366	341	309	230	-
22	Total Nitrogen	mg/l	0.56	0.61	0.67	0.59	0.63	0.41	-
23	Total Phosphorus	mg/l	0.05	0.05	0.1	0.05	0.05	0.07	-
24	Zinc	mg/l	0.014	0.028	0.009	ND	ND	0.007	-
25	Total	MPN/	>160,00	54,000	160,000	92,000	35,000	>160,00	-

	Coliform	100ml	0					0	
--	----------	-------	---	--	--	--	--	---	--

ND: Non-Detectable

Source: REM Survey, 2018 (Twante Canal Project)

There was no surface water standard in National Emission guidelines for comparative assessments.

Table 5.2-15: Impact Significance on Water Quality during Construction and Operation Phase

Source of Impact	Description: water consumption is mainly related to: <ul style="list-style-type: none"> domestic use due to the presence of the staff and construction workers; water for concrete batching; soil watering for dust mitigation and management during excavation works and construction vehicles transits and washing down and cleaning equipment at localized work sites; and fire-fighting system. Environmental Concern: Water environment is likely to contaminate by the construction and site clearance activities, wastewater discharge from workers use, piling operations for foundation and accidental oil spill from the project operations (e.g.: refueling operations). Surface and groundwater will be at residue to wastewater discharge, site preparation works and accidental spillage of fueling oils and lubricants. Groundwater may be subjected by piling operation, underground services and accidental spillage of oils and lubricants. These impacts will affect the health of those who use the canal water for drinking and general use.				
Magnitude	Insignificant	small	Moderate	High	Very High
	Rationale: Surface water is likely to receive the discharge wastewater from construction activities, like foundation and ground leveling activities. The surface water is subjected to impact as the result of rainfall on the construction unpaved areas, cement and wet concrete. Groundwater can be potentially impacted by deep piling for foundation works and accidental spillage of oils and lubricants while fueling operations.				
Duration (D)	0- 1 year	2- 5 year	6- 15 year	Life of operation	Post Closure
	Rationale: The construction phase will take about 2-5 years in proposed plan. Impacts will be temporary associated with the construction phase.				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
	Rationale: People in affected communities might occur sometimes contaminated water in downstream area of construction site for a temporary by specific activity such as trenching and piling operations which affect to those who use the canal water as their water source.				
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite
	Rationale: Surface water contamination is potentially occurred by washing of construction equipment and vehicles and sedimentation from construction activities such as soil digging, and excavation works. The impact is likely to affect the people from nearby downstream affected area during the specific construction activities and accidental spill of oils, lubricants and leakage.				
Significant Level	Magnitude (4) + Duration (2) + Extent (1) * Probability (3) = 21				Low impact (U)

5.2.4.4 Mitigation Measures for Water Quality

As discussed above, during the construction phase, the potential impacts on water resources are expected to be limited, because wastewater discharges from the construction site will be considered as a temporary event.

The potential contamination and/or erosion risks during construction phase related activities shall be mitigated by adopting good construction management practices.

Therefore, the following mitigation options shall be put in place to reduce the potential negative impacts on the water environment:

- direct runoff away from disturbed areas through temporary drainage ways, utilizing, for example, cut-off drains;
- provide containment measures for hazardous material and storage areas to prevent spills or leakage of fluid materials which may soak into the ground and reach the groundwater table;
- design of store hazardous material providing suitable reception facility with impervious flooring, roofing and suitable drainage control;
- regular maintenance and checking of all machinery and vehicles in order to minimize the risk of fuel or lubricant leakages;
- no discharge of untreated wastewater to soil and groundwater and onto surface water bodies;
- as construction activities typically generate disturbed soil, concrete fines, oils and other waste, on-site collection and settling of storm water, the prohibition of equipment washes down, and prevention of soil loss from the construction site are necessary to minimize water pollution; and
- training and equipping relevant staff in protected storage and handling practices, and rapid spill response and clean up techniques.

5.2.5 Impact Assessment on Soil

Potential impacts on soil associated to construction phase are identified and assessed in the following:

- Soil run-off during rainy seasons is another temporary impact, which would affect the surface water quality around the project area. Construction activities would also affect a part of vegetation and potentially interrupts the (inland water) traffic (and also land traffic) temporarily. Soil pollution may occur unless construction equipment is well maintained in order to prevent the illegal effluence of waste oil;
- Modification of the geomorphological condition: The construction activities at the site of interest will not cause detrimental changes in geomorphologic landforms and site setting, considering that the site is quite flat;
- Changes in geological and lithological conditions: After excavation activities and following backfilling, compaction of soil as well as mixing of construction material with natural soil, should lead to changes in the physical, mechanical and other soil properties. These modifications are in any case evaluated as negligible because of a small entity. Furthermore, the changes will not affect soil with particular archaeological or natural landscape values, therefore the possible related impacts could be considered negligible also on the historical and archaeological point of view; and


- **Pollution of soil:** Pollution could affect soil in case of accidental spillage of oil from vehicles used for transportation of construction material and accidental spillage from the building material used for construction purposes. These accidental events could be considered remote if specific maintenance activities and safety procedures will be correctly implemented. More details are provided in the following section presenting the main applicable protection and mitigation measures;
- **Changes in geological and lithological conditions:** After excavation activities and following backfilling, compaction of soil as well as mixing of construction material with natural soil, should lead to changes in the physical, mechanical and other soil properties. These modifications are in any case evaluated as negligible because of small entity;

5.2.5.1 Assessment of Baseline Soil Conditions

There are four main types of soil are found in the entire project area and southern part of Yangon Region. They are:

- Meadow & Meadow Alluvial soil
- Lateritic Soil
- Saline Swampy & Meadow Gluey Soil
- Dune Forest and Beach Sand

About 90% of these soils are composed of silt and clay, but humus content varies from place to place. These soils are favorable for paddy cultivation. The main problem, however, is poor drainage and water-logged conditions. These soils are usually found in lowlands under impeded drainage. In rainy season, they are covered with flood water. Because of the high content of clay, these soils become very dry and cracked in the dry season.



Source: Data from the Land Use Division, Myanmar 2006

Figure 5.2-3: Soil Map of Yangon Area

Table 5.2-16: Impact Significance on Soil Quality during Construction and Operation Phase

<p>Source of Impact</p>	<p>Description: The vegetation which are potentially interrupts the (inland water) traffic (and also land traffic) at the localized construction site will be cleared within the 30 m ROW along with the canal during construction phase that can cause soil run-off during the rainy season. Furthermore, the accidental waste oil effluent might be occurred while the construction equipment is not in well maintained.</p> <p>The accidental spillage of oil from vehicles used for transportation of construction material and accidental spillage from the building material used for construction purposes are also</p>
--------------------------------	---

	considered as soil contamination sources. Environmental Concern: Soil erosion during the construction phase is expected that can indirectly impact to natural archaeological and/or landscape values.				
Magnitude	Insignificant	small	Moderate	High	Very High
	Rationale: After excavation activities and following backfilling, compaction of soil as well as mixing of construction material with natural soil should lead to changes in the physical, mechanical and other soil properties, but the impact is for temporary, which cannot affect on geological and lithographical changes. Soil run-off and soil erosion interest is slightly expected during the construction activities which is unlikely to change the natural archaeological and landscape values due to the purpose of the project itself is for bank protection, bed scour prevention and flood embankment. Furthermore, the project has no correlation with the toxic and acid deposition into the soil.				
Duration (D)	0- 1 year	2- 5 year	6- 15 year	Life of operation	Post Closure
	Rationale: The construction phase will take about 2-5 years in proposed plan. Impacts will be temporary associated with the construction phase.				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
	Rationale: The impact is likely to affect only the people who are in nearby communities from the specific construction site along the Twante canal within 30 m ROW.				
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite
	Rationale: Soil run-off interest from clearance of vegetation for construction area within 30 m ROW along the canal is expected.				
Significant Level	Magnitude (2) + Duration (2) + Extent (1) * Probability (3) = 15				No impact (-)

5.2.5.2 Mitigation Measures of Impacts on Soil

With reference to the construction phase, the following environmental protection and mitigation measures will be implemented in order to reduce or prevent potential impacts on soil:

- to prevent soil contamination by oil or grease spills, leakages or releases, all manipulations of oil derivate in the process of construction and provision of fuel to the machines should be performed with maximum attention;
- leak proof containers should be used for storage and transportation of oil/grease and wash off from the oil/grease handling area shall be drained through drains and treated properly before disposal;
- construction waste and debris shall be collected on a regular basis, covered by roof and disposed of at designated landfills;
- it must be prohibited to operate with equipment and vehicles outside the designated work areas and roads; and
- training and equipment will be in place to minimize the potential environmental impact in the case of accidents (for example using spill kits).

5.3 Identification and Assessment of Impacts on Biodiversity

Work components such as development of borrow pits, leveling the site ground, and flood embankment can increase the turbidity and contamination of the Yangon River, which may obstruct photosynthesis and supply dissolved oxygen of water, which in turn will cause the decrease of the oxygen supply for swamps. A removal of the herbaceous plant and topsoil will generally cause erosion of ground surface of the earth. These impacts will be limited only within the construction sites, but cautions are needed during the watering. During the construction, fauna and flora in the project area also may be in danger due to various construction activities. However, as there are neither primeval forests, tropical rain forest, nor ecologically valuable habitats in and around the project area, the environmental impact by the quality of the water during watering may not be significant. Existence of the mangrove habitats draws particular attention. An effective management plan should be established and observed to conserve and protect them.

5.3.1 Biodiversity Survey Methodology

A series of methodologies and surveys will be conducted for the assessment of ecological impacts by the project activities.

Table 5.3-1: Ecological Survey Methodology

No.	Methodology	Reason	Area
1.	Global Positioning System	Navigate and mark coordinates at the location of all listed plant species	Within the AOI
2.	Field observation	Surveying the ground conditions	in and around the project area
3.	Plotless sampling methods	Random selection of points	within a particular survey area
4.	Desktop study	publicly available scientific publications	Investigation area the ecology and biodiversity of the project AOI
5.	Listing and Classification/ Identification of the plant and animal species	To Identify the species	Judgements by Skilled local Experts
6.	Collection of Listed Protected Areas and Forests	To assess the ecological impacts	Within the AOI
7.	Generation of fine-scale vegetation map	To identify and map the different plant	Community Present Site
8.	Walk-through-surveys	To record	across the site and all plant and animal species observed

5.3.2 Forests

The Current environmental situation of the forest cover of around Twante canal may be around 60%. Some extent of the trees was found in/around the residential area and mangrove were found along the river side. The natural vegetation grown in Twante Township were Thayet, Malaka, Peinne, Kanazo, Danyin, Padauk, Htan, Ohn, Gant-gaw, Kha-yay, Kokko, Ingyin, Magyi, Rubber, Tama, Zi, Kwel-

gaw, Shauk and Thanpaya. And the natural vegetation grows in Seikgyi and Kanaungto were Lamu, Thamae, Kanaso, Khaya and Dani.

5.3.3 Flora Species and their Habitat

Around the Twante canal area, only two major habitat types were observed namely (1) agricultural land and (2) Mangrove area and some extent of trees were found in/around the residential area. There is no intact forest around the Twante canal area. Habitat Map and sceneries of Twante canal area is shown in the following figure (Figure 5.3-1).




Figure 5.3-1: Habitat Map of the Project ROW and Indirect Impact

5.3.3.1 Description of Valued or Sensitive Ecological Habitats

Spatial distribution of rare, endangered and vulnerable species: Mangrove

Mangrove can be found in low altitude coastal and sub-coastal areas along river valleys and across watersheds. A mangrove is a tree, shrub, palm or ground fern, generally exceeding one half meter in height that normally grows above mean sea level in the intertidal zone of marine coastal environments and estuarine margins. A mangrove is also the tidal habitat comprising such trees and shrubs.


Htan (*Borassus flabellifer*)

Based on the information of IUCN organization, this species is endemic to Madagascar. The distribution is highly fragmented and based on specimens this species is known from five locations, but there are supposed sight records from other areas which require confirmation. Occurs from sea level up to 100 m. But this species can be found abundantly in Central Region of Myanmar.

Manipur Osterobrama (*Osteobrama belangeri*)

According to the spatial distribution data of IUCN organization, the range of spatial distribution of endangered species presented by IUCN organization is away from the project area. However, rivers communicate with each other so that this species can be found in this area. The extinction of this species mainly in Manipur was due to construction activities, habitat degradation and introduction invasive species which caused fragmentation. Threats to this species in Myanmar are unknown.





Source: IUCN.org

5.3.3.2 Species of Economic Value

Flora

During the field survey period of Twante canal project, five economically important plant species among 76 were collected. Among them, two merchantable hardwood species such as Pyin-ka-doe and Padauk are included in Hardwood Group 1 which is extracted from Myanmar Timber Enterprise (MTE) and the rest of species such as Dani, Wanet and Nget-pyaw in local market.

There were 76 plant species identified around the Twante canal area as listed in Table 4.6-1.

Fauna

During the field survey period of Twante canal project, 5 groups of fauna: mammals (5 species), birds (55 species), insects (27 species including 22 butterflies and 5 dragonflies), Herpet (10 species) and Fish (23 species) were identified as listed in Tables 4.6-2, 4.6-3, 4.6-4 4.6-5, 4.6-6 and 4.6-7 . Out of these, six economically important aquatic species such as Hilsa, Seabass, Pangas Catfish, Croaker, Indian salmon and Monsoon River Prawn were collected, and the rest species of fauna were not collected as economically important species.




Common Sandpiper (*Tringa hypoleucos*)



Brown Shrike (*Lanius cristatus*)



White-rump Munia (*Lonchura striata*)



Black-Capped Kingfisher (*Halcyon pileata*)



Oriental Magpie-robin (*Copsychus saularis*)



Jungle Myna (*Acridotheres fuscus*)

Figure 5.3-2: Some Bird Species Recorded in the Study Area



Common Flying Frog



Spiny-tailed House Gecko



Garden fence Lizard



Streamside Skink



Forest crested lizard

Figure 5.3-3: Some Herpet Species Recorded from Study Area



Tenuulosa ilisha



Polynemus paradiseus



Otolithoides pama



Labeo rohita



Amblypharyngodon mola



Channa orientalis

Figure 5.3-4: Some Fish Species Recorded from Study Area



Pachliopta aristolochiae (Common Rose)



Eurema andersonii (Anderson Grass Yellow)



Delias hyparete (Painted Jezebel)



Euploea core (Common Crow)



Junonia almanac (Peacock Pansy)



Junonia atlites (Grey Pansy)



Danaus genutia (Common Tiger)



Danaus melanippus (White Tiger)

Figure 5.3-5: Some Butterfly Species Recorded from Study Area



Brachythemis contaminata (Ditch Jewel)



Diplacodes trivialis (Ground Skimmer)



Orthetrum sabina (Green Marsh Hawk)



Crocothemis servilia (Scarlet Skimmer)



Neurothemis tullia (Pied Paddy Skimmer)

Figure 5.3-6: Some Dragonfly Species Recorded from Study Area

Table 5.3-2: Impact Significance on Biodiversity during Construction and Operation Phase

Source of Impact	<p>Description: Clearance of vegetation and riverbank for the construction site and ground leveling within 30 m ROW along the canal is directly impact to the surrounding biodiversity including flora and fauna species. The direct impact zone for ecological survey is considerable for 200 m of ROW. Some specific places within 30 m along the canal are slightly covered with the regional Mangrove species, shrubs and small trees which are the indicator of maintaining the coastal ecosystems by nourishing biodiversity for coastal and marine species and support the fisheries. They can also serve as a buffer zone to stabilize the coastlines and reduce soil erosion against the extreme weather such as hurricanes. The regional fauna species are also expected to face loss of their habitats due to clearance of vegetation in 30 m ROW along the canal.</p> <p>Environmental Concern: Deterioration of natural protection system for soil erosion during the construction phase is expected due to removal of vegetation and ground leveling at the construction site. Loss of habitats for regional fauna species are also the interest.</p>				
Magnitude	Insignificant	small	Moderate	High	Very High
	<p>Rationale: The vegetation clearance activity for construction area which is only 30 m ROW along the canal will be considered as the direct impact zone. The vegetation within 30 m ROW are covered small trees, shrubs and local mangrove species and there is no predatory animals within both the direct and indirect zone of ROW because the proposed area is closed to residential area.</p>				
Duration (D)	0- 1 year	2- 5 year	6- 15 year	Life of operation	Post Closure
	<p>Rationale: The construction phase will take about 2-5 years in proposed plan. Impacts will be temporary associated with the construction phase.</p>				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
	<p>Rationale: The impact is likely to affect in terms of visual contrast and aesthetics of the receiving area within 30 m ROW as the direct impact zone and 200 m for indirect impact zone.</p>				
Probability (P)	Very improbable	Improbable	Probable	Highly	Definite

				probable	
	Rationale: The vegetation clearance interest for construction area within 30 m ROW along the canal is highly expected.				
Significant Level	Magnitude (4) + Duration (2) + Extent (2) * Probability (4) = 32				Moderate impact (C)

5.3.3.3 Rehabilitation and Restoration of Mangrove Trees

Clearance of mangrove trees during construction stage is a must. Mangroves are critically important for coastal ecosystems by nourishing biodiversity for coastal and marine species and support the fisheries. They also served as a buffer zone to stabilize the coastlines and reduce soil erosion against the extreme weather such as hurricanes. Therefore, the mitigation measures for restoration of mangrove trees shall be carefully taken and cash compensation will be taken when there will be unavoidable of clearance for construction activities.

The possible tree compensation plan should be developed such as seeding the same species in nursery for re-plantation by consulting with the project proponent, DWIR, Ministry of Natural Resources and Environmental Conservation (MONREC) and the consultant adequately in terms of visual contrast and aesthetics of the receiving area at the available and suitable place in the region.

5.3.3.4 Mitigation Measures for Ecological Components

The mitigation measures should be based upon the configuration of vegetation, plantation, animals, birds, aquatic life, wild life features, bird sanctuaries, national parks, reserved forests etc., in the study area in order to assess the probable effect likely to be reflected on the existence of these features after the commissioning of the proposed project.

Mitigation measures are to be recommended for biodiversity area within the project area as:

- routine checking of trenches (if any) and escape routes;
- preservation of excavated top-soil for future site restoration procedures particularly in highly disturbed areas;
- reporting of any violation relating to hunting and trading activities;
- minimize vegetation clearance and habitat disturbance by demarcating the clearing boundaries in the construction site;
- unnecessary cleaning the trees is to avoid;
- environmental awareness training to be given to all workers for the preservation of local biodiversity species and induct the nature of the sensitivity of project area;
- site specific instruction/protocol for identifying and relocation of plant and wildlife species if necessary, shall be provided to all workers with education materials including photographs; and
- works areas in temporarily affected areas shall be reinstated with tree/shrub/ grass upon completion of the works;

- Strictly enforcement of the workers in the construction camp not to allow the fishing in the water resources near the project area;

5.4 Impact Assessment on Receiving Environmental Bodies

5.4.1 Hydrology

Hydrology would not be altered as a result of the canal improvement projects such as, Bank protection, Bed scour prevention and Flood embankment due to no change in water source, timing and quantity, and water quality in the canal.

The entire construction phase is expected to continue for 2-5 years. During the construction phase, the potential **surface water quality** impacts may arise due to **contamination of domestic wastewater discharge from construction camp and washing of construction equipment and vehicles and sedimentation** from construction activities such as soil digging, and excavation works. However, it will benefit water quality because bank protection will be protected soil erosion during the project operation phase.

The current hydrological stations, Pyay station and Maubin station, located in the region and Maubin station is nearer to the project area.




Figure 5.4-1: Location Map of Hydrological Stations

5.4.2 Geology and Soil

Soil run-off during rainy seasons is another temporary impact, which would affect the surface water quality around the project area. Construction activities would also affect a part of **vegetation and potentially interrupts the (inland water) traffic (and also land traffic) temporarily**.

There will be no change in geology and soil by the project activity because the proposed project activities will be implemented in the existing canal and right-of-way and it can even protect the soil run-off impacts by Bank protection, Bed scour prevention and Flood embankment.

5.4.3 Land Use

The land use of the project area is mainly urban, farmland and canal. A little portion along the Yangon River also include plantation area. Out of the total ≈ 92 ha of the area that is to be affected, the urban area accounts for ≈ 35 % (about 30.2 ha), farmland ≈ 55 % (about 50.44 ha) and canal land 9 % (about 8.57 ha). Canal land is the area under the administration and ownership of the DWIR in accordance with the Canal Act in 1905.

For the demarcation of canal, Section 1 of said law described that the canals include all canals, channels and reservoirs constructed, maintained or controlled by the Government for the supply or storage of water. Normally, the projects are used to demarcate 30 m ROW from the project area as a standard provision.


Table 5.4-1: Affected Land Area in Project 30 m ROW

Township	CN/ DWIR Land (Ha)	Farmland (Ha)	Urban Private/Public Land (Ha)	Shipyard (Ha)	MPA Land (Ha)	Total Land (Ha)
Dala	2.13027	0.555857	2.845527	0.004181	0.046452	5.582287
Twente	4.1529	47.4568	8.79360	-	-	60.4033
Seikgyi Kanaungto	2.289995	2.428114	16.960467	1.40313	0.838217	23.919923
Kyimyindaing	-	-	1.583	0.0068	-	1.5898
Total	8.573165	50.440771	30.182594	1.414111	0.884669	91.49531

Ocular inspections indicate that canal land area has a number of residential and economic structures (huts, houses and storages etc.) as well as farming land. It was found that there are a number of registered and unregistered residences and economic structures located. The scale of the unregistered (thus informal) settlers are estimated to be appeared within the entire direct social impact boundary. A large portion of them is found to be residing and farming in the canal land area. Informal settlers would need to be entitled to compensation for their loss of investments (movable and immovable assets invested by themselves, such as crops, fruit and commercial trees, residential and other types of structures).

In June 2018 YRG has announced the 2040 Greater Yangon Strategic Urban Development Plan (SUDP). SUDP designates Twante Township, Seikgyi Kanaungto Township and Dala Township as Phase 1 development focus area (largely due to the geographical proximity to the CBD in downtown Yangon). Being in a preliminary stage of planning, it is likely that the three affected Townships along the Twante Canal will witness rapid industrialization and urbanization over time, which will increase

the portion of the urban area along the Canal in due course of time. Rapid urbanization along Twante Canal could be partly spurred by the proposed project itself, with booster effects of the inland transport activities (including river tourism) by improving the stability and volume of the inland water transportation. In any case, the proposed project would be one of the contributing factors for the region's urbanization and industrialization but not the sole major factor.



Source: Land Use map and data of Survey Department. (2006)

Figure 5.4-2: Land Use Map for the Project Area and the Area Round

Flood embankment work and access road building may affect land use and economic activities around the construction sites. Temporary disturbance of the economic and livelihood activities along the construction site would occur during the construction period. However, the spatial scopes of the construction area would be linear, locally contained in a limited scale and only temporary during the construction. Thus, economic activities (such as inland water transport business (mini boat buses, taxis) and fishing) would not be significantly affected. Shipyard operations along the construction site in Kanaungto Section would be minimized as the ROW for the land clearing will be drawn in a way not to trespass the structures and buildings in the existent shipyards. However, there may also be temporary disruption of the shipyard operations in case the pier for the vessel's entry need to be temporarily or permanently blocked or relocated due to the project implementation.

One way to minimize the impacts as such would be sequentially sectioning the construction sites in small scale so that the affected individuals could resort to the adjacent area as an alternative resort for their activities during construction.

5.4.4 Wildlife

The proposed canal improvement project is located near the residential area all along the canal and there is no effect on wildlife resources, apart from listed endangered plant and fish species in the region.

5.4.5 Recreation

Twante canal has regular tourist ferry operation for visitors and tourists to the mangroves and swamp areas in the Twante Township (at least twice a day during the weekdays). The construction related to the project, however, is not expected to directly affect the ferry operations as the projection site and the ROWs are not overlapping with the boarding and land spots of the ferries. The proposed project area had no designed recreation areas either. Notwithstanding this, the construction work may hamper the overall canal landscape for the ferry tourists, but the impacts would be locally contained and temporary. In the longer term, the improved embankment facilities with better inland water transport safety are expected to improve the landscape while enhancing the capacity of overall recreational activities along the canal.

5.4.5.1 Protected Areas

The nearest Protected Area to the Project is the Hlawga Wildlife Park located to the north of Yangon city. Other protected areas include Kandawgyi Park, Inya Lake.

5.4.5.2 Hlawga Wildlife Park

The nearest National Park of the proposed project site is the Hlawga National Park. It is also known as Hlawga Wildlife Park. The Hlawga Wildlife Park with an area of 1542 acres (624 ha) has a fenced core area of 808 acres (327 ha). It is situated in Mingaladon Township of Yangon Division, northern part of Yangon City. The eastern part of the park is bordered by the Yangon Pyay road, the southern part by Hlawga forest reserve, the western part by paddy fields and the northern part by Pe-Nwe-Gone Village.

The Hlawga Wildlife Park has key environmental resources such as Eld's Deer, Sambar Deer, Barking Deer, Hog Deer and migratory birds. The habitat's characteristic is the combination of evergreen forest (typical), Mixed deciduous forest (lower) and swamp forest. It is around 20 km distance from project areas and located upper Yangon River. It is unlikely that the Park biophysical environment would be affected by the implementation of the Proposed Project.

5.4.5.3 Urban Greenery Areas

The urban greenery areas include parks and garden areas of Yangon city. Parks and gardens are covered with natural and man-made vegetation. The commonly known greenery areas are Kandawgyi Lake Garden and Inya Lake greenery area. Inya Lake and Kandawgyi Lake Garden are of 37 acres (15 ha) and 150 acres (61 ha) in total land size respectively. Kandawgyi Lake Garden is about 4736 m distant from the project site and Inya Lake for 7202 m distant from the nearest construction site at "0" mile. Both areas are outside the spatial boundary of biophysical impacts of the proposed improvement of Twante Canal project.




Figure 5.4-3: Location of Distance of Enlisted Urban Greenery Area in Yangon City from the Project Site




Figure: 5.4-4: Location of the Inya Lake

5.4.6 Landscape

As the proposed project aims to maintain and improve the Twante canal, the overall landscape of the canal would remain unchanged by the project implementation. However, the light color and design appearance of some control and maintenance infrastructures would need to be planned in order not to disrupt the existing public scenery views.

5.4.7 Cultural Resources

According to the Protection and Preservation of Cultural Heritage Regions Law of Myanmar (1998, amended on 20th January 2009) which is to protect and preserve the cultural heritage regions and the cultural heritage therein so as not to deteriorate due to natural disaster or man-made destruction and to protect the cultural heritage regions from destruction. The article 21 (c) prescribes that the proponent shall request the prior permission from the Department to carry out building road, constructing bridge, irrigation canal, embankment or extending the same and the article 23 of the said law described that “No person shall plough and cultivate or carry out any activity which may cause damage to the cultural heritage within the boundary notified by the Department in the cultural heritage region.

In addition, the Ministry of Culture prescribes the screening procedure of the cultural heritages in case any development project is prepared: A project proponent is required to screen the areas 90 feet (27.4 meter) radius from the limit of the construction sites, according to Annex (a): the general provisions for the cultural heritage region, the Protection and Preservation of Cultural Heritage Regions Rules (2011).

YDCD enlists and manages the culturally valuable sites and assets in Yangon Region by registering them in the Yangon City Heritage List. As of 2010, there are 204 items are on this list including a range of religious and historic sites and structures in about 20 townships. As of 20 townships in the list, only the affected Kyimyindaing township is included and there was no established area of religious and historic sites and structures for Twante, Dala and Kanaungto Township.

The list includes total 3 sites in Kyimyindaing Township, whose list are shown in the tables below:

Table 5.4-1. Cultural Sites/Structures in Kyimyindaing Township enlisted in the Yangon City Heritage List (as of 2010)

Items	Distance from the Project site (km)
Ohnbindan Sunni Jamahh Mosque	4.38
St. Michael’s Church	4.71
Salin Monastery Ordination Hall	4.85



Figure 5.4-5: Location of the Yangon City Heritages near the Project Sites

The proposed project will be implemented with the 30 m ROW of Twante Canal. No cultural buildings and monuments enlisted on the Yangon City Heritage List were found in the four affected Townships within the range of 90 feet from the limit of the construction site.

In addition, there is no registered UNESCO World Heritage Site in Yangon Region.

In case of chance-find during construction and operation, the following measures would need to be taken. (See the Box below.) The required procedural measures for chance-find will be included in ESMP.

Box.5.1: Standard Provisions for New Cultural Heritage Finding

According to the IFC (chance find procedure⁵) and reference⁶, standard provisions in construction contracts in this specific project foresee the following steps in case of chance finds:

- to interrupt the construction activities in the chance, find;
- to delineate the discovered site or area;
- to secure the site to prevent any damage or loss of removable objects;
- to notify the supervisory Engineer who in turn will notify the responsible local authorities;
- responsible local authorities and the relevant Ministry would be in charge of protecting and preserving the site before deciding on subsequent appropriate procedures;
- decisions on how to handle the finding shall be taken by the responsible authorities and the relevant Ministry (this could include changes in the layout, conservation, restoration and salvage);
- implementation for the authority decision concerning the management of the finding shall be communicated by the relevant Ministry;
- Could resume the construction work after the closed-out of the issue and only after permission is given from the responsible local authorities and the relevant Ministry concerning safeguard of the heritage.

5.4.8 Impact Assessment on Solid Wastes

Various types of construction solid wastes are likely to occur during the implementation stage of the project construction as the followings;

1) Non-hazardous Wastes

- Concretes, Bricks, Tiles and Ceramics
- Wood, Glass and Plastics (All plastic resin waste including, processed waste, packing materials, and plastic resin sludge including PVC)
- Metallic Wastes: Copper, Iron, Steel, Tin, Brass, Bronze, Lead, Cable and Metals
- Soil, Contaminated soils, stones and dredging spoils
- Gypsum
- Cardboard Containers
- Textiles: clothes, rags
- Bulky items

2) Hazardous Wastes

- Insulation containing asbestos
- Fiberglass
- FRP
- Unused/Unset Cement
- Paints and Varnishes
- Organic solvents
- Adhesive/Sealant container
- Rubber: tires

⁵ https://www.ifc.org/wps/wcm/connect/39e39000498007fda1fff3336b93d75f/Updated_GN8-2012.pdf?MOD=AJPERES

⁶ <https://www.mpwt.gov.la/attachments/article/1896/ANNEX%209-Chance%20Find%20Procedures.pdf>

3) Office Wastes

- Papers (single used and others)
- Used Pens
- Cardboard
- Residual Ink

4) Composting Wastes

- Food wastes: Human or animal wastes from processing or overruns

(5) Others

- Oils and grease
- Domestic wastes

Note: Every non-hazardous waste could be turned into hazardous when contaminated with hazardous wastes in alone or mixture.

5.4.8.1 Mitigation Measures for Solid Wastes

The overall impacts during operation should be considered as negligible if the following mitigation measures will be considered during the operation phase:

- a waste management plan shall be developed including requirements for source separation, collection with the adequate solid waste containers, handling and disposal of all waste generated;
- The containers shall be labeled or separated by colors: red for hazardous wastes, yellow for office wastes, green for organic and composting wastes;
- all hazardous materials shall be stored in clearly and specially labeled containers;
- storage and handling of hazardous materials should be in accordance with national and local regulations appropriate to their hazard characteristics;
- waste shall be separated on site and waste storage areas shall be roofed and bounded to prevent potential cross-contamination;
- spent oils (including transformer oil) shall be recycled;
- fire prevention systems and secondary containment shall be provided for storage facilities, where necessary, to prevent fires or releases of hazardous materials;
- all waste shall be disposed of in line with local requirements at a suitable and licensed waste disposal facility; and
- suitable disposal sites shall be identified with capacities for disposal for general and hazardous waste prior to the operation phase.

1) Waste Minimization

The minimization of the amount of waste produced during the construction should be reached by carefully selecting materials and avoiding over-ordering and will be performed carefully selecting materials and avoiding over-ordering. Regardless of whether the solid waste is recycled or sent to a transfer company for disposal, the chosen facility will be contacted prior to initiation of construction activities so that scheduling and other details can be arranged.

2) Source Separation at Collection Origins

The solid waste generated during the construction phase of the Project will either be recycled or sent to a transfer facility for subsequent disposal. Solid waste, addressed to be recycled and reused, needs to be source separated during the construction activities. The most efficient way to accomplish this separation is to make recycling containers available to all construction personnel (i.e. place such containers at all parts of the jobsite where work with recyclable materials is likely to occur) and make separation of materials mandatory for all workers.

3) Reuse and Recycling

If possible, a range of materials will be donated or sold for reuse and recycling in the local community and/or regionally. Furthermore, in case of hazardous one (such as lead acid batteries) the recycling process will be undertaken in an appropriate way to avoid H&S and environmental issues.

Concerning re-use, some of the more inert waste, such as motor, concrete, etc. can be reused for example in the construction of access roads, hard standings or car parks. Furthermore, it may be possible to sell or hand out some excess materials (wood or metals) to be reused or recycled in the local communities.

4) Waste Collection and Management

A commercial carter will continue to pick up the municipal solid waste generated during the construction activities from the working site where it will be taken to transfer stations for eventual transport to landfills.

In any case, taking into account the proposed measures to ensure proper handling and disposal of generated solid waste, and if all the potentially hazardous waste is disposed of correctly and the additional waste deposited at the local dumpsites can be reduced to the absolute minimum, the residual impact associated with waste generated during the construction phase should be of low significance and of a short-term duration.

5.5 Impact Assessment on Climate Change

Any of the proposed project activities has no correlation with the greenhouse gas emission in massive density except the emission generated from the access road construction and some energy used construction activities, however, the impact can be considered as neutral due to temporary and relatively small amount of emission generation which can be recovered within the project construction phase and the generated emissions will no longer relate with the greenhouse gases which can cause climate change impact during the operation period.

However, the project itself would even improve the flood prevention function along the canal by conserving water from bank protection, bed scour prevention and flood embankment activities which rather help to mitigate the climate change impacts such as flood related disasters along the canal.

5.6 Impact Assessment on Socioeconomic Components

A large scale of land acquisition and potential involuntary relocation are expected to occur during pre-construction (preparation) and construction stage. Direct and indirect social impacts including land

acquisition and involuntary resettlement, income and livelihood improvements, safer living environments during flood seasons and less inland water transport safety accidents, will occur mainly during and after the construction (i.e. operation) stage both in positive and negative manner.

5.6.1 Impacts on Land and Tangible Properties

With the current setting of the construction design and ROW, acquisition of the land and associated properties (such as buildings, structures, crops, trees and other economic and social investments) for construction work either permanently and temporarily are expected to occur in a sizable scale. Right-of-ways (ROWs) of the embankment and other canal improvement works are designated to be as follows:

- ③ **Area 1:** ROW in Twante Section and Dala Section- Areas along, adjacent to Twante Canal, within 30 meter from the limit of the construction site (canal improvement and embankments)




Figure 5.6-1: Project Land Impact Areas
(Source: REM Survey (Twente Project, 2018))

- ④ **Area 2:** ROW in Seikyi-Kanaungto Section- ROW will be drawn outskirts from the limits of the shipyard area inward to the landside, not cross-cutting the existent facilities. The exact alignment of the ROWs is currently in planning by the Project Proponent. Consultations and negotiations with the affected community, particularly the shipyard business operators were carried out to assess their views on this issue on 24th December 2018 (For more details, please see the Chapter 8 of this EIA report and Appendix 8-3.). In-determination of the ROW in Area 2 remains to be the limitations of this EIA: It is not possible at this point to assess the exact scale of direct social impacts until the ROW is finalized in this area.
- ⑤ **Area 3:** ROW in Yangon River section of the project site (including Kanungto, Dala, and Kyimyindaing Section) : Management of the Yangon River is administered by the authority of the Myanmar Port Authority (MPA). ROW in this area will be tentatively drawn to 30meter from the limit of the construction site of embankments (as in the Area 1).

According to land confirmation survey, there are 6 ward/village in Twante, 6 wards in Dala, 9 ward/village in SeikgyiKanaungto and 3 wards in Kyimyindaing which are to be affected by the project implementation.

Township	Affected Ward/Village
Twante	<ol style="list-style-type: none"> 1. PyawBwelay 2. Paikswal 3. Tharsi 4. Satsam 5. Pathein 6. Kalar Tan
Dala	<ol style="list-style-type: none"> 1. Kyaung Su 2. Tar Gyi 3. Sarbarchaung 4. Hmawset 5. Kamarkasit 6. Settmyay
Seikgyi Kanaungto	<ol style="list-style-type: none"> 1. Seikgyi East 2. Seikgyi West 3. Kanaungto East 4. Kanaungto West 5. ThakhinBaThaung 6. AuTunAoe 7. PanPinChaung 8. SamarDuWar 9. ChaungWineLay
Kyimyindaing	<ol style="list-style-type: none"> 1. Seik Kyi 2. U Myar 3. Nga Zin




Figure 5.6-3: Affected Structure and Land within the ROW in the Entire Project Area (Blue lines: ROW Boundary & Black Dots: Locations of the Structures)
 (Source: REM Survey (Twente Project, 2018))



Figure 5.6-4: Affected Structure and Land within the ROW at the Yangon River-Twante Canal junction and from Point 0 mile to Point 3.5 mile (Blue lines: ROW boundary & Red dots: Locations of the Structures)
 (Source: REM Survey (Twente Project, 2018))



Following table shows the results of the counting of the affected households, the number of the structure and land ownership type by township. In total, as many as 2,697 households are found to be

affected in the four affected townships with 2,028 structures (including residential and economic buildings and structures)⁷ in about 120 hectare in total are expected to be affected.

Table 5.6-1: Affected Households, Structures and Landowners within the Project's 30 m ROW

No.	Township	Households (PAFs)	Structures	Land Owners
1.	Twente	479	203	276
2.	Dala	646	490	156
3.	Seikkyi Kanaungto	1,220	1,034	186
4.	Kyimyindaing	352	301	51
	Total	2,697	2,028	669

According to the findings, Seikgyi-Kanaungto Township has a highest number of affected households, structures, with the biggest portion of the land subject to land acquisition. The least affected in terms of the scale of the land acquisition and relocation impact is Twante Township. In total about 25% of the affected households are landowners, who are entitled to the land compensation. The rest 75% of 1,592 households are either registered sentence or informal settlers.

5.6.2 Disturbance of Shipyard business operations in SeikgyiKanaungto Section

As of May 2015, there were 29 officially registered shipyards located along the Twante canal in Seikgyi-Kanaungto Township (DWIR Data 2015-2016). Confirmation of the total number of the affected shipyards would need to be made in the future. The shipyard facilities in Kanaungto Township have been established since the 1960s and serve to build, repair and disintegrate the vessels for inland water transportation. The assessment based on the field study during the ESIA exercise indicates that there are about 40 registered shipyards are being operated, out of which 32 shipyards are owned and run by private owners and the 8 shipyards by MPA as of Dec 2018. On the average one shipyard company is hiring about 10 employees based on a daily labor basis (with 12,000~15,000 kyat (about 80~ 100 USD) for a daily wage).

Although the shipyard operations are recognized *de facto* by the Myanmar government, *de jure* recognition is not clear: According to the Kanaunto Shipyard Association, an interest group of the shipyard business owners and operators, the Association has been paying the "fees" to the Myanmar government according to the Canal Act [BURMA ACT II. 1905]. With the new civilian government taking the power in 2015, they stopped paying the fees. It is found that formal licenses have not been issued to the shipyard owners.

While the official mandate for the canal management for inland water transport lies with the DWIR, the Shipyard Association claimed that regular canal maintenance (such as regular sedimentation clearing through dredging etc.) have been carried out by the shipyard operators themselves on their costs⁸.

⁷ Some households may be affected only in their land, but not their structures. That's why number of the affected households are higher than that of the affected structures.

⁸ Findings are based on the FGD meeting with the Kanaungto shipyard community on 24 December 2018.

According to the land confirmation survey as of May 2015, the large portion of the areas (1.1286 ha with 29 shipyards) where the shipyard facilities are located belongs to the category of canal land under the DWIR ownership.

Typical structure of the shipyard facilities includes a machine shop, a pipe and boiler shop, warehouse plate, carpenter shop and slipways⁹. The shipyards in Kanagunto Section are relative of a small scale (with 1.1286 ha occupancy on the average) which deals with the small and medium size vessels. It was observed that in Twante canal area, painting and repairing of the vessels are often done at the slipway or dry dock in open air. (See the pictures below.)



Figure 5.6-7: Images of Shipyard Operations in Dala Township (source: alamy stock photo, www.alamy.com)

The size and structures of each of the shipyards are shown in the following table:

Table 5.6-2 List of Shipyards in Affected Areas (SeikgyiKhanaungto Section)

No.	Location (Ward/Township)	Size (ha)
1	SeikgyiKanaungto	0.0248
2	SeikgyiKanaungto	0.0248
3	SeikgyiKanaungto	0.0414
4	SeikgyiKanaungto	0.0248
5	SeikgyiKanaungto	0.0248
6	SeikgyiKanaungto	0.0248
7	SeikgyiKanaungto	0.0248
8	SeikgyiKanaungto	0.0248
9	SeikgyiKanaungto	0.0248
10	SeikgyiKanaungto	0.0644
11	SeikgyiKanaungto	0.0248
12	SeikgyiKanaungto	0.0248
13	SeikgyiKanaungto	0.0644

⁹An Interesting Study of Capacity Improvement of a Shipyard in Myanmar, ResearchGate, 2017
(https://www.researchgate.net/publication/317698559_An_Interesting_Study_of_Capacity_Improvement_of_a_Shipyard_in_Myanmar)

14	SeikgyiKanaungto	0.0248
15	SeikgyiKanaungto	0.0414
16	SeikgyiKanaungto	0.0414
17	SeikgyiKanaungto	0.0414
18	SeikgyiKanaungto	0.0248
19	SeikgyiKanaungto	0.0248
20	SeikgyiKanaungto	0.0414
21	SeikgyiKanaungto	0.0368
22	SeikgyiKanaungto	0.248
23	SeikgyiKanaungto	0.0248
24	SeikgyiKanaungto	0.0248
25	SeikgyiKanaungto	0.0248
26	SeikgyiKanaungto	0.0248
27	SeikgyiKanaungto	0.0248
28	SeikgyiKanaungto	0.0248
29	SeikgyiKanaungto	0.0368
	Total	1.1286

(Source: DWIR Data 2015-2016)

Concerns have been raised during FGD and public consultations sessions regarding potential disturbance of the shipyard operations by the project implementation. Currently, DWIR holds a position that the shipyard facilities would not be disturbed, and their business operations should be able to continue during construction without stoppage, as ROW for the construction would not be drawn to dissect the shipyard areas. However, until now DWIR has not determined the exact demarcation of the ROW in Kanaungto Section.

From technical point of view, several issues need to be addressed in drawing the ROW in SeikgyiKanaungto Township:

First, management of slipways (wet docks): Each shipyard has an open gateway to the canal for the vessels' entry to the yard. It is not clear at this point how the project will manage to let this slipway intact, while ensuring the embankment facilities. Leaving all the 40 slipways open and intact would mean the embankment would not be continuous but would need to have some gaps and intervals. It is not technically clear at this point, how the embankment would effectively serve its purpose with all the spillways being left open and unaddressed.

Second, if the embankment is designed to be located behind the shipyard facilities, the shipyard operation would continue to be subject to the continuous inundation from the regular flooding¹⁰. Considering the shipyard operation constitutes a large portion of residents and functions as a major

¹⁰ Sedimentation is another problem the shipyard operators are suffering. During the FGD with the Kanaungto Shipyard community on 24 Dec 2018, the participants reported that the regular sedimentation effects virtually make it almost impossible to run the business as the depth of the water becomes too shallow for the vessel to move in and that the shipyard operators are dredging every year to clear the waterway in and around their sites.

business sector in Kanaungto Township, excluding them from the beneficiary group means a significant size of the beneficiary segments are to be excluded from the project's benefits.

A more integrated approach of the creek's shipyard issues into the overall regional development plan (such as SUDP) for longer-term sustainable development purpose would be desirable.

5.6.3 Loss of Income and Business Opportunities

Another group to be affected by the project implementation include those whose source of income and livelihood are significantly dependent upon the Twante Canal and the adjacent land to the canal subject to acquisition. This includes, among others, owners of crops and fruit (and other commercial) trees, agricultural workers (sharecroppers and sustenance farmers), people running small boat crossing enterprises (mini boat bus and taxis) and their employees, etc.

First of all, it is reported that most of 120 ha of the affected land are farming land (mostly rice and small farming). Owners of crops and fruit (and other commercial) trees and other resources that are attached to the land that is to be taken for construction and ROW, would need to be compensated based on the replacement cost principle (which includes both the current market price of the assets and the transaction costs). Agricultural workers based on labor contract, be it sharecroppers with or without any written (legal) contractual documents, whose livelihood is predominantly dependent upon the sharecropping on the affected land, are likely to lose their means of livelihood, constituting the primary vulnerable group of the proposed project. During the detailed measurement study (DMS), the project proponent would need to count the number of the sharecropping households on the affected land, provide disturbance allowances to minimize the negative impacts upon the group. Compensation should be made in compliance with the relevant laws and regulations in Myanmar and the EDCF Safeguard Policy and other internationally recognized safeguard policies (such as WB ESF ESS 5 and ADB SPS(2009)).

Small boat business community include small boat owners, boat mini-bus and taxi operators and their employees (staff onboard, ticket-office clerk, etc.) along the canal and Yangon river (project area). According to information source from DWIR, a number of boat taxis and boat mini-buses are being operated a day along the Twante Canal, catering about a huge number of passengers a day. Currently, there are about 15 boat bus and taxi stops along the Yangon river and the Canal (project area).

Table 5.6-3: Inland Water Transport Services Routes in Myanmar¹¹

Sr. No.	Division/Route	Schedule
1.	Yangon – Dala	Daily (46) trips
2.	Wadan – Dala	Daily (19) trips & 9 trips on Sundays
3.	Yangon – Kanaungto	Daily (8) trips & 6 trip on Sundays
4.	Sintohtan – Sarparchaung	Suspended
5.	Wadan – Saikgyi	Suspended

While commercial fishing is not officially allowed in the Yangon River and Twante Canal, it is

¹¹<https://dlca.logcluster.org/display/public/DLCA/2.5+Myanmar+Waterways+Assessment;jsessionid=65544D60369D1146343AFBD789B97D16>

reported that about several hundred people are still practicing fishing in the river and the canal¹². In effect, fishing practice is condoned by the authority and a significant number of households are making a living partially, if not entirely, from fishing. There is no existent data on the actual scale of the fishing community in Yangon River or Twante canal.

This project is, however, unlikely to make significant impacts on the fishing community as the construction work is largely focused on the canal side, not the canal itself. Fishing is a mobile activity, in bed scouring area, fishermen could simply move to alternative location for fishing as the fish swam would also alter their movement tracks away from the construction site.

During the focused group discussion (FGD) with farmers on 24th December 2018, it was also found that some farming lands are using the river and canal water for irrigation through pumping and piping. In case their waterway is temporary/permanent blocked due to the construction work, alternative channel and water way would need to be provided by the project proponent/contractor to ensure continued farming activities.


Negative impacts on their income and business opportunities, however, are judged to be locally contained and temporary. One way to minimize the disturbance due to the construction is to sequentially section out area by area for construction work. In this way, those whose passage to the river is blocked by construction, could make avail of alternative passages during construction. The project proponent may need to arrange for alternative route to access the canal, in case any pier or boat bus/taxi stops are to be closed due to construction work.

5.6.4 Safety and Stability of Inland Water Transport

Positive social impacts would be mainly enhanced safety and stability of inland water transport along the Twante Canal area. Safety accidents due to rapid flows at some points of the canal would be reduced and the flood-related disasters and accidents would be mitigated. Enhanced safety of the inland water transport in Twante Canal will primarily benefit the regular/frequent users of the inland water transportation such as commuters crossing the canal on regular basis as well as the inland transport operators. In principle, all the users of the inland water transport in the canal will be beneficiaries. Population living along the canal have been most vulnerable to the damages and disasters related to the regular flooding in the canal. The vulnerability to the disaster is expected to be reduced to a certain extent.

During the last 14 years, from 2004 to 2018, the number of 34 accidents in total were recorded within the project region, especially Twante canal and Kanaungto creek area. According to the records, there was no occurrence of an accident in 2013 and 2014. Accidents most commonly include the collides between the vehicles during operation or with, the anchored vehicles in the middle of water and sometimes with the bollard at the jetty. Sometimes the accidents are caused by weak strength of water vehicles which can make seeping of the water into the vehicles while anchoring at the berth or sometimes by anchoring for a long time. and then sank underwater. Other types of accidents involve overloading of the goods on the ships. Also, one fire accident was recorded in one shipyard in Kanaungto creek in 2008.

¹² The finding is based on an interview of a local resident in Dala in January 2018.



<Map 1: Transportation Map along Twente Canal>

The following table shows the records of accident of shipwreck and other inland water transport accident in Twante Canal in the last 14 years:

Table 5.6-4: Records of the Inland Water Transport Accidents from 2004 to 2018 in the Project Area

No.	Year	Accident /Location	Human Casualties (Number)
1	2004	Twante Canal (Near 1.0 mile)	None
2		Twante canal (at the point of A Kauk Sa Khan)	2 Lost
3	2005	Twante Canal (4 mile)	None
4		Twante Canal (3.25 mile, Lat Pan Gone Village)	None
5	2006	Twante Canal (Above 7 mile)	None
6		Twante Canal (3.75 mile)	None
7		Twante Canal (3.5 mile)	None
8		Kanaungto Creek	None

9		Twante Canal (Near 11 mile)	None
10		Twante Canal (Lat Pan Gone Village)	None
11	2007	Twante Canal (12 mile)	None
12		Twante Canal (0 mile)	2
13		Twante Canal (between 19.5 mile and 20 mile)	10
14		Twante Canal (4.5 mile)	None
15		Twante Canal (3.5 mile)	1+ 2 Lost
16		Twante Canal (14.5 mile)	None
17	2008	Twante Canal (4.5 mile)	None
18		Kanaungto Creek (Tha-nin-thar-ri shipyard)	None
19		Twante Canal (3.25 mile)	None
20		Twante Canal (3.5 mile, Lat Pan Gone, A Kauk Sa Khan)	None
21	2009	Twante Canal	None
22		Twante Canal (Near 5 mile)	None
23		Twante Canal (12.5 mile)	None
24		Twante Canal	4
25		Twante Canal (0.5 mile)	None
26	2010	Twante Canal (21 mile)	1 + 3 Lost
27	2011	Twante Canal (10.5 mile)	None
28	2012	Twante Canal (4 mile)	1
29		Kanaungto Creek	None
30		Junction of Twante Canal and Toe River	1 Lost
31	2013	Twante Canal (Near 9.5 mile)	None
32	2016	Twante Canal (4 mile)	None
33		Kanaungto Creek	None
34	2018	Kanaungto Creek	None

(Source: Directorate of Water Resources and Improvement of River Systems-DWIR)

According to GAD officer during a consultation meeting, although the annual floods usually take place along with the Twente canal, there were no records of human casualties and asset loss during the floods, except the flood in 2018, which lasted for about one week. Some volunteers and officers had to provide food and other secure materials to the affected households along the canal. With the climate change impacts, more extreme level of the flood may occur irregularly in the future.

Once the construction of the proposed project is complete, the loss of lives and property damages is expected to be reduced related to the inundation and flooding due to the instability of the water flow and low level of resilience to the flood-related disasters in Twante Canal and adjunct area in Yangon River.

5.6.5 Long-term Income and Livelihood Enhancement and General Improvement of Living Condition (including Traffic, Health and Sanitation Conditions etc.)

About 100-200 jobs are expected to be created related to the construction work of the project. Local job creations, although of temporary nature (the construction period being 5 years), would boost local economy together with the associate business creations (e.g. amenity facilities such as shops and restaurants to cater the construction workers).

It is not clear at this point if a mere the enhancement of safety and stability of the inland water facilities in the canal would sufficiently lead to boosting eco-tourism. While frequent safety accidents could be a discouraging factor of river tourism, the additional investment would be required to revamp the eco-tourism in the region. In combination with such initiative, this project could synergize the river tourism industry. Likewise, the proposed project could be a contributing factor for longer-term regional development and improvement of livelihood of the communities when combined with a set of the regional development plan, such as SUDP.

5.6.6 Evaluation of the Impacts

Different social and economic impacts have a different level of magnitude, duration, and extent respectively. To summarize, major negative social impacts by the proposed project are as follows:

1) **Land acquisition and involuntary resettlement:** About 92 hectares of land (including both public and privately-owned) will be acquired for construction work of the project (access building is not included; the additional plot of land would be claimed for this.) Based on the land confirmation survey, it is estimated that 2,697 households (out of which 699 households with land ownership) with 2,028 structures in about 120- ha will be affected due to land clearing (of ROW and construction side) along the canal and Yangon riverside in the four affected Townships, namely Twante, Seikyi-Kanaungto, Dala and Kyimyindaing. The scale of the impacts would need to be updated and confirmed in the future upon the finalization of the detailed engineering design (DED). 2) **Disturbance of canal and river-based business operations, permanent and temporary loss of incomes:** Business and economic activities based on Twante Canal and the Yangon River include shipyard operations, small boat mass transport services (mini boat buses and taxis), as well as fishing and river/canal water-irrigated farming. About half of 120 total affected land areas that are to be affected is found to be agricultural/farming land. About 40 shipyard operations were identified along the canal in Seikgyi-Kanaungto section. Out of them, 8 shipyards are owned by the MPA and the rest (32 shipyards) are owned by private individuals. While DWIR intends to adjust the project design and reduce the ROW area, the feasibility of such an option would need to be assessed and confirmed technically and financially. At this point, this study assumes the 30 m ROW criteria unanimously for the impact assessment.

The mini-bus/taxi stops were identified to be located for boat operations (a mini boat bus cruises the itinerary along the canal within the construction site and ROW (at Point 0 mile and Point 7 mile along the Twante canal). Relocation of the existent quays is necessary, and the project proponent is recommended identifying most suitable locations nearby the original location(s) so that the

passengers' inconveniences are minimized. If the relocations of the mini boat bus/taxi are required only temporary (during construction), the project would need to include a plan to restore the original site once the construction is complete. It is recommended that the alternative site selection be decided based on extensive consultations of the passengers, local community and their representatives and this process need to be properly documented.

In addition to land acquisition, business disturbances, whether shipyard operations, boat transport operations, fishing or farming, would need to be duly compensated by the project proponents.

Socio-economic survey and consultation meetings found that almost 50 % of residents in the affected area have their artesian wells for drinking purpose and the others use commercially manufactured drinking water. It is found that that canal water is not the main source for drinking in this region.

Following tables are the results of the significance analysis of each of the major social impacts identified:

Table 5.6-5: Impact Significance on Land Acquisition and Involuntary Resettlement

Source of Impact	Description: The proposed project is likely to change the land use pattern in the project area permanently. Scalable size of loss of lands, crops and houses and structures within the canal area are expected due to the requirement of land for the construction site (30 m ROW) during the construction phase. Social Concern: The impact is likely to lead involuntary resettlement of the land and structure owners, residents and those who farm such lands (including sharecroppers). The impact reaches to both land owners, tenants, sharecroppers and informal settlers in different manners.				
Magnitude	Insignificant	small	Moderate	High	Very High
	Rationale: The total land size subject to the acquisition is 120 ha in total. About 2,697 households(out of which 669 households are with land ownership) and 2,028 structures are expected to face their properties loss within 30 m ROW. Additional relocation and involuntary resettlement may take place related to the access road buildings and establishment of associated facilities (if any).				
Duration (D)	0- 1 year	2- 5 year	6- 15 year	Life of operation	Post Closure
	Rationale: Loss of land and houses will be permanent after receiving land acquisition process.				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
	Rationale: The impact is likely to affect within 30 m ROW as the direct impact zone and 200-500 m for indirect impact zone.				
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite
	Rationale: It is definite and certain that land acquisition and involuntary resettlement will take place as long as the project is to be implemented as planned and designed.				
Significance Level	[Magnitude (5) + Duration (4) + Extent (2)] * Probability (5) = 55				Major impact (A)

Mitigation Measures	<p>1) Avoid:</p> <ul style="list-style-type: none"> - Project Proponent (DWIR) is currently considering the re-adjustment of the ROW criteria in Kanaungto Section in order to avoid unnecessary incurrence of involuntary resettlement. <p>2) Minimize:</p> <ul style="list-style-type: none"> - Project Proponent (DWIR) to design alternative access to river (e.g. spillway docks for shipyards, piers for boat operations and waterway (for agricultural irrigation purpose) for farming operations) as an integrated part of the ESMP - Project Proponent (DWIR) to consider planning sequential construction schedules section by section (rather than blocking and carrying out construction over the entire project area simultaneously) <p>3) Offset/Compensation:</p> <ul style="list-style-type: none"> - Project Proponent (DWIR) to establish an entitlement matrix covering a comprehensive list of the direct affected households and persons by the project, including both land owner, tenants, private business operators as well as share croppers and informal settlers, according compensation measures should be established in accordance with the related laws and regulations in Myanmar as well as the EDCF Safeguard Policy and internationally accepted safeguard policies (in particular, WB ESF ESS 5)
---------------------	--

Table 5.6-6: Impact Significance on Shipyard Operations in Seikgyi Kanaungto Section

Source of Impact	<p>Description: Project implementation in Seikgyi Kanaungto Section is likely to disturb the shipyard operations and may incur land acquisition (if not physical relocations), subject to the project proponent (DWIR)'s final decision on the project designs and ROW demarcation in this area. In case some of the facilities that are to be installed as part of the project implementation hampers their access to the river and take some of their operation area, the productivity capacity of the affected shipyard companies may be compromised and some of the current employees may be laid-off.</p> <p>Shipyard operations in Kanaungto has over 60 years' history and the owners and operators have strong invested interests. The revenue of the total of 40 shipyards' operations is not known yearly. About 400 employees (daily wage workers) and their families of the 40 shipyard companies are also the potentially affected groups in case their operation operations are partially or entirely, temporarily or permanently affected due to the construction activities. In case the shipyard operations are put to halt, it is not clear whether there are alternative resorts for the vessel owners. If not, the second-round negative impacts would reach to the vessel owners/users.</p> <p>Social Concern: If the project proponent (DWIR) maintains the current presumption of setting the 30-meter ROW criteria inward from the boundaries of the existent shipyards, most of the shipyard's operations would not be significantly partially. However, in case any adjustment occurs and some parts of the areas of the shipyard operations are taken for the construction and other project-associated activities. Currently, there is a strong concern and request not to disturb their business operations from the shipyard business community in Kanaungto.</p>				
Magnitude	Insignificant	small	Moderate	High	Very High
	Rationale: The impact is predicted to be insignificant as long as the current ROW demarcation is sought.				
Duration (D)	0-1 year	2-5 year	6-15 year	Life of	Post Closure

				operation	
	Rationale: Loss of the economic activity will be permanent once land acquisition takes place.				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
	Rationale: The impact is expected to income loss for specific area that can be affected by the project activity in a direct way.				
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite
	Rationale: Based on a series of consultation with the Project Proponent (DWIR), it is judged that the final design and demarcation of the ROW is probable to be modified in the future.				
Significant Level	[Magnitude (1) + Duration (1) + Extent (1)] * Probability (3) = 9				No impact (-)

Table 5.6-7: Impact Significance on Other River/canal-based Businesses (Small Boat transport, Fishery and River-Irrigated Farming etc.)

Source of Impact	<p>Description: Temporary inconvenience of fishery community and small boat owners/operators/passengers) who are operating the private inland water transportation sectors shall be inevitable due to disturbance of small quays along the canal by project construction activities such as retaining walls, flood embankment, etc.</p> <p>Social Concern: Small boat operations, farming and fishing activities may be temporarily disturbed due to the construction. It was found that there are some mini boat transport operators (registered) with about vessel units. A standard size mini boat bus cater about 15~20 passengers in full capacity. Some units of quays are located within the ROW and construction areas.</p> <p>However, long term income and livelihood activities and the living standards of the region (such as traffic, health and sanitation conditions etc.) can then be improved during the operation phase. The primary beneficiaries are likely to effect the residents along the canal by a better service of inland water transportation by the project which can be broadly contribute to the regional community together with the spill-over and ripple effects as the secondary beneficiaries among 4 affected townships. Moreover, safe navigation for inland water transportation is highly benefited to the region during the project operation phase.</p>				
Magnitude	Insignificant	small	Moderate	High	Very High
	Rationale: The impact is predicted as moderate due to temporary disturbance of their operation quays for small boats that will also affected to stevedores at that quay.				
Duration (D)	0- 1 year	2- 5 year	6- 15 year	Life of operation	Post Closure
	Rationale: The impact is expected to see during the construction phase of the project about 2-5 years. The impact will be worse if the project construction period is not compliance according to the target schedule.				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International

	Rationale: The extent will be reflected to regional area for transportation of goods from and to somewhere in the region upon demands.				
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite
	Rationale: The probability is high during the project construction phase of the project although positive effects can be expected during the operation phase.				
Significant Level	[Magnitude (3) + Duration (2) + Extent (3)] * Probability (4) = 32				Moderate impact (C)
Mitigation Measures	<p>1) Avoid:</p> <ul style="list-style-type: none"> - No feasible options available. <p>2) Minimize:</p> <ul style="list-style-type: none"> - These quays within the construction site and ROW would need to be permanently relocated. Fishery community would need to find alternative fishing locations. The project proponent (DWIR) would need to consult them and provide alternative access channel to the river and the canal water for their continuous business activities. <p>3) Offset/Compensate</p> <ul style="list-style-type: none"> - Small boat owners/operators, fishermen and farmers whose source of income is being lost either permanently or temporarily (including farm owners and tenants and sharecroppers, both formal and informal) would need to be provided with the transition allowance to minimize their livelihood disturbance in accordance with the Myanmar laws and the international safeguard standards. 				

5.6.7 Land Acquisition and Resettlement Action Plan (LARAP)

5.6.7.1 Major Components of LARAP

As mentioned above, the RAP will likely deal with two main components impacting four townships, Dala, Twante, SeikgyiKanaungto and Kyimyindaing:

1. Construction Site/Land acquisition required during construction: Land acquisition will mainly involve agricultural land, residential land, shipyards. Some forest land and idle land are also expected to be acquired.
2. Permanent and/or Temporary Resettlement during the Construction Phase

With regards to land acquisition and resettlement, the land acquisition and resettlement action plan (LA & RAP) will be prepared based on the following existing laws of Myanmar described as below:

- 1) Transfer of Property Act (1882)
- 2) Land Acquisition Act (1894)
- 3) Farmland Law (2012), and
- 4) Vacant, Fallow and Virgin Lands Management Law (2012)
- 5) Conservation of Water Resources and River Law (2006)
- 6) Canal Act (1905)

7) Rangoon Development Trust Act (1920)

8) City of Yangon Development Committee Law (1990)

The full-fledged Resettlement Action Plan (RAP) needs to be developed once the detailed engineering design (DED) is finalized. At this point, as a part of the EIA, we present a preliminary (Framework) Resettlement Action Plan.

Detailed contents will be found in the Framework RAP chapter.

5.6.7.2 The Land Compensation and Resettlement Committees

1) Basic structure of the Land Compensation and Resettlement Committee




Figure 5.6-7: Basic structure of the Land Compensation and Resettlement Committee

2) Establishment of the Land Compensation and Resettlement Committee

•Yangon Regional Government held a meeting in 26 July 2018, in order to set up and assign the committee who has responsibility of all the related issue for EIA/SIA progress and land compensation and resettlement plan of Twante Canal Improvement project.




Figure 5.6-8: Official Letter for the Establishment of the Committee

•The committee consists of 13 Members of the following organization:

- YRG (Yangon Regional Government)
- YCDC (Yangon City Development Committee)
- MOTC (Ministry of Electricity, Industry, Transport and Communication)
- MPA (Myanmar Port Authority)
- Yangon Township Electricity Supply Cooperation

•At the same meeting, Yangon Regional Government set up the sub-Committees for three township that will be affected by the project: Dala, Twante, and Khanaungto.




Figure 5.6-9: Official Letter for the Establishment of the Three Sub-Committees

•Yangon Regional Government held an additional meeting in 18 October 2018, in order to set up the 4th sub-committee (Kyi Myin Daing) as some part of this township area is included in this project.




Figure 5.6-10: Official Letter for the Establishment of the Remaining Sub-Committee

•All four sub-committees have the same structures and consist of 10 Members of the following organization:

- YRG
- DWIR
- Township GAD: Departments of irrigation, agriculture, township development, etc.
- Township Electricity Supply Cooperation

5.7 Vulnerability Assessment

5.7.1 Identification of Vulnerable Groups among Affected Households

Identification of vulnerable groups in the project area include women household heads, older persons (above 75 years old) and disable' persons.

Table 5.7-1: Vulnerable Groups of the Affected Townships

Township	Women-headed households	Old Persons without family support (> 75 years)	Disabled persons
Twante	60	34	19
Dala	197	111	44
Seikgyi Kanaungto	54	56	143
Kyimyindaing	10	12	25
Total	321	213	231




Figure 5.7-1: Vulnerable Group of the Affected Townships

The majority of them are household heads who are over seventy-five years old. According to key-informants, there is no special program or activity to support these vulnerable people in this area. By social structure, they are taken care of by relatives and neighbors and are living in the communities without difficulties. The Myanmar Poverty and Living Condition Survey (2017) indicates that the national poverty line for 2017 is 1,590 kyat per adult equivalent per day (in 2017 quarter 1 kyat)¹³. In the later socio-economic census for the PAPs/PAFs identified based on the detailed engineering design, it is recommended that all the four types of the vulnerable groups within the PAPs/PAFs to be identified and integrated into the project's livelihood restoration program. The majority of them are household heads who are over seventy-five years old. According to key-informants, there is no special program or activity to support these vulnerable people in this area. By social structure, they are taken care of by relatives and neighbors and are living in the communities without difficulties.

5.7.2 Minority Groups

Only nine families in Twante Township are Kayin ethnicity and among them are four families of Kayin and Rakhine in Seikkyi Kanaungto Township. Families in remaining townships are Bamarn, practicing Buddhism and speaking Burmese language. Therefore, minority group is not found to be a major issue in the project development. The development of a separate indigenous peoples plan (IPP) is not required.

5.7.3 Gender Consideration

EDCF Safeguard Policy recommends considering the gender equity issue in conducting environmental and social assessment. To quote: "15. *The borrower shall assess the social impacts of projects, Social impacts includes [...] equity (vulnerable groups, gender difference, indigenous peoples).*" (EDCF Safeguard Policy, [Appendix 2] Requirements of Environmental and Social Assessment, Para 15)

¹³ <https://www.worldbank.org/en/country/myanmar/publication/poverty-report-myanmar-living-conditions-survey-2017>

- As illustrated under the Gender section of Chapter 4, a few impacts on gender equity are subjects to consideration in the planning and implementation of the proposed project. **Health and Sanitation – Effective control of water quality is required during construction** to alleviate the risk of any breakout of airborne diseases in the area, to which women and children are especially vulnerable. The construction management plan (CMP) needs to include the water quality control measures to prevent aggravation of the water quality along the construction area. While the affected communities are reported to acquire drinking and domestic use water from the reservoir or underground water source, some portion of the population may use the canal water and in case the underground water source (aquifer) is linked to the river and the canal, the underground and reservoir water may be affected to a certain degree.
- **Business opportunities** –In case there are existing business or production activities by women along the waterway such as small-scaled fisheries or aquaculture, any measures to respect and maintain them during and beyond the construction timeline should be sought. The construction activities should **ensure the fishers and the community continue to carry out their economic activities based on the canal and the river**. It is desirable that the GRM-related to the blockage and interruption of the canal/river-related economic activities would be actively responded by the Contractor in coordination with the Project Proponent (DWIR).
- **Economic Empowerment**
 - In the Southeast Asia region, it is often observed that women are often marginalized in controlling and managing domestic financial assets, and overtaken in the decision-making process about them or the disposal of them. To improve the current status of women lacking control over domestic financial matters, and better the economic independence of women in and around the project site, it is imperative to ensure **the female real property owners will enjoy the benefit of compensation payment**. To be able to ensure this, international good practices indicate that the project proponent, in association with other relevant local bodies, take steps to support and create domestic financial management scheme or tools; and to offer training sessions on financial management and economic viability for those who are not familiar with financial management skills, particularly targeting the female-headed project affected families as part of the livelihood programme for the proposed project.
- In addition to the above-mentioned financial intelligence and ownership training, economic empowerment for women in the project region can be realized through their **participation in the project-related works**. Based on the fact that more women successfully finish a higher degree or education today, and the highlighted ratio of female students in architecture and civil engineering schools, as presented in Chapter 4 of this report, it is recommended for Contractor (and sub-contractor) **setting a certain quota of local employment for Myanmar women in the construction and other project-related works**.
- **Prevention of sexual harassment:** A sudden influx of the construction-related employees from outside may cause cultural conflict and tension while making women of the project host communities vulnerable to sexual violence and infection of the sexually transmitted disease such as HIV/AIDS. –Education against sexual crimes especially for the on-site workers, and education on sexual diseases for both the construction workers and the host community need to be included as part of the CMP.

5.7.4 Political and Social Organizations

Villages in Myanmar have a number of social groups setup for community development and improvement of income and quality of life. Civil groups or NGOs also encourage villagers to learn how to collaborate and participate.

Key social groups in the villages are: mother and childcare groups, women groups, youth groups, funeral groups, social-welfare groups, saving groups, religious groups, health funds, environmental, water quality and health groups; malaria prevention groups, and TB prevention groups etc.

It was found that the four affected township by the proposed project area have no formal social groups and community-based organizations. Villagers meet to form a group on an *ad-hoc* basis when they required for particular activities. For example, they meet when they have to respond to local needs related to religious and funerals activities. Each informal and *ad-hoc* group consists of members who have the same interest and are normally led by the village elders. These groups are usually active, occasionally.

For the consultation and mobilization of the affected communities and persons during the construction and operation phases, Township administration office (GAD) with the ward/village leaders' coordination may be effective channel. In the future, the project proponent(DWIR) is recommended identifying any other viable grass root interest groups and organization for future cooperation and participation particularly in terms of income generation and livelihood program development and implementation.

5.8 Impact Assessment on Natural Disasters

'Hazard Profile of Myanmar' prepared by five Government Ministries and Departments in Myanmar and four non-government agencies in July 2009, describes nine types of disasters in Myanmar: 1) Cyclone, 2) Drought/Dry zone, 3) Earthquake, 4) Fire, 5) Floods, 6) Forest Fire, 7) Land slide, 8) Storm, and 9) Tsunami. Among them, "Cyclone" is the potential natural hazard for the study area and discussed as follows.

Cyclones that originate in the Bay of Bengal generally move westward heading for India and then turn towards Bangladesh and Myanmar. Severe cyclones tend to occur either during the pre-monsoon season from April to May or post-monsoon season from October to November.

Cyclones have three destructive forces, namely: i) storm surge, ii) heavy rainfall and iii) strong winds. According to 'Hazard Profile of Myanmar', 1,248 tropical storms formed in the Bay of Bengal during the period from 1887 to 2005, of which 80 storms (6.4% of the total) hit the Myanmar coast. In all, 12 cyclones caused severe damage in Myanmar mainly due to the accompanying storm surge, and the maximum death or missing toll was 138,373 caused by Cyclone Nargis in May 2008.

Cyclone **Nargis** also hit Greater Yangon and flood water spread on a number of Townships around Yangon City. Most of the inundated area during Cyclone Nargis are Dala, Twante, Htantabin and Hlegu areas.

5.8.1 Natural Hazards by Floods

The vulnerability to tidal flood is one of the key factors of interrupting inflow of industrial and commercial infrastructures and lowering potential of urban development and expansion in the Project site near Yangon downtown. Also, it is apparent that invaded saline water pollutes drinking and

agricultural water and destroys the widespread farmland in the townships. Figure 5.7-1 shows the status of flood due to the largest springtide in the Project site from 13 to 14 August 2014. It can be seen in the figure that impacts of the tidal flood on residential and farmland area in the Project site are more extensive and significant on the Yangon River side.






Figure 5.8-1: Status of the Largest Spring Tide Flood along Twante Canal

5.8.1.1 Channel Training

The Twante Canal is strongly affected by the tidal level; especially, on the Yangon River side the maximum tidal range reaches 5.72 m during the spring tide and the maximum flow velocity averaged over the Twante Canal becomes about 1.35 m/s. However, at the narrow channel section such as 0.5 mile, the maximum flow velocity is over 3.0 m/s, which is high enough to scratch seriously the channel bed and bank.

Securing the safe ship navigation through channel training will attract more traders to transport by inland waterway, which in turn may increase of traffic volume for freight by inland waterway. In a longer term expected economic growth and development of Yangon region will further revamp the river freight quantities and overall inland water transport system, which in turn, will boost further socio-economic development and return. As the bank protection in channel training will prevent the further land loss, life and livelihood loss of the communities along the canal and farm land will be secured from further land erosion and resultant economic and other welfare loss.

5.8.1.2 Flood Embankment

In the studied townships, factors to give rise to the flood in Twante, Dala and SeikgyiKanaungto Townships along the Twante Canal were investigated from the flood records from Irrigation Department, which is responsible for the flood issue in Myanmar, by literature survey like research reports and papers, and interview from administration offices of the relevant townships. It was found from the data survey and investigation that the Project site has experienced no severe flood damage for a long time but annual flood inundation for short term during the spring tide in townships on the Yangon River side. These findings indicate that the Project site is partly below the high spring tide level causing the high potential of flood damages as shown in Figure 5.8-2.




Figure 5.8-2: Lowland around Twante Canal

5.8.2 Natural Hazards by Seismicity


The probabilistic seismic hazard map of PGA for 2% probability of exceedance in 50 years is shown in Figure 5.8-3. The maximum PGA is $> 0.9g$ which also comprises of the eastern portion of Yangon Region as in the hazard distribution of 10% probability of exceedance in 50 years, especially along the areas lie along the Sagaing Fault. The minimum seismic hazard zones can be observed in the western part of the Yangon Region with PGA value of $< 0.2g$, whereas the Project area is also situated.

The project related activities will be only within the canal ROW area and there will be no impact on the change of seismic condition within the region.



Source: Probabilistic seismic hazard map of Yangon Region, Myo Thant, 2012ASEAN Engineering Journal, vol.3 no., 2.

Figure 5.8-3: Probabilistic Seismic Hazard (PGA) Map of Yangon Region with 10% Probability of Exceedance in 50 Years



Source: Probabilistic seismic hazard map of Yangon Region, Myo Thant, 2012ASEAN Engineering Journal, vol.3 no., 2.

Figure 5.8-4: Probabilistic Seismic Hazard (PGA) Map of Yangon Region with 2% Probability of Exceedance in 50 Years

Table 5.8-1: Impact Significance on Natural Disasters during Construction and Operation Phase

<p>Source of Impact</p>	<p>Description: The vast area around the Twante Canal in southwest region of Yangon has been frequently inundated due to the tidal floods. Through completion of this component, the four sections in the project area, i.e., SeikgyiKanaungto, Dala, Kyimyindaing and Twante Township, will be ensured the safety from the annual tidal floods. Natural seismic and storms, such as cyclones are also interest.</p> <p>Social Concern: Major Positive impacts will be obviously benefited on natural hazards because of the waterway change due to the Waterway maintenance which is to protect the shore and stabilize embankment to prevent soil erosion along the Twante (Twante) canal and Flood prevention to construct embankment for flood prevention. The project activities are</p>
--------------------------------	---

	not expected to relate with the seismic and cyclones.				
Magnitude	Insignificant	small	Moderate	High	Very High
	Rationale: Project components at Phase 1 is composed of channel training and flood embankment. One of the most important positive impacts the Phase 1 implementation is to offer the foundation of further social and economic development in Yangon region and beyond by ensuring safe and efficient inland water transport system along the Twante Canal.				
Duration (D)	0-1 year	2-5 year	6-15 year	Life of operation	Post Closure
	Rationale:				
Extent (E)	Limited to the site	Limited to the local area	Limited to the region	National	International
	Rationale:				
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite
	Rationale: The removal of households will be highly impacted within 30 m ROW.				
Significant Level	Magnitude (4) + Duration (4) + Extent (3) * Probability (5) = 55				Moderate impact (A ⁺)

5.9 Characterization and Assessment of Overall Impacts and Residual Impacts and Risks

The overall impact assessments are listed in Table 5.9-1 and the negative impacts are expected with the construction phase and seek some significant benefits during the operation period.

Table 5.9-1: Overall Assessment for Environmental and Social Impacts during Construction and Operation Phases

Impact Parameter	Descriptions	M	D	E	P	(Pre-) & Construction Phase	Mitigation Measures	
						Impact Evaluation	Necessary	Not Necessary
Air Emission	The construction activities could generate dust and SO ₂ in high condition according to baseline generation. Affected people nearby the construction site are likely to suffer.	4	2	1	3	21 (-)	√	
Greenhouse gases	Any correlation of greenhouse gas emission cannot be reflected.	1	2	1	1	4		√

Noise and Vibration	The related impact of noise and vibration for those who lived nearby the construction site during operation period of the noisy machinery is human health, loss of hearing, stress and insomnia.	4	2	1	4	28 (-)	√	
Water Quality	Potential to increase run-off and erosion, predominantly during construction, increasing turbidity and impacting water quality.	4	2	1	3	21 (-)	√	
Solid Wastes	Generation of waste and hazardous waste from construction activities could lead to water and soil contamination if not managed properly.	3	2	1	3	18 (-)	√	
Biodiversity (Forest, Flora, Fauna)	Ecosystem: Protected or Conservation area Flora: Mangrove natural conservation forest was identified in the project site or the Area of Influence (AoI).	4	2	2	4	32 (-)	√	
Climate Change	There is no correlation action of the project activity with climate change impact.	1	2	1	1	4		√
Soil	Soil run-off is expected by removal of vegetation cover for 30 m ROW.	2	2	1	3	15 (-)		√
Geology and Soil	No activity is related with changes in existing geology and soil condition.	1	2	1	1	4		√
Land use	Land use changes is expected within 30 m ROW along with Twante canal of the project area due to flood embankment and economic activities around the Project area.	3	2	1	3	18 (-)	√	
Hydrology	No hydrology condition is expected.	1	2	1	1	4		√
Wildlife	No wildlife is expected to find nearby community area.	1	2	1	1	4		√
Protected Area	No protected area is related with the project activity.	1	2	1	1	4		√
Recreation	There was no recreation	1	2	1	1	4		√

Area	centre within the proposed project area.							
Visual Resource	Removal of mangroves will be slightly changed in visual for those who lived in the 30 m ROW.	3	2	1	3	18 (-)	√	
Cultural Resource	No cultural resource will be built within 30 m ROW area.	1	2	1	1	4		√
Socioeconomic Components	Involuntary resettlement: A level of land acquisition and involuntary resettlements of residents along the canal area (esp. ROW) that are subject to construction will take place. (Estimated: 120 ha) with 2,697 PAFs & 2,028 structures to be affected)	5	4	2	5	55 (-)	√	
	Income and Livelihood Loss (1): Shipyard community About 40 shipyard operators and workers (about 10 employees per shipyard) with their families in Kanaungto Township may be affected in their income and livelihood in case of permanent (or temporary) halt of the shipyard operations. (in case of the adjustment of the current 30 m ROW boundary tentatively set by the project proponent (DWIR)) is modified in the future.) With the current assumption however, the impacts on the shipyard community would be minimal or virtually non-existent.	1	1	1	3	(-)	√	
	Income and Livelihood Loss (2): Fishers & Irrigated Farmers Fishers and other residents whose livelihoods are dependent upon the canal (i.g. farmers whose plots are being irrigated by the canal and Yangon river) may be also	3	2	2	4	28 (-)	√	

	temporarily affected in their livelihood due to the temporary blockage and inaccessibility of the canal area subject to construction work.							
Natural Disasters	Any project activity cannot be triggers for the natural disaster impacts. Even annual inundation impact by natural floods will be minimized after project construction. Positive impacts can be expected.	1	2	1	1	4		√
Occupational Health	Construction dust and noise will affect the workers' health.	3	2	4	3	27 (-)	√	
Community and Public Health	The nearby communities with the construction site is temporarily encountered with the dust and noise emissions, social stress with the foreigners and workers from non-regional area.	3	2	1	3	18 (-)	√	
Impact Parameter	Descriptions	M	D	E	P	Operation Phase	Mitigation Measures	
							Necessar y	Not Necessar y
Natural Disaster	Annual inundation by floods during the abnormal conditions within the regions such as extreme weather conditions will be reduced or minimized and even benefited by the project as the project itself represent the channel training, bank embankment and flood protection.	4	4	3	5	55 (+)		√
Socioeconomic Components	The regional communities will receive more opportunities for employment, food supplies, and fuel stations, facilitation of inland water transportation, distribution of the goods (in/out) of the region. Canal improvement project	4	4	4	4	48(+)		√

	can also positively effect on the development of regional inland water transportation system to navigate safely within the region which in turn seeking the improvement of livelihood for the employment opportunity and motivate regional economic development process.						
Natural Disasters	Positive impacts can be expected from waterway maintenance activity and flood protection.	4	4	3	5	55 (+)	√
Soil	Soil run-off will be no further encountered within 30 m ROW due to bank protection activity of the project.	3	4	1	4	32 (+)	√
Community and Public Health	The regional residents will get received the medical care through CSR program of the project.	3	4	3	3	30 (+)	√

(+) = Positive Impact

(-) = Negative Impact

No Remark (+ nor -) = Neutral

<15 = No Impact

5.9.1 Trans-boundary and Cumulative Impacts

Trans-boundary impacts are impacts that occur outside the jurisdictional borders of a project's host country. Potential Project trans-boundary impacts are considered to include:

- Socio-economic issues surrounding the sourcing of labour, goods and, services from the international market; and

Cumulative impacts arise from:

- Interactions between separate project-related residual impacts; and
- Interactions between project-related residual impacts in combination with impacts from other projects and their associated activities.

These can be either additive or synergistic effects, which result in a larger (in terms of extent or duration) or different (dependent on impact interaction) impacts when compared to project related residual impacts alone.

Cumulative and trans-boundary Impacts and Accidental Events initially consider the potential for impact interaction and accumulation in terms of the following:

- Temporal Overlap – the impacts are so close in time that the effect of one is not dissipated

before the next one occurs; and

- Spatial Overlap – the impacts are so close in space that their effects overlap.

More detailed trans-boundary and cumulative impact assessment are in Chapter 6 of this report.

5.9.2 Risk Mitigation Plan

Risk mitigation plans should:

- Characterize the root causes of risks that have been identified and quantified in earlier phases of the risk management process;
- Evaluate risk interactions and common causes;
- Identify alternative mitigation strategies, methods, and tools for each major risk;
- Assess and prioritize mitigation alternatives;
- Select and commit the resources required for specific risk mitigation alternatives;
- Communicate planning results to all project participants for implementation.

CHAPTER 6: CUMULATIVE IMPACT ASSESSMENT

6.1 Legal/Institutional Background

A. Requirement of Myanmar's EIA Procedure

In compliance with Article 2 (i) of Title and Definitions Section in EIA procedure (2015) in Myanmar, cumulative impacts should be assessed as the successive, incremental and/or combine effects arising from the project together with other existing and/or future projects, other development activities within a defined spatial and temporal framework in two aspects:

- i) the surrounding natural and social environments
- ii) on the project itself

Thus, EIA Report should include a section on CIA (Cumulative Impact Assessment) in the following structure:

- Methodology and Approach
- Cumulative Impact Assessment
 - Brief descriptions and maps of relevant existing and future private and public projects and developments
 - Identification and assessment of the potential cumulative impacts on the components in the surrounding environment and the Project's contribution to such impacts
 - Determination of the leverage and influence that the Project may have over the significant and project-related cumulative impacts
 - Description of measures to mitigate the Project's contribution to the cumulative impacts

B. Requirement of the EDCF Safeguard Policy

The EDCF safeguard policy also requires conducting the CIA as part of ESIA. To quote:

*"22. Environmental and social impacts need to be analyzed in all stages of project cycle. The borrower shall identify potential direct, indirect, **cumulative** and induced environmental impacts on and risks to physical, biological, socioeconomic, and physical cultural resources and determine their significance and scope, in consultation with stakeholders, including affected people."*

In addition, the EDCF safeguard policy [Appendix 2] Requirements of Environmental and Social Assessment) mentioned about the cumulative impacts as:

"3. Impacts and risks will be analyzed in the context of the project's area of influence. This area of influence encompasses [...] (3) The areas and communities potentially affected by cumulative impacts from further planned development of the project, other sources of similar impacts in the geographical area, any existing project or condition, and other project related developments that are realistically defined at the time the assessment is undertaken.; [...]"

The assessment needs to identify potential transboundary effects, such as air pollution, increased use or contamination of international waterways, as well as global impacts, such as emission of greenhouse gases and impacts on endangered species and habitats.

6.2 Methodology and Approach: Rapid Cumulative Impact Assessment (RCIA)

Full-fledged CIA requires a multi-party coordination of data collection and assessment efforts

including the (local, responsible) government unit as a key agent in order to assess collective and time-consuming assessment of key environmental and social impacts of a range of projects in the past, present and in the near future in the broader areas of influence beyond an area of direct influence of a particular project. Thus, it is beyond the scope of an EIA assessor of a particular EIA study team¹.

Typically, RCIA takes the 6-step approach as illustrated in Figure 6.2-1:




Figure 6.2-1: RCIA Six-Step Approach

1 For more details of the definition of CIA and its commonly accepted methodology, see for example, "IFC Good Practice Handbook: Cumulative Impact Assessment and Management: Guidance for the Private Sector in Emerging Markets" (2013, available at: https://www.ifc.org/wps/wcm/connect/3aebf50041c11f8383ba8700caa2aa08/IFC_GoodPracticeHandbook_CumulativeImpactAssessment.pdf?MOD=AJPERES)

6.3. Cumulative Impact Assessment

6.3.1 Identification of VECs and Boundaries

A. Identification of VECs

Identification of the VEC for CIA requires an extensive stakeholder and expert discussions as the VEC covers the receptors which are scientifically or socio-culturally valuable. The projection of VEC for CIA in this report would be preliminary based on the EIA team's expert conjecture.

VECs are environmental and social attributes that are considered to be important in assessing risks; Twante Canal can affect important physical features as like mangrove habitat, and natural processes as a watershed in Twante Canal and Yangon River, and social conditions as residential health, economics in the project site.

From socio-economic perspective, cumulative impacts of the proposed project on the communities and individuals in the region, when combined with a series of listed projects that would occur simultaneously with the implementation of the proposed project or expected near future development activities (related mainly to the SUDP), would include: accelerated urbanization and population growth as well as the infrastructure and socio-economic development in the region. The livelihood of the community in the four affected Township and the broader community of the Yangon Region shall be a VEC.

B. Setting up Spatial and Temporal Boundaries for CIA

From hydraulic and ecosystem service perspective, the spatial boundary for the CIA would be the areas along the Twante Canal and the Yangon River. From socio-economic and cultural perspective, the spatial boundary for the CIA would cover the entire administrative boundaries of the four affected Townships, respectively. Thus, in combination the spatial boundary for CIA would include: 1) The four affected townships (Dala, Twante, Seikyi-Kanaungto and Kymindaing) and 2) Twante Canal and the Yangon River in its entirety.

The temporal boundary for CIA of this project is set to be the duration of the full cycle of the project, i.e. from present till the end of the operation of the installed facilities. The cumulative impacts could reach well beyond the construction period of the proposed project (i.e. during the years from 2019 to 2024). It is suggested the temporal boundary is tentatively set to 8 years (including 5 years construction and another 3 years during the operation.)

In review of the development activities in Yangon Region (esp. along the Yangon River and Twente Canal) which are currently ongoing or at planning stage, it is unlikely that the proposed project may lead to substantial environmental cumulative impacts.

6.3.2 Relevant Existing and Future Private and Public Project Development

A) Project and Programmes within Yangon City Area

Due to insufficient data and information about the comprehensive list of the projects, the EIA could not guarantee to cover all the development projects in Myanmar but only based on the officially available information.

The Yangon urban development master plan (SUDP) prioritizes 45 projects at an estimated cost of 2.6 billion U.S. dollars including nine urban development projects, 10 central business district renovation projects and nine social service and management projects until the year 2040. The 885 million U.S. dollars have been allocated to implement 25 projects for the urban development management sector,

while the remaining 17 projects are with the infrastructural development sector at an estimated budget of 1.802 billion U.S. dollars.

As accordingly to the Yangon Investment Forum held in 10 and 11 May, the new urban development projects for Yangon region will include the establishments of sub-centers, new towns, railway stations and industrial zones.

The four sub-center projects are planned for Mindama Secondary Central Business District with a trade center, convention center, social service center, logistics, information technology and software center, commercial, business and tourist centers, a sports complex, an amusement park and an inland port within in Yangon city and along with Yangon river. In addition, new town projects are planned for Thilawa New City, Southwest New City, Dagon East New City and Dala New City.

With a national road network, the Yangon urban structure will be decentralized to outer areas or the southern seaport. There are 29 existing industrial zones as well as Thilawa Special Economic Zone in Yangon, and 53 % of the industrial zones in Myanmar are located in Yangon.

Twente is also in the list of 11 new industrial zones which are also projected to be established outside Yangon municipal areas, including Kawhmu, Kungyangon, Twantay, Thanlyin and Kyauktan to prevent development gap between the municipal areas and areas on its periphery. These industrial zones will spread up to more than 1,800 acres (730 hectares).

Yangon Urban Development Master Plan	
Urban Development Projects	9
Central Business District Renovation projects	10
social service and management projects	9
infrastructural development sector	17
Total	45

B. Development Plans, projects and Programmes in Yangon River and other townships near the project area

1) Thilawa Special Economic Zone (SEZ)


The Thilawa Special Economic Zone- located on the outskirts of Yangon is the first Special Economic Zone (SEZ) built in Myanmar and had become fully operational in September 2015. Inside Thilawa SEZ, both hard and soft infrastructure form roads and utilities to supporting services such as maintenance are developed in accordance with the international standard. It is located at around 20 km South-East of Yangon, which is the biggest commercial city of Myanmar.

It is the first international standard SEZ of Myanmar and is developed by a Myanmar-Japan joint venture company with the name of Myanmar-Japan-Thilawa Development Limited, where the Myanmar government, Japanese government, Myanmar private consortium, and Japanese private consortium have stakes.³

³ <http://www.myanmarthilawa.gov.mm/public-disclosure-final-environmental-impact-assessment-eia-report-and-scoping-report-thilawa-0>

Table 6.3-1: Development Project and Programs in Yangon River

Project/Program Title	Project Owner	Location/Size (ha)	Period	Major Components	Donor/Finance Source	Distance from Project (km)	Current Status	Remark
Thilawa Special Economic Zone (SEZ)	Myanmar Japan Thilawa Development Limited (MJTD)	Corner of Thilwa Development Road and Dagon-Thilawa Road, Thilwa Special Economic Zone (SEZ), Thanlyin Township		Industrial Zone	Myanmar Government and The Japanese Government	57837 ft	Zone A (established) Zone B (still processing)	Zone C (planning)



<Map 1. Distance between Proposed Project Site and the Thilawa SEZ>

2) New Yangon City Development Project

The New Yangon city development project is currently in the status of pipeline, which will be developed by the Yangon Regional Government and the proposed project area is located about 28.97 km far from it and it can be predicted that the Twente township will be included in the affected community list.

Table 6.3-1: Development Project and Programs in Twente Townships (Present/Past/Future)

Project Title	Project Owner	Location / Size (ha)	Period	Major Components	Donor/ Finance Source	Distance from Project (km)	Current Status	Remark
New Yangon City	Yangon Regional Government	7632.78	-	Infrastructure development activity	Yangon Regional Government	28.97	Consulted with the regional people in the project area and reported to Government	Pipeline



<Map 2: Location of Planning Projects in Yangon Area>

3) Yangon-Dala Bridge (Myanmar-Korea Friendship Bridge of Dala) Project

In October 2012, the President, U Thein Sein made an amicable agreement on developing a bridge with a pledge of friendship from the Republic of Korea and the Republic of Union of Myanmar during his visit to Korea. The feasibility study was conducted on 1st April 2013 by Sambo Engineering Co., Ltd and Korea Engineering Consultants Corporation and completed by 9 months later. The construction has started in 2019 with the finalization of the detailed engineering design of the bridge construction, and is expected to complete its construction by July 2022.

The brief information of the project is as below:

- Bridge Type: Cable Stayed Bridge
- Capacity: 75 Ton/vehicle
- Total Length: 1872.5 m
- Main bridge length: 590 m
- Approach bridge length (Yangon): 617.5 m
- Approach bridge length (Dala): 665 m
- Width (4-ways): 26.5 m
- Approach bridge width (Yangon) 14.3 m
- Approach bridge width (Dala) 20.9 m

Table 6.3-2: Development Project and Programs in Dala Townships (Present/Past/Future)

Project Title	Project Owner	Location / Length (m)	Period	Major Components	Donor/ Finance Source	Distance from Project (km)	Current Status	Remark
Korea-Myanmar Friendship Bridge (Dala) project	Ministry of Construction	Dala-Yangon 1872.5	-	Constructions	South Korea Government	-	Designing on Expression of Interests (EOI)	Pipeline



<Map 3: Location of the Yangon-Dala Bridge Construction Site and the Distance from the Site of the Proposed Project>

4) Other Development Plans (Rural Roads and Railway Stations)


4.1) Embankment Protection Work by YRG between 3.5 ~ 7.9 Mile point of the Twante Canal (During Construction Stage)

The Yangon Regional Government has been carrying out the embankment protection work along the Twante Canal between 3.5 Mile ~ 7.0 Mile point. (See the Map 4 below). The section corresponds to the Twante township section on the Twante canal.

The installation of embankment may affect water quality, such as temporary muddy water. In addition, the operation of construction equipment may have temporary impacts on the atmosphere due to noise and dust.

However, since construction is currently underway, it is expected that there will be no cumulative effect as the construction period does not overlap with this Twante Canal Integrated Management project.

In the long-term, the construction of this embankment is expected to have a positive effect on the protection of farmland and houses in the vicinity of Twante Canal (between 3.5 to 7.9 Mile Point).



<Map 4. Location of the Embankment Repair Work Site by the YRG, along the Twante Canal>

Project Title	Project Owner	Location/Length (m)	Period	Major Components	Donor/Finance Source	Distance from Project (km)	Current Status	Remark
Twante Canal Improvement Project	YRG	3.5 ~ 7.0 Mile point along the Twante Canal (in Kanaungto Township)	2019-2024	Embankment Construction	ODA loan of Economic Development Cooperation Fund (EDCF) by the Government of the	--	Construction	Pipeline (EIA processing)

					Republic of Korea			
--	--	--	--	--	-------------------	--	--	--

4.2) Rural Road Development Project by the MOC (in Planning Stage)

The Ministry of Construction (MOC) will have the improving and developing rural roads plan in SeikgyiKanaungto township area but at this point, further information is not available.

4.3) Railway Station Area Development Project in Kyimyindine Township

Kyimyindine Township will be one of the six main railway stations areas for the development project of the railway station area , together with the area of Yangon Central, Insein, Yegu, Mingaladon and Danyingone railway stations in the future. Currently a preparatory survey is in progress.

Table 6.3-3: Development Project and Programs in Project Areas: Kyimyindaing Township (Present/Past/Future)

Project Title	Project Owner	Location/ Size (ha)	Period	Major Components	Donor/ Finance Source	Distance from Project (km)	Current Status	Remark
Yangon Railway Station Project	The Central Transport Development Consortium (CTDC)	25.7 hectares	≈ 8 years	6 zones: twin tower office, office buildings, housings, hotels, a park and museum	-	-	Conducting On-ground survey	-

Table 6.3-4: Development Project and Programs in Project Areas -Khanaungto Township (Present/Past/Future)

Project Title	Project Owner	Location/ Size (ha)	Period	Major Components	Donor/ Finance Source	Distance from Project (km)	Current Status	Remark
Rural Road Development Plan (TBC)	Myanmar Government	Seikgyi Kananungto	TBD	Regional road upgrading facilities	Nil	Nil	Planning	Pipeline

6.3.3 Assessment of Cumulative Impacts on VECs

The VECs in the list below have been assessed for the Twante canal improvement project only as of the present. Impact leverage would need to be changed when cumulative impacts of other predictable projects are added.

Following table presents preliminary predictions and suggested leverages of the cumulative impacts on identified VECs related to the proposed project:

Table 6.3-5: Prediction and Leverage Assessment of Cumulative Impacts

Project Name	Comments	Elements included within CIA
Thilawa Special Economic Zone Korea-Myanmar Friendship (Dala) Bridge Project	The project site is located far enough or different watershed, for relevant impact cumulative are less	Cumulative impact during construction would be negligent level. mangrove habitat needs to be protected along the canal and the Yangon river during construction
New Yangon Development	The project site is located in near Twante Canal Project. While the development would occur prior to the year 2040, it is hard to predict a definite project implementation period at this point of time.	If the project's timing overlaps with the period of the proposed project, further review is required whether the flood embankment is suitable for flood defense in New Yangon Development through consultation with YGCG and YRG while conducting detailed design. Need to update additional ESMP to reduce construction impacts if the periods of the two projects overlap.
Embankment Protection Work by YRG between 3.5 ~ 7.9 Mile point of the Twante Canal	The project site is located within Twante Canal Project and it is constructing.	Need to be reviewed the Embankment Protection and Twante Project's embankment while conducting detailed design to harmonize both projects.
Other projects; Rural Road Development Project by the MOC Railway Station Area Development Project in Kyimyindyne Township Embankment Protection in Yangon River by MPA Industrial Zone Wastewater Treatment Plant	The projects site is near Twante Canal Project	Need to update additional ESMP to reduce construction impact if the periods of the two projects overlap. through coordination with the project proponent of the respective projects and activities Need to be reviewed the Embankment Protection in Yangon River and Twante Project's embankment while conducting detailed design to consult with MPA

Table 6.3-6: Prediction and Leverage Assessment of Cumulative Impacts on Value Environmental and Social Components (VECs)

Impact Parameter (VECs)	Cumulative Impact Evaluation					Descriptions /Mitigation Measures
	Level of Significance			Temporal Frame (2020~2030) (5 years for constructio n + 5 years for operation)	Spatial Frame ((1) Four affected townships + 2) Area along the Yangon River and the Twente Canal)	
	1	2	3			
Air Emission	√			2-5 years for constructio	Area along the Yangon River and	Stakeholder consultation and strictly follow to EMP
Water Quality		√				Stakeholder consultation and take

				n (2020-2025)	the Twente Canal	mitigation actions
Noise and Vibration		√				Stakeholder consultation and avoid repeat action with other noise generation activities and working at night time
Biodiversity (Forest, Flora, Fauna)		√				Stakeholder consultation and establish a tree-compensation plan
Geology and Soil			√			Need to be reflected in detail design if the periods of the two projects overlap. through coordination with MPA. Monitoring action as ESMP plans
Socio-economic Component		√		2030 beyond (due to 2040 SUDP)	Beyond the four affected townships (to the entire Yangon Region)	<p>Combined with a series of listed projects that would coincide or in the near future with the proposed project (largely related to the SUDP) would accelerate urbanization and population growth as well as the infrastructure and socio-economic development in the region.</p> <p>Livelihood of the community in the four affected Township and the broader community of the Yangon Region shall be affected positively.</p> <p>[Mitigation measures] ► YRG to coordinate the overall management of the cumulative socio-economic impacts of the multiple projects that are to be implemented in the region in coordination with the YCDC and the related local government agencies.</p>
Hydrology			√	5 years for operation (2025-2030)	Beyond the four affected townships (to the entire Yangon Region)	<p>Need to further review whether flood embankment is suitable for flood defense in New Yangon Development through consultation with YGDG while conducting detail design</p> <p>Monitoring action as EMP plans</p>
Wildlife			√	2-5 years for construction (2020-2025)	Area along the Yangon River and the Twente Canal	Strictly forbid to hunt the animals and took a stringent action when would be happened.
Protected Forest Area			√	2-5 years for construction (2020-2025)	Area along the Yangon River and the Twente Canal	Establishing Protection Measures for the Forested Mangrove Tree Monitoring protected existing Mangrove habitat
Cultural Resource	√			Impact not triggered	Impact not triggered	Regular stakeholder consultation and Chance find procedure to be implemented
Land Use & Involuntary Resettlement	√			Before/During construction period (2005)	Four affected Townships (only)	<p>While the scale of the involuntary resettlement of the proposed project is significant, the impact as such is spatially contained and unlikely to generate cumulative impacts in combination with the other projects/programs as the respective projects' location are largely isolated and not adjacent or overlapping.</p> <p>[Mitigation Measures] ► Good practice in resettlement plan and compensation policy development in compliance with the Myanmar laws and</p>

						observance of the EDCF Safeguard Policy and related international safeguard standards shall ensure to mitigate any possible future dispute and grievances of the communities in the long term.
Natural Disasters			√	5 years for operation (2025-2030)	Beyond the four affected townships (to the entire Yangon Region)	Positive impacts can be predicted.
Recreation Area			√	5 years for operation (2025-2030)	Area along the Yangon River and the Twente Canal	Monitoring Action
Visual Resource		√		5 years for operation (2025-2030)	Area along the Yangon River and the Twente Canal	Consultation Monitoring actions

6.3.4 Design of the Management Strategies: Measures to Mitigate the Project's Contribution to the Cumulative Impacts

The Thilawa Special Economic Zone, the Korea-Myanmar Friendship (Dala) Bridge Project are located far enough or on a different watershed. Thus, their environmental relevant cumulative impacts can be negligent.

The cumulative impacts may be expected from the same and/or similar activities from those projects such as construction activities of New Yangon City Development Plan, Embankment Protection Work by MPA, and rural roads improvement which in turn causes the increment in the neutral and low level impacts to moderate or high where the temporal and spatial area (at the same time and place) of the project construction activities, especially for VEC components, from the side of Twente Canal Project, clearance of regional vegetation and biodiversity, changes in ambient air quality, waterways transport, land use, soil and geology features, noise and vibration and socioeconomic loss etc. Besides, the impacts such as aesthetic visual impacts, solid waste generation, occupational and public health and safety can then be above the thresholds due to temporal and spatial cumulative impacts of the projects within the region.

The mitigation measures should carefully implement for the selected VECs mentioned above in the Table 6.3-6 during the construction phase where there will have the construction activities of other reasonably predictable projects with natural influences such as New Yangon City project within the temporal frame.

The mitigation measures would include:

- 1) Stakeholders engagement to identify the relevant VECs matter that may be potentially affected;

- 2) Estimation of affected VECs of the project as the livelihoods of cumulative impact assessments from other predictable projects;
- 3) Evaluation of the future condition of the VECs relative to threshold(s) of VEC condition (Stakeholders engagement);
- 4) Avoidance and minimization of the development's impact on the VECs for the life of the development;
- 5) Monitoring and management of impacts and risks to the project over its lifespan from VECs reaching their limits (Stakeholders engagement);
- 6) Compilation and sharing of project-related monitoring and VEC condition data to governments and other stakeholders for the life of the development.
- 7) If Yangon Development Project's timing between Twante Canal Project matches, it needs to be further reviewed whether flood embankment is suitable for flood defense through consultation with YGDG while conducting detail design.

In the case of stakeholder engagement actions related to the cumulative impacts that may arise along the Twante Canal, DWIR, the project proponent, shall take the leading role of any engagement with the local governments and any stakeholder in conducting the preliminary analysis for the integration of more comprehensive CIA for more sustainable overall development of the region in the longer term. The overall coordination among a set of development projects shall require the leading role of the YRG.

The stakeholders may include the local governments, the top management of other projects within the project area, contractors from the Twente project and other predictable projects, the local resident communities and the other project related committees such as land committee and other consultative bodies of compensation procedures for the losses.

CHAPTER 7.0: ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN

7.1 Background

The Environmental and Social Management Plan (ESMP) lists mitigation measures and monitoring framework to the significant environmental and social impacts of the project that have been identified through the assessment in accordance with the EIA Procedure of Myanmar and the EDCF Safeguard Policy. Mitigation and monitoring plans cover the entire period of pre-construction/ construction/ operation/ dismantlement (decommissioning) of the proposed project. The ESMP also presents management and monitoring roles and responsibilities of the project proponent (DWIR) and other relevant agencies (including MONREC-ECD) in the format of implementation schedules. Budgeting and cost estimations of each of the major mitigation and monitoring activities are also mapped out at a preliminary level (i.e. subject to later adjustment and fine-tuning at the detailed designing stage).

7.2 Relevant Laws and Guidelines of ESMP

7.2.1 Requirements of Myanmar's EIA Procedure (2015)

MONREC has issued, on 28 June 2018, that the proposed project should be prepared with the EIA in accordance with the laws, rules and regulations by the MONREC. Per Art. 63 of the Myanmar EIA Procedure, the EIA Report shall contain a separate chapter on ESMP with the following contents:

In addition, Section VII (Article 76~92) of the EIA Procedures (2015) elaborate the Project Proponent's obligation to endorse and submit the ESMP to MONREC, which, in turn, will review and approve/reject it.

Regarding the environmental and social monitoring, according to Section 106 of the EIA Procedures (2015), the Project Proponent *"shall, during all phases of the Project (pre-construction, construction, operation, decommissioning, closure and post-closure), engage in continuous, proactive and comprehensive self-monitoring of the Project and activities related thereto, all Adverse Impacts, and compliance with applicable laws, the Rules, this Procedure, standards, the ECC, and the EMP."*

According to Section 108 of the EIA Procedures, the Project Proponent shall submit monitoring reports to the Ministry every six (6) months at the least frequency, as provided in a schedule in the ESMP, or periodically as prescribed by the Ministry.

7.2.2 Requirements of the EDCF Safeguard Policy

According to Section 24 of the EDCF Safeguard Policy, *"ESIA or IESE shall include ESMP. The level of ESMP and the priority of identified mitigation measures are proportionate to the impacts and risks of the project. Major considerations of ESMP include: i) mitigation of adverse impacts to the extent of "no significant impacts to third parties," ii) the polluters-pay principle, and iii) precautionary principles. For category A and B projects, the borrower is required to provide Korea Exim Bank with RP and/or IPP, if applicable, in addition to an ESIA or IESE report."*

Section 25 of the Policy also indicates that Mitigation measures are to be suggested in the priority order of avoid, mitigate(minimize) and off-set(compensate): *"The borrower shall avoid, and where avoidance is not possible, minimize, mitigate, and/or offset adverse impacts. If impacts are unavoidable, the borrower shall prepare impact mitigation measures to design, construct, and operate the project in compliance with EDCF Safeguard Policy. If some residual impacts are likely to remain*

significant after mitigation, the ESMP will also include appropriate compensatory measures (offset) that aim to ensure that the project does not cause significant net degradation to the environment."

[Appendix 3] of the Policy illustrates the content of the ESMP as part of the ESIA report as the following:

<p>11. Environmental and Social Management Plan (ESMP): This section is a detailed plan prepared to manage adverse impacts during the implementation of a project. The level of detail of the ESMP is commensurate with the significance of the impacts. The ESMP encompasses mitigation measures, monitoring programs, corrective measures, and performance indicators.</p> <p>a. Mitigation measures</p> <ul style="list-style-type: none">• Identification and summary of significant environmental and social impacts.• Technical description of each mitigation measure including the types of impacts, the design of mitigation measures, the equipment specifications, the operation procedure, and application conditions. <p>b. Monitoring</p> <ul style="list-style-type: none">• Description of monitoring measures with technical details, including the parameters to be measured, methods to be used, sampling locations, frequency of measurement, detection limits, and definitions of thresholds that will signal the need for corrective action.• Description of monitoring procedures to measure the results of the application of mitigation measures. <p>c. Implementation arrangement</p> <ul style="list-style-type: none">• Detailed implementation schedule for ESMPs.• Coordination of responsibilities such as the strengthening of environmental and social management capabilities, technical assistance programs, training programs, and the purchase of equipment and supplies among main agents implementing and monitoring mitigation measures. <p>d. Performance indicators</p> <ul style="list-style-type: none">• Development of criteria to measure major environmental and social performance levels. <p>e. Evaluation and Conclusion</p>
--

According to EDCF Safeguard Policy Section 34, "*The borrower shall prepare a periodic monitoring report to track the progress of ESMP implementation and submit it to Korea Exim Bank. For a project classified as category A or B, the borrower shall submit the monitoring report at least on an annual basis up to the completion of project construction. For category A projects anticipated to cause significant adverse environmental and social impacts, Korea Exim Bank may request semi-annual monitoring reports during project construction period until expiration of the loan contract, if necessary.*"

Also in Section 35: "*Periodic monitoring reports shall be posted in a location readily accessible to the public. The project budget shall include the costs of monitoring and the expenses associated with reporting. The borrower shall consider participation of representatives of the affected people in monitoring activities.*"

7.3 Summary of Impacts & Mitigation Measures

A. Pre-Construction Phase

Various factors which affect negatively the environment should be considered to ensure environmentally sustainable development plan at the location selection phase. Negative impacts of the project components on the environment during the **land selection and clearing activities** during the pre-construction stage include **air, water and soil pollution** among others. The environmental impacts as such are expected to be relatively small in scale and temporary when compared to large-scaled urban development, industrial complex development, or tourism site development projects, etc.

In the process of land acquisition and clearing, **physical and economic dislocation of some of the residents** along the Twante canal will take place. The scale of the expected dislocation is expected to be up to about a couple of thousands of households (final determination will be generated based on the completion of the detailed design and the ROW demarcation of the shipyard areas in SeikkyiKanaungto Township).

For this scale of social impacts, a **land acquisition and resettlement action plan (LARAP or simply, resettlement action plan(RAP))** would need to be developed as a full-fledged and separate plan from this ESIA. A concrete resettlement plan would be required at this point of time with the YRG and the other related local government agencies work together with the Project Proponent (DWIR). Given the massive scale of potential involuntary resettlement need (ranking from several hundreds to a couple of thousand households), and that the majority of the potential relocatees are found to be either tenants or informal settlers (our survey indicates the percentage of the land owners among the potential resettlers are only about 25%). The Project Proponent (DWIR) has established four Land Compensation and Resettlement Negotiation Committees at the township level (in the affected four Townships). Once the land acquisition and compensation policy is set by the committees, the due information disclosure and consultation process would need to be followed in order to collect and reflects the key stakeholders' feedbacks and to ensure the compliance with the required procedural requirements in Myanmar.

B. Construction Phase

Project components proposed in the Study comprise of measures to resolve urgent and serious problems such as bed and bank erosion and flood damages. The objective of the Project is to propose sustainable and systematic measures for the Twante (Twantay) Canal improvement and management securing the safe inland navigation, protecting residential and farmland areas from bank erosion and flood damages.

The Project-caused temporary impacts such as **dust or noise due to construction vehicles**, these impacts are caused mainly by carrying construction materials and negatively affect the health of both workers and residents inevitably. **Soil run-offs** during rainy seasons is another temporary impact, which would affect the **water quality around the project area**. Construction activities would also affect **a part of vegetation, existing plants such as mangroves** and potentially **interrupt the (inland water) traffic (and also land traffic) temporarily**. **Soil pollution** may occur unless construction equipment is well maintained in order to prevent the illegal effluence of waste oil.

Mainly, the potential impacts are anticipated as **air quality** due to dust generation, **vibration and noise, water quality, biological components (flora and fauna)** and socioeconomic impacts due to **land acquisition and resettlement** issues. The overall anticipated impacts and their mitigation measures are listed in Table 7.6-1.

The process of land acquisition and resettlement campaign could continue to the construction period as long as each and individual affected households are duly consulted and compensated, and their

resettlement measures are provided prior to the land clearing and begin the construction in their property sites.

C. Operation Phase

The Project contributes to the Twante Canal improvement and management securing the safe inland navigation, protecting residential and farmland areas from bank erosion and flood damages by flood embankment and providing foundation of local economic growth.

For the project to be effective, the embankments shall be maintained stable, and it is necessary to monitor how to implement resettlement appropriately and replant trees if applicable.

7.4 Institutional Arrangement

7.4.1 Overview

Directorate of Water Resources and Improvement of River Systems (DWIR), as the project executing entity, will take overall responsibility for the successful implementation of the ESMP. During construction phase, the Project Proponent (DWIR) needs to hire a third-party contractor which will ensure to minimize environmental impacts and meet all environmental, social and health management-related ("EHS" hereafter) requirements during the construction. The overall responsibility of environmental (and social) management and monitoring (both general and site-specific) would need to be stipulated in the contractual documents as a set of obligations. Regular environmental and social monitoring shall be carried out by the DWIR and also be reported by the Contractor (from a designated field manager(s)) to the DWIR on a regular basis as a separate process or as part of the overall construction progress reporting. In case a sudden, or unexpected environmental and social issues arise in the course of the project implementation, a prompt *ad hoc* reporting is required to inform DWIR of the issue status as well as the actions to be/have been taken.

Environmental and social considerations based on the findings of this Study and the recommended ESMP need to be duly reflected in adopting designs, selecting construction methods and technology, as well as managing overall construction and operation. The Project's EHS performance will be measured and evaluated against applicable national or international standards and guidelines prescribed by MONREC or proposed in the ESMP. The Project will establish a separate, more concrete environmental management system (EMS) for the Project construction based on this ESMP.

During operation phase, DWIR will ensure to minimize environmental and social impacts and meet all EHS requirements of the canal operation and maintenance (O&M). The Project's performance will be measured and evaluated against applicable national or international standards and guidelines prescribed by MONREC in the proposed ESMP.

7.4.2 Responsibilities of the Project Proponent (DWIR/PMU)

Following are the primary responsibilities of the project (DWIR/PMU):

a) Ensure the project is complying with the environmental and social requirements included in this ESMP, namely through implementing provisions related to the conduct of the contractor in the environmental and social sections in the TOR for the construction works.

- b) Develop, promote and foster a shared sense of responsibility for environmental and social performance of the project among employees and contractors and community towards environmental and social management and linking project environmental performance to its overall performance;
- c) Monitor environmental and social performance throughout the project and implement an adaptive management approach to continuous improvement;
- d) Maintain an on-going commitment to informing, engaging and involving local stakeholders of the key environmental and social issues during the entire period of the project implementation and operation.
- e) Operationalize the Grievance Redress Mechanism (GRM) for local community and ensure their concerns and grievances raised are properly addressed in a timely manner.

[Project Management Unit (PMU)]

The project management unit was organized by the project proponent (DWIR), on 16th March 2018 for the implementation of Twente Development project in a strategic way.

Table 7.4-1: Project Management Unit (PMU) for Project Implementation

No.	Name	DWIR Position	PMU Position
1	U Sein Lwin	Deputy Director	Project Director
2	U Kyaw Zin Than	Deputy Director	Assistant project Director
3	U Mg Mg Lwin	Assistant Director	Project Officer
4	Daw Khin Myo Lwin	Officer (Finance)	Finical Offer
5	Daw Phyo Zar Ni Myint	Office Superintendent	Assistant Project Officer
6	Daw Kyawt Hmue Khin	Office Superintendent	Assistant Project Officer
7	Daw Lay Mi Mi San	Branch Clerk	Supervisor
8	Daw Wut Yee Cho	Accounting-4	Account Assistant
9	U Sett Paing Oo	Deputy Superintendent	Admin Staff
10	Daw Thaw Zin Oo	Lower Divisional Clerk	Admin Staff
11	Daw Sandar Win Aye	Store Keeper G-1	Procurement Officer
12	Daw Yu Zin Mon	Store Keeper G-4	Procurement Assistant

The DWIR/PMU will supervise a third-party contractor who shall develop and implement an integrated environment management system which is based on the following principles:

- 1) Avoiding of negative environmental effects (prevention)
- 2) Reduction of negative environmental impacts
- 3) Recycling of materials and substances
- 4) Disposal of unavoidable residuals.

The environmental performance of the Project as prescribed in the ECC and other permits will be legally responsible by the project proponent, DWIR. The project proponent will report to MONREC on the relevant project environmental and social performance, and also to other funding authorities which is responsible for specific environmental and social issues.

Specifically, the Project Proponent will have the following responsibilities during the construction phase;

- 1) Ensure that the Contractor(s) will update a detailed ESMP based on the results of detailed design, construction plan, and construction schedule.

- 2) Establish and operate an environmental and social management system (ESMS) containing elements
- 3) Supervise the Contractor closely in implementing the ESMP as an integral part of its project implementation management and construction supervision.
- 4) Submit periodic monitoring and audit reports to MONREC as required in the EIA Procedure.
- 5) Notwithstanding the periodic monitoring reports to be submitted to MONREC, keep MONREC and other concerned authorities informed of any serious environmental events and responses to the events.
- 6) Conduct periodic audit of environmental and social performances of the Contractor.

7.4.3 Contractor(s) &(Sub-contractors)

Following are the primary responsibilities of the Contractor(s) (and sub-contractors):

- a) Ensure to satisfy the environmental and social requirements included in this ESMP through implementing provisions and with the advice from Environmental and Social Consultant (as applicable) during the planning and execution of the project works
- b) Promote environmental awareness and understanding among employees through training, identification of roles and responsibilities towards environmental and social management and linking project environmental and social performance to the overall performance evaluation of the responsible staff;
- c) Work with local communities and project-affected stakeholders to ensure that they benefit as a result of project development by being offered employment to the local community members/ taking part in the On-site Project Implementation Committee (OPIC) throughout the project implementation
- d) Support the DWIR/PMU appointed Environmental and Social Consultant(s) (as applicable) during his/her site visits and monitoring activities
- e) Report immediately any irregularity or issue that might cause environmental problems (such as fuel leakage or pollution) or social conflict (such as complaint from the local community) to PMU/DWIR and/or the Environmental and Social Consultant (as applicable) for an appropriate remediation and report/inform to DWIR/PMU for a decision to implement the remediation.

7.4.4 Environmental and Social Consultant(s) (as applicable)

Following are the primary responsibilities of the Environmental and Social Consultant(s), as applicable:

- a) Provide ongoing support to the PMU/DWIR to supervise Contractor's performance in Environmental and Social aspects;
- b) Provide training to the Contractor's staff on Environmental and Social, Health and Safety Codes of Practices and their application;
- c) Provide advice to the Contractor on the preparation of specific management plan required by this ESMP
- d) Carry out environmental monitoring and prepare [quarterly/monthly/weekly-TBC] observation and monitoring records to feed into periodic (monthly-TBC) ESMP Reporting and submit the report to PMU/DWIR;

- e) Provide support for PMU/DWIR and Contractor on mitigation of any unforeseen or environmental and social impact identified during the project implementation in coordinating with the engineering supervision specialist;
- f) Participate in OPIC meetings and additional stakeholder consultation as required

7.4.5 On-site Project Implementation Committee (OPIC) - TBC

OPIC will be the key institutional arrangement facilitating communication and addressing concerns of local stakeholders related to the construction site and project management. The PMU/DWIR will chair the committee and will hold a [fortnightly-TBC] update on-site meeting and/or initiate further meetings to address any pressing issue. In addition, the OPIC shall be considered as a platform for identifying and addressing grievances reported by the members of local communities or other stakeholders.

7.5 Key Legal Requirements of the Project

Environmental management of the Project during construction and operation will comply with the national or international environmental guidelines and standards as appropriate together with the compliance of ECDF Safeguard Policy.

Table 7.5-1: Environmental Impact Assessment Procedure (2015)

Title	Relevant Articles
Content of the EMPs	60, 63 (8.0)
Project Approval Requirements	
- Issuance of an ECC	67
- Conditions of the ECC	76, 77, 78, 80, 81, 82, 83, 84, 86, 87, 88
- Submission of an CEMP and OEMP	82, 84
- Revision and updating the EMPs	84, 87, 88, 89
- Implementing the EMPs	93, 94
Monitoring and Reporting	
- Responsibility for Monitoring	95, 96
- Content of Monitoring Report	98
- Submission of Monitoring Report	97
- Disclosure of Monitoring Report	99
- Inspection by MOECF	100-111

Table 7.5-2: Ambient Air Quality Standards (National Emission Quality Guidelines)

Parameter	Averaging Period	Guideline Value $\mu\text{g}/\text{m}^3$
Particulate matter PM_{10} ^a	1-year	20
	24-hour	50
Particulate matter $\text{PM}_{2.5}$ ^b	1-year	10
	24-hour	25
Sulfur dioxide	24-hour	20
	10-minute	500

^a Particulate matter 10 micrometers or less in diameter

^b Particulate matter 2.5 micrometers or less in diameter

Table 7.5-3: WHO Ambient Air Quality Guidelines

Parameter	Averaging Period	Period Guideline Value in mg/m ³
Sulfur dioxide (SO ₂)	24-hour	125 (Interim target -1) 50 (Interim target-2) 20 (guideline)
	10 minute	500 (guideline)
Nitrogen dioxide (NO ₂)	1-year	40 (guideline)
	1-hour	200 (guideline)
Particulate Matter PM ₁₀	1-year	70 (Interim target-1) 50 (Interim target-2) 30 (Interim target-3) 20 (guideline)
	24-hour	150 (Interim target -1) 100 (Interim target -2) 75 (Interim target-3) 50 (guideline)
Particulate Matter PM _{2.5}	1-year	35 (Interim target-1) 25 (Interim target-2) 15 (Interim target-3) 10 (guideline)
	24-hour	75 (Interim target-1) 50 (Interim target-2) 37.5 (Interim target-3) 25 (guideline)
Ozone	8-hour daily maximum	160 (Interim target -1) 100 (guideline)

Table 7.5-4: Noise Level (National Emission Quality Guidelines)

Receptor	One Hour LAeq (dBA)	
	Daytime (7:00-22:00) (10:00-22:00 for public holidays)	Nighttime (22:00-7:00) (22:00-10:00 for public holidays)
Residential, institutional, educational	55	45
Industrial, commercial	70	70

Table 7.5-5: Indicative Values for Treated Sanitary Sewage Discharges ^a

Pollutants	Units	Guideline Value
pH	pH	6 – 9
BOD	mg/l	30
COD	mg/l	125
Total Nitrogen	mg/l	10
Total Phosphorus	mg/l	2
Oils and Grease	mg/l	10
Total Suspended Solids	mg/l	50
Total Coliform Bacteria	MPN ^b / 100 ml	400 ^a

Notes: ^a Not applicable to centralized, municipal, wastewater treatment systems which are included in EHS Guidelines for Water and Sanitation.

^b MPN = Most Probable Number

Table 7.5-6: Summary of Recommended Personal Protective Equipment According to Hazard (IFC-EHS)¹

Objective	Workplace Hazards	Hazards Suggested PPE
Eye and face protection	Flying particles, molten metal, liquid chemicals, gases or vapors, light radiation.	Safety glasses with side- shields, protective shades, etc.
Head protection	Falling objects, inadequate height clearance, and overhead power cords.	Plastic helmets with top and side impact protection.
Hearing protection	Noise, ultra-sound.	Hearing protectors (ear plugs or ear muffs).
Foot protection	Falling or rolling objects, pointed objects. Corrosive or hot liquids.	Safety shoes or boots for protection against moving & falling objects, liquids and chemicals.
Hand protection	Hazardous materials, cuts or lacerations, vibrations, extreme temperatures.	Gloves made of rubber or synthetic materials (Neoprene), leather, steel, insulating materials, etc.
Respiratory protection	Dust, fogs, fumes, mists, gases, smokes, vapors.	Facemasks with appropriate filters for dust removal and air purification (chemicals, mists, vapors and gases). Single or multi-gas personal monitors, if available.
	Oxygen deficiency	Portable or supplied air (fixed lines). On-site rescue equipment.
Body/leg protection	Extreme temperatures, hazardous materials, biological agents, cutting and laceration.	Insulating clothing, body suits, aprons etc. of appropriate materials.

7.6 Environmental and Social Management and Monitoring Plan (ESMMP)

Mitigation of the construction phase for environmental and social impacts will be managed under an Environmental and Social Management and Monitoring Plan (ESMMP).

A contractor(s) responsible for carrying out the proposed project will be primarily responsible for executing the ESMP. The Contractor(s) together with the PMU/DWIR (and if necessary, the external environmental and social consultant will be hired by the PMU/DWIR) will ensure that the environmental awareness of project personnel is maintained through appropriate instruction/training in the Environmental, and Social, Health and Safety Codes of Practices.

A [monthly/weekly/daily] compliance report on ESMP implementation will be submitted to PMU/DWIR by the Contractor as part of the project implementation progress report. In case the external environmental and social consultants are hired by the PMU/DWIR, [monthly/weekly/daily] compliance report on ESMP implementation shall be submitted to PMU/DWIR in addition.

Incident Register and Complaint Register will be established by PMU/DWIR to keep record of all irregularities and issues of concern. In case of Contractor's failure to respond directly to complaints or accommodate reported grievances, any affected person can report its concern to [the On-site Project Implementation Committee (OPIC)] involving the PMU/DWIR.

[On-site Project Implementation Committee (OPIC)] will be established upon the initiative of the PMU/DWIR and following stakeholders are to be invited:

- Village Leaders and local representatives and administrator of the four affected townships

¹Environmental, Health, and Safety (EHS) Guidelines GENERAL EHS GUIDELINES: OCCUPATIONAL HEALTH AND SAFETY

- DWIR Office
- Department of Labour
- Police
- Contractor's staff (work crew manager and supervisor)

The roles and responsibilities of key actors in the context of this ESMP are further specified below.

The main measures that can be considered are outlined in Table 7.6-1.

Table 7.6-1: Mitigation and Management Measures

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
Pre-Construction				
Environmentally responsible procurement	ESMP is reflected in Detail Design and related procurement documents to reduce environmental social impacts	ESMP is reflected and updated in Detail Design Report and included in tender documents to ensure that mitigation measures are budgeted and to prepare the contractors	-Monitor the Detail Design Report and tender documents whether to reflect ESMP.	DWIR, Engineering Consultant
Construction Management Plan	Including environmental requirements in CMP and contractors will take important role to fully reflect Environmental Social Management Framework	Specify in CMP that Contractors and Consultants shall engage capable to take responsibility for the ESMP and safety issues at the construction level and to monitor the effectiveness and review the mitigation measures Any recommendations and initiatives from DWIR, MONREC or other stakeholders will be incorporated in the CMP	-Monitor the CMP	DWIR, Engineering Consultant
Socioeconomic Impacts	Land acquisition and involuntary resettlement (for land clearing, equipment mobilization and access road development (if applicable))	The mitigation measures will be resettlement of project affected people to new sites nearby and compensation for the loss of land and crops, and livelihood development assistance. The detailed measures are presented in the framework (and later updated) resettlement action plan (RAP).	- Monitor the resettlement procedure and its adequacy in accordance with RAP.	DWIR, in close cooperation with Land Compensation and Resettlement Committees of each township
Info disclosure, consultation	PAPs, communities and other major stakeholders are informed of the project and its progress and have access to the grievance address mechanism as well	Put up the project overview and ESIA and RAP information at: 1) DWIR Internet website; 2) Public places (GAD office, Townhalls, clinics etc.) and major convening locations of the affected four townships all time. Set up GRM mechanism and operationalize it all through the project cycles.	- Monitor the public information disclosure, consultation and GRM operationalization on a regular basis, whose summary shall be reflected in the self-monitoring report submitted by the DWIR to MONREC-EMB	DWIR (and MONREC-EMB to review)
Construction				
Air Quality (NO ₂ , PM ₁₀ , SO ₂)	-Increases in air pollutants caused by fugitive dust from rock blasting, site excavation, and emissions from operation of vehicles and trucks and heavy	- Spray water at and around the construction areas and access roads during site preparation and grading. - Enforce a speed limit for vehicles and trucks in the construction sites not to exceed 40 km/hr.	Ambient air quality at the main construction site (Quarterly)	EHS Manager (Contractor)

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
	<p>construction equipment.</p> <ul style="list-style-type: none"> - Occupational health concern for construction workers and community health lived in the closed surroundings of the construction site are expected. 	<ul style="list-style-type: none"> - Construction activities shall be kept as planned so that the disturbed areas will be minimized at any time. - Restore, resurface, and rehabilitate the disturbed areas as soon as practicable after completion of construction or disturbance. - Prohibit the open burning of waste in the construction area. - Dust masks should be provided (where applicable) to all construction workers. - Cover construction materials by canvas during transportation, if necessary, before transportation. - Establish a vehicle washing facilities to minimize the quantity of material deposition on public roads. - Establish a checkpoint at project gate to ensure the vehicles leaving the project site are following the measures prescribed to reduce dust emissions. - Adopt procedures to avoid construction vehicles idling for excessive periods (e.g. more than 5 minutes) if required to queue to enter the construction sites; - Maintain all construction equipment in proper working conditions according to the manufacturer's specifications. - The engines of the construction equipment fleet must be routinely maintained by qualified mechanics to ensure their proper conditions during operations. - Provide adequate training to the equipment operators in the proper use of equipment. - Use the equipment fitted engines with latest low emission technologies (repowered engines, electric drive trains). For example, the diesel generator set to be used must be equipped with modern pollution control equipment. - Check vehicle and equipment inspection daily; -Stop dust generating activities in high wind. -Turn off the engine while not in use. -Optimize construction schedule to minimize time that vehicles are in operation. 	<p>Daily check appropriate conducting air quality mitigation during construction.</p>	

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
Noise and Vibration	<ul style="list-style-type: none"> - Increase ambient noise level at the construction site, and communities near the material transport routes, especially, the poor buildings which could be destroyed by vibration. -Long-term noise exposure will reduce hearing and labor productivity, and will cause fatigue, stress, and insomnia. 	<ul style="list-style-type: none"> - Major construction activities which generate loud noise should be limited to only during the daytime. - Activities that are necessary to be carried out at nighttime will need approval of the site engineers and will need to have adequate noise control equipment or measures. - Speeds of vehicles in the construction site will not be more than 40 km/hr. - Noise performance requirements of construction equipment will need to be clearly stated in contract specifications. - Select adequate equipment (fit with noise mufflers). - Minimize machinery and equipment unused conditions with engines in action. - Maintain machinery and equipment in good conditions. - Post warning signs within the vicinity of the impact and all personnel shall be provided with personal protective equipment. For example, workers operating equipment that generates noise should be equipped with the appropriate noise protection gear. - To restrict the construction activities that will generate disturbing sounds to normal working hours. - Need to include an efficient complaints redress procedure and an efficient corrective action procedure to address the non-compliance of noise performance. 	<p>Ambient Noise level at day and night times at the construction receptor site (Quarterly)</p> <p>Daily check appropriate conducting noise mitigation during construction.</p>	EHS Manager (Contractor)
Water Quality (pH, COD, BOD, TSS)	<ul style="list-style-type: none"> - Increase turbidity of canal water due to construction activities and canal bed excavation or dredging. - Degradation of canal water quality due to inappropriate management of construction wastes and domestic waste from camp site. - Impacts on canal water availability and accessibility with respect to the water 	<ul style="list-style-type: none"> - The contractor will be required to implement the best management practices in reducing the impacts on water turbidity caused by excavation - Reducing the dredging rate; - Changing dredging operations based on site conditions such as currents and wind; - Using a sequence of dredging such as moving upstream to downstream; and - Changing the number of vertical cuts (passes) to increase sediment capture. 	Canal water quality will need to be monitored during the construction period (Quarterly)	EHS Manager (Contractor)

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
	<p>needs requested by the Project, during the construction phase.</p> <p>-Impacts on groundwater quality as a result of construction activities such as deep foundation and piling works, and discharges.</p>	<ul style="list-style-type: none"> - Silt screens and silt curtains may be the main engineered controls (if necessary). - The site preparation activities, including land clearing and site filling and compaction, should be carried out during the dry season to avoid the problem of surface runoff with high turbidity discharging into the surrounding paddy field or nearby drainage channels, if applicable. - Direct runoff away from disturbed areas by means of temporary drainage ways, utilizing for example cut-off drains; - Design of store hazardous material providing suitable reception facility with impervious flooring, roofing and suitable drainage control; - Regular maintenance and checking of all machinery and vehicles in order to minimize the risk of fuel or lubricant leakages; - No discharge of untreated wastewater to soil and groundwater and onto surface water bodies; - As construction activities typically generate disturbed soil, concrete fines, oils and other waste, on-site collection and settling of stormwater, prohibition of equipment washes down, and prevention of soil loss from the construction site are necessary to minimize water pollution. - Provide training and equipping relevant staff in protected storage and handling practices, and rapid spill response and clean up techniques. 		
Solid Wastes (nonhazardous wastes, hazardous)	Various types of solid construction wastes are likely to occur during the implementation stage of the project construction.	-A waste management plan shall be developed including requirements for source separation, collection with the adequate solid waste containers, handling and disposal of all waste generated.	Construction Site and worker camp (Daily)	EHS Manager (Contractor)

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
wastes, office wastes, composting wastes, other domestic wastes)		<ul style="list-style-type: none"> -The containers shall be labeled or separated by colors: red for hazardous wastes, yellow for office wastes, green for organic and composting wastes. -All hazardous materials shall be stored in clearly and specially labeled containers. - Storage and handling of hazardous materials should be in accordance with national and local regulations appropriate to their hazard characteristics. - Waste shall be separated on site and waste storage areas shall be roofed and bounded to prevent potential cross-contamination. - Spent oil (including transformer oil) shall be recycled. - Fire prevention systems and secondary containment shall be provided for storage facilities, where necessary, to prevent fires or releases of hazardous materials. - All waste shall be disposed of in line with local requirements at a suitable and licensed waste disposal facility. - Suitable disposal sites shall be identified with capacities for disposal for general and hazardous waste prior to the operation phase. 		
Soil Quality	<ul style="list-style-type: none"> -The accidental spillage of oil from vehicles used for transportation of construction material and accidental spillage from the building material used for construction purposes are also considered as soil contamination sources. -Soil erosion during the construction phase is expected that can indirectly impact to natural archaeological and/or landscape values. 	<ul style="list-style-type: none"> - Prevent soil contamination by oil or grease spills, leakages or releases, all manipulations of oil derivate in the process of construction and provision of fuel to the machines should be performed with maximum attention. - Leak proof containers should be used for storage and transportation of oil/grease and wash off from the oil/grease handling area shall be drained through drains and treated properly before disposal. - Construction waste and debris shall be collected on a regular basis, covered by roof and disposed of at designated landfills. 	Construction site (twice a year)	DWIR

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
		<ul style="list-style-type: none"> - Prohibit to operate with equipment and vehicles outside the designated work areas and roads. - Training and equipment will be in place to minimize the potential environmental impact in the case of accidents (for example using spill kits). 		
Ecological Components	<ul style="list-style-type: none"> -A removal of the herbaceous plant and topsoil will generally cause erosion of ground surface of the earth. -The increase in turbidity and subsequent sedimentation downstream will affect all aquatic organisms such as plankton, benthic organisms and fish. - The regional fauna species are also expected to face loss of their habitats due to clearance of vegetations in 30 m ROW along the canal. 	<ul style="list-style-type: none"> - Routine checking of trenches (if any) and escape routes. - Preservation of excavated top-soil for future site restoration procedures particularly in highly disturbed areas. - Reporting of any violation relating to hunting and trading activities. - Minimize vegetation clearance and habitat disturbance by demarcating the clearing boundaries in the construction site. - Avoid unnecessary clearing of the trees- Environmental awareness training for all workers to preserve local biodiversity species and induct the nature of the sensitivity of the project area. - Site specific instruction/protocol for identifying and relocation of plant and wildlife species if necessary, shall be provided to all workers with education materials including photographs. - Work areas in temporarily affected areas shall be reinstated with tree/shrub/grass upon completion of the works. - Strict enforcement of the workers in the construction camp not to allow the fishing in the water resources near the project area. - Establish mangrove habitat protection measures the project area if necessary, establish replanting plan 	ROW of canal (30 m) (Replantation after project establishment)	DWIR

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
Socioeconomic Impacts	-Land acquisition and potential involuntary relocation are expected.	- The mitigation measures will be resettlement of project affected people to new sites nearby and compensation for the loss of land and crops, and livelihood development assistance. More detailed measures are presented in the framework resettlement action plan (Framework RAP) and to be updated later (for full RAP).	- Monitor the resettlement procedure and its adequacy in accordance with RAP.	DWIR, in close cooperation with Land Compensation and Resettlement Committees of each township
	-For those whose source of income and livelihood are significantly dependent upon the Twante Canal and the adjacent land subject to acquisition, economic activities can be interrupted, which could threaten the living of PAPs.	-Initiate livelihood development programs designed to make the best use of new economic opportunities that will come with the project spending and employment. - Prepare alternative ways of making a living, utilizing the non-construction parts of the canal at the detailed design stage. (e.g. identifying and providing alternative agricultural irrigation channel (flow) from the canal to the nearby farms and rice paddies)	- Monitor the implementation of livelihood development programs - Check if there will be any available non-construction parts during the detailed design and establish additional measures to make a living, on the basis of consultation with PAPs.	DWIR, in close cooperation with GADs of each affected township
	- Traffic congestion and related problems can happen during construction, including movement constraint and inconvenience.	- Establish a Traffic Management Plan (TMP) in close coordination with the traffic regulations by local/regional traffic authority. in order to: 1) Minimize traffic risks on the existing access roads 2) Build additional access roads to the project site to disperse the total traffic	- Monitor TMP implementation - Address grievances related to the traffic disturbances, if triggered	DWIR, in close cooperation with local/regional traffic authorities
	-Safety problems on construction workers and residents of local communities	-Build fences surrounding the construction site - Conduct training programs on safety issues for workers, and if necessary, for residents as well - Distribute safety equipment and encourage to wear it	- Monitor the safety regulations and ensure that workers and residents follow them. - Check the fence regularly.	DWIR in close coordination with the Contractor.
	- Disturbance to the shipyard business (in Khanaungto Township)	-Adjust ROW to minimize the damage on buildings and facilities of existing shipyards	- Monitor the construction will be	DWIR, in close cooperation with

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
		- Identify other mitigation measures to temporary or permanent loss of incomes and livelihoods of the affected communities, as appropriate	carried out as planned. - Ensure GRM operates properly.	GADs of Seikkyi Khanaungto township
Info disclosure, consultation	PAPs, communities and other major stakeholders are informed of the project and its progress as well as have access to the grievance address mechanism.	Put up the project overview and ESIA and RAP information at: 1) DWIR Internet website; 2) Public places (GAD office, Townhalls, clinics etc.) and major convening locations of the affected four townships all time. Set up GRM mechanism and operationalize it all through the project cycles.	- Monitor the public information disclosure, consultation and GRM operationalization on a regular basis, whose summary shall be reflected in the self-monitoring report submitted by the DWIR to MONREC-EMB.	DWIR (and MONREC-EMB to review)
Operation				
Air Quality	-The Project will have no air pollution during its operations.	No mitigation measures will be required.	-	DWIR
Noise and Vibration	The water vehicles along the canal will be likely to produce. During the operation phase, vibration will mainly be generated by inbound-outbound traffic. The vibration levels would not exceed the control target.	No mitigation measures will be required.	-	DWIR
Water Quality	The project will have no impact on water quality.	DWIR will have to control any disturb to avoid canal water contamination.	Regular check	DWIR
Biodiversity	The project will have no impact on any biological component.	The potential negative impacts will have to be controlled through canal operational management to flush out aquatic plants, if necessary.	Regular check	DWIR
Socioeconomic Impacts	Increase of visitors through the inland waterway transportation.	Public security system will be supported in compliance with the Government guidelines.	Regular check	Administrative Department
Info disclosure, consultation	PAPs, communities and other major stakeholders are informed of the project and its progress as well as have access to the grievance address mechanism.	Put up the project overview and ESIA and RAP information at: 1) DWIR Internet website; 2) Public places (GAD office, Townhalls, clinics etc.) and major convening locations of the affected four townships all the time Set up GRM mechanism and operationalize it all through	- Monitor the public information disclosure, consultation and GRM operationalization on a regular basis, whose summary shall be	DWIR (and MONREC-EMB to review)

Indicators	Impacts	Mitigation Measures	Proposed Monitoring Plan	Responsible Institution
		the project cycles.	reflected in the self-monitoring report submitted by the DWIR to MONREC-EMB	

7.6.1 Monitoring, Evaluation and Reporting

7.6.1.1 Overall Budget for Implementation of the ESMP

All mitigation measures to be implemented in the construction will be included in the contract cost. As most mitigation measures are operation control measures, it is not possible to estimate their costs.

7.6.1.2 Monitoring Costs

During the construction phase, a budget of about US\$ 53,370 equivalents per year will be allocated for monitoring and evaluation of the Project's environmental and social performance over the construction period of 5 years.

During the operational phase, an annual budget of about US\$ 25,850 will be allocated for monitoring activities.

Table 7.6.2: Indicative Budget Allocation for ESMP

Indicator (Survey item)	Location of Data Collection	Method and Frequency	Institution	Annual Cost (USD)
Construction Phase				
Monitoring EMP implementation <input type="checkbox"/> Mitigation measures <input type="checkbox"/> Enhancement measures <input type="checkbox"/> Contingency <input type="checkbox"/> Compensation	Project area	Daily monitoring and documenting, and quarterly reporting	DWIR	14,400
Air quality (NO ₂ , SO ₂ , PM ₁₀)	locations (same as baseline data collection locations)	Quarterly	Third Party	19,500
Noise	locations (same as baseline data collection locations)	Quarterly	Third Party	10,755
Surface Water Quality Analysis (Parameter are same as IFC standard) (pH, COD, BOD, TSS)	Locations and number of samples are same as baseline data collection	Quarterly	Third Party	8,715
Operation Phase				
Implementation of Ecosystem Management plan	Within project area	Regular monitoring and quarterly report	DWIR	10,350
Occupational Health and Safety	Construction Site	Twice per year Record of accidents and infectious diseases	Contractor	1,250
Community Health and Safety	villages nearby the project sites	Twice per year Record of accidents and infectious diseases related to the community	DWIR	14,250

7.6.2 Management Sub-plans during Construction and Operation Phases

The construction phase impacts are varied based on the progress of construction activities in terms of impact types, magnitudes, duration and locations in the environment.

The following parameters will be reflected for the changes in construction phase management as necessary:

- (i) General construction
- (ii) Fugitive dust and air quality management
- (iii) Noise and vibration
- (iv) Soil Erosion and Drainage Management
- (v) Construction waste management
- (vi) Domestic Wastewater Management Plan
- (vii) Traffic management
- (viii) OHS and Social Environment

(i) General Construction

Component	Contents
Objectives	Manage construction in accordance with the Construction EMP and CEMP sub-plans to avoid or minimize impacts on the environment and the community.
Performance Criteria	<ul style="list-style-type: none"> • To prepare the worksites in accordance with designs providing for the management and mitigation of construction impacts • To manage the construction works to avoid or mitigate and manage impacts on the amenity and environmental conditions prevailing in the vicinity of the worksites • To minimize and avoid the non-compliance of EMP guidelines and standards • To keep safe and efficient access near worksites for emergency vehicles • to minimize potential construction risks to construction workers, to the general public in adjacent areas and to the environment.
Mitigation Measures	<p>Working hours:</p> <ul style="list-style-type: none"> • The excessive noise & vibration and dust generation activities shall be undertaken during the hours of between 6.30 am and 6.30 pm and public holidays are expected for workers only for the special circumstances. • Special circumstances include works on transport of heavy and large process equipment to the construction sites, transport of materials for site filling, and transport of large construction equipment to the construction sites. • The local residents shall be notified for duration and timing of works to be conducted outside of usual working hours. <p>Construction worksites:</p> <ul style="list-style-type: none"> • Design the management plan for the construction works to mitigate the construction impacts • The main construction site will include canteen with adequate space and facilities for eating and washing, decent worker accommodation, adequate number of hygienic toilets and baths, adequate clean piped water supply, drainage, wastewater disposal facilities, solid waste disposal facilities, material storage, equipment sheds, vehicle washing areas and project management offices. • Spoil handling, storage and loading will be conducted at all times within enclosures designed and constructed to achieve environmental objectives and performance criteria for noise and air quality as set out in the EMP; • Night lighting, including security lighting will be included to avoid light spill onto adjoining premises measured at the common boundary; • Fencing will be established to worksite boundaries to ensure site security and public safety.
Monitoring	Site inspections will be conducted as outlined in this EMP.
Reporting	• Results of site inspections will be included in the environmental monitoring reports.

(ii) Air Quality Management Plan

Objectives	<ul style="list-style-type: none">▪ To maintain the ambient air quality in the construction sites and at the identified sensitive receptors meets the prescribed standards throughout the construction period▪ To address the community concerns and complaints about air quality quickly and effectively.
Legal Requirements	National Environmental Quality (Emission) Guidelines, 2015 Yangon City Development Committee Law, 2018
Implementation Schedule	Construction phase of the project
Management Action	<ul style="list-style-type: none">▪ Keep construction equipment and generators in good operating condition▪ Keep vehicles under good condition, with regular checking of vehicle condition to ensure compliance with national standards▪ Adopt machine and equipment that energy saving and create less pollution▪ Proper storage including covering of sand, gravel and other materials which are easily spread into the atmosphere▪ Sprinkle and cover stockpiles▪ Clean construction sites, especially near site entrance▪ Cover top of trucks carrying materials to the site and carrying construction debris away from the site▪ Protect of all works and materials by installing green net or other measures that will prevent dust from spreading around▪ Dust mask will be provided to the construction workers working in dusty areas
Responsibilities	Staff of Contractor's HSE Department under the guidance of DWIR

(iii) Noise & Vibration Management Plan

Objectives	<ul style="list-style-type: none">▪ To minimize noise and vibration of construction activities from operation of construction machinery to generate the level of noise increase at the nearby affected residents and sensitive receptors (e.g. schools, hospitals and monastery)▪ To ensure that the noise and vibration levels at the identified sensitive receptors will not exceed the maximum limits prescribed by MOECAP as a condition of the ECC and will be acceptable to the sensitive receptors.
Legal Requirements	National Environmental Quality (Emission) Guidelines, 2015 Yangon City Development Committee Law, 2018
Implementation Schedule	Construction phase of the project
Management Action	<ul style="list-style-type: none">▪ Routine maintenance of vehicles and construction equipment▪ Schedule deliveries during non-school hours and after regular working hours▪ Install barrier fences during construction to reduce noise disturbance, especially near sensitive receptors▪ Develop working rules so as to, for example, avoid unnecessary use of air-horns, keep to the speed limit, turn off engines when not in operation and train drivers and operators to follow the rules▪ Schedule to avoid much equipment operating at the same time near sensitive receptors▪ Avoid, as much as possible, construction equipment producing excessive noise during school hours▪ Avoid prolonged exposure to noise (produced by equipment) by workers

	<ul style="list-style-type: none"> Supply construction workers who will be operating noisy equipment with appropriate personal noise protection gear (e.g. earmuffs, ear plugs, etc.)
Responsibilities	Staff of Contractor's HSE Department under the guidance of DWIR

(iv) Soil Erosion and Drainage Management Plan

Objectives	<ul style="list-style-type: none"> To control and prevent surface water quality in case of soil erosion To prevent flash flooding in construction site during heavy rain
Legal Requirements	Environmental Conservation Law, 2012 Yangon City Development Committee Law, 2018
Implementation Schedule	Construction phase of the project
Management Action	<ul style="list-style-type: none"> Ensure that the existing protected trees will not be damaged during the progress of construction works Adequate temporary drainage channels will be constructed to help facilitate the outflow of onsite runoff to existing drainage facilities. These temporary drainage channels will be constructed in such a manner that they, <ul style="list-style-type: none"> (a) feed into existing, offsite, natural/engineered drains and (b) do not result in compromise and overtopping of existing offsite drainage features Storm water should be controlled (channeled), before it enters the site, to ensure that the processing plant is not jeopardized during heavy rains.
Responsibilities	Staff of Contractor's HSE Department under the guidance of DWIR

(v) Construction Waste Management Plan

Objectives	<ul style="list-style-type: none"> To minimize all types of wastes generated at the construction sites To control and prevent groundwater quality in case of dumping of solid waste
Legal Requirements	Environmental Conservation Law, 2012 Yangon City Development Committee Law, 2018
Implementation Schedule	Construction phase of the project
Management Action	<ul style="list-style-type: none"> Comply with waste management rule under township development committee for disposing waste at disposal site Prepare a temporary waste dumping site during storage Install a signboard to prohibit waste dumping in inappropriate areas Collect residues of oils, including lubricating oil Prohibit placing materials (e.g. soil, gravel, and sand) on roadside or any other areas outside the project site Reuse sand materials for road improvement and others Arrange garbage bin for general waste and hazardous waste separately General waste will be cleaned out once per week and hazardous waste will be clean out once per month
Responsibilities	Staff of Contractor's HSE Department under the guidance of DWIR

(vi) Domestic Wastewater Management Plan

Objectives	<ul style="list-style-type: none"> To ensure that all wastewater generated during the construction will be adequately treated before discharge into the river
Legal Requirements	Environmental Conservation Law, 2012 Yangon City Development Committee Law, 2018

Implementation Schedule	Construction and operation phases of the project
Management Action	<ul style="list-style-type: none"> ▪ Regular maintenance and checking of all vehicles and machinery to minimize the risk of fuel or lubricant leakages ▪ As construction activities typically generate disturbed soil, concrete fines, oils and other waste, on-site collection and settling of storm water, prohibition of equipment washes down, and prevention of soil loss and toxic releases from the construction site are necessary to minimize water pollution; and ▪ Training and equipping relevant staff in protected storage and handling practices, and rapid spill response and clean up techniques ▪ Prepare proper sewage system of existing toilets ▪ The contractor will procure portable toilets and locate them at the construction site if the existing toilets may not enough for construction workers ▪ Wastewater generated from washing of concrete mixer and machines will be stored in the special storage (e.g. fiber drum) and send to the designated treated place after discussion with YCDC
Responsibilities	Staff of Contractor's HSE Department under the guidance of DWIR

(vii) Traffic Safety Plan

Objectives	<ul style="list-style-type: none"> ▪ Manage construction traffic and transport issues to minimize potential impacts on the communities and the operation of the road network
Legal Requirements	NA
Implementation Schedule	Construction Phase of the Project
Management Action	<ul style="list-style-type: none"> ▪ Install traffic signs and warnings at the entrance and exit gates for vehicles and heavy equipment ▪ Provide adequate parking lots at the construction site and to forbid parking vehicles on the roadside ▪ Arrange a schedule of mobilization of equipment to avoid increasing traffic congestion and to avoid busy hours ▪ Coordinate with the traffic police to manage the traffic during traffic congestion period ▪ Reduce speed limit to 10 km per hour within the sensitive receptors zone, e.g. school zones
Responsibilities	Contractor (Monitoring by HSE section and/or third party)

(viii) OHS and Social Environment

Objectives	<ul style="list-style-type: none"> ▪ To avoid or mitigate and manage construction impacts on the social environment. <p>Note: The social environment includes residential and neighborhood amenity, connectivity, community health, community diversity, social infrastructure provision, and safety.</p>
Legal Requirements	Occupational Safety and Health Law (2019) Environmental Impact Assessment Procedure (2015)
Implementation Schedule	Construction and operation Phases of the project
Management Action	<ul style="list-style-type: none"> ▪ Liaise with key stakeholders and the community through a public consultation process to ensure insignificant impacts of the construction on community facilities, schools, and public transport stations, ▪ As soon as is practicable after the completion of construction, the Contractor shall reinstate community facilities affected by the works, if any. ▪ Consult with managers of community facilities in neighborhoods adjacent

	<p>to worksites to develop effective mitigation strategies and maintain regular communication with these facility managers.</p> <ul style="list-style-type: none"> ▪ Develop an effective and responsive system for receiving, handling and responding to complaints received during the construction of project works. ▪ Ensure complaints are received and responded to around the clock for the duration of the construction phase. ▪ Provide reporting on complaints received, responses provided, timeliness of responses, and corrective actions taken on a monthly basis. ▪ Raise community awareness on the complaints systems and procedures through public notifications and website facilities. ▪ Initiate consultation with owners and occupants of directly affected properties and nearest neighbors to construction activities as soon as practicable before commencing the construction. ▪ Conduct consultation and community information strategies in conjunction with the public or community consultation process. ▪ Establish a tripartite committee to provide mechanism and channel for the committees to participate in the project environmental management. ▪ Undertake and maintain a comprehensive community information program to inform residents, businesses, community groups and motorists of Project activities and potential impacts. ▪ Ensure medical facilities, childcare centers, community centers and schools along the construction corridors have access to construction updates and community education during the construction. ▪ Monitor traffic volumes and traffic congestion affecting the regional population during construction and if necessary, adopt travel demand and signal stage management strategies. ▪ Evaluate effectiveness of consultation, liaison and mitigation outcomes. <ul style="list-style-type: none"> • Cases of conflicts between the construction workers and local people. • Survey and report on actual impacts of the construction on community amenities and infrastructure. • Report community consultation's activities and on consultation, liaison and environmental compliance and public transport access in work site neighborhoods.
Responsibilities	Contractor, DWIR and Township Development Committee

7.6.3 Schedules

The schedule for implementing the ESMP for both construction and operation phases will be linked to the project schedule. After the Contractor completes the detailed designs and detailed construction plan and schedule, the Contractor should prepare a detailed ESMP within one month. The reporting to MONREC is expected twice a year.

Before commencing the construction, the Contractor will review and update existing data on relevant baseline environmental condition, particularly at locations expected to be affected by the construction. Scheduled monitoring of environmental performance is required throughout the construction phase of the Project to evaluate compliance with legal requirements, the environmental management objectives, and relevant policies, standards and guidelines. The monitoring and evaluation will enable the overall effectiveness of the environmental controls to be determined and allow areas of non-compliance to be identified so corrective actions can be taken. The environmental monitoring plan for each issue to be managed is also presented in each sub-plan. Environmental monitoring will be undertaken according to the following:

- The Contractor's EHS Manager is responsible for implementing the monitoring plans and arranging training and specialist consultants for the monitoring as required.
- The monitoring will be conducted by the Contractor using the approved methods stated in the Contract.
- Environmental results that do not meet the required standards will be managed as per the corrective action process and issued with a non-compliance report.
- The EHS Manager will advise the Contractor Project Manager of any noncompliance from monitoring and will report these to the Owner's EHS Manager as required.

7.6.4 Site Inspections

In addition to scheduled environmental monitoring, the Contractor's EHS Manager will conduct daily, weekly, and monthly general inspections for construction sites. The objectives are to early identify or detect factors which, if unattended to, could result in major environmental events and/or non-compliance. A general scope of inspections is outlined below in Table 7.4-1 and it will need to be updated site specific ESMP when the detailed construction plan is made.

The daily inspections will be informal visual inspections to observe conditions of the construction sites. The focus will be on the construction site where construction activities are concentrated.

The weekly inspections will be formal visual inspections in more details than the daily inspections. The Contractor's EHS Manager will be responsible for the daily and weekly site inspections. The Owner's EHS Manager will participate in the weekly site inspections, and occasionally in the daily site inspections.

The monthly inspections will be conducted in more detail than the weekly inspections. The monthly inspections will also include risk triggers identified in the environmental risk management plan. The monthly inspections will be conducted jointly by personnel from both sides, including the Project Managers, the Construction Manager and the EHS Managers.

- 1) The environmental engineer will undertake regular audits at quarterly intervals and utilize the Contractor's on-site practices and procedures as a means of assessing the ongoing performance of the Contractor. The audits will be conducted based on the ESMP of the Contractor and previous site inspection results.
- 2) In addition to the quarterly audits by the environmental engineer, a weekly site inspection will be undertaken by the Contractor's staff to inspect the construction activities in order to ensure that appropriate environmental protection and pollution control measures are properly followed and implemented.
- 3) The contractor will prepare an environmental monitoring report and submit to DWIR for comments or amendments and consent for adoption. It shall contain a contract specific comprehensive Environment Inspection checklist as the requirement of the ESMP.
- 4) The area of inspection will not be limited to environmental compliance within the site but areas outside the site that are likely to be affected, directly or indirectly by activities at the site.
- 5) The results of the inspection will be discussed with the environmental engineer and his recommendation for a better environmental protection will be provided to the Contractor for immediate action and rapid resolution of identified non-compliance issues.

6) The environmental engineer will carry out *ad hoc* site inspection when necessary, and it is not limited to instances where significant environmental problems are identified, or environmental complaints are received or as a part of the investigation work. The contractor will designate a responsible staff to attend to this inspection.

CHAPTER 8: PUBLIC CONSULTATION AND INFORMATION DISCLOSURE

8.1 Purpose and Objectives

The objective of conducting public consultation and information disclosure is to obtain the suggestions/concerns for appropriate ESIA Study and Environmental and social Management Plan, while ensuring to inform the key stakeholders including the project affected people and communities in a timely manner. In this way, the proposed project could obtain social acceptance by the public and other stakeholders, which will facilitate smooth implementation of the project ahead.

More specifically, PCM (Public Consultation Meeting) conducted as a part of the Scoping Stage and EIA investigation of this Project has three objectives:

- (i) Inform the stakeholders about the Project, its potential positive and negative environmental and social impacts related to the project implementation and preliminary mitigation measures to minimize environmental and social impacts;
- (ii) Seek views and opinions of the stakeholders on the Project, anticipated impacts and according mitigation measures;
- (iii) Ensure participation of and partnership with the key stakeholders to identify major concerns and suggested/agreed solutions for effective environmental and social management of the proposed project. The feedback needs to be duly reflected in the ESIA and the ESMP, whose final output will be disclosed to the stakeholders in a timely manner.

8.2 Procedural Requirements and Summary of the Activities Taken

Public consultation and information disclosure will be conducted in compliance with the EIA Procedure of Myanmar (2015). The Procedure requires two rounds of public consultation and information disclosure activities by the project proponent in the course of the EIA process: during 1) the scoping stage and 2) the EIA preparation stage.

Once the EIA report is completed and submitted by the project proponent to MONREC-ECD, the review and approving body of the EIA, another round of the public information disclosure session is required in coordination with the local government (YRG) and other GADs.

Relevant provisions of the Myanmar EIA Procedure (2015) on the public consultation and information disclosure are quoted in the left column of the table below: the right column indicates the actual activities carried out by the project proponent with the EIA Study Team's technical support for the proposed project. (See the Table 8.2-1 right below.)

All the listed activities were carefully documented and recorded. The details of each of the activities are presented in the following Sections as well as their respective annexes.

Table 8.2-1: Implementation Activities by the Project Proponents and EIA Study Teams

Stage	Myanmar EIA Procedure (2015)	Activities carried out for the Proposed Project	Comments
I. Scoping paper preparation stage	" Article 50. As part of the Scoping, the Project Proponent shall ensure that the following public	1) Two rounds of consultation meetings with Twante, Dala and Seikyi Kanaungto Township GADs	- The overall activities are to get people's attitudes and concerns on the project and to

	<p>consultation and participation process is carried out:</p> <p>a) disclose information about the proposed Project to the public and civil society through posting on the Project or Project Proponent's website(s) and local media, including by means of the prominent posting of legible sign boards and advertising boards at the Project site which are visible to the public; and</p> <p>b) arrange the required complement of consultation meetings as advised by the Ministry, with local communities, potential PAPs, local authorities, community-based organizations, and civil society, and provide appropriate and timely explanations in press conferences and media interviews."</p>	<p>(6 Feb 2018 and 26 April 2018).</p> <p>2) 3 PCMs at Twante (20 Sep 2018), Dala (21 Sep 2018) and Seikyi Kanaungto Township (21 Sep 2018) and Kyimyindaing Township respectively.</p> <p>(Note: Kyimyindaing township was not initially included in the affected area and added after a series of consultation meetings.)</p> <p>3) Announcement posters at the public places (including GAD offices and wards, schools, fire force offices, village head's offices, DWIR offices and public libraries etc.) (See Figure 8.4-6) and national and private newspapers (New Light of Myanmar (Myanmar Ah Lin), the Mirror (Kyaymon) and Daily Eleven in Sep 2018) (See Figure 8.4-64).</p> <p>4) Consultation meetings with the other relevant government agencies including MONREC-ECD (5 Feb 2018), MOC (5 Feb 2018), YDCD (6 Feb 2018), IWTD (7 Feb 2018), MPA (7 Feb 2019) including presentation slides (PPT) of the project overview and preliminary survey results of the expected environmental and social impacts</p>	<p>identify the potential impacts and stakeholders.</p> <p>Some main concerns include:</p> <ul style="list-style-type: none"> - The community people (Pa Thi Village) concerned of their fishery livelihood and jetty for facilitation of public transportation. - Residential people worried about big collapse by the project activities due to past experience during another project construction. - The local people questioned about the compensation plans and their related losses. - Some CSO people need detailed project design. - YCDC people want to explore future plan for the jetty, creek and bridge of this area. - The government officers want to explore the source of project fund and the project supporters.
II. ESIA investigation stage	<p>"Article 61. As part of the EIA investigations, the Project Proponent shall undertake the following consultation process:</p> <p>a) timely disclosure of all relevant information about the proposed Project and its likely Adverse Impacts to the public and civil society through local and national media, the website(s) of the</p>	<p>1) Consultation meeting with the relevant ministries and government agencies including: MPA (12 Dec 2018), MONREC-ECD (13 Dec 2018)</p> <p>2) 4 PCMs at each of the four affected Townships including: Seikkyi-Kanaungto Township (26 Jan 2019), Twante Township (28</p>	<p>The overall activities of these PCMs are to inform the affected community and concerned stakeholders of the potential impacts of environmental and social conditions by the project activities with their related mitigation measures.</p> <p>These PCMs were</p>

	<p>Project or Project Proponent, at public places such as libraries and community halls, and on sign boards at the Project site visible to the public, and provide appropriate and timely explanations in press conferences and media interviews;</p> <p>b) arrange consultation meetings at national, regional, state, Nay Pyi Taw Union Territory and local levels, with PAPs, authorities, community-based organizations and civil society;</p> <p>c) consultations with concerned government organizations including the Ministry, the concerned sector ministry, regional government authorities and others; and</p> <p>d) field visits for the Ministry and concerned government organizations."</p>	<p>Jan 2019), Dala Township (28 Jan 2019), and; Kyimyindaing Township (29 Jan 2019)</p> <p>3) Announcement posters at the public places (including relevant GAD offices and DWIR) (See Figure 8.4-16) and national and private newspapers (New Light of Myanmar (Myanmar Ah Lin), the Mirror (Kyaymon) (20 Jan 2019) (See Figure 8.4-15).</p> <p>4) 2 rounds of FGDs with the shipyard operators' community in Seikiy Kanaugto Township and affected farmers near Twante canal (24 Dec 2018)</p> <p>5) Household perception survey conducted against total 353 households in the four affected households between 29 Oct and 28 Nov 2018, mainly asking the following:</p> <ul style="list-style-type: none"> - Degree of project awareness - The sources of information - Expected benefits and adverse impacts of the project - Further comments, opinions, and suggestions 	<p>conducted in all affected four townships and collected more opinions based on stakeholder concerns.</p> <p>The additional concerns about the project during PCMs are:</p> <ul style="list-style-type: none"> -questions for the resettlement plan and job opportunities for local people during the project implementation -worries about possible incidents in the region like bank erosions and whirlpools in 2012 -willing to build recreation parks between the canal and the town for community development
III. After submission of EIA Report to ECD	<p>"Article 65. Not later than fifteen (15) days after submission of the EIA Report to the Department, the Project Proponent shall disclose the EIA Report to civil society, PAPs, local communities and other concerned stakeholders:</p> <p>(i) by means of national media (i.e. newspapers);</p> <p>(ii) the website(s) of the</p>	<p>This process will take place in the future once the EIA report is completed and submitted to the MONREC-ECD.</p>	-

	Project or Project Proponent; (iii) at public meeting places (e.g. libraries, community halls); and (iv) at the offices of the Project Proponent."		
--	---	--	--

8.3 Identification of Stakeholders and Project Affected Groups

The project is located in the south-western Yangon Region and the townships that are to be directly affected are Twante, Dala, Seikkyi Khanaungto, and Kyimyindaing. For Twante Canal Improvement Project, public consultations led by DWIR, the Project Proponent, were conducted in these four townships respectively.

The stakeholders include the local communities, PAPs, local government authorities, civil society and non-government organizations as well as business associations in the affected localities. Regarding the PAPs, given the current assumptions of the ROW demarcation, about as many as 2,697 households and a number of (about 40) shipyards (in case the current ROW demarcations for the Kanagungto Township is modified in the future) were identified during the preliminary site survey in areas that are subject to be affected by the project implementation. Given the estimation as such, it is expected a full-fledged Resettlement Action Plan (RAP) is expected to be developed in addition to the ESMP¹ (At this stage, we provide an initial (framework) RAP as part of ESIA.

A list of stakeholders of the proposed project is mapped in Table 8.3-1 below, with respective engagement plan:

Table 8.3-1: Preliminary Stakeholder Mapping with Engagement Strategies

No.	Stakeholders	Organizational Analysis & Engagement Strategies (Inform/Consult/Involve/Collaborate)
I. Ministry		
1.	Ministry of Natural Resources and Environmental Conservation (MONREC)	- Director, ECD (Nay Pyi Taw) - Director, ECD (Yangon Region) - Forest Department -> Consult /Involve
2.	Ministry of Transport and Communications (MOTC)	- Directorate of Water Resources and Improvement of River Systems (DWIR) - Project Proponent (& Supervisor of the overall project implementation)
3.	Ministry of Transport and	- Department of Meteorology and -> Consult/Involve/Collaborate

¹According to the WB OP4.12, Para 25: "where impacts on the entire displaced population are minor, or fewer than 200 people are displaced, an abbreviated resettlement plan may be agreed with the borrower.[...]" "Impacts are considered to be minor if the affected people are not physically displaced and less than 10 percent of their productive assets are lost." In this project, it is suggested that full LARAP shall be established when the PAPs subject to physical relocation and/or whose productive assets are affected by more than 10% is equal to or more than 200. If not, an abbreviated resettlement action plan shall be suggested.

	Communications (MOTC)	Hydrology - Marine Administration Department - Myanmar Shipyards - Myanmar Port Authorities - Inland Water Transport	
4.	Ministry of Agriculture, Livestock and Irrigation	-Department of Agriculture Land Management and Statistics -Irrigation and Water Utilization Management Department -Department of Fisheries -Department of Rural Development	-Other responsible agencies (who contribute relevant aspects about specific issues and matters within their jurisdiction. Specific agendas may include detailed legislative requirements, policy objectives, standards, technical knowledge and expertise, and experience with similar projects or local conditions. Certain agencies also may have the role in providing licenses, permits, approvals or leases.) ->Consult/Involve/Collaborate
5.	Ministry of Social Welfare, Relief and Resettlement	-Department of Relief and Resettlement	
6.	Ministry of Religious Affairs and Culture	-Department of Archeology and National Museum	
7.	Ministry of Health and Sports	-Department of Health	
II. Region/District/Township Level			
1.	Land compensation and Resettlement Committee	Daw Nilar Kyaw, Minister of Electricity, Industry, Transport and Communication	-> Consult/Involve/Collaborate
2.	South Yangon District General Administration Department	South Yangon District Administrator	
3	Twante, Dala Seikkyi-Khanaungto, and Kyimyindaing Township Development Committee		
4	Twante, Dala Seikkyi-Khanaungto, and Kyimyindaing Township GAD		
III. Village (Quarter) Level			
1.	Village Tract and Village Administrator		Wider community
2.	Communities living in and around the project area (residents in the Dala, Twante, Kyimyindaing and Seikkyi Khanaungto Township)		-> Inform/Consult/Involve
3.	Vulnerable Groups (e.g the elderly without family support, the physically	List of the group by category among the PAPs shall be identified during the EIA investigation (PAP	Affected groups (have a significant role in identifying concerns and issues, and in

	disabled, ethnic minorities, female-headed households, etc.)	profiling)	providing local knowledge and information. Their views should be taken into account in choosing among alternatives, in deciding on the relative importance of issues, and in identifying mitigation measures, compensation provisions and the objectives of environmental management plans)
4.	Representatives from local businesses (shipyard owners, boat/ship owners, farmers, fishermen and employees in the associated businesses etc.)		
5.	Directly affected Land Owners and House/Structure Owners and tenants in the land that are to be affected		

8.4 Detailed Activities

8.4.1 Activities during Scoping Stage

8.4.1.1 Consultations with the Government Organizations at Scoping Phase

The following public consultation meetings were done during January, February and April in 2018.

- Meeting with the ECD-MONREC
- Meetings with the three affected Township GADs during the first and the second missions
- Meeting with IWTD, MOC & MPA respectively, and
- Meetings with the Project Proponent (DWIR/PMU) a number of times

(1) First Mission Activities

Table 8.4-1: Details of the First Mission Activities

Date	Organization
31 Jan. 2018/7 Feb. 2018	DWIR
1 Feb. 2018	Meeting with local consultants (Sunchuang cooperation)
2 Feb. 2018	Site survey with F/S team and meeting with local consultant (REM)
3 Feb. 2018	Meeting with PMU from DWIR
5 Feb. 2018	Meeting with MONREC-ECD and MOC
6 Feb. 2018	Meeting with Dala, Twante, Seikkyi Khanaungto Township Meeting with Yangon City Development Committee
7 Feb. 2018	Meeting with Inland Water Transport Department Meeting with Myanmar Port Authority

The following key points were discussed in first mission.

- Myanmar EIA procedure
- Submission of project proposal
- Resettlement and land compensation issue
- Cumulative Impact Assessment
- Study limit and project AOI and Public Consultation Plan

(2) Second Mission activities

Table 8.4-2: Details of the Second Mission Activities

Date	Organization
24 Apr. 2018	Meeting with Local Consultant (REM)
25 Apr. 2018	Meeting with working group, DWIR Meeting with Local Consultant (REM)
26 Apr. 2018	Site survey with F/S team and REM Meeting with Twante, Dala and Seikkyi Khanaungto Township GAD
27 Apr. 2018	Official Kick-off meeting & wrap up meeting with DWIR

The following key points were discussed in second mission.

- Land ownership type
- Data collection support
- ECD approval issue
- ESIA coverage
- Cut – off date confirmation
- Township GAD support for survey, public consultation, cadastral map development



Figure 8.4-1: Disclosure about the Project with ISAN and REM at Dala Township



Figure 8.4-2: Disclosure about the project with ISAN and REM at Seikkyi Khanaungto

8.4.1.2 Project Perception Survey (as part of Socioeconomic Survey)

The public meeting method was complemented by the household surveys and one-on-one interviews used in collecting socio-economic information on communities in the study area. These two methods played significant roles in seeking specific views of project affected people.

- Purpose
 - Investigation into current situation of socio-economic conditions of potential PAHs
 - Examination of awareness and understanding of the project
- Sampling method: random sampling (about 13% of the total PAFs/ 353 respondents out of 2,697 PAFs)
- The field survey was carried out by 9 enumerators of REM
- Structure and major contents of perception survey are presented in the table below (Section A~E were part of the baseline socio-economic survey :)

Table 8.4-3: Structure and Major Contents of the Perception Survey

Section/Title	Major Contents	
F. Perceptions and Expectations	- Awareness and understanding of the project - Information sources for the project information	
	1. Village committee & Township meeting	
	2. TV & Radio, Newspaper	
	3. Facebook& Social media	
	4. Posters by local government and relevant agencies (GAD and/or DWIR)	
	5. Community & Neighbors	
	6. Governmental officers	
	7. Other (please specify): _____	
	- Expectations and concerns on positive/negative impacts of the project (Selecting the highest three benefits and negative impacts)	
	• Selection table for expected benefits	
	Expected benefits	① Socioeconomic development ② Safe and efficient inland water transport system ③ Safe ship trip navigation ④ Income increase and improved living standards Reduced annual tide flooding/inundation along the canal (less chance of accidents: life and livelihood loss and facility destructions etc.) ⑤ Farm land protection from land erosion

		⑥ Improvement living environment ⑦ Boost tourisms and local economy
	• Selection table for expected negative environmental and social impacts	
	Expected Negative impacts _ Environmental	① Noise from the construction and traffic ② Decline in water quality ③ Air pollution ④ Vibration
	Expected Negative impacts _ Social	⑤ Inconvenience of movement ⑥ Relocation (e.g. eviction) ⑦ Loss of income ⑧ Loss of jobs/economic opportunities ⑨ Intervention/disruption of business ⑩ Change in land usage and socio-cultural environment ⑪ Conflicts among residents/community members ⑫ Conflicts between residents/community members and construction workers ⑬ Demolition/Damages of the community/religious/cultural sites and facilities
- Other opinions in relation to the project		

• Results of the perception survey:

Table 8.4-4: The Result Summary of the Perception Survey

Township	Survey Period	The number of villages/wards	Respondents		
			Male	Female	Total
Twante	10.29~11.7 2018	5	57(52%)	36(48%)	93(100%)
Dala		3	16(21%)	61(79%)	77(100%)
Seikkyi Khanaungto		7	45(28%)	115(72%)	160(100%)
Kyimyindine	11.26~28 2018	3	7(30%)	16(70%)	23(100%)
Total	-	18	125(35%)	228(65%)	353 (100%)

1) Sources of the project Information

- Most of the respondents from four townships (40%~50% of the respondents) received information of the project from communities and neighbors.
- Other sources are TV, radio and newspaper (10~25%) as well as social media (3~10%) and related government offices.




Figure 8.4-3: Responses to Sources of the Project Information

2) Expected Adverse Impacts: Environments

- Respondents selected noise from the construction and traffic as the biggest environmental adverse impact (maximum 55%).
- Vibration (20~34%) and air pollution (10~30%) have the next positions, while decline in water quality was not a great concern (less than 10% in the all four townships).
- Potential PAPs worried more about environmental impacts that they can feel immediately, such as noise, than other less direct impacts.




Figure 8.4-4: Responses to Expected Adverse Impacts (Environments)

3) Expected Adverse Impacts: Social

- Inconvenience of movement was overwhelmingly selected as the most significant social impact (more than 80% in all the four townships), followed by the concerns about the relocation due to the project implementation.
- In Seikkyi Khanaungto and Twante, relocation (up to 40 %) and economic factors (income, jobs, etc.) (up to 30%) are also major issues of concern.
- Residents in Seikkyi Khanaungto township have more apprehension over loss of jobs or economic opportunities, which is meant to be from concerns of shipyard workers.




Figure 8.4-5: Responses to Expected Adverse Impacts (Social)

8.4.1.3 Public Consultation Meeting (PCM) for Scoping Stage

[Approach]

The following approach to PCM preparation and implementation was adopted for public consultations both at scoping and EIA investigation stages:

- Each meeting was organized with assistance of the Township Administration and village headmen in identifying participants to be invited, in making arrangements for the meeting venue, and in issuing the invitations.
- Representatives from the Project Proponent (DWIR) and the Consultant (EIA Study Team) jointly conducted the meetings. The Project Proponent's representatives were responsible for briefing project information including Project development plan and answering questions from the meeting or clarifying points raised in the meeting regarding the Project development plan. The Consultant was responsible for providing information on the EIA, and clarifications on issues related to impacts of the Project. The two parties worked as a Project team.

- Each meeting was chaired by the district chief and village headman. The meeting began with introduction of the objectives of the meeting and expected outcome. After that, the Project team gave information on the Project and the EIA.
- Each meeting provided an open forum for the participants to express their concerns, offer their views and suggestions, and raise questions or points which needed to be responded by the project team. The project team answered to their concerns, views and suggestions as appropriate. The meeting was interactive, i.e. the Project team and the participants engaged in constructive and relevant discussions.

[PCMs for Scoping Stage]

For the public consultation meetings, three meetings were held on two different days. Firstly, the 1st meeting in the Twante Township on 20 September 2018; and secondly, 2nd meeting in the morning at the Dala and 3rd meeting in the afternoon at the Seikkyi Khanaungto on 21 September 2018. The venue was selected with several considerations, such as easy accessibility from villages in and around the affected townships and the meeting room capacity of the building.

The project proponent (DWIR) prepared the invitation letter together with the notice of the meeting in Myanmar language and announced to the invitees, including villagers and the relevant governmental organizations, non-governmental organizations (NGOs), community-based organizations and anyone who are interested. Information on the meeting was announced to the invitees in advance, one week before the meeting, by sending invitation letters to the respective invitees. (See Figure 8.4-6 below.)

For the villagers, the information on the meeting was announced based on the administrative procedure and local practice. Firstly, the invitation letter was sent to the township offices in order to ask them to provide instructions to each village-tract office under their jurisdiction. The information of the meeting was also announced together with the invitation letters on the public notice board of townships and on the newspapers (The New Light of Myanmar and The Mirror) between 10 and 14 September 2018. The presentation and handouts were prepared and explained in Myanmar language. The announcement of the invitations on newspaper for the PCM is shown in Figure 8.4-6 and the venue of the meeting was presented in Table 8.4-5.



Figure 8.4-6: Public Announcement with Invitation Letter at the Public Places and Newspapers for the First PCM

Table 8.4-5: Summary of Public Consultation Meeting for EIA at the Scoping Stage

Time and Date	1) Thursday, 20 September 2018 - 1 st session (for Twante Township): 1:00 PM to 3:00 PM 2) Friday, 21 September 2018 - 2 nd session (for Dala Township): 9:00 AM to 11:00 AM, - 3 rd session (Seikkyi Kanaungo Township): 1:00 PM to 3:00 PM
Venue	- Administrative Office of Twante Township - Administrative Office of Dala Township - Administrative Office of Seikkyi Kanaungto Township
Invitees	- Director, Environmental Conservation Department in Yangon Division, MONREC - General Administration Department, Yangon Southern District Officers, General - Administration Department in Twante, Dala and Seikkyi - Kanaungto Townships - Officers, Myanmar Port Authority, Ministry of Transportation and Communication - Local residents in and around the respective three townships - Project proponent (DWIR) and related government organizations (Department of Planning, Department of Marine administration, Myanmar Shipyards) - Other organizations and individuals who are interested in the Project (such as Ayeiksit, Saytanar Emergency Association, Anargatalinyaung Philanthropic Association)
Attendee	- Twante: 85 people (men:75, women:10) - Dala: 72 people (men:60, women:15) - Seikkyi Kanaungto: 63 people (men: 53, women: 10)
Agenda	- Introduce the meeting and major agendas by Township Administrator - Explain the project by Project Proponent (DWIR) - Explain the EIA project - Major positive and negative environmental and social impacts from the draft scoping results - Scope of the EIA study - Further schedule of EIA Implementation - Q&A
Language Used	In local language: Myanmar language

Source: EIA Study Team (Resource and Environment Myanmar)

8.4.1.4 Summarized Outcomes of PCMs at the Scoping Stage

Three PCMs were organized on 20 and 21 September 2018 at the Administrative Offices of Twante, Dala, and SeikkyiKhanaungto Townships. On 20 September 2018, 85 people attended in Twante Township public consultation, while on 21 September 2018, 72 people attended at morning session in Dala Township and 71 people attended the afternoon session in Seikkyi Khanaungto Township. In total, approximately 15% of the participants are women. In the consultation meeting, after the explanation on the project plan, the expected key environmental and social benefits as well as major positive and negative environmental and social impacts analyzed in the scoping report were explained. In addition, scope of the EIA study and further schedule of the EIA were presented to the participants. At the end, the question and answer session was organized in all the meetings. As a whole, twenty-eight questions were raised from the participants and discussed with the project proponent (DWIR) and representatives from REM and ISAN Consortium.

The following topics and concerns have been discussed and collected during the meetings:

- Land compensation for project affected people;
- Potential impacts on the agricultural sector by the saltwater from Yangon and Tow Rivers;
- Concerns about saltwater level which can damage on the riverbank;
- Request for guarantee of the construction quality and maintenance of the project;
- Request for plantation of mangrove at the bank of the canal area;
- Request to government to control the construction under the rules and regulations regarding boat utilization near the Canal;
- Request for the accurate ESIA survey implementation



Figure 8.4-7: Picture of PCM at Scoping Stage in Twante Township (First Session)



**Figure 8.4-9: PCM at Scoping Stage in Seikkyi Khanaungto Township
(Third Session)**

8.4.1.5 Information Disclosure at the Scoping Stage

All meetings were carefully documented and logged with each meeting minute, and followup activities were also recorded. The Project Proponent (DWIR) posted posters at the major public locations in the affected Townships (including GAD offices, sport stadium, village's head offices) and also publicized the overview of the project and invitation for the PCM in major local newspapers including New Light of Myanmar (Myanmar Ah Linn), the Mirror (Kyaymon) and Daily Eleven (See

Figure 8.4-10) between 20~21 September 2018. The detailed minutes of meeting for the public consultation meeting are presented in Annex 7.



Figure 8.4-10: Public Disclosure in Newspaper

8.4.2 Activities during EIA Stage

8.4.2.1 Consultations with the Government Organizations during the EIA Stage

Table 8.4-6: Consultations with the Government Organizations during the EIA Stage

Meeting Dates	Organizations	Venue	Major contents
12. Dec. 2018	MPA	MPA office (Yangon)	Discussion on the environmental and social survey in regions along the Yangon river (which belong to MPA)
12. Dec. 2018	DWIR	DWIR office (Yangon)	Discussion on the project progress
13. Dec. 2018	MONREC-ECD	MONREC office (Naypyidaw)	Request for the timely approval of the scoping report to facilitate the remaining processes
13. Dec. 2018	DWIR-PMU	DWIR office (Yangon)	Discussion on how to conduct FGD and the 2 nd public consultation
29. Jan. 2019	DWIR	DWIR office (Yangon)	Results of the 2nd Public consultation and the future plan for ESIA

8.4.2.2 Public Consultation Meeting (PCM) at the EIA Stage

Public consultations with the three identified categories of stakeholders were held on several occasions between 26th to 29th January. The meeting dates, group of agencies, and number of participants are given in Table 8.4-7. Minutes of meeting and list of participants in each meeting are shown in Annex 8 and Annex 12.

Table 8.4-7: Meeting with Projects Stakeholders

Meeting Dates	Stakeholders	Number of Participants
26 th January 2019	Seikkyi-Khanaungto Township	
	1. Government officials	32
	2. Parliament members	1
	3. Project Proponent's representatives (DWIR)	6
	3. EIA Consultant (TEAM)	5
	4. NGOs	14
	5. Local people	64
	6. Shipyard association	17
	Total	139
28 th January 2019 9:00 am to 11:00 am	Twente Township	
	1. Government officials	17
	2. Project Proponent's representatives (DWIR)	1
	3. Parliament members	2
	3. EIA Consultant (TEAM)	9
	4. NGOs	2
	5. Local People	147
	Total	178
28 th January 2019 2:00 pm to 4:00 pm	Dala Township	
	1. Government officials	17
	2. Project Proponent's representatives (DWIR)	2
	3. Parliament members	5
	3. EIA Consultant (TEAM)	9
	4. NGOs	3
	5. Local People	83
	Total	119
29 th January 2019 9:00 am to 11:00 am	Kyimyindaing Township	
	1. Government officials	16
	2. Project Proponent's representatives (DWIR)	1
	3. Parliament members	1
	3. EIA Consultant (TEAM)	8
	4. NGOs	4
	5. Local People	12
	Total	42

[Summary of the Outcomes of PCMs at the EIA Stage]

Four PCMs were organized on 26th to 29th January 2019 at the Administrative Offices of Twante, Dala, Seikkyi Khanaungto and Kyimyindaing Township. In total, approximately 28% of the participants are women. In the consultation meeting, after the explanation on the project plan, the expected key environmental and social benefits as well as major positive and negative environmental and social impacts analyzed in the draft EIA report were explained. In addition, findings of the EIA study and further schedule of the EIA were presented to the participants. All the meeting was ended with the question and answer session. As a whole, about 26 questions (although some of them are duplicated) were raised from the participants and discussed with the project proponent (DWIR) and representatives from REM and ISAN consortium.



Figure 8.4-11: 2nd PCM in Seikkyi Khanaungto Township



Figure 8.4-12: 2nd PCM in Twente Township



Figure 8.4-13: 2nd PCM in Dala Township



Figure 8.4-14: 2nd PCM in Kyimyindaing Township

[Summary of Comments from PCMs at the EIA Stage]

The following topics and concerns have been discussed and collected during the meetings:

- Land compensation for project affected people and communities;
- Relocation of the houses even before the project starts;
- Concerns about discharge sewage into the creek directly;
- Request to announce the project information in DWIR Facebook page;
- Request to repair the houses in rainy season before the project implementation;
- Request to DWIR to use and repair the village roads;
- Suggest that they want to promote their livelihood;
- Suggest to grow the mangrove trees along the Twente Canal;
- If resettlement happens, wish to be relocated to other places which is near the current residential places;
- The other side of Kyimyindaing is quite poor and has health, education and bank erosion issues. Thus, it is necessary to consider their potential opportunities and threats. As summarized, they welcomed the project and are willing to help and cooperate as much as they can.

8.4.2.3 Information Disclosure at the EIA Stage

During the public consultation activities, the DWIR, the Project Proponent, disclosed information regarding the project activities and relevant changes in the Project. The project proponent and ESIA team (REM and the Isan Consortium) disclosed the information on the proposed project in the National and Private Newspaper such as New Light of Myanmar (Myanma Ah Lin) and the Mirror (Kyaymon), and also provided the public disclosure plan in each township office on 22nd January 2019.




Figure 8.4-15: 2nd Public Disclosure in Newspaper



Figure 8.4-16: 2nd Public Disclosure at the Public Area in Townships

The detailed of minutes of meeting and power point presentation used in public consultation meeting are presented in Annex 8 and Annex 10.

8.5 Focus Group Discussions (FGDs)

A series of focus group discussions had been carried out as described in the Table below:

Table 8.5-1: Focus Group Discussion in the Study Area

Meeting Dates	Place	Target	Main concerns/opinions
24 th December 2018 (Morning)	Taung Thu Gyi Restaurant, Seikkyi Khanaungto Township	Shipyards Association (Business people)	<ul style="list-style-type: none"> - Most residents are considered to be involved in shipyard-related businesses (including operation and management work). Thus, this community has particular interests, quite different from those of other communities or townships. - Discussion points: income level, the number of workers and households affected, ROW, potential economic loss by the project. - They wanted good livelihoods within their region and facilitation of communication system with the project proponent and the regional government. - They wanted the regular income during and after the project.
24 th December 2018 (Afternoon)	Hpayar Gyi Village, Twente Township	Farmers (Residential people)	<ul style="list-style-type: none"> - Project activities will be highly likely to have significant impacts on the lives of farmers along the river, not just because most parts of their farmlands could be subject to land acquisition, but because they might have to be relocated and resettled in other places. - The farmers who lost their farmland wanted proper level of compensation (for example, land for land or other livelihood activities) in the project. - Discussion points: income level, the number of farmers and households affected, the scale of farmlands and houses to be acquired, proper time and place to be resettled



Figure 8.5-1: Focus Group Discussion with Shipyard Association



Figure 8.5-2: Focus Group Discussion with Farmers

8.6 Results of Public Consultations

Table 8.6-1: Major Opinions from Interested Parties and Responses by the Project Proponent

No.	Major opinions/concerns identified	Responses during PCM	Solutions/Plans (reflected in this ESIA report)
1	Questions on the plan on relocation and resettlement	<ul style="list-style-type: none"> - Avoid the rainy season - From the second half of 2019 (expected) - As of yet, no confirmation on the potential resettlement site selection yet. 	<ul style="list-style-type: none"> - Broad plan for resettlement and compensation will be included in on the Framework RAP report within the ESIA report.
2	Questions on the compensation plan	<ul style="list-style-type: none"> - To be conducted according to the decisions of the Land Compensation and Resettlement Committees - The plan will include land value surveys and the whole compensation 	<ul style="list-style-type: none"> - Detailed matters on resettlement and compensation will be decided after the detailed design and DMS (Detailed Measurement

		<p>process.</p> <ul style="list-style-type: none"> - Although committees are already established, details on compensation has not yet determined. 	<p>Survey).</p> <ul style="list-style-type: none"> - All decisions will be made by the Land Compensation and Resettlement Committees. <p>(For further details, see the Framework RAP Report)</p>
3	Expected difficulties regarding irrigation (especially for farming) during construction	<ul style="list-style-type: none"> - Understood - To be considered at the detailed design stage so as not to have problems 	<ul style="list-style-type: none"> - It is necessary to have thoughtful considerations for PAHs on their livelihood, such as waterway, irrigation, and agricultural activities, at the detailed design stage. - To be considered at the detailed design stage so as not to have problems - Mitigation measures will be included as part of the site-specific Construction Management Plan (CMP) (e.g. identifying and providing alternative diversion of the farming irrigation channel in case of the construction work disrupts the existent irrigation routes temporarily or permanently) → Reflected in the ESMP Table in Chapter 7 ("Socioeconomic impacts")
4	Request for the information disclosure of the project		<ul style="list-style-type: none"> - Records or reports on the project will be properly disclosed.
5	Request for more public relations on the project and discussion/consultation, via Facebook and other routes	<ul style="list-style-type: none"> - Noted. - Project-related documents will be able to be seen at the GAD offices. - Project information will be also disclosed at the DWIR website. 	<ul style="list-style-type: none"> - Transparent information disclosure via various channels is necessary. - Measures should be well taken before the commencement of the construction → Reflected in the ESMP Table in Chapter 7 ("Socioeconomic impacts")
6	In other projects, unnecessary compensation issues happened in relation to the cut-off date. How has the project dealt with this problem?	The cut-off date was set on 31 Jul 2018.	-

7	Necessity for the bank protection engineering works at the meeting point of Yangon river and Twante canal, because of erosions	Already included in the project	-
8	What are benefits from the project for the communities?	<ul style="list-style-type: none"> - The fundamental goals: flood prevention and more convenient waterway navigation - Hiring local community workers during construction 	<ul style="list-style-type: none"> - Continuous consultation and discussion with local communities throughout the whole project period - Utilization of local labor forces during construction as well as operation stages
9	The priority of this project should be on 0~3.5 mile section of the Twante Canal.	Embankments will be built as planned.	-
10	Concern on construction near the shipyard areas in the Kanaungto Creek	Establishment of walls is being considered, instead of embankments.	The precise plan will be confirmed to minimize the adverse impacts at the detailed design stage.

8.7 Recommendations

- Public consultation activities should be conducted throughout all the stages of the project.
- The establishment and operation of GRM (Grievance Redress Mechanism) is highly recommended as a vital consultation activity.
- Monitoring by the project proponent (DWIR) and external agents/specialists should include both regular and ad-hoc consultations and discussions with diverse stakeholders of the project, especially project-affected people, in order to supervise environmental and social performances and to manage unexpected impacts, if any.
- Installation of comment boxes at GAD offices of each township could be a good means of collecting opinions, concerns, and feedback from local communities, with timely delivery to the project proponent (DWIR), the local government (YRG), and the Contractor for construction.
- Last but not least, public consultation during the project is to be carried out and improved in accordance with RAP, which will be fully established in more detail after the detailed design on the basis of the Framework RAP.

CHAPTER 9: GRIEVANCE REDRESS MECHANISM (GRM)

9.1 Background

Grievance redress mechanism (GRMs) is an integrated system consisting of institutions, instruments, methods, and processes to settle down grievances from diverse stakeholders with regard to the project. Grievances and dissatisfactions about the actual and perceived impacts of development projects are normally raised by project affected people or communities who are adversely influenced by such projects. These grievances usually stem from physical, situational, and social losses and can be imposed on the project developer at different stages of the project cycle.

GRM for Twante Canal Improvement project will also be implemented with establishment Grievance Redress Committees (GRCs). GRM provides a predictable, transparent, and credible process to all parties, resulting in outcomes that are seen as fair, effective, and lasting. The specific procedures receiving complaints shall be prepared in advance, and all details of purpose, investigation, analysis and response of complaints shall be recorded in the Grievance Redress System (GRS).

9.2 Guidelines for GRM Establishment

GRM needs to be mutually beneficial in ways that grievances and dissatisfactions could be easily raised and enough hearing should be provided and that satisfactory solutions should be identified (ADB, 2010).

In addition, the EDCF Safeguard Policy (2016) also mentioned in [D. Principle, 14] as “The borrower shall establish and maintain a grievance redress mechanism scaled to the risks and impacts of the project to receive and facilitate resolution of affected people’s concerns and grievances”.

Also, in the section M. Information Disclosure, articles 39 and 40 mentioned the information disclosure to help the affected communities and other concerned stakeholders:

- Objectives, nature, scale, and period of activities pertaining to the proposed project.
- Potential risks and impacts as well as mitigation measures.
- Process of stakeholder participation and grievance-redress mechanisms.

Moreover, according to the section O, a grievance redress mechanism has to be established and maintained to receive and facilitate resolution of affected peoples’ concern and grievances about the environmental and social performance at project level using an understandable and transparent process including gender responsive, culturally appropriate and readily accessible to most affected people.

The EDCF Safeguard Policy also recommends the EDCF-financed project shall include the local grievance redress mechanism for ESIA and the grievance redress mechanism for the Resettlement Action Plan (RAP).

Since there is no legal procedure related with grievance redress mechanism in Myanmar EIA procedure (2015), the project proponent shall follow the best international practices to cope with grievances and facilitate the resolution process.

9.3 Purpose, Objectives and Key Principles for GRM Establishment

9.3.1 Purpose

DWIR will be responsible for establishing the Grievance Redress Mechanism and setting the contact point at the place where the project will be located; and ensuring the stakeholders get informed about the GRM. The main purpose of GRM is to create a platform where grievances and complaints from PAPs due to the project could be collected and the finest resolutions for such grievances and complaints could be identified and conducted.

9.3.2 Objectives

The objectives are:

- To prevent any potential disputes among diverse stakeholders, especially PAPs
- To register and resolve the grievances and complaints of the project affected people
- To promote transparency and accountability during the project implementation
- To deter fraud and corruption
- To mitigate adverse impacts and potential risks from the project

9.3.3 Key Principles for GRM Establishment

According to the EDCF Safeguard Policy, the GRM needs to be established based on the following principles:

- **Systematic and appropriate scale to the anticipated risk of the project:** Due to the potentially significant social impacts of the project, it is highly important to establish a fully developed GRM Mechanism in a timely manner.
- **Gender consideration:** It is desirable that the focal point of the GRM also includes a designated person in charge to deal with the grievances related to women
- **GRM operation in a culturally acceptable way of the recipient country:** Most GRM process are related with land acquisition and compensation plan about the loss of assets and lands. Thus, the government body such as GAD offices or the project related government departments should ensure that GRM will be operated in concord with local contexts.
- **Application of project-specific procedures:** GRM processes should consider each aspect of projects in a specific way and all contents of complaints and grievances are required to be presented.

9.4 Status of GRM establishment for the proposed project

The Project Proponent (DWIR) has established a focal point for GRM. The focal point should be clearly identified to receive and register complaints from the PAPs. The process and the contact information of GRM was disclosed to the main local stakeholders including the affected communities during the 2nd round of the public consultation session in January 2019.

One particular staff was designated to take overall responsibility for tracking and following up the

complaints being raised as below.

Table 9.4-1: GRM Focal Point Person (who has overall responsibility)

Proponent Name:	Directorate of Water Resources and Improvement of River Systems (DWIR)		Company Registration Number (if any):	
Contact name of Proponent:	U Sein Lwin			
Proponent`s address for correspondence:	No-400, Lower Pazundaung Road, Yangon Myanmar			
Telephone(fixed/mobile):	+95-1-292961(office) +95-9-5404894 (mobile)	Fax: +95-4-290230	E-mail address:	<u>lwin.sein275@gmail.com</u>

While the GRM focal point of the Project Proponent (DWIR) constitutes the core of the overall GRM, the GRM requires a more extended mechanism as follows:

- Designation of the community level GRM focal point (in each of the four affected Townships)
- Designation of the site grievance redress team (SGRT)
- Establishment of the Grievance Redress Committee (GRC)

9.5 Future Recommendations for Effective GRM Operation

9.5.1 Installation of the Grievance Boxes

The grievance boxes for the project shall be set up at each of the Township GAD offices to collect grievances of the project affected communities.

Issues that are to be addressed through the GRM include the following. This list should be attached to the grievance boxes for the communities' information (together with the GRM focal point contact information):

- Institutional arrangements and the procedures for recording and processing grievances
- The mechanisms for adjudicating grievances and appealing judgments
- Schedule, with deadlines, for all steps in the grievance redress process
- Grievance Owner (Project proponent (DWIR)) and GRM focal point
- Knowledge on Project
- Measures on entitlement and affected lands
- Information on lost assets/crops
- Rates and means of compensation
- Others

The GAD Administrator shall designate a GAD-level GRM focal point to manage the Grievance Box. On a regular basis (at least on a biweekly basis) the GAD-level GRM focal point shall collect the gathered grievances and deliver them to the GRM focal point of DWIR.

9.5.2 Establishment of the Site Grievance Redress Team (SGRT)

The Project Proponent (DWIR) shall designate a group of staff in the field who are in charge of the collecting and immediately addressing the grievances which could be addressed right away by the contractor and the project implementation entities, which are raised by the affected communities.

The results of grievances dealt with in the field will be reported to the Project Proponent in a regular basis.

9.5.3 Establishment of the Grievance Redress Committee (GRC)

GRC should be legitimized by the Directorate of Water Resources and Improvement of River Systems (DWIR). The GRCs are to provide the project affected people with accessibility to grievances redress mechanism and to make the fair decision on the grievances and complaints. The decision of the regional GRCs will be final in resolving the grievances and complaints.

The GRCs at the project level shall include;

- Focal Point Person (Chair)
- Administrators: 4 GADs from Twante, Seikgyi Kanaungto, Dala and Kyimyindaing
- Two Project Staffs: Secretary and Construction Site Manager for grievance registration
- Village/Ward Representatives
- Supporting committees (village/ward)

The GRC to be convened on a regular (e.g. quarterly) as well as on ad-hoc basis (in case of a significant grievance case is referred and required immediate attention and solution.)

Major duties and responsibilities of GRC are described as following.

Box 9.5-1: Duties and Responsibilities of GRC

- Facilitate and provide information and services to resource persons as required by the grievance redress committee (GRC) to deal with reported grievances;
- Register grievances on a prescribed form;
- Document the GRC proceedings, decisions, and recommendations;
- Maintain grievance-related documents, reports, and attendance sheets as well as payment registrations of GRC members;
- Liaise with the GRC chairperson;
- Facilitate arrangements for field inspections;
- Handle all payments and expenses related to GRC operations;
- Provide feedback to project affected people and agencies involved in grievances; and
- Report the resolution progress to the Twante canal improvement project manager

CHAPTER 10: CONCLUSIONS AND RECOMMENDATIONS

10.1 Conclusions

10.1.1 Overall conclusion

The proposed project, the Twante Canal Improvement Project, comprises of measures to resolve urgent and serious problems such as bed and bank erosion, and flood damages in Twente Canal and adjacent areas. The objective of the Project is to achieve sustainable and systematic improvement and management of the Twante Canal in Yangon, Myanmar, securing the safe inland waterway navigation and protecting residential and farmland areas from bank erosion and flood damages. Channel training measures are designed to reduce the flow velocity influenced by the tidal flow and to stabilize the flow field in the Twante Canal, whereas flood embankment measures are to maintain the stable water level during the largest spring tide.

Based on the scoping results, EIA investigations and technical surveys were prepared and undertaken in a professional manner and in accordance with EIA Procedure (2015) as well as other Myanmar legislation and applicable standards, requirements and guidelines. In addition, the ESIA was carried out in accordance with the Safeguard Policy of the Economic Development Corporation Fund (EDCF) of the Export-Import Bank of Korea, a financier of the proposed project.

In support of conducting and approval for EIA, a joint team of the Korean consultant consortium ("ISAN Consortium") and a Myanmar consultant team (REM) have collected and analyzed biophysical, ecological and socioeconomic data including people's perceptions, concerns, opinions, and expectations on the project.

The environmental components for the detailed EIA investigation and effective management plan include a scale of land acquisition and involuntary resettlement which is incurred by the ROW acquisitions, followed by land acquisition and asset losses in the construction area along the Twante Canal and a segment of the Yangon River. This may bring about substantial level of economic and physical relocation of residents (The total land area subject to the acquisition is 120 ha. About 2,697 households, 2,028 structures and 669 landowners are expected to face their properties loss within 30m ROW. Additional relocation and involuntary resettlement may take place related to the access road construction and establishment of associated facilities (if any)). Resettlement and compensation for the land and assets should be implemented by the Project Proponent (DWIR) and other relevant entities (relevant local government agencies) while utilizing the social maps to ensure the best available data for locating the affected households and land divisions.

Resettlement and compensation for project affected people will also be conducted in compliance with the relevant laws and regulations of Myanmar, including: The Land Acquisition Act (1894), the Transfer of Property Act (1982), Farmland Law (2012) and the Vacant, Fallow and Virgin Lands Management Law (2012), the Conservation of Water Resources and River Law (2006) and the Canal Act (1905). In case there is difference between the above-listed laws and the internationally accepted practices as stipulated by the EDCF Safeguard Policy, it is recommended that more stringent standards be adopted unless compelling justification of selecting the other option is presented.

In addition, in case the current ROW demarcation which tentatively set to be the areas within 30 m from the current shipyard boundaries, project implementation in Seikgyi Kanaungto Section is likely to disturb the shipyard operations and may incur land acquisition (if not physical relocations), subject to the project proponent (DWIR)'s final decision on the project designs and ROW demarcation in this area. In case some of the facilities that are to be installed as part of the project implementations hampers their access to the river and take some of their operation area, the productivity capacity of the

affected shipyard company may be compromised and some of the current employees may be laid-off.

Shipyard operations in Kanaungto have been over 60 years' history, and the owners and operators have strong invested interests. The revenue of the total 40 shipyards' operations is not known yearly. About 400 employees (daily wage workers) and their families of the 40 shipyard companies are also the potentially affected groups in case their operations are partially or entirely, temporarily or permanently affected due to the construction activities. In case the shipyard operations are put to a halt, it is not clear whether there are alternative resorts for the vessel owners. If not, the second-round negative impacts would reach the vessel owners/users.

The temporary and local environmental impacts with minor significance during the construction period include dust and air pollution as well as water contamination and run off. A particular attention would be required to protect the mangrove area for its ecological sustainability. The environmental and social management and monitoring plan shall be established to reflect the investigation findings and impact identification that are to be resolved.

During the construction period, noise and vibration, dusts and waste gas, wastewater and construction refuse are expected to be generated, and the construction engineering entities shall conduct their building activities in strict accordance with requirements of the environmental protection authorities, arrange their working hours in a reasonable way, and implement all environmental protection measures as put forward in the present EIA Report. Such environmental protection measures, upon implementations, may minimize impacts of noise, waste gas, wastewater and construction refuse on ambient environment during the construction period; those impacts are of a temporary nature and will disappear upon completion of the proposed project.

After some alternative activities are to be considered as expressed in Chapter 3, all prevention and control measures proposed herein are reliable and will be effectively implemented by the project Contractor according to ESMP during the construction period so that the proposed project will just have insignificant impacts from dust and noise generation on ambient and nearby community environment ; besides, the project will also cause insignificant impacts on ambient environment during its operation period.

To sum up, the construction and operation of the proposed Twente Canal Development project is feasible from the perspective of environmental protection. However, from social impact point of view there some scalable social impacts that would occur especially in terms of the land acquisition and involuntary resettlement indicates that the level of significance is high (with about 2,697 households that are subject to land acquisition, including both formal and informal settlers in the area of 120 ha). In case the current ROW assumption of circumventing all the existent shipyards from the ROW in Kanaungto, potential disturbance of the shipyard operations is expected in a scalable level, affecting negatively the shipyard business communities, either temporarily or permanently, depending on the DWIR's final decision on the ROW demarcation and final designing. Upon completion of the project construction, the project is expected to generate the positive benefits that can countervail the negative impacts during the construction period.

10.1.2 Social Impact Assessment and Mitigation Recommendations

Following are the key social impacts with associated mitigation and monitoring measures recommended:

Table 10.1-1: Summary of Major Socioeconomic Impacts and Mitigation Measures

Impacts	Mitigation Measures
<p>I. Land Acquisition and Involuntary Resettlement</p> <p>- The proposed project is likely to change the land use pattern in the project area permanently. Scalable size of loss of lands, crops and houses and structures within the canal area are expected due to the requirement of land for the construction site (30 m ROW) during the construction phase.</p> <p>The total land size subject to the acquisition is 120 ha in total. About 2,697 households, 2,028 structures and 669 landowners are expected to face their properties loss within 30 m ROW. Additional relocation and involuntary resettlement may take place related to the access road buildings and establishment of associated facilities (if any).</p> <p>The impact involves both land owners, tenants, sharecroppers and informal settlers..</p>	<p>1) Avoid:</p> <ul style="list-style-type: none"> - Project Proponent (DWIR) is currently considering the re-adjustment of the ROW criteria in Kanaungto Section in order to avoid unnecessary incurrence of involuntary resettlement. <p>2) Minimize:</p> <ul style="list-style-type: none"> - Project Proponent (DWIR) to design alternative access to river (e.g. spillway docks for shipyards, piers for boat operations and waterway (for agricultural irrigation purpose for farming operations) as an integrated part of the ESMP - Project Proponent (DWIR) to consider planning sequential construction schedules section by section (rather than blocking and carrying out construction over the entire project area simultaneously) <p>3) Offset/Compensation:</p> <ul style="list-style-type: none"> - Project Proponent (DWIR) to establish an entitlement matrix covering a comprehensive list of the direct affected households and persons by the project, including both land owner, tenants, private business operators as well as share croppers and informal settlers, appropriate compensation measures should be established in accordance with the related laws and regulations in Myanmar as well as the EDCF Safeguard Policy and internationally accepted safeguard policies (in particular, WB OP/BP 4.01 and 4.12)
<p>II. Shipyard Operations in Seikgyi Kanaungto Section</p> <p>In case the current ROW demarcation which tentatively set to be the areas within 30 m from the current shipyard boundaries, project implementation in Seikgyi Kanaungto Section may disturb the shipyard operations and may incur land acquisition (if not physical relocations), subject to the project proponent(DWIR)'s final decision on the project designs and ROW demarcation in this area.</p> <p>Shipyard operations in Kanaungto have over 60 years' history and the owners and operators have strong invested interests. The revenue of the total 40 shipyards' operations are not known yearly. About 400 employees (daily wage workers) and their families of the 40 shipyard companies are also the potentially affected groups in case their operations are partially or entirely, temporarily or permanently affected due to the construction</p>	<p>1) Avoid & 2) Minimize</p> <ul style="list-style-type: none"> - Project Proponent (DWIR) has tentatively set 30 m ROW criteria in a way to circumvent the entire area of the existent shipyards. Technical (and otherwise) feasibility of such assumption is to be further reviewed. In any case final ROW demarcation should consider maximum possible avoidance of unnecessary incurrence of involuntary dislocation of the shipyard community, physical or economical, or temporary or permanent. <p>3) Offset/Compensate:</p> <ul style="list-style-type: none"> - For those whose land and structures are inevitably affected in the course of construction, project proponent (DWIR) would need to assess their loss and damages of assets and provide appropriate compensation to the replacement costs. For those whose source of income is jeopardized due to the temporary/permanent closure related to the project implementation (e.g. shipyard employees' losing jobs and consequential loss of livelihood of the employees and their families), project proponent (DWIR) would need to extend transition allowances or provide livelihood program to ensure them to restore their income

Impacts	Mitigation Measures
activities. In case the shipyard operations are put to a halt, it is not clear whether there are alternative resorts for the vessel owners. If not, the second-round negative impacts would reach to the vessel owners/users.	sources and the same or higher level of living standard as soon as possible.

10.2 Commitments

According to the study and the environmental, social and health impacts assessment, the Twente Development project will have largely negative impacts during construction period but positive impacts in the long-term during operation period. In order to avoid and minimize the expected negative impacts, an Environmental Monitoring, Health, Safety & Environmental Management Plan (EMP) is recommended to be developed and fully implemented by the project proponent.

The following commitments are recommended and proposed for implementation as shown in Table 10.2-1.

Table 10.2-1: Project Key Commitments

Sections of ESIA Report	Key Commitments
Chapter 1. Context of the Project	The EIA report shall be prepared in accordance with the EIA procedure of Myanmar (2015) with the project proponent (DWIR) and highly experienced third-party consultants as per mentioned.
Chapter 2. Overview of Policy, Legal and Institutional Framework	<p>The project owner shall earnestly carry out all national and local laws, regulations and requirements on environmental protection, clearly define main duties and responsibilities of environmental protection departments of the project, establish and optimize its rules and regulations.</p> <p>The project shall conform on the followings:</p> <ul style="list-style-type: none"> - relevant standardizations for ambient air quality (NEQG) - relevant standardizations for wastewater discharges (General application of NEQG) - relevant standardizations for Construction noise and vibration (Industrial noise standard of NEQG) - relevant guidelines for solid wastes by the concerned departments (YCDC, Yangon City) - will separate the domestic wastes, construction wastes such as asbestos and hazardous wastes when disposed. - will follow strictly the local and international relevant laws, guidelines, and procedure while implementing environmental and social management plans as mentioned in the EIA report. - shall monitor the EMP and SEP in accordance with the EMoP as designated in the EIA report. <p>In addition, the project shall observe the key relevant principles of the EDCF Safeguard Policy and other international good practices (of ADB and World Bank) as appropriate.</p>
Chapter 3. Project Descriptions and Alternative Analysis	The project commits to utilize and maintain the facilities' designs and modernized equipment and machinery as described in Project description for construction period.

Chapter 4. Description of Surrounding Environment	The project commits not to disturb the Existing Environmental and socioeconomic Conditions and will keep forwards maintaining the natural conditions and developing the regional livelihood and living standards as far as possible.
Chapter 5. Impact and Risk Assessment and Mitigation Measures	The project commits to precisely follow the discussed mitigation measures for avoiding or reducing such environmental and socioeconomic impacts generated in temporarily or permanently by the Project activities during both the construction and operation phases.
	Arrangement of personal protective equipment such as gloves, helmet, mask, glasses and other tools, safety boots and uniforms for each worker so that the workers can keep themselves safe from any kinds of accident and the occupational health training will also be provided.
	The labor recruitment policy must be formulated in such a way that local laborers can be prioritized (esp. directly affected persons and families) for employment in the project.
	Construction risk management plan shall be prepared and implemented.
Chapter 6. Cumulative Impact Assessment	The project will also consider the cumulative impacts by the project activities and keep maintaining to minimize the potential negative impacts and maximizing the benefits positively.
Chapter 7. Environmental and Social Management Plan	The project commits to follow up the main tasks for Environmental and Social Consideration of the project implementation team and project management team in accordance with the main parts of CEMP & OEMP and the relevant sub-plans.
	The project will ensure to hire the contractor and subcontractor with highly qualified and licensed organizations and/or personnel with the adequately satisfied environmental management certification bodies for the construction activities.
	The project contractor/subcontractor will ensure to purchase the construction machinery and equipments, and the natural resources from adequate licensed suppliers accordingly.
	The compliance monitoring report along with the checklist will be indexed and annexed with the monthly and annual monitoring report. It may be required to submit the annual monitoring report to Department of Environmental Conservation for renewing of the Environmental Clearance Certificate each year.
	The project will develop and implement a monitoring and reporting plan as presented in the said section.
Chapter 8. Public Consultation and Information Disclosure	The project commits to engage the affected community and any project stakeholder in adequate manner and meaningfully consult them for any environmental and/or social issue related with the project activities.
	Land acquisition and resettlement action plan (LARAP or RAP) will be consulted and informed to the concerned stakeholders with active manner and will also link to the regional social development schemes.
Chapter 9. Grievance Redress Mechanism.	The project management units and focal person will also proactive address any project-related grievances raised in accordance with the established grievance redress process and procedure in a timely manner.
Chapter 10. Conclusions and Recommendations	The project will follow strictly the commitments and further suggestions as illustrated in Table 10.2-1 and section 10.3.

10.3 Further Recommendations


Although the project can be regarded as the foundation of the regional socioeconomic development process and safe inland transportation system, special attention to appropriate environmental and social management must be paid during construction phase and operation phase in order to avoid the environmental depletion due to careless manners and construction activities, and not burden the

regional social environment around the project site. A full implementation of the mitigation actions and resettlement actions are required to be carried out for those who would lose their economic and livelihood assets especially in the four expected townships: Twente, Seikkyi Khanaungto, Dala and Kyimyindaing. The ESMP for environmental protection, land acquisition process, grievance redress process and RAP for social and economic losses would need to be further elaborated and updated for adoption in the future, as appropriate.

The mitigation and resettlement actions should be in line with the current existing national laws and regulations of Myanmar and international safeguard standards and the Safeguard Policy of the Economic Development Corporation Fund (EDCF) of the Export-Import Bank of Korea.

Further suggestions are listed below for effective implementation of the ESMP:

- 1) The designated personnel within the project proponent (DWIR) shall be responsible for environmental protection and social management and shall resolve, in a timely manner, any environmental and social problem which may occur during the construction period.
- 2) All the environmental management activities shall be carried out against standardization of any pollutant outlet in accordance with the relevant standards.
- 3) The project proponent (DWIR) shall strengthen its maintenance and management of environmental protection facilities and social management activities, so as to ensure their normal functioning along with the project implementation.



စာအမှတ်၊ ၄ / ၇ - ၂ (၁၀) / လျှပ် ဆက်
ရက်စွဲ၊ ၂၀၁၈ ခုနှစ်၊ စက်တင်ဘာလ ၂၇ ရက်
အကြောင်းအရာ။ မြေယာလျော်ကြေးနှင့် မြေနေရာချထားရေး ညှိနှိုင်းဆောင်ရွက်ရေးကော်မတီ
ဖွဲ့စည်းတာဝန်ပေးအပ်ခြင်း

၂၀၁၈ ခုနှစ်၊ ဇူလိုင်လ(၂၆)ရက်နေ့တွင် ကျင်းပပြုလုပ်သည့် ရန်ကုန်တိုင်းဒေသကြီးအစိုးရအဖွဲ့ အစည်းအဝေးအမှတ်စဉ်(၂၈/၂၀၁၈)၊ ဆုံးဖြတ်ချက်အပိုဒ်(၅၉)အရ တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေး လုပ်ငန်းစီမံကိန်း၏ EIA-SIA လုပ်ငန်းများဆောင်ရွက်ရာတွင် မြေယာလျော်ကြေးနှင့်မြေနေရာ ချထားရေးကိစ္စရပ်များနှင့်စပ်လျဉ်း၍ ညှိနှိုင်းဆောင်ရွက်ရေးကော်မတီ အောက်ဖော်ပြပါပုဂ္ဂိုလ် များဖြင့် ဖွဲ့စည်းတာဝန် ပေးအပ်လိုက်ပါသည်-

မြေယာလျော်ကြေးနှင့်မြေနေရာချထားရေး ညှိနှိုင်းဆောင်ရွက်ရေးကော်မတီ

- | | | |
|-----|--|----------|
| (က) | ဒေါ်နီလာကျော် | ဥက္ကဋ္ဌ |
| | တိုင်းဒေသကြီးလျှပ်စစ်၊ စက်မှုလက်မှုနှင့်လမ်းပန်း ဆက်သွယ်ရေးဝန်ကြီး | |
| (ခ) | ဦးသစ္စာ | အဖွဲ့ဝင် |
| | ဌာနမှူး၊ မြို့ပြစီမံကိန်းနှင့်မြေစီမံခန့်ခွဲမှုဌာန
ရန်ကုန်မြို့တော်စည်ပင်သာယာရေးကော်မတီ | |
| (ဂ) | ဦးသန့်ဇင် | အဖွဲ့ဝင် |
| | အမှုဆောင်အရာရှိချုပ်၊ ရန်ကုန်လျှပ်စစ်ဓာတ်အားပေးရေး ကော်ပိုရေးရှင်း | |
| (ဃ) | ဦးကြည်တင် | အဖွဲ့ဝင် |
| | ညွှန်ကြားရေးမှူး၊ ရန်ကုန်တိုင်းဒေသကြီးစည်ပင်သာယာရေး အဖွဲ့ | |
| (င) | ဦးဇော်မိုးအောင် | အဖွဲ့ဝင် |
| | တိုင်းဒေသကြီးဦးစီးမှူး၊ လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့် စာရင်းအင်းဦးစီးဌာန | |
| (စ) | ဦးကျော်ကျော် | အဖွဲ့ဝင် |
| | တိုင်းဒေသကြီးဦးစီးမှူး၊ ရန်ကုန်တိုင်းဒေသကြီးစိုက်ပျိုးရေး ဦးစီးဌာန | |

- (ဆ) ဆီစီးဆင်းဝင်း
ညွှန်ကြားရေးမှူး၊ ရန်ကုန်တိုင်းဒေသကြီးစီမံကိန်းရေးဆွဲရေး
ဦးစီးဌာန
အဖွဲ့ဝင်
- (ဇ) ဦးနေဝင်းအောင်
ခရိုင်အုပ်ချုပ်ရေးမှူး၊ ရန်ကုန်တောင်ပိုင်းခရိုင်အထွေထွေ
အုပ်ချုပ်ရေးဦးစီးဌာန
အဖွဲ့ဝင်
- (ဈ) ဦးဘိုစိုး
တိုင်းဒေသကြီးတာဝန်ခံ၊ မြန်မာ့ဆိပ်ကမ်းအာဏာပိုင်
အဖွဲ့ဝင်
- (ည) ဦးမောင်မောင်လွင်
လက်ထောက်ညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်
မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ရန်ကုန်တိုင်း
ဒေသကြီး
အဖွဲ့ဝင်
- (ဋ) ဦးဌေးလွင်
လက်ထောက်ညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်
မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ရန်ကုန်တိုင်း
ဒေသကြီး
အဖွဲ့ဝင်
- (ဌ) ဦးအောင်ကျော်မှူး
တိုင်းဒေသကြီးဦးစီးမှူး၊ ရေအရင်းအမြစ်နှင့်မြစ်ချောင်းများ
ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ရန်ကုန်တိုင်းဒေသကြီး
အတွင်းရေးမှူး
- (ဍ) ဦးကျော်စိုး
ဒုတိယညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်မြစ်ချောင်းများ
ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ရန်ကုန်တိုင်းဒေသကြီး
တွဲဖက်အတွင်းရေးမှူး




ဝန်ကြီးချုပ်(ကိုယ်စား)

(နီလာကျော်၊ လျှပ်စစ်စက်မှုလက်မှုနှင့်လမ်းပန်းဆက်သွယ်ရေးဝန်ကြီး)

ဖြန့်ဝေခြင်း

မြေယာလျော်ကြေးနှင့် မြေနေရာချထားရေးညှိနှိုင်းဆောင်ရွက်ရေးကော်မတီဝင်များအားလုံး
မိတ္တူကို

ရန်ကုန်တိုင်းဒေသကြီးအထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန
ရုံးလက်ခံစာတွဲ/မျှောစာတွဲ



ပြည်ထောင်စုသမ္မတမြန်မာနိုင်ငံတော်
တိုင်းဒေသကြီးအစိုးရအဖွဲ့
ရန်ကုန်တိုင်းဒေသကြီး

စာအမှတ်၊ ၄ / ၇ - ၂ (၁၀) / လျှပ် ဆက်
ရက်စွဲ၊ ၂၀၁၈ ခုနှစ်၊ စက်တင်ဘာလ ၂၇ ရက်

အကြောင်းအရာ။ မြေယာလျော်ကြေးနှင့် မြေနေရာချထားရေးညှိနှိုင်းဆောင်ရွက်ရေး ဆပ်ကော်မတီ
ဖွဲ့စည်းတာဝန်ပေးအပ်ခြင်း

၂၀၁၈ ခုနှစ်၊ ဇူလိုင်လ(၂၆)ရက်နေ့တွင် ကျင်းပပြုလုပ်သည့် ရန်ကုန်တိုင်းဒေသကြီးအစိုးရအဖွဲ့
အစည်းအဝေးအမှတ်စဉ်(၂၈/၂၀၁၈)၊ ဆုံးဖြတ်ချက်အပိုဒ်(၅၉)အရ တွဲတေးတူးမြောင်းဖွံ့ဖြိုး တိုးတက်ရေး
လုပ်ငန်းစီမံကိန်း၏ EIA-SIA လုပ်ငန်းများဆောင်ရွက်ရာတွင် မြေယာလျော်ကြေးနှင့်မြေနေရာ
ချထားရေးကိစ္စရပ်များနှင့်စပ်လျဉ်း၍ ညှိနှိုင်းဆောင်ရွက်ရေးကော်မတီကို ဖွဲ့စည်းပြီးဖြစ်၍ ညှိနှိုင်း
ဆောင်ရွက်ရေးဆပ်ကော်မတီအား အောက်ဖော်ပြပါပုဂ္ဂိုလ်များဖြင့် ဖွဲ့စည်းတာဝန်ပေးအပ်လိုက်သည်-

မြေယာလျော်ကြေးနှင့်မြေနေရာချထားရေး ညှိနှိုင်းဆောင်ရွက်ရေးဆပ်ကော်မတီ(၁)

- | | |
|--|---------------------|
| (က) ဦးကျော်စိုး | အဖွဲ့ခေါင်းဆောင် |
| ဒုတိယညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်မြစ်ချောင်းများ
ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ရန်ကုန်တိုင်းဒေသကြီး | |
| (ခ) ဦးမြင့်ကြိုင် | ဒု-အဖွဲ့ခေါင်းဆောင် |
| လက်ထောက်ညွှန်ကြားရေးမှူး၊ လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့်
စာရင်းအင်းဦးစီးဌာန၊ ရန်ကုန်တောင်ပိုင်းခရိုင် | |
| (ဂ) ဦးမိုးခိုင်ထွန်း | အဖွဲ့ဝင် |
| မြို့နယ်အုပ်ချုပ်ရေးမှူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန၊
တွဲတေးမြို့နယ် | |
| (ဃ) လယ်ယာမြေနှင့်အခြားမြေများ သိမ်းဆည်းခြင်းခံရမှုများ | အဖွဲ့ဝင် |
| ပြန်လည်စိစစ်ရေးကော်မတီဝင်များ၊ တွဲတေးမြို့နယ် | |
| (င) ဦးသိန်းထူး | အဖွဲ့ဝင် |
| မြို့နယ်အုပ်ချုပ်ရေးမှူး၊ မြို့နယ်စည်ပင်သာယာရေးအဖွဲ့၊
တွဲတေးမြို့နယ် | |
| (စ) ဦးငြိမ်းချမ်းဇော် | အဖွဲ့ဝင် |
| မြို့နယ်လျှပ်စစ်မန်နေဂျာ၊ မြို့နယ်လျှပ်စစ်ဓာတ်အားပေးရေး၊
တွဲတေးမြို့နယ် | |
| (ဆ) ဦးခင်မောင်ဦး | အဖွဲ့ဝင် |
| မြို့နယ်မန်နေဂျာ၊ စိုက်ပျိုးရေးဦးစီးဌာန၊ တွဲတေးမြို့နယ် | |


- (ဇ) ဦးသန်းမောင် အဖွဲ့ဝင်
မြို့နယ်ဦးစီးမှူး၊ ဆည်မြောင်းဦးစီးဌာန၊ တွံတေးမြို့နယ်
- (ဈ) ဦးဖြိုးဆေကျော် အတွင်းရေးမှူး
မြေစာရင်းဦးစီးမှူး၊ မြို့နယ်လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့်
စာရင်းအင်းဦးစီးဌာန၊ တွံတေးမြို့နယ်
- (ည) ဦးသိန်းဇော် တွဲဖက်အတွင်းရေးမှူး
ဦးစီးအရာရှိ၊ ရေအရင်းအမြစ်နှင့်မြစ်ချောင်းများဖွံ့ဖြိုး
တိုးတက်ရေးဦးစီးဌာန
- မြေယာလျော်ကြေးနှင့်မြေနေရာချထားရေး ညှိနှိုင်းဆောင်ရွက်ရေးဆပ်ကော်မတီ(၂)
- (က) ဦးကျော်စိုး အဖွဲ့ခေါင်းဆောင် ✓
ဒုတိယညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်မြစ်ချောင်းများ
ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ရန်ကုန်တိုင်းဒေသကြီး
- (ခ) ဦးမြင့်ကြိုင် ဒု-အဖွဲ့ခေါင်းဆောင်
လက်ထောက်ညွှန်ကြားရေးမှူး၊ လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့်
စာရင်းအင်းဦးစီးဌာန၊ ရန်ကုန်တောင်ပိုင်းခရိုင်
- (ဂ) ဦးယဉ်ထွေး အဖွဲ့ဝင်
မြို့နယ်အုပ်ချုပ်ရေးမှူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန၊
ဒလမြို့နယ်
- (ဃ) လယ်ယာမြေနှင့်အခြားမြေများ သိမ်းဆည်းခြင်းခံရမှုများ အဖွဲ့ဝင်
ပြန်လည်စိစစ်ရေးကော်မတီဝင်များ၊ ဒလမြို့နယ်
- (င) ဦးခင်မောင်ကြွေ အဖွဲ့ဝင်
မြို့နယ်အုပ်ချုပ်ရေးမှူး၊ မြို့နယ်စည်ပင်သာယာရေးအဖွဲ့၊
ဒလမြို့နယ်
- (စ) ဦးမြရွှေ အဖွဲ့ဝင်
မြို့နယ်လျှပ်စစ်မန်နေဂျာ၊ မြို့နယ်လျှပ်စစ်ဓာတ်အားပေးရေး၊
ဒလမြို့နယ်
- (ဆ) ဦးမျိုးသူ အဖွဲ့ဝင်
မြို့နယ်မန်နေဂျာ၊ စိုက်ပျိုးရေးဦးစီးဌာန၊ ဒလမြို့နယ်
- (ဇ) ဦးရန်မိုးဦး အဖွဲ့ဝင်
မြို့နယ်ဦးစီးမှူး၊ ဆည်မြောင်းဦးစီးဌာန၊ ဒလမြို့နယ်

- (ဈ) ဦးမျိုးမင်းခိုင်
မြေစာရင်းဦးစီးမှူး၊ မြို့နယ်လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့်
စာရင်းအင်းဦးစီးဌာန၊ ဒလမြို့နယ်
အတွင်းရေးမှူး
- (ည) ဦးဌေးလွင်
လက်ထောက်ညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်
မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန
တွဲဖက်အတွင်းရေးမှူး
- မြေယာလျော်ကြေးနှင့်မြေနေရာချထားရေး ညှိနှိုင်းဆောင်ရွက်ရေးဆပ်ကော်မတီ(၃)
- (က) ဦးကျော်စိုး
ဒုတိယညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်မြစ်ချောင်းများ
ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ရန်ကုန်တိုင်းဒေသကြီး
အဖွဲ့ခေါင်းဆောင်
- (ခ) ဦးမြင့်ကြိုင်
လက်ထောက်ညွှန်ကြားရေးမှူး၊ လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့်
စာရင်းအင်းဦးစီးဌာန၊ ရန်ကုန်တောင်ပိုင်းခရိုင်
ဒု-အဖွဲ့ခေါင်းဆောင်
- (ဂ) ဦးဇော်သိန်း
မြို့နယ်အုပ်ချုပ်ရေးမှူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန၊
ဆိပ်ကြီးခနောင်တိုမြို့နယ်
အဖွဲ့ဝင်
- (ဃ) လယ်ယာမြေနှင့်အခြားမြေများ သိမ်းဆည်းခြင်းခံရမှုများ
ပြန်လည်စိစစ်ရေးကော်မတီဝင်များ၊ ဆိပ်ကြီးခနောင်တိုမြို့နယ်
အဖွဲ့ဝင်
- (င) ဦးအောင်ဇော်မိုး
မြို့နယ်အုပ်ချုပ်ရေးမှူး၊ မြို့နယ်စည်ပင်သာယာရေးအဖွဲ့၊
ဆိပ်ကြီးခနောင်တိုမြို့နယ်
အဖွဲ့ဝင်
- (စ) ဦးမြလှိုင်
မြို့နယ်လျှပ်စစ်မန်နေဂျာ၊ မြို့နယ်လျှပ်စစ်ဓာတ်အားပေးရေး၊
ဆိပ်ကြီးခနောင်တိုမြို့နယ်
အဖွဲ့ဝင်
- (ဆ) ဦးလှဌေး
မြို့နယ်ဦးစီးမှူး၊ စိုက်ပျိုးရေးဦးစီးဌာန၊ ဆိပ်ကြီးခနောင်တို
မြို့နယ်
အဖွဲ့ဝင်
- (ဇ) ဦးခင်ဇေ
မြေစာရင်းဦးစီးမှူး၊ မြို့နယ်လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့်
စာရင်းအင်းဦးစီးဌာန၊ ဆိပ်ကြီးခနောင်တိုမြို့နယ်
အတွင်းရေးမှူး

(ဈ) ဦးဌေးလွင်

တွဲဖက်အတွင်းရေးမှူး

လက်ထောက်ညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်
မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန



ဝန်ကြီးချုပ်(ကိုယ်စား)

(နီလာကျော်၊ လျှပ်စစ်၊ စက်မှုလက်မှုနှင့်လမ်းပန်းဆက်သွယ်ရေးဝန်ကြီး)

ဖြန့်ခွဲခြင်း

မြေယာလျော်ကြေးနှင့် မြေနေရာချထားရေးညှိနှိုင်းဆောင်ရွက်ရေးဆပ်ကော်မတီဝင်များအားလုံး

မိတ္ထူကို

ရန်ကုန်တိုင်းဒေသကြီးအထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန

ရုံးလက်ခံစာတွဲ/မျှောစာတွဲ

ပြည်ထောင်စုသမ္မတမြန်မာနိုင်ငံတော်

တိုင်းဒေသကြီးအစိုးရအဖွဲ့

ရန်ကုန်တိုင်းဒေသကြီး

စာအမှတ်၊ ၄ / ၇ - ၂ (၁၀) / လျှပ်ဆက်
ရက်စွဲ၊ ၂၀၁၈ ခုနှစ်၊ နိုဝင်ဘာလ ၆ ရက်

အကြောင်းအရာ။ မြေယာလျော်ကြေးနှင့် မြေနေရာချထားရေးညှိနှိုင်းဆောင်ရွက်ရေးဆပ်ကော်မတီ
ထပ်မံဖွဲ့စည်းခွင့်ပြုပါရန် တင်ပြလာခြင်းကိစ္စ

ရည်ညွှန်းချက်။ ရန်ကုန်တိုင်းဒေသကြီးရေအရင်းအမြစ်နှင့် မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေး
ဦးစီးဌာန၏ ၁၁.၁၀.၂၀၁၈ ရက်စွဲပါ စာအမှတ်၊ ၄၄ / ရလထ / ဒေသ - ၁ /
၈၈ (၁၀) / ၂၀၁၈

၁။ တွဲထားတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးလုပ်ငန်းစီမံကိန်း၏ EIA- SIA လုပ်ငန်းများဆောင်ရွက်
ရာတွင် မြေယာလျော်ကြေးနှင့် မြေနေရာချထားရေးကိစ္စရပ်များနှင့် ပတ်သက်၍ ညှိနှိုင်းဆောင်ရွက်ရေး
ကော်မတီ(၃)ခုကို ဖွဲ့စည်းပြီးဖြစ်ပါကြောင်း၊ ယခုအခါ ကြည့်မြင်တိုင်မြို့နယ်၏ နယ်မြေအနည်းငယ်
ပါဝင်နေသဖြင့် ဆပ်ကော်မတီ(၄)အဖြစ် အောက်ပါပုဂ္ဂိုလ်များဖြင့် ထပ်မံဖွဲ့စည်းတာဝန်ပေးအပ်ခွင့်ပြုပါရန်
ရန်ကုန်တိုင်းဒေသကြီးရေအရင်းအမြစ်နှင့် မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာနမှ ရည်ညွှန်းပါစာဖြင့်
တင်ပြလာခြင်းနှင့်စပ်လျဉ်း၍ ၁၈.၁၀.၂၀၁၈ ရက်နေ့တွင် ကျင်းပပြုလုပ်သော ရန်ကုန်တိုင်းဒေသကြီး
အစိုးရအဖွဲ့ အစည်းအဝေးအမှတ်စဉ်(၄၀/၂၀၁၈)၊ ဆုံးဖြတ်ချက်အပိုဒ်(၆)အရ အောက်ဖော်ပြပါပုဂ္ဂိုလ်
များဖြင့် ဖွဲ့စည်းတာဝန်ပေးအပ်လိုက်ပါသည်-

မြေယာလျော်ကြေးနှင့် မြေနေရာချထားရေးညှိနှိုင်းဆောင်ရွက်ရေးဆပ်ကော်မတီ(၄)

(က) ဦးကျော်စိုး

အဖွဲ့ခေါင်းဆောင်

ဒုတိယညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့် မြစ်ချောင်းများ
ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ရန်ကုန်တိုင်းဒေသကြီး

(ခ) ဦးမြင့်ကြိုင်

ဒု - အဖွဲ့ခေါင်းဆောင်

လက်ထောက်ညွှန်ကြားရေးမှူး၊ လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့်
စာရင်းအင်းဦးစီးဌာန၊ အနောက်ပိုင်းခရိုင်

(ဂ) ဦးဇာနည်ဝင်း

အဖွဲ့ဝင်

မြို့နယ်အုပ်ချုပ်ရေးမှူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန
ကြည့်မြင်တိုင်မြို့နယ်

(ဃ) လယ်ယာမြေနှင့် အခြားမြေများသိမ်းဆည်းခြင်း

အဖွဲ့ဝင်


ခံရမှုများပြန်လည်စိစစ်ရေးကော်မတီဝင်များ၊
ကြည့်မြင်တိုင်မြို့နယ်

(င) ဦးဇော်ရှင်းခမ်

အဖွဲ့ဝင်

မြို့နယ်အုပ်ချုပ်ရေးမှူး၊ မြို့နယ်စည်ပင်သာယာရေးအဖွဲ့
ကြည့်မြင်တိုင်မြို့နယ်

- (စ) ဦးအောင်သိန်း
မြို့နယ်လျှပ်စစ်မန်နေဂျာ၊ မြို့နယ်လျှပ်စစ်ဓာတ်အားပေးရေး
ကြည့်မြင်တိုင်မြို့နယ် အဖွဲ့ဝင်
- (ဆ) ဦးလှဌေး
မြို့နယ်ဦးစီးမှူး၊ စိုက်ပျိုးရေးဦးစီးဌာန၊ ကြည့်မြင်တိုင်မြို့နယ် အဖွဲ့ဝင်
- (ဇ) ဦးဝေမြိုးကျော်
မြို့နယ်ဦးစီးမှူး၊ မြို့နယ်လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့်
ဓာရင်းအင်းဦးစီးဌာန၊ ကြည့်မြင်တိုင်မြို့နယ် အဖွဲ့ဝင်
- (ဈ) ဦးဌေးလွင်
လက်ထောက်ညွှန်ကြားရေးမှူး၊ ရေအရင်းအမြစ်နှင့်
မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊
ရန်ကုန်တိုင်းဒေသကြီး အဖွဲ့ဝင်


ဝန်ကြီးချုပ်(တိုယ်စား)

(နီလာကျော်၊ လျှပ်စစ်၊စက်မှုလက်မှုနှင့် လမ်းပန်းဆက်သွယ်ရေးဝန်ကြီး)

ဖြန့်ဝေခြင်း
ကော်မတီဝင်များအားလုံး
မိတ္တူကို

ရန်ကုန်တိုင်းဒေသကြီးအထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန
ရန်ကုန်တိုင်းဒေသကြီးရေအရင်းအမြစ်နှင့် မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန ✓
ရုံးလက်ခံစာတွဲ
မျှောစာတွဲ

96° 07' 30" E



Pagoda

Pagoda







16° 48' 52.5" N

16° 48' 52.5" N

30m-2

0 m 500 m 1000 m

96° 07' 30" E

-  Anchorage
-  Church
-  Hospital
-  Mosque new
-  School
-  Pagoda

Seikkyi Khanaungto

96° 05' 37.5" E



96° 07' 30" E







16° 45' 00" N


16° 45' 00" N

96° 05' 37.5" E


96° 07' 30" E



-  Anchorage
-  Church
-  Hospital
-  Mosque new
-  School
-  Pagoda







ပြည်ထောင်စုသမ္မတမြန်မာနိုင်ငံတော်အစိုးရ
သယံဇာတနှင့်သဘာဝပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဝန်ကြီးဌာန
ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဦးစီးဌာန
ရုံးအမှတ် (၅၃)၊ နေပြည်တော်

စာအမှတ်၊ အီးအိုင်အေ- ၁ / ၇ (၉.၅၂ / ၂၀၁၉)
ရက်စွဲ ၂၀၁၉ ခုနှစ်၊ မေလ ၈ ရက်

ညွှန်ကြားရေးမှူးချုပ်
ရေအရင်းအမြစ်နှင့် မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန
ပို့ဆောင်ရေးနှင့်ဆက်သွယ်ရေးဝန်ကြီးဌာန

အကြောင်းအရာ။ တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သည့် ပြန်လည်
တင်ပြလာသော နယ်ပယ်အတိုင်းအတာသတ်မှတ်ခြင်း အစီရင်ခံစာ
(Revised Scoping Report) အပေါ် အတည်ပြုကြောင်းပြန်ကြားခြင်း

- ရည်ညွှန်းချက်။ (၁) ပို့ဆောင်ရေးနှင့်ဆက်သွယ်ရေးဝန်ကြီးဌာန၊ ရေအရင်းအမြစ်နှင့်
မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၏ ၁၁-၂-၂၀၁၉ ရက်စွဲပါ
စာအမှတ်၊ ၂/ ရလထ/ EDCF (တွဲတေး)/ ၂၀၁၉
(၂) ဤဝန်ကြီးဌာန၊ ပြည်ထောင်စုဝန်ကြီးရုံး၏ ၂၃-၄-၂၀၁၉ ရက်စွဲပါ
စာအမှတ်၊ (သစ်တော) ၃(၂)/၁၆(ဃ)/(၁၇၀၇/၂၀၁၉)

၁။ အထက်အကြောင်းအရာပါကိစ္စနှင့်ပတ်သက်၍ ပို့ဆောင်ရေးနှင့်ဆက်သွယ်ရေးဝန်ကြီးဌာန၊
ရေအရင်းအမြစ်နှင့်မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာနမှ ကိုးရီးယားသမ္မတနိုင်ငံ၏ ချေးငွေဖြင့်
ဆောင်ရွက်မည့် တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သည့် ပြန်လည်ပြင်ဆင်
တင်ပြလာသော နယ်ပယ်အတိုင်းအတာသတ်မှတ်ခြင်းအစီရင်ခံစာ (Revised Scoping Report) အား
လိုအပ်သလိုဆောင်ရွက်ပေးနိုင်ပါရန် ရည်ညွှန်း (၁) ပါစာဖြင့် ပေးပို့လာခြင်းအပေါ် အတည်ပြုနိုင်
ပါကြောင်း စိစစ်တင်ပြရာ ပြည်ထောင်စုဝန်ကြီးရုံးမှ ပြန်ကြားခွင့်ပြုကြောင်း ရည်ညွှန်း (၂) ပါစာဖြင့်
အကြောင်းကြားလာပါသည်။

၂။ အဆိုပြုစီမံကိန်းအား ပို့ဆောင်ရေးနှင့်ဆက်သွယ်ရေးဝန်ကြီးဌာနအောက်ရှိ ရေအရင်းအမြစ်
နှင့် မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာနမှ အကောင်အထည်ဖော်ဆောင်ရွက်မည်ဖြစ်ပြီး
တင်ပြလာသည့် နယ်ပယ်အတိုင်းအတာသတ်မှတ်ခြင်း အစီရင်ခံစာအား တတိယအဖွဲ့အစည်းဖြစ်
သည့် Resource & Environment Myanmar Ltd. (REM) နှင့် ကိုးရီးယားနိုင်ငံ ISAN Corporation မှ
ရေးသားပြုစုထားပါသည်။ အစီရင်ခံစာတွင် အကျဉ်းချုပ်အစီရင်ခံစာအပါအဝင် နိဒါန်း၊ ပတ်ဝန်းကျင်
ဆိုင်ရာ ဥပဒေများနှင့် အဖွဲ့အစည်းဆိုင်ရာမူဘောင်များ၊ စီမံကိန်းအကြောင်းအရာဖော်ပြချက်နှင့်
အခြားဆောင်ရွက်နိုင်သောနည်းလမ်းများ၊ အဆိုပြုစီမံကိန်း၏ပတ်ဝန်းကျင်ဆိုင်ရာအခြေအနေများ၊

၇။ ပတ်ဝန်းကျင်ဆိုင်ရာဖော်ပြချက်များအနေဖြင့် တံတွေးတူးမြောင်းဝန်းကျင်ရှိမြေမျက်နှာပြင် အနေအထားမှာ မြစ်ဝှမ်းဒေသ၏အင်္ဂါရပ်များဖြင့် ဖွဲ့စည်းထားပါကြောင်း၊ မြေမျက်နှာပြင်အမြင့်မှာ ၁.၀ မီတာ မှ ၁.၅ မီတာရှိပြီး ၆၂၆ စတုရန်းကီလိုမီတာလွှမ်းခြုံလျက်ရှိပါကြောင်း၊ စီမံကိန်းဧရိယာ၏ မြေအသုံးချမှုမှာ အဓိကအားဖြင့် မြို့ပြ၊ လယ်ယာမြေနှင့် တူးမြောင်းတို့ဖြစ်ပါကြောင်း၊ စီမံကိန်းဧရိယာတစ်ခုလုံးမှာ Meadow Alluvial မြေဆီလွှာအမျိုးအစားဖြစ်ပါကြောင်း၊ စီမံကိန်းဧရိယာအတွင်းရှိ လေထုသို့ထုတ်လွှတ်သည့် အဓိကအရင်းအမြစ်များမှာ စိုက်ပျိုးရေးဆိုင်ရာ ဟင်းလင်းပွင့် မီးရှို့ခြင်း၊ စက်မှုလုပ်ငန်းဆိုင်ရာ အခိုးအငွေ့များနှင့် သယ်ယူပို့ဆောင်ရေးမှ ထုတ်လွှတ်မှုများ ဖြစ်ပါကြောင်း၊ ဆူညံသံအရင်းအမြစ်မှာ စီမံကိန်းနေရာမြောက်ဘက် ဆိပ်ကြီး ခနောင်တိုချောင်းအနီး ဆိပ်ကမ်းအပါအဝင် တူးမြောင်းအတွင်းရှိ သင်္ဘောများနှင့် အနီးအနားရှိ လမ်းမကြီးမှ ယာဉ်သွားယာဉ်လာများမှဖြစ်ပါကြောင်း ဖော်ပြထားပါသည်။

၈။ ဒေသခံပြည်သူများနှင့် တွေ့ဆုံဆွေးနွေးခြင်းနှင့်ပတ်သက်၍ သက်ဆိုင်သူများနှင့်တွေ့ဆုံ ဆွေးနွေးခြင်း အခမ်းအနားကို တွံတေးမြို့နယ်၊ ဒလမြို့နယ်နှင့် ဆိပ်ကြီးခနောင်တိုမြို့နယ်တို့တွင် ကျင်းပခဲ့ပါကြောင်း၊ သက်ဆိုင်ရာ အစိုးရအဖွဲ့အစည်းများ၊ အနီးဝန်းကျင်ရှိ နေထိုင်သူများ၊ အခြား အဖွဲ့အစည်းများနှင့် စီမံကိန်းအား စိတ်ဝင်စားသည့်သူများ တက်ရောက်ခဲ့ကြောင်း စိစစ်တွေ့ရှိ ရပါသည်။

၉။ သို့ဖြစ်ပါ၍ ပို့ဆောင်ရေးနှင့်ဆက်သွယ်ရေးဝန်ကြီးဌာန၊ ဧရိယာအရင်းအမြစ်နှင့် မြစ်ချောင်းများ ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာနမှ ကိုးရီးယားသမ္မတနိုင်ငံ၏ ချေးငွေဖြင့်ဆောင်ရွက်မည့် တွံတေး တူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေး စီမံကိန်းနှင့်ပတ်သက်သည့် ပြန်လည်ပြင်ဆင်တင်ပြလာသော နယ်ပယ်အတိုင်းအတာသတ်မှတ်ခြင်းအစီရင်ခံစာ (Revised Scoping Report) သည် ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာ လုပ်ထုံးလုပ်နည်းနှင့် ကိုက်ညီမှုရှိသဖြင့် အတည်ပြုပါကြောင်းနှင့် အောက်ဖော်ပြပါအချက်များကို အလေးထားလိုက်နာဆောင်ရွက်ရန် လိုအပ်ကြောင်း သဘောထား ပြန်ကြားအပ်ပါသည် -

- (က) တင်ပြလာသည့် နယ်ပယ်အတိုင်းအတာသတ်မှတ်ခြင်းအစီရင်ခံစာနှင့် ဆောင်ရွက်မည့် လုပ်ငန်းတာဝန်များ (Terms of Reference - TOR) ကို အခြေခံ၍ ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ခြင်း အစီရင်ခံစာကို ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာ လုပ်ထုံးလုပ်နည်း အပိုဒ် (၆၀)၊ (၆၁)၊ (၆၂)၊ (၆၃)၊ (၆၅) ပါဖော်ပြချက်နှင့် အညီ ပြုစုရေးဆွဲတင်ပြရန်၊
- (ခ) ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာ လုပ်ထုံးလုပ်နည်း အပိုဒ် (၆၂) ပါဖော်ပြ ချက်များအတိုင်း စီမံကိန်းအဆိုပြုသူမှ လိုက်နာရမည့်အချက်များကို လက်မှတ် ရေးထိုးထားသည့် အတည်ပြုဝန်ခံချက်နှင့်အတူ အစီရင်ခံစာတွင် ထည့်သွင်းဖော်ပြရန်၊

- (ဂ) အဆိုပါသတ်မှတ်ချက်များနှင့်အညီရေးဆွဲပြုစုပြီး သယံဇာတနှင့်သဘာဝပတ်ဝန်းကျင် ထိန်းသိမ်းရေးဝန်ကြီးဌာနသို့ တင်ပြအတည်ပြုချက်ရယူရန်၊
- (ဃ) စီမံကိန်းဆောင်ရွက်ရာတွင် အသုံးပြုမည့် စက်ကိရိယာများ၊ သယံဇာတအရင်းအမြစ် များကို ဝယ်ယူအသုံးပြုသည့်အခါ တရားဝင်ခွင့်ပြုချက်ရရှိထားသည့် အဖွဲ့အစည်း များထံမှ ဝယ်ယူအသုံးပြုရန်၊
- (င) အဆိုပြုစီမံကိန်းကြောင့် မြေသိမ်းဆည်းခံရနိုင်မှုများ ရှိလာနိုင်သဖြင့် သိမ်းဆည်းခံရ နိုင်သော မြေနေရာများ၊ ပမာဏ၊ မြေအမျိုးအစား၊ သိမ်းဆည်းခံရနိုင်သော ဒေသခံ ပြည်သူအိမ်ထောင်စုအရေအတွက်၊ ၎င်းတို့၏ သက်မွေးဝမ်းကျောင်းအလုပ်အကိုင် နှင့် ပြန်လည်နေရာချထားရေး အစီအစဉ်တို့ကို ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်း အစီရင်ခံစာတွင် ထည့်သွင်းဖော်ပြရန်၊
- (စ) နယ်ပယ်အတိုင်းအတာသတ်မှတ်ခြင်း (Scoping Report) နှင့် Terms of Reference (TOR) တွင် ထည့်သွင်းဖော်ပြထားသည့် အချက်များအပြင် ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းအစီရင်ခံစာကို စိစစ်ပြီးနောက် အကယ်၍ ဖြည့်စွက်ပြင်ဆင်ဆန်းစစ်ရန် လိုအပ်သော အချက်များရှိပါက ထပ်မံ၍လေ့လာဆန်းစစ်ခြင်း ဆောင်ရွက်ရန်။



ညွှန်ကြားရေးမှူးချုပ် (ကိုယ်စား)
(ဒေါက်တာဆန်းဦး၊ ဒုတိယညွှန်ကြားရေးမှူးချုပ်)

မိတ္တူကို













ရုံးလက်ခံ၊ မျှောစာတွဲ

တွံတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- 21.9.2018

နေရာ- ဒီလမြို့

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၁	ဝင်းစိုးဝင်း	Director	REN	၉၅-၅၇၅၄၇၅၈	
၂	ဦးစိုးဝင်း	AGM	I.W.T	၀၉-၅၀၄၁၉၉၂	
၃	ဦးစိုးဝင်း	AGM	M.S	၀၉-၇၇၄၃၁၃၄၆၄	
၄	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၇၂၀၁၇၃၆၃	
၅	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၄၅၃၈၉၇၉၀	
၆	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၄၅၀၀၄၃၃၅၈	
၇	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၄၅၀၀၄၃၃၅၈	
၈	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၇၇၄၃၁၃၄၆၄	
၉	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၇၇၄၃၁၃၄၆၄	
၁၀	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၇၇၄၃၁၃၄၆၄	
၁၁	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၇၇၄၃၁၃၄၆၄	
၁၂	ဦးစိုးဝင်း	AGM	စက်မှု	၀၉-၇၇၄၃၁၃၄၆၄	

တွံတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၁.၉.၂၀၁၈

နေရာ- ဒီလမြို့













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၁၃-	အုန်းမိုးညို	သတ်မှတ်ထားသော	Transcom	၀၉၆၇၇ ၈၀၁၀ ၄၃	
၁၄-	ဦး ယသီဦး	မြို့နယ်သမဂ္ဂရေးရာ	အမျိုးသမီး	၀၉-၁၅၁၁၇၁၇၆	
၁၅-	ဦးကျော်စိုးဝင်း	အမျိုးသမီးရေးရာ	အမျိုးသမီး	၀၉-၇၇၇၈၇၇၇၇	
၁၆-	မောင်အောင်ဝင်း	မြို့နယ်	အမျိုးသမီး	၀၉-၂၅၀၅၀၇၅၇	
၁၇-	ဦးစိုးစိုး	အထွေထွေရေးရာ	အမျိုးသမီး	၀၉၇၇၇၇၇၇၇	
၁၈-	ဦးအောင်အောင်	ငါး	အမျိုးသမီး	၀၉ ၇၇၇၇၇၇၇၇	
၁၉-	ဦးအောင်အောင်	အထွေထွေရေးရာ	အမျိုးသမီး	၀၉-၂၅-၄၇၇၇၇၇	
၂၀-	ဦးအောင်အောင်	အထွေထွေရေးရာ	အမျိုးသမီး	၀၉-၇၇၇၇၇၇၇၇	
၂၁-	ဦးအောင်အောင်	အထွေထွေရေးရာ	အမျိုးသမီး	၀၉၇၇၇၇၇၇၇၇	
၂၂-	ဦးအောင်အောင်	အထွေထွေရေးရာ	အမျိုးသမီး	၀၉၇၇၇၇၇၇၇၇	
၂၃-	ဦးအောင်အောင်	အထွေထွေရေးရာ	အမျိုးသမီး	၀၉-၇၇၇၇၇၇၇၇	
၂၄-	ဦးအောင်အောင်	အထွေထွေရေးရာ	အမျိုးသမီး	၀၉-၇၇၇၇၇၇၇၇	

တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- 21.9.2018

နေရာ- ဒီလမြို့

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
25	ဦးလေးစိန် ဖွဲ့	ဒါရိုက်တာချုပ်	P.C.D.C	09420172943	
26	ဦးစောလှိုင်	ဆေးကုသရေး	ဇန်နဝါရီလ ၁	၄၂၀၁၅၇၁၂	
27	ဒေါ်လှိုင်စိုး	Reporter	MYRTV-4 news	09258545781	
28	Samphon Lee	EDUCATION	YooShin	rahun.lee@naver.com	
29	ဦးစောလှိုင်	ဥပဒေ/မ	ဒလ	09253998400	
30	ဦးစောလှိုင်	အထွေထွေရေး	ကမ္ဘာ့မိမိ	09125005400	
31	ဦးစောလှိုင်	မ/စ.မန်ဂျာ	M.P.A.	09448015836	
32	ဦးစောလှိုင်	ဦးစီးဌာန	M.P.A	09401324284	
33	ဒေါ်စောလှိုင်	ရင်းနှီးမြှုပ်နှံမှု	ဒလ	09422966799	
34	ဦးစောလှိုင်	အထွေထွေရေး	ကမ္ဘာ့မိမိ	09443172568	
35	ဦးစောလှိုင်	အထွေထွေရေး	ဒလ	09443172568	
36	Dr. စောလှိုင်	တာဝန်ခံ	ဒလ (ကျေးဇူး)	09455074447	

တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၁.၅.၂၀၁၆

နေရာ- ဒီလဖြူ













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၃၇	ဦးကျော်ကျော် (ဦးစီးဌာန: ၆၂၂/၃၀)	ဦးစီးဌာန: ၆၂၂/၃၀	ဒီလဖြူ	၀၉ ၄၂၀၀၈၅၅၆၇	
၃၈	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	၆၀၃/၁၄၆	၀၉ ၅၇၀၇၆၅၄	
၃၉	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀		၀၉ ၇၉၇၂၇၇၃၀၀	
၄၀	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	တာကြီး	၀၉၂၅၅၂၀၅၆၆၀	
၄၁	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	ဘဏ်သက်တော့အဖွဲ့အစည်း	၀၉၇၂၀၂၆၂၇၂၅	
၄၂	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	အလုပ်အကိုင်အဖွဲ့အစည်း	၀၉-၄၄၄၀၈၈၀၀၄	
၄၃	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	မောင်စု	၀၉၄၂၄၅၅၄၇၄၆	
၄၄	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	မောင်စု	၀၉ ၇၈၈၆၆၄၃၉	
၄၅	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	မောင်စု	၀၉-၅၄၄၅၅၅၀	
၄၆	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	ဒီလဖြူ	၀၉ ၇၃၁၀၆၇၀၇	
၄၇	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	မောင်စု	၀၉ ၄၃၁၆၈၄၃၁	
၄၈	ဦးစီးဌာန: ၆၂၂/၃၀	ဦးစီးဌာန: ၆၂၂/၃၀	မောင်စု	၀၉ ၇၇၇၅၅၅၇၇	

တုံ့တေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

လိုအပ်သော စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၁.၅.၂၀၁၈

နေရာ- ဒလမြို့













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
49	ဦးစောစော	ဒညွန့်	စာမကဆစ်ကျေးရွာ	၀၉၄၃၀၅၅၅၃	
50	ဦးကျော်စိုး	အထွေထွေ	ကျေးရွာ	၀၉၄၃၀၅၅၃	
51	ဦးစောစော	ဒညွန့်	ကျေးရွာ	၀၉၄၃၀၅၅၃	
52	ဦးကျော်စိုး	ဒညွန့်	MRTV	၀၉-၅၈၅၅၅၃	
53	ဦးကျော်စိုး	ဒညွန့်	ဒညွန့်	၀၉၄၃၀၅၅၅၃	
54	ဦးကျော်စိုး	ဒညွန့်	ကျေးရွာ	၀၉၄၃၀၅၅၅၃	
55	ဦးကျော်စိုး	ဒညွန့်	ကျေးရွာ	၀၉၄၃၀၅၅၅၃	
56	THE HO UAH	Manager	ISAN	+82-10-511-2144	
57	UTIN IM	Manager	GAIA Consult	+82-10-9649-5362	
58	YOUNN KANG	Director	ISAN Corp.	+82-10-6219-6229	
59	ဦးကျော်စိုး	ဒညွန့်	ကျေးရွာ	+09421103209	
60	ဦးကျော်စိုး	Director	REM	+959 799899391	

တံတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးမိမိမိမိနန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အစဉ်အနား

နေ့စွဲ- ၂၁.၅.၂၀၁၈

နေရာ- ဒီပဲယင်းမြို့













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၆၁	ဦး ဝင်းနု၊ ဦးစီး	ဥပဒေ	ကမ္ဘာ့စီးပွားရေးဦးစီးဌာန	၄၃၀ ၂၃၇၀၀၀	
၆၂	ဦး ရှင်မိုး	ဥပဒေ	မြန်မာ့စီးပွားရေးဦးစီးဌာန	၀၉ ၇၇၇၄၀၂၅၅၄	
၆၃	ဦးမျိုး	ဆက်သွယ်ရေး	ဒီပဲယင်း	၀၉ ၂၅၂၀ ၇၈၆၆၇	
၆၄	ဦးစောစော	မဟာဗျူဟာ	မြောက်ဥက္ကဋ္ဌ		
၆၅	ဦးစောစော	PC	REM	၀၉ ၄၀၃၅၀၅၈၈၆	
၆၆	ဦးစောစော	ဥပဒေ	DWR	၀၉ ၅၀၇၆၇၇၇	
၆၇	ဦးစောစော	ဥပဒေ	DWR	၀၉ ၄၂၀၀၆၅၇၅	
၆၈	ဦးစောစော		"	၀၉ ၄၄၈၀၀၆၆၆	
၆၉	ဦးစောစော	ဥပဒေ	"	၀၉ ၄၂၀၁၆၇၆၇၈	
၇၀	ဦးစောစော	ဥပဒေ - ၄	"	၀၉ ၄၅၁၆၇၇၇၇၇	
၇၁	ဦးစောစော		"	၀၉ ၄၇၆၇၇၇၇၇	
၇၂	ဦးစောစော	ဥပဒေ	"	၀၉ ၄၈၇၇၇၇၇၇	

တုံ့တေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အစည်းအနာ

နေ့စွဲ- ၂၁.၅.၂၀၁၆

နေရာ- အိပ်ကြီး၊ ခရော့စ်ဝဦး








စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁	ဒေါ်ကေဦး	ဦးစီးအရာရှိ	စီမံကိန်း	၀၇-၇၄၅၅၂၁၇၂၅	
၂	ဒေါ်ခင်နုလင်းလင်း	"	"	၀၇-၄၆၁၃၈၇၂၆၈	
၃	ဦးဂျွန်	ဦးစီးအရာရှိ	ကျေးဇူး	၀၇-၇၄၆၂၄၅၀၆၆	
၄	ဦးအောင်	ဦးစီးအရာရှိ	ဝဠာရပ်ကွက်	၀၇-၇၇၆၆၆၆၆၆	
၅	ဦးစောဝင်း	အထောက်အကူပြု (အထောက်အကူပြု)	အထောက်အကူပြု		
၆	ဒေါ်အေးအေး	အထောက်အကူပြု	"		
၇	ဦးအောင်	"	"		
၈	ဦးအောင်	"	"		
၉	ဦးအောင်	"	"		
၁၀	ဒေါ်အေးအေး	"	"		
၁၁	ဒေါ်အေးအေး	"	"		
၁၂	ဒေါ်အေးအေး	"	"		

တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၁.၉.၂၀၁၆

နေရာ- ဆီပုံကြီး၊ ခရော့စ်ပို့









စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁၃	ဦး ဖေဝင်း	မဟာမုတ္တမမြို့တော်	အိန္ဒိယ၊ ရန်ကုန်	၀၉ ၇၇၄၃၁၃၄၆၄	
၁၄	ဦး စိုးအောင်	အိုင်အိုင်အိုင်အိုင် ဦးစီးဌာန	အောင်အောင် (၇၇၇၇)	၀၉ ၅၅၀၂၅၀၀၀	
၁၅	ဦးမင်းမောင်မောင်	မဟာမုတ္တမမြို့တော်	အိန္ဒိယ	၀၉ ၂၅၀၇၈၅၇၀၀	
၁၆	ဦးအောင်	ရန်ကုန်	SPC	၉၇ ၄၀၀ ၅၅၀၁၅၁	
၁၇	CHITANIN WA	Manager	MBPI	၀၉ ၇၈၇၈၂၀၉၇	
၁၈	UTIN IM	Manager	GAIA Consult	+82 10 9649 5362	
၁၉	ဦးစိုးစိုးအောင်	Director	REM	၀၉ - ၅၇၅၆၇၆၈	

တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၁.၅.၂၀၁၈

နေရာ- ဆီပိကြီး၊ ခရောက်စိုင့်










စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၂၀	ဒေါ်ခင်အေး	မြို့နယ်ဦးစီးဌာန	လဝက	၀၉.၄၅၅၅၀၀၉၃	
၂၁	ဒေါ်ခင်အေး	ဆရာတော်	မင်း	၀၉.၇၇၇၇၇၇၇၇	
၂၂	ဒေါ်ခင်အေး	၅၆/၇၈		၀၉.၄၅၅၅၀၀၉၃	
၂၃	မ. နေအိမ်	အထက			
၂၄	မ. နေအိမ်	၁၁			
၂၅	မ. နေအိမ်	၅၆/၇၈		၃၁၃၄၇၇၇၇	
၂၆	မ. နေအိမ်	၁၁		၀၉.၄၅၅၅၀၀၉၃	
၂၇	မ. နေအိမ်	၅၆/၇၈	မင်း	၀၉.၄၅၅၅၀၀၉၃	

တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၁.၅.၂၀၁၆

နေရာ- သီပေါမြို့နယ်၊ နီမို











စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၂၈	ဒေါ်အေးဝင်းနု	ဒု. ဒီ. ဇီ. ဇီ.	မန္တလေးတိုင်းဒေသကြီး၊ ပုသိမ်မြို့နယ်၊ အထူးစစ်ဆေးရေးဌာန	၀၉-၂၆၃၁၂၁	
၂၉	ဦးစခိုင်စိုး	ဧည့်သည်အဖြစ်ပါဝင်ခြင်း	အထူးစစ်ဆေးရေးဌာန	၀၉-၂၆၃၁၂၁	
၃၀	" စခိုင်စိုး	စခိုင်စိုး	"		
၃၁	" အေးနု	ရန်ကုန်/အထူးစစ်ဆေးရေးဌာန	ခ/ဧည့်သည်အဖြစ်ပါဝင်ခြင်း	၀၉-၂၆၃၁၂၁	
၃၂	" သန်းစိုး	ရန်ကုန်/အထူးစစ်ဆေးရေးဌာန	ခ/ဧည့်သည်အဖြစ်ပါဝင်ခြင်း	၀၉-၂၆၃၁၂၁	
၃၃	၁. အထူးစစ်ဆေးရေးဌာန	ရန်ကုန်/အထူးစစ်ဆေးရေးဌာန	မန္တလေးတိုင်းဒေသကြီး၊ ပုသိမ်မြို့နယ်	၀၉-၂၆၃၁၂၁	
၃၄	" အထူးစစ်ဆေးရေးဌာန	ရန်ကုန်/အထူးစစ်ဆေးရေးဌာန	မန္တလေးတိုင်းဒေသကြီး၊ ပုသိမ်မြို့နယ်	၀၉-၂၆၃၁၂၁	
၃၅	ဦးအောင်စိုး	ဦးအောင်စိုး	မန္တလေးတိုင်းဒေသကြီး၊ ပုသိမ်မြို့နယ်	၀၉-၂၆၃၁၂၁	
၃၆	TAE HO NAM	Manager	ISAN Corp.	၀၉-၂၆၃၁၂၁	

တွဲတေးတေးပြောင်းပွဲပြီးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၁.၅. ၂၀၁၈

နေရာ- ဆိပ်ကြီး၊ခရောင်မို











စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၃၇	ဦးမိုးမြင့် (ဦးမိုးမြင့်၊ ဦးမိုးမြင့်)	ဦးမိုးမြင့်	ဦးမိုးမြင့်	၀၇ ၄၂၈၀၈၃၃၆၇	
၃၈	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၀၇ ၄၂၀၂၆၀၈၀၀	
၃၉	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၀၇ ၂၅၇၀၇၀၂၅၇	
၄၀	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၇၉၉၇၀၀၇၇၇	
၄၁	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၇၇၇၇၇၇၇၇	
၄၂	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၇၇၇၇၇၇၇၇	
၄၃	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၇၇၇၇၇၇၇၇	
၄၄	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၇၇၇၇၇၇၇၇	
၄၅	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၇၇၇၇၇၇၇၇	
၄၆	ဦးမိုးမြင့်	ဦးမိုးမြင့်		၇၇၇၇၇၇၇၇	

တွဲထားတူးပြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- 21.9.2018

နေရာ- ဆိပ်ကြီး၊ ခရောက်တို

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၄၇	ဦးအုန်းမင်း	လမ်းဆုံ (အလုပ်)	စုပေါင်း	၀၇၇၈၁၀၀၂၄၀၄	
၄၈	။ မောင်အောင်	ရပ်ကွက်	အစိုးရ	၀၉၅၈၀၅၈၁၈၈	
၄၉	။ ဦးကျော်	ရပ်ကွက်	။	၀၇၇၈၁၀၁၃၆၆၇	
၅၀	။ အောင်အောင်	အမှုကြီး	အမှုကြီး	၀၉၅၈၀၅၈၁၈၈	
၅၁	ဦးအောင်	ဦးအောင်	။	၀၇၇၈၁၀၁၃၆၆၇	
၅၂	ဦးအောင်	အမှုကြီး	အမှုကြီး	၀၇၇၈၁၀၁၃၆၆၇	
၅၃	ဦးအောင်	အမှုကြီး	။	၀၇၇၈၁၀၁၃၆၆၇	
၅၄	။ အောင်အောင်	။	။	၀၇၇၈၁၀၁၃၆၆၇	
၅၅	ဦးအောင်	။	။	၀၇၇၈၁၀၁၃၆၆၇	
၅၆	ဦးအောင်	။	။	၀၇၇၈၁၀၁၃၆၆၇	

ဝိမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံစေရေးနှင့် အခမ်းအနား

နေရာ- သီပေါမြို့နယ်၊ ခရီးစဉ်

[illegible]

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

കേന്ദ്ര-മധ്യ പ്രദേശ്













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
63	ဒေါ်ခန့်အေးလှ	ပစ္စည်းထိန်းသိမ်းရေးမှူး	ဘက်	၀၉-၄၂၀၁၆၇၆၁၈	Dea
64	ဒေါ်ဖြူလှအေး	နည်းဗျူဟာ	"	၀၉-၄၂၀၁၆၇၆၁၈	Dea
65	ဒေါ်ခန့်အေးလှ	"	"	"	"
66	ဒေါ် ယုတလှ	ထိန်းသိမ်းရေးမှူး	၀.၈.၆.၆	၀၉-၄၂၀၁၆၇၆၁၈	Dea
67	ဒေါ် ယုတလှ	"	"	၀၉-၄၂၀၁၆၇၆၁၈	Dea
68	ဒေါ် ယုတလှ	ဒေါ် ယုတလှ	၀.၈.၆.၆	၀၉-၄၂၀၁၆၇၆၁၈	Dea
69	ဒေါ် ယုတလှ	ဒေါ် ယုတလှ	"	"	"
70	ဒေါ် ယုတလှ	ဒေါ် ယုတလှ	"	၀၉-၄၂၀၁၆၇၆၁၈	Dea
71	ဒေါ် ယုတလှ	ဒေါ် ယုတလှ	၀.၈.၆.၆	၀၉-၄၂၀၁၆၇၆၁၈	Dea

တွဲထားတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၀.၅.၂၀၁၈

နေရာ- တွံတေး













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁	ဦးစောဝင်းသိန်း	Project manager	NVDC	၀၇-၇၈၀၈၃၃၃၄	
၂	ဦးစိုးမင်းဦး	Manager	"	၀၇-၂၆၀၂၁၃၅၄	
၃	ဦးကျော်လင်းထက်	City Planner III	"	၀၇-၇၇၇၇၇၂၈၄၇	
၄	ဦးလွင်လွင်	CSO, CMAA ကုမ္ပဏီလီမိတက်	"	၀၇-၇၈၀၄၈၅၄၇၀	
၅	ဦးအောင်ကျော်စိုး	ဧည့်သည်	"	၀၉၁၂၂၀၀၂၄၂၃၃	
၆	ဦးမျိုးခင်အေး	မြို့တော်ဦးစီးဌာန	သစ်တော	၀၇၂၂၂၂၅၆၈၈	
၇	ဦးမိုးကျော်စိုး	အထွေထွေ/လမ်းမ/မြို့တော်	မြို့တော်ဦးစီးဌာန	၀၇၄၄၇၁၇၄၇၄၆	
၈	ဦးကျော်စိုး	အထွေထွေ	မြို့တော်ဦးစီးဌာန	၀၇-၇၇၇၇၂၈၇၂၅၇	
၉	ဦးကျော်စိုး	အထွေထွေ	မြို့တော်ဦးစီးဌာန	၀၇-၇၇၇၇၂၈၇၂၅၇	
၁၀	ဦးကျော်စိုး	Media Journalist	NVDC News	၀၇၅၅၅၅၅၅၅၅	
၁၁	ဦးကျော်စိုး	အထွေထွေ	မြို့တော်ဦးစီးဌာန	၀၇၇၇၇၇၇၇၇၇	
၁၂	ဦးကျော်စိုး	အထွေထွေ	သစ်တော	၀၇၇၇၇၇၇၇၇၇	

တွဲတေးတူးပြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အစဉ်အနား

နေ့စွဲ- 20.9.2018

နေရာ- တွံတေး

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁၃	စိုးဖေစိုး	ကမ္ဘာ့ဂျပန်	ကမ္ဘာ့ဂျပန်	၀၉-၅၀၂၆၇၉၆	
၁၄	စိုးချိုထွန်း	"	ကျေးသစ်ဂျပန်	၀၉-၅၁၇၃၃၇၂၅	
၁၅	ဦးကျော်စိုး	တာဝန်ခံ	စစ်တပ် အရေးပေးအဖွဲ့၊ ၀၉-၇၈၂၅၆၀၂၉၂		
၁၆	ဦးတင်ဝင်းကျော်	ဒုတိယ	တွံတေး မြို့နယ်	၀၉-၅၈၉၆၁၈၁	
၁၇	ဒေါ်ခင်စိန်	ကုမ္ပဏီအုပ်ချုပ်	ကျေးသစ်ဂျပန်	၀၉-၅၀၅၇၆၀၁၄	
၁၈	ဦးအောင်ကျော်	ဥပဒေရေးရာ	YCDL . PC	၀၉-၅၄၀၈၁၃၄	
၁၉	ဒေါ်ခင်စိန်	လေ့လာရေး	လေ့လာရေး	၀၉-၇၇၂၄၇၈၁၅၅	
၂၀	ဦးကျော်စိုး	ကမ္ဘာ့ဂျပန်	ကျေးသစ်	၀၉-၅၁၆၈၀၆၉	
၂၁	ဦးကျော်စိုး	ကမ္ဘာ့ဂျပန်	ကျေးသစ်	၀၉-၅၁၆၈၀၆၉	
၂၂	ဦးကျော်စိုး	အထွေထွေ	ကျေးသစ်	၀၉-၇၇၂၄၇၈၁၅၅	
၂၃	ဦးကျော်စိုး	ကမ္ဘာ့ဂျပန်	ကျေးသစ်	၀၉-၇၇၂၄၇၈၁၅၅	
၂၄	ဦးကျော်စိုး	ကမ္ဘာ့ဂျပန်	ကျေးသစ်	၀၉-၇၇၂၄၇၈၁၅၅	

တွဲတေးတေးပြောင်းဖွဲ့ပြီးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၀.၅.၂၀၁၈

နေရာ- ဝဉ္စတော














စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၂၅	ဒေါ်ခေမာထွန်း	ဦးစီးအရာရှိ (အမျိုးသမီး)	ဆေးကုသရေးဦးစီးဌာန	၀၉-၅၄၈၃၆၄၇	
၂၆	ဦးသက်ဦး	အထောက်အကူပြု	ဆေးကုသရေးဦးစီးဌာန	၀၉-၄၄၄၄၇၆၆၆	
၂၇	ဦးသိန်းဝင်း	၇၁၂၃	မင်းဦး	၀၉-၇၈၆၆၈၇၇၇	
၂၈	ဦးကျော်မိုး	အထောက်အကူပြု	မင်းဦး	၀၉-၄၂၀၀၈၃၃၃	
၂၉	ဦးအောင်ကျော်	ဦးစီးအရာရှိ	အထောက်အကူပြု	၀၉-၇၈၆၆၈၇၇၇	
၃၀	ဦးစိုးဝင်း	အထောက်အကူပြု	အထောက်အကူပြု	၀၉-၄၂၁၁၇၇၇၇	
၃၁	ဦးစိုးဝင်း	အထောက်အကူပြု	အထောက်အကူပြု	၀၉-၄၂၁၁၇၇၇၇	
၃၂	ဦးစိုးဝင်း	အထောက်အကူပြု	အထောက်အကူပြု	၀၉-၄၂၁၁၇၇၇၇	
၃၃	Sangham Lee	EDCF TEAM	Yoshin	Sangham Lee	
၃၄	THE HO NAM	"	ISAN	namth 544@gmail.com	
၃၅	ဦးစိုးဝင်း	အထောက်အကူပြု	ဆေးကုသရေးဦးစီးဌာန	၀၉-၇၈၆၆၈၇၇၇	
၃၆	ဦးစိုးဝင်း	အထောက်အကူပြု	ဆေးကုသရေးဦးစီးဌာန	၀၉-၇၈၆၆၈၇၇၇	

တွဲထားသောအစည်းအရုံးကို ဖြစ်တည်စေရန်နှင့် ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အစည်းအနား

နေ့စွဲ- ၂၀၂၀/၁၀/၁၈

နေရာ- တွံတေး












စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၃၇	ဦးအောင်ကျော်မိုး	ဥက္ကဋ္ဌ (DWR)	DWR	၀၇-၅၀၇၈၇၇၇	
၃၈	ဦးမျိုးစိုးအောင်	မန်နေဂျာ (စီမံကိန်း)	စီမံကိန်းဌာန	၀၉-၄၄၈၀၂၇၉၅၅	
၃၉	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၅၄၀၄၈၇၄	
၄၀	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၀၇၄၄၄၄	
၄၁	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	
၄၂	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	
၄၃	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	
၄၄	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	
၄၅	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	
၄၆	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	
၄၇	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	
၄၈	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	
၄၉	ဦးစိုးမိုး	ဦးစီးဌာန	DWR	၀၇-၄၄၄၄၄၄၄၄	

တွဲထားသောအဖွဲ့အစည်းများ၏အဖွဲ့အစည်းများကိုစိစစ်ရန်နှင့်ပတ်သက်သောပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စိစစ်ကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၀၁၅. ၁၀.၁၆

နေရာ- တွံတေး









စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၄၉	ဦးကျော်	ခွန်ကြီး	သယံဇာတဌာန	၀၅-၄၇၀၀၈၄၈၄၇	
၅၀	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၉-၄၅၀၄၄၄၄၄	
၅၁	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၉-၄၅၀၀၃၃၃၃	
၅၂	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၅-၄၇၀၀၃၃၃၃	
၅၃	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၅-၄၇၀၀၃၃၃၃	
၅၄	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၅-၄၇၀၀၃၃၃၃	
၅၅	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၅-၄၇၀၀၃၃၃၃	
၅၆	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၅-၄၇၀၀၃၃၃၃	
၅၇	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၅-၄၇၀၀၃၃၃၃	
၅၈	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၅-၄၇၀၀၃၃၃၃	
၅၉	ဦးအောင်	ဆေးကုသရေး	ကျေး	၀၅-၄၇၀၀၃၃၃၃	

တွဲထားတူးပြောင်းဖွဲ့ပြီးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၀.၅.၂၀၁၈

နေရာ- ချုံတော

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁၀၁	Pawng Htet	Reporter	MgitMakha News	၀၉၄၂၀၁၇၁၆၄၆	
၁၀၂	Sare Thiri Khin	Reporter	Sly Net (Cone new)	၀၉ - ၉၀၀၉၅၅၀၀	
၁၀၃	မြတ်ဗောဓိ	စာဖတ်/စာရေး	အောင်တောင်လွှာ	၀၉, ၅၃၉၆၄၃၁	
၁၀၄	ဒေါ်အေးအေး	စာဖတ်	အောင်တောင်လွှာ အ. ဦးစိုးမိုး	၀၉-၉၀၂၀၄၆၂၃	
၁၀၅	မ. အေးနီ	စာဖတ်/စာရေး	အောင်တောင်လွှာ	၀၉ - ၇၇၀၀၀၇၅၇	
၁၀၆	မ. အောင်မြင်	စာဖတ်	မြို့တော်မြို့	၀၉-၉၇၇၇၇၇၇၇	
၁၀၇	မ. အောင်အောင်	စာဖတ်/စာရေး	ပိတ်တောက်	၀၉-၇၈၀၀၀၆၈၁၂	
၁၀၈	မ. အောင်အောင်	စာဖတ်/စာရေး	အောင်တောင်လွှာ	၀၉-၇၇၈၈၈၈၈၈	

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေရာ-
သို့







စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၀၉	ဦးသန်းထွန်း		၁၇၂၆၀	၀၉-၂၅၄၀၃၉၉၈	
၁၀	ဦးသန်းဦး	၁၀/၁၃၃၁	အိမ်ထောင်ရေး	၀၇-၇၂၃၀၇၇၆၃၄	
၁၁	ဦးပန်းစုံ	၇၄/၁၂၂၀	၁၀၀၀	၀၇-၄၂၀၇၆၇၂၆	
၁၂	ဦးသန်းအောင်	၇၅/၁၂၂၀	အိမ်ထောင်ရေး	၀၉-၂၅၄၀၃၉၉၈	
၁၃	ဦးသန်းအောင်	၇၆/၁၂၂၀	အိမ်ထောင်ရေး	၀၇-၇၂၃၀၇၇၆၃၄	

တွဲတေးတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၀. ၉. ၂၀၁၈

နေရာ- တွံတေး

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၇၄	ဦးစာဒဦး	အုပ်ချုပ်ရေးမှူး	မွန်မြို့နယ်ဌာန	၀၉/၇၈၈၂၂၆၁၂	
၇၅	ဦးစိုးစိုးကျော်	အမှုဆောင် မဟုတ်	အမတ်	၀၉ ၄၂၀၄၈၈၀	
၇၆	ဦးအောင်အောင်	ပရိသတ်	အ.က.ပ.ဌာန		
၇၇	အောင်အောင်	ကလေးကလေး	အုပ်ချုပ်ရေးမှူး	၀၉ ၇၈၈၂၂၆၁၂	
၇၈	ဦးကျော်စိုး	အထောက်အကူ	အမတ်	၀၉ ၄၂၀၄၈၈၀	
၇၉	ဦးကျော်စိုး	အုပ်ချုပ်ရေးမှူး	ကလေး	၀၉-၇၇၈၂၂၆၁၂	
၈၀	ဦးကျော်စိုး	အုပ်ချုပ်ရေးမှူး	အထောက်အကူ	၀၉ ၇၇၈၂၂၆၁၂	

ଉତ୍ତର-ପୂର୍ବ

၀၃	အမည်		၄၁/၂၀၁၆	လက်မှတ်
၀၁	Yoon Min KANG	Director from Korea, ISAN		Kang
၀၂	Moe Hsint Phyu	Interpreter.		Hsint Phyu
၀၃	CHIT HAIN WAI @ veska	Myanmar Business Research Institute (Manager)		Wai
၀၄	NANT ROSE LINDA	Researcher of (MBRI) Myanmar-Business Research Institute		Rose
၀၅	TAE HO UAM	ISAN Corporation		Jam
၀၆	Tim Aung Thaw	NYDC - PM		Aung Thaw
၀၇	Yu Lin Se	NYDC - Manager		Lin Se
၀၈	Kyaw Lin Htet	NYDC - City Planner III		Htet
၀၉				
၁၀				
၁၁				
၁၂				
၁၃				
၁၄				
၁၅				
၁၆				
၁၇				
၁၈				
၁၉				
၂၀				

Appendix 8. Public Consultation Meeting (PCM) Minutes during the EIA Report

1. Seikkyi Khanaungto Township

တွဲစာတရားပြောင်းလဲခြင်း၊ ဦးစီးတိုင်းတော်တရားရုံးနှင့် ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ခုတ်ယူဆွဲကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အသိပေးအမှာစာ

နေ့စွဲ- ၂၆.၁.၂၀၁၅

နေရာ- သီပေါမြို့၊ သရက်တန်း

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၀၁	ဦးခင်သန်းစိုး	ဦးစီးဌာနမှူး	သမ္မတမြန်မာနိုင်ငံတော်	၀၉-၂၅၀၇၁၁၁	
၀၂	ဦးစိုးမိုးစိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၀၃	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၀၄	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၀၅	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၀၆	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၀၇	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၀၈	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၀၉	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၁၀	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၁၁	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	
၁၂	ဦးကျော်စိုး	ဦးစီးဌာနမှူး	ဧရာဝတီတိုင်းဒေသကြီး	၀၉-၄၂၀၁၁၁၁	

၂၀၁၅-၀၁-၂၆













တွဲစာတရားပြောင်းဖွဲ့ ဦးတိုက်တက်ရောက်ရန်နှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

(2)

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ခုတ်ယူအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့ရက်- ၇၆.၁.၂၀၁၅

နေရာ- သီပေါကြီး ၁၈၇၆၀၇

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၀၁	ဦးရွှေမင်း	ကဗျား ဥပဇ္ဈာန်	ဓမ္မဗျူဟာ	၀၉၅၉၆၃၀၀၃၇၃	
၂	ဦးစုဇော်	အစီအစဉ်ရေးဆွဲသူ	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇၅၀၈၈၈၈၈	
၃	ဦးစုဇော်	ဝန်ထမ်းချုပ်	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇-၅၇၇၂၆၄၇၇၄	
၄	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇ ၅ ၇ ၈ ၈ ၄ ၇	
၅	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇-၅၇၇၂၆၄၇၇၄	
၆	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇၅၀၈၈၈၈၈၈၈	
၇	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇-၅၇၇၂၆၄၇၇၄	
၈	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇၅၀၈၈၈၈၈၈၈	
၉	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇၅၀၈၈၈၈၈၈၈	
၁၀	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇၅၀၈၈၈၈၈၈၈	
၁၁	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇၅၀၈၈၈၈၈၈၈	
၁၂	ဦးစုဇော်	၀၇၅၀၈၈၈၈၈၈၈	စစ်ကိုင်းတိုင်းဒေသကြီးအစိုးရ	၀၇၅၀၈၈၈၈၈၈၈	

တွဲစာတရားပြောင်ဖွဲ့ပြီးတိုက်ရိုက်ရေစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစစ်အမှန်

နေ့စွဲ- ၂၆.၁. ၂၀၁၉

နေရာ- သီပေါမြို့၊ သောကတော

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၀၁	Mr. Aung Mye	ဥက္ကဋ္ဌ	Myanmar Myanmar	၀၇-၅၅၃၈၈၈	မူရင်း
၀၂	စာအုပ်အုပ်စု		သီပေါမြို့၊ သောကတော		မူရင်း
၀၃	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၀၄	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၀၅	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၀၆	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၀၇	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၀၈	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၀၉	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၁၀	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၁၁	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း
၁၂	ဦးမြင့်မိုး	တာဝန်ရှိသူ	သီပေါမြို့၊ သောကတော	၀၇-၂၂၂၂၂၂၂၂	မူရင်း

တုံ့တေးကွာခြောင်းဖွဲ့ ဦးစီးဌာနတက်ရောက်မိန့်နှင့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ခုတ်ယူဆက်ပြန်ခြင်းအတွက်ဆွေးနွေးခြင်း အစီရင်ခံစာများ

နေ့စွဲ- ၂၆.၁.၂၀၁၅

နေရာ- ဆိပ်ကြီးခရိုင်တွင်

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၀၁	ဦးမောင်ကျော်မိုး	ဒုတိယဗဟို	ဥပဒေ	၀၉၀၇၈၁၅၅	မောင်ကျော်မိုး
၀၂	ဒေါ်မောင်အေး	ဥပဒေ	မ	၀၉.၅၀၅၆၅၄	ဒေါ်မောင်အေး
၀၃	ဒေါ်မိုးလွင်	မ	မ	၁၅၅၄၀၇၅၅၈၈	ဒေါ်မိုးလွင်
၀၄	ဒေါ်မောင်အောင်	ဥပဒေ	မ	၁၀၀၀၅၅	ဒေါ်မောင်အောင်
၀၅	ဒေါ်မောင်အောင်	ဥပဒေ	မ		ဒေါ်မောင်အောင်
၀၆	ဒေါ်မောင်အောင်	မ			ဒေါ်မောင်အောင်
၀၇	ဒေါ်မောင်အောင်	မ			ဒေါ်မောင်အောင်
၀၈	ဒေါ်မောင်အောင်	မ			ဒေါ်မောင်အောင်
၀၉	ဒေါ်မောင်အောင်	မ			ဒေါ်မောင်အောင်
၁၀	ဒေါ်မောင်အောင်	မ			ဒေါ်မောင်အောင်
၁၁	ဒေါ်မောင်အောင်	မ			ဒေါ်မောင်အောင်
၁၂	ဒေါ်မောင်အောင်	မ			ဒေါ်မောင်အောင်

တို့ထားတူခြင်းနှင့် ဦးတိုးတက်ဆောင်ရွက်နိုင်ရန်နှင့် ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သည့်အား ခုတ်ယူအကြံပြုနိုင်ရန်အတွက်ဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၁၆.၁.၂၀၁၅

နေရာ- ဆိပ်ကြီး၊ ခရိုင်

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၀၁	ဒေါ်အေးစိုးဝင်း	မှတ်တမ်း	သတင်းနှင့်အချက်အလက်	၀၉-၅၀၁၉၈၂၁	
၀၂	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	"	၀၉၃၆၁၅၈၆၇၇	
၀၃	ဒေါ်အေးစိုးဝင်း	နည်းပညာ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၀၄	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၀၅	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၀၆	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၀၇	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၀၈	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၀၉	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၁၀	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၁၁	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	
၁၂	ဒေါ်အေးစိုးဝင်း	အထွေထွေ	အချက်အလက်	၀၉၃၆၁၅၈၆၇၇	

တွဲစားတူးမြောင်းဖွဲ့ပြီးတိုးတက်ရန်မံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

26.1.2019

பெயர்: அருண் செல்வம்

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရေးနံပါတ် Contact Phone	လက်မှတ် Sign
၁	ဦးဦးဝင်း	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးဦးဝင်း
၂	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၃	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၄	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၅	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၆	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၇	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၈	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၉	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၁၀	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၁၁	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး
၁၂	ဦးစိုးမိုး	၇၆၆၇၆၇	၁/၀၇ ၁၇၆၆၆		ဦးစိုးမိုး

တွဲစာတရားပြောင်းဖွဲ့ပြီးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ခုတ်ယူအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစီရင်ခံစာအား

နေ့စွဲ- ၂၀၁၆.၁၀.၂၅

နေရာ- သီပေါ(ကြီး)ခရိုင်













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်စုံနိုး Contact Phone	လက်မှတ် Sign
၀၁	ဦးအောင်အောင်		သဒ္ဓါစာတိုက်		
၀၂	ဦးသီရိသီရိ	ဦးစီး	သဒ္ဓါစာတိုက်		
၀၃	ဦးအောင်အောင်	ဦးစီး		၀၉-၇၅၀၀၇၇၀၈	
၀၄	ဦးအောင်အောင်	ဦးစီး			
၀၅	ဦးအောင်အောင်	ဦးစီး			
၀၆	ဦးအောင်အောင်	ဦးစီး			
၀၇	ဦးအောင်အောင်	ဦးစီး			
၀၈	ဦးအောင်အောင်	ဦးစီး			
၀၉	ဦးအောင်အောင်	ဦးစီး			
၁၀	ဦးအောင်အောင်	ဦးစီး			
၁၁	ဦးအောင်အောင်	ဦးစီး			
၁၂	ဦးအောင်အောင်	ဦးစီး			

တုံ့ပြန်ချက်အရ နယ်လုပ်ငန်းဆိုင်ရာ ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၆.၁.၂၀၁၅

နေရာ- ဆီလီဆွီ အောက်

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၁	Engr U Tun Tun Win	Engineer	Myanmar Engineering Society	09309 708 44	
၂	ဦးသီရိသီ	၇၄/၇၃၈	အေ/၃၃	၀၇၄၂၀၂၆၀၄၃၀	
၃	ဦးအုန်းမောင်	အိုင်အိုင်အိုင်			
၄	မောင်အောင်အောင်			၀၉.၇၇၄၂၈၇၇၈၅	
၅	ဦးဗဟိဒ္ဓ	မောင်အိုင်အိုင်အိုင်	အိုင်အိုင်အိုင်အိုင်	၀၉၇၂၀၇၀၈၈၈	
၆	ဒေါ်ခင်စန်းစန်း	အောင်အိုင်		၀၉-၂၅၁၀၇၀၆၇၀	
၇	ဦးမောင်မောင်	မောင်မောင်	မောင်မောင်မောင်	၀၉-၄၄၀၀၆၇၄၄	
၈	မောင်မောင်		မောင်မောင်မောင်-မောင်	၀၉၇၄၃၀၇၃၃၀၄	
၉	ဦးမောင်မောင်	မောင်မောင်		၀၉၇၄၄၄၄၄၄၄	
၁၀	ဦးအောင်အောင်	မောင်မောင်	မောင်မောင်မောင်	၀၉-၇၇၇၇၇၇၇၇	
၁၁	မောင်မောင်		မောင်မောင်မောင်	၀၉-၇၇၇၇၇၇၇၇	
၁၂	ဦးသီရိသီ		မောင်မောင်မောင်		

တွဲစာတေးရောင်းခွင့် ပြုစုတိုးတက်ရေးမိမိမိမိနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

မိမိမိမိနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစိမ်းအနား

နေ့စွဲ- ၂၆.၁.၂၀၁၉

နေရာ- သီပေါမြို့၊ အရှေ့အလယ်

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁။	သုခမောင်	အထိပဒေသကြီး	အိတ်/ပေးကမ်း		
၂။	ဦးစုန်းမောင်တို့	ကျေးဇူးတင် ဂုဏ်ထူးဆောင် သမား၊ မြို့သူ	မင်္ဂလာဒုံမြို့နယ်၊ သစ်တောတန်း	၀၉ ၇၇၄၁၃၁၁၁၁	
၃။	ဒေါ်ခင်စန်း	ဥပဒေရေးရာ	အရှေ့အလယ်		
၄။	ဦးစုန်းမောင်	"	"		
၅။	ဦးစုန်းမောင်	"	"		
၆။	ဦးစုန်းမောင်	"	"		
၇။	မောင်မောင်	ဥပဒေရေးရာ	"		
၈။	အောင်မြင်	"	"		
၉။	အောင်မြင်	ကျေးဇူးတင် ဂုဏ်ထူးဆောင် သမား၊ မြို့သူ	အရှေ့အလယ်		
၁၀။	ဦးစုန်းမောင်	ဥပဒေရေးရာ	အရှေ့အလယ်		
၁၁။	ဦးစုန်းမောင်	ဥပဒေရေးရာ	အရှေ့အလယ်		
၁၂။	ဦးစုန်းမောင်	ဥပဒေရေးရာ	အရှေ့အလယ်		

တို့ကတော့ကွေးပြောင်းဖို့ ဦးတိုက်တာကရေစိမ့်ကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စိမ့်ကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်ပြောကြားတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၆.၁.၂၀၁၇

နေရာ- ဆိပ်ကြီး၊ ခန္တောစေတီ

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၀၁	ဦးဝင်း၊ ဦး	ဇယား	ဆိပ်ကြီး ကျောက်		— S. —
၀၂	ဦးရှင်လွန်း၊	ကလေး - ၁	မင်းမင်းလွန်း		Y. A.
၀၃	ဦးမင်းမင်းလွန်း၊	ကျောက်	စောလင်း ဇီဝိဒ္ဓါလေ၊	၇၆၁၆၁၃၇၀၀	မောင်
၀၄	ဦးတင်မောင်၊	ရပ်ကွက်	အမှတ် ၁၃၃		မောင်
၀၅	ဦးဆွေ၊	မ	မ		မောင်
၀၆	ဦးကျော်ဝင်း၊	မ	မ		မောင်
၀၇	ဦးစံလွင်	အယ်ဒီတာ	မ	၀၇-၄၃၀၂၆၀၀၅၈၈	မောင်
၀၈	ဦးဖြူမောင်၊	ရပ်ကွက်	မ		မောင်
၀၉	ဦးဝင်းမင်းလွင်		ဆိပ်ကြီးကျောက်		မောင်
၀၁၀	ဦးမောင်၊	မ	ဆိပ်ကြီးကျောက်		မောင်
၀၁၁	ဦးမောင်၊	မ	ဆိပ်ကြီးကျောက်		မောင်
၀၁၂	ဦးမောင်၊	မ	ဆိပ်ကြီးကျောက်		မောင်

တို့ထားသောခြင်းဖွဲ့ပြီးတိုက်ရင်းရင်းပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- 26. ၁. 2019

နေရာ- သီပေါမြို့၊ ခရိုင်တို့





စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ရုံး Contact Phone	လက်မှတ် Sign
၁။	အောင်မင်း		စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		မင်း
၂။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၃။	အောင်မင်း				အောင်မင်း
၄။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၅။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၆။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၇။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၈။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၉။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၁၀။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၁၁။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း
၁၂။	အောင်မင်း	အောင်မင်းလမ်းမှတ်တမ်း	စစ်ကိုင်းတိုင်းဒေသကြီး၊ ပုသိမ်မြို့		အောင်မင်း

တွဲထားသောအခြေခံသို့ ပြုစုထိန်းသတ်ရေးမိခံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစီရင်ခံစာအား

နေ့စွဲ- ၂၀၁၁.၁၀.၂၀

နေရာ- သီပေါမြို့၊ ခရိုင်အောင်

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၁	ဒေါ်အိန်းခင်		မိမိ/၄၇ ဘဏ္ဍာရေး	၀၇-၇၄၃၃၁၁၇၀	
၂	မိုးဦးမိုး		မိမိ/၄၇	၀၇-၇၄၇၁၆၂၃၀၃	
၃	ဦးစွန်းမိုးသန်း		မိမိ/၄၇	၀၇.၄၃၀၆၄၀၇၃	
၄	ဦးစိုးကြည်		သစ်စက်မှုရေးရာ		
၅					
၆					
၇					
၈					
၉					
၁၀					
၁၁					
၁၂					

တို့တရားလွှာကြောင်း၌ ဦးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းခေါ်ရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဖုတ်ယအကြံပြုခြင်းတွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၇.၁.၂၀၁၇ နေရာ- သီပေါမြို့မဧကခြေ






စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ရုန်း Contact Phone	လက်မှတ် Sign
၁။	ဦးစိုးဦး		မိမိ ၁/၄၅ ကြာကတ်ခြေ		ဦးစိုးဦး
၂။	ဦးစိုးအောင်	ကျေး (ကျေး)	မိမိ ၁/၄၅ ကြာကတ်ခြေ		ဦးစိုးအောင်
၃။					
၄။					
၅။					
၆။					
၇။					
၈။					
၉။					
၁၀။					
၁၁။					
၁၂။					

တုံ့တားကူးပြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစမ်းအနား

၀၉-၂၆-၂၀၁၇

နေရာ- သီပေါ၊ ၁၀၇၆၀၃၂၉-၂၄










စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ရုံး Contact Phone	လက်မှတ် Sign
၁	Einpyung Lee	Consultant	GreenArk Inc/ Seoul	၀၉-၇၆၃၄၄၇၃၅	
၂	Reu Khin Ohnner Htwe	Rem "	REN	၀၉-၇၇၅၄၆၂၃၂	
၃	Jernyeim	REN	REN	၀၉-၇၇၆၄၄၇၃၅	
၄	TIN TUN NAIN (MR.)	M.P.	Member of Parliament	၀၉-၇၇-၇၇၇၇၇၇	
၅	Daw Lai Lai Win	Principal Consultant	REN	၀၉-၇၇၇၇၇၇၇၇	
၆					
၇					
၈					
၉					
၁၀					
၁၁					
၁၂					

တို့တဝါးတရားပြောသုံးပြီးတိုတဝါးရေစီမံကိန်းနှင့်ပတ်သက်သော သတ်သန်ကျင့်ထိမိကိစ္စဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်ပြောကြားစေရန်ဆောင်ရွက်ခြင်း အစီရင်ခံစာများ

နေ့စွဲ- ၂၀၁၉.၁.၁၀

နေရာ- တွံတေး

စဉ် Sr.	အမည် Name	ရာထူး Position	အဖွဲ့အစည်း/ Organization/ Address	ဆက်သွယ်ရေးနံပါတ် Contact Phone	လက်မှတ် Sign
၀၁	ဦးအောင်ကျော်	ဦးစီး	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	
၀၂	ဦးအောင်ကျော်	အထွေထွေ	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	
၀၃	ဦးအောင်ကျော်	အထွေထွေ	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	
၀၄	ဦးအောင်ကျော်	အထွေထွေ	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	
၀၅	ဦးအောင်ကျော်	အထွေထွေ	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	
၀၆	ဦးအောင်ကျော်	အထွေထွေ	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	
၀၇	ဦးအောင်ကျော်	အထွေထွေ	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	
၀၈	ဦးအောင်ကျော်	အထွေထွေ	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	
၀၉	ဦးအောင်ကျော်	အထွေထွေ	မိုးလျားလမ်း(၁၀၁)	၀၉၄၂၀၁၇၄၇၄၆	

တို့စာတရားပြင်ဆင်မှု၊ ငြိမ်းချမ်းစေရေးမိန့်နှင့်ပတ်သက်သော ယဝ်းမိန့်ကျင့်ထိခိုက်မှုဆန်းစစ်ခြင်းကော်မရှင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဖုန်းနံပါတ်ပြန်ကြော်ငြာစာတွင်ဖော်ပြပါ အချက်အလက်များ

နေ့စွဲ- ၂၀၁၁.၁၁.၁၅

နေရာ- ထွဲစာ

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁	ဦးဇော်ဝင်း	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၂	ဦးမောင်အောင်		မင်းမိမိလမ်း		
၃	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၄	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၅	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၆	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၇	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၈	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၉	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၁၀	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၁၁	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	
၁၂	ဦးမောင်အောင်	ဦး/၂၄	မင်းမိမိလမ်း	၀၉ ၇၇ ၁၅၀၈၁၁	

၀၀၀

တံတားတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၈.၁.၂၀၁၅

နေရာ- တွံတား













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၀၁	ကိုဝင်းလ		မင်္ဂလာဒုံ		ချစ်
၀၂	မောင်မောင်		"		ဝင်း
၀၃	မောင်မောင်		"		မောင်
၀၄	မောင်မောင်		"		မောင်
၀၅	မောင်မောင်		"		မောင်
၀၆	မောင်မောင်		"		မောင်
၀၇	မောင်မောင်		"		မောင်
၀၈	မောင်မောင်		"		မောင်
၀၉	မောင်မောင်		"		မောင်
၁၀	မောင်မောင်		"		မောင်
၁၁	မောင်မောင်		"		မောင်
၁၂	မောင်မောင်		"		မောင်

တွဲစာတေးတွဲပြောင်းဖွဲ့ ဂြိုဟ်တိုက်တက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစီရင်ခံစာအား

နေ့စွဲ- ၂၆.၁.၂၀၁၉

နေရာ- တွဲစာ













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၀၁	ကိုအောင်မျိုးဝင်း		အဆင့်မြင့် မြေကွယ်စာ		
၀၂	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၀၃	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၀၄	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၀၅	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၀၆	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၀၇	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၀၈	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၀၉	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၁၀	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၁၁	ဒေါ်အိမ်စိန်		လမ်းမတော်		
၁၂	ဒေါ်အိမ်စိန်		လမ်းမတော်		

တွဲထားသောကြောင်းပုံ၊ ဖြစ်တိုက်သက်ရောက်မှုရှိသည့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၇.၈.၂၀၁၉

နေရာ- တွဲကော့

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ရက် Contact Phone	လက်မှတ် Sign
၀၁	မအော့အော့သူ	ဆက်ဆံရေး			
၂	ကိုဗိုလ်မှူးအောင်	ဆက်ဆံရေး			
၃	ဦးသန်းကျော်		ဗဟိုဌာန		
၄	အောင်ကျော်စိုး		ဗဟိုဌာန		
၅	အောင်ကျော်စိုး		ဗဟိုဌာန		
၆	ဦးမောင်ကျော်		ဗဟိုဌာန		
၇	ဦးသန်းကျော်		ဗဟိုဌာန		
၈	မအော့အော့သူ		ဗဟိုဌာန		
၉	ဦးသန်းကျော်		ဗဟိုဌာန		
၁၀	ဦးသန်းကျော်		ဗဟိုဌာန		
၁၁	ဦးသန်းကျော်		ဗဟိုဌာန		
၁၂	ဦးသန်းကျော်		ဗဟိုဌာန		

တုံ့ထောတူးခြင်းနှင့် ငြိမ်းတုံ့ထောက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၀၁၈.၁.၁၀

နေရာ- တွံတား

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁	ဦးမြတ်ဦး	ဆယ်စုနယ်မှူး	ဒဂုံခရိုင်	၀၉၇၈၇၄၁၁၁၁၁	ဦး
၂	ဒေါ်အေးအေးအေး		ဒဂုံခရိုင်		
၃	ဒေါ်စိုးစိုးစိုး		ဒဂုံခရိုင်		
၄	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		
၅	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		
၆	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		
၇	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		
၈	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		
၉	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		
၁၀	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		
၁၁	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		
၁၂	ဒေါ်ခင်ခင်ခင်		ဒဂုံခရိုင်		

တုံ့ထေးတူးခြင်းနှင့် ဖြိုဖိုတိုတက်ရောက်နိုင်ရန်နှင့် ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက် တွေ့ဆုံဆွေးနွေးခြင်း အစီရင်ခံစာအား

နေ့စွဲ- ၂၈.၁.၂၀၁၅

နေရာ- တွံတေး

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၀၈	ဦး ရဲ နီ ဖွဲ့စည်း		ဘဏ်		
၂၈	ရဲဘခေတ္တ		သာစည်		
၃၈	မောင်မောင် ဦးဝဇ် သွင်		သာစည်		မောင် ဝဇ်
၅၈	ဒေါ်ခင်ခင်		သာစည်		မောင် ဝဇ်
၆၈	ဦးမောင်မောင်		သာစည်		မောင် ဝဇ်
၇၈	ဦးမောင်မောင်		သာစည်		မောင် ဝဇ်
၉၈	မောင်မောင်		သာစည်		မောင် ဝဇ်
၁၀၈	မောင်မောင်		သာစည်		မောင် ဝဇ်
၁၁၈	မောင်မောင်		သာစည်		မောင် ဝဇ်
၁၂၈	မောင်မောင်		သာစည်		မောင် ဝဇ်

တွဲစာတရားကြောင်းဖွဲ့ပြီးတိုက်ရောက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစီရင်ခံစာအား

နေ့စွဲ- ၂၀၁၈.၁.၂၀

နေရာ- တွဲစာ :

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၀၈	မိုးမြင့်စိုး		အာဝဠာ	၀၉၆၉၆၈၂၃၁၉	my
၀၉	စိုးဝင်းအောင်		အာဝဠာ	၀၉၄၄၄၅၇၇၃၉၀၀၀၀	စိုးဝင်း
၁၀	မိုးမြင့်စိုး		အာဝဠာ		
၁၁	ဒေါ်အေးအေး		အာဝဠာ		အေး
၁၂	ဒေါ်အေးအေး		အာဝဠာ	၇၇၅၇၇၇၇၇	
၁၃	ဒေါ်အေးအေး		အာဝဠာ	၀၉၇၇၇၇၇၇၇၇	အေး
၁၄	အေးအေး		အာဝဠာ		အေး
၁၅	အေးအေး		အာဝဠာ		အေး
၁၆	အေးအေး		အာဝဠာ		အေး
၁၇	အေးအေး		အာဝဠာ		အေး
၁၈	အေးအေး		အာဝဠာ		အေး
၁၉	အေးအေး		အာဝဠာ		အေး
၂၀	အေးအေး		အာဝဠာ		အေး

တွဲထားတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဖုတ်ယူအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၆.၁.၂၀၁၅

နေရာ- တွဲတေး

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ရုန်း Contact Phone	လက်မှတ် Sign
၁။	မြသောဇာသုဂါ		မူလ၊တပ်၊		စိုး
၂။	မိုးသန်းမောင်ဖြူ		မော်ဂျသ်လေး		-
၃။	မော်ခင်မောင်		လက်ပံကွန်း		စန်
၄။	ဖိုးနွယ်စိုး		၈		မောင်
၅။	ဖိုးခင်ဝင်း		၈		သ
၆။	ဦးသိန်းသွင်		၈		ဦး
၇။	ဦးဝင်းကျော်		မူလ၊တပ်၊		ကျော်
၈။	ဒေါ်သီရိဝင်း		၈		သီရိ
၉။	ဒေါ်လင်း		၈		လင်း
၁၀။	ကျော်လင်းဦး		၈		ကျော်
၁၁။	ဂျော့စီ		၈		ဂျော့
၁၂။	ကျော်လင်း		၈		ကျော်

၃

တွဲထားသောအခြေအနေအထားကို ဖြစ်တည်နေရာနှင့်ဆက်သွယ်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၀၁၈.၁.၁၀

နေရာ- တွဲထား

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၁	ကျော်စိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၁၇
၂	ဦးစိုးမိုး		ကုလားတန်း		၀၉
၃	ဦးမိုးမိုး		အစိုးရ		၀၉
၄	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉
၅	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉
၆	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉
၇	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉
၈	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉
၉	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉
၁၀	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉
၁၁	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉
၁၂	ဦးမိုးမိုး		ပြည်သူ့ဝန်ထမ်း		၀၉

တို့ထားတားခြင်းနှင့် ငြိတ်တားရန်မိန့်ခွင့်ပတ်သက်သော ယာယီတားမြစ်ဆုံးဖြတ်ချက်ချမှတ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစီရင်ခံစာအား

နေ့စွဲ- ၂၀၁၈.၁၀.၁၀

နေရာ- တွံတေး

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁။	စိုးဝင်း		သာစံ ဂျီ		ဝင်း
၂။	ဦးမင်းသိန်းဦး		(သာစံ)		ဦး
၃။	ဒေါ်ခင်စိန်		ကုမ္ပဏီ		ခင်စိန်
၄။	မောင်မောင်		သာစံ		မောင်မောင်
၅။	ဦးအောင်		သာစံ		အောင်
၆။	လှိုင်လှိုင်		သာစံ		လှိုင်
၇။	မောင်မောင်		သာစံ		မောင်မောင်
၈။	ဦးမင်းဦး		သာစံ		မင်းဦး
၉။	ဒေါ်မိုးမိုး		ကုမ္ပဏီ		မိုးမိုး
၁၀။	ဦးမင်း		သာစံ		မင်း
၁၁။	မောင်မောင်		သာစံ		မောင်မောင်
၁၂။	ဦးမောင်		သာစံ		မောင်

တွဲစာအုပ်များဖြင့် ဖွဲ့စည်းထားသော အဖွဲ့အစည်းများ၏ အဖွဲ့အစည်းများကို အသိပေးခြင်းအားဖြင့် အသိပေးခြင်း

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား အသိပေးခြင်းအားဖြင့် အသိပေးခြင်း

နေ့စွဲ- ၂၀၁၈.၁.၁၀

နေရာ- တွဲစာအုပ်

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန် Contact Phone	လက်မှတ် Sign
၁	အ. အ. အ. အ.		ဌာန/လိပ်စာ		
၂	ဦး သန်းလွင်	ဥပဒေ/အ.အ.	ဗဟိုဌာန		
၃	ဦးစီးချုပ်	"	ဗဟိုဌာန		
၄	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		
၅	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		
၆	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		
၇	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		
၈	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		
၉	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		
၁၀	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		
၁၁	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		
၁၂	ဦးစီးချုပ်	ဗဟိုဌာန	ဗဟိုဌာန		

တွဲထားရသူများနှင့် ပူးတွဲထားသော စာမျက်နှာများကို ဖော်ပြပါအတိုင်း အစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၆.၁.၂၀၁၇

နေရာ- တွံတေး

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန် Contact Phone	လက်မှတ် Sign
၀၁	ဦးမိုးလွင်		ဝန်ဆောင်		မိုးလွင်
၂	ဦးအောင်		မ		အောင်
၃	ဦးကျော်		မ		ကျော်
၄	ဦးမိုးမိုး		မ		မိုးမိုး
၅	ဦးမိုးမိုး		မ		မိုးမိုး
၆	ဦးမိုးမိုး		မ		မိုးမိုး
၇	ဦးမိုးမိုး		မ		မိုးမိုး
၈	ဦးမိုးမိုး		မ		မိုးမိုး
၉	ဦးမိုးမိုး		မ		မိုးမိုး
၁၀	ဦးမိုးမိုး		မ		မိုးမိုး
၁၁	ဦးမိုးမိုး		မ		မိုးမိုး
၁၂	ဦးမိုးမိုး		မ		မိုးမိုး

တုံ့ပြန်ချက်အားဖြင့် ပြုစုထားသော အချက်အလက်များနှင့်ပတ်သက်သော အချက်အလက်များကို အောက်ဖော်ပြပါအတိုင်း အတည်ပြုနိုင်ပါသည်။

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်ပြောဆိုအတည်ပြုခြင်းအစီရင်ခံစာအတွက်

နေ့စွဲ- ၂၆.၁.၂၀၁၇

နေရာ- တွံတေး

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၀၁	ဦးအောင်ကျော်		အစဉ်		
၀၂	ဦးကျော်စိုး		ပြောဆိုရေးရာ		
၀၃	ဦးကျော်စိုး		၁		
၀၄	ဦးကျော်စိုး		လက်မှတ်ရေးထိုး		
၀၅	ဦးကျော်စိုး	ဗဟို/ဗဟို	လက်မှတ်ရေးထိုး		
၀၆	ဦးကျော်စိုး	ဗဟို/ဗဟို	လက်မှတ်ရေးထိုး		
၀၇	ဦးကျော်စိုး	ဗဟို/ဗဟို	လက်မှတ်ရေးထိုး		
၀၈	ဦးကျော်စိုး	ဗဟို/ဗဟို	လက်မှတ်ရေးထိုး		
၀၉	ဦးကျော်စိုး	ဗဟို/ဗဟို	လက်မှတ်ရေးထိုး		
၁၀	ဦးကျော်စိုး	ဗဟို/ဗဟို	လက်မှတ်ရေးထိုး		
၁၁	ဦးကျော်စိုး	ဗဟို/ဗဟို	လက်မှတ်ရေးထိုး		
၁၂	ဦးကျော်စိုး	ဗဟို/ဗဟို	လက်မှတ်ရေးထိုး		

တုံ့ပြန်စာတမ်းများကို ဖြန့်ချိပေးသော အချိန်နှင့်ပတ်သက်သော ယာယီဆုံးဖြတ်ချက်များကို အတည်ပြုရန်အတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဖုန်းဆက်သွယ်ခြင်းဖြင့် အချိန်အကန့်အသတ်ဖြင့်

နေ့စွဲ- ၂၀၁၈.၁.၂၀

နေရာ- ဝန်ကြီးရုံး










စဉ် Sr.	အမည် Name	ရာထူး Position	အဖွဲ့အစည်း/ Organization/ Address	ဆက်သွယ်ရန် Contact Phone	လက်မှတ် Sign
၁။	ဦးသန်းလွင်		ဝန်ကြီးရုံး		၁၂၃၄
၂။	ဦးကျော်စိုး		ဝန်ကြီးရုံး		၅
၃။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၆၇၈
၄။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၉၀၁
၅။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၂၃၄
၆။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၅၆၇
၇။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၈၉၀
၈။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၁၂၃
၉။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၄၅၆
၁၀။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၇၈၉
၁၁။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၀၁၂
၁၂။	ဦးကျော်စိုး	အထူးအကြံပေး	ဝန်ကြီးရုံး		၃၄၅

ဝတ္တရားတရားရုံးသို့ ပြုစုထားသောစီမံခန့်ခွဲမှုပတ်သက်သော ယာယီကန့်သတ်ချက်ဆိုင်ရာစီမံခန့်ခွဲမှုပတ်သက်သော

စီမံခန့်ခွဲမှုပတ်သက်သောစီမံခန့်ခွဲမှုပတ်သက်သော ခုတ်ယူချက်ပြန်လှည့်စာရွက်စာတမ်းများ အပ်နှံထားရာ

နေ့စွဲ ၂၀၁၈.၁.၂၀

နေရာ၊ ယွန်တို






စဉ် Sr.	အမည် Name	ရာထူး Position	အဖွဲ့အစည်း Organization/ Address	ဆက်သွယ်ရေး Contact Phone	လက်မှတ် Sign
၁	YOUNG KATY	Director	ISAL	+82-10-6247-6229	
၂	THE HO NAIN	Manager	ISAN	+82-10-5131-2144	
၃	UTIN IM	Manager	GAIA	+82-10-9649-5162	
၄	CHIT HAIN ABERICA	Manager	MBPI	09787182093	
၅	SALINE ZAI	Interpreter	h.g.	09.43044032	
၆	ဒေါ်ခင်စုစု	Director	REM Co.,		
၇	ဒေါ်ခင်စုစု	PM	"		
၈	ဒေါ်ခင်စုစု	Director			
၉	ဒေါ်ခင်စုစု	Principal Consultant	REM		
၁၀					
၁၁					
၁၂					

တွဲစာတရားပြင်ဆင်မှု ဖြိုဖျက်တိုက်ခတ်မှုအစီအစဉ်နှင့်ပတ်သက်သော ယတ်ခန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၀၁၈.၁.၂၀၁၇

နေရာ- တွဲစာတရား













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁	မော်စုစိုးဝင်း		လူ့စားဝတ်		
၂	ဦးဝင်းလွင်		၁၃၇၊ ဦးစု		
၃	မော်ခင်မိုး		၇		
၄	မြသောင်းမြတ်		လောင်ဂျီ		
၅	ဦးစုစိုးဝင်း	Director	KEM	၀၅-၅၇၁၄၇၈	
၆					
၇					
၈					
၉					
၁၀					
၁၁					
၁၂					

တို့တေသားပြောင်းဖွဲ့ ဖြစ်တိုက်သက်ရောက်မှုနှင့်ပတ်သက်သော ယတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ ၂၈.၁.၂၀၁၉

နေရာ တွေ့ဆုံခြင်း : မန္တလေးမြို့၊ အောက်လမ်း

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁။	ဦးကျော်ကျော်အောင်	အကြံပေး	သယံဇာတ	၀၇၄၀၇၈၂၇၇	
၂။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၃။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၄။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၅။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၆။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၇။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၈။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၉။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၁၀။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၁၁။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	
၁၂။	ဦးကျော်ကျော်အောင်	အကြံပေး	အထွေထွေအဖွဲ့အစည်း	၀၇၇၇၇၇၇၇၇၇	











3. Dala Township

တက္ကသိုလ်ဆိုင်ရာ ဌာနချုပ်များနှင့် ပတ်သက်သော လက်ဝန်ကိုင်ဆောင်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သည့်အချက်အလက်များအား အတိအကျပြောဆိုရန်အတွက် အောက်ဖော်ပြပါအတိုင်း

နေ့စွဲ- ၂၀၁၈.၁.၂၀

နေရာ- ဒီလမြို့

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန် Contact Phone	လက်မှတ် Sign
၀၁	ဦးအောင်ကျော်မင်း	ဦးစီးအရာရှိ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၀၂	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၀၃	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၀၄	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၀၅	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၀၆	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၀၇	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၀၈	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၀၉	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	
၁၀	ဦးအောင်	အထောက်အကူ	မြို့/မကွေးမြို့နယ် (၁၇၇၇)	၀၇၂၅၀၆၅၂၉၉၆	

တွဲထားသောအခြေခံအားဖြင့် ဦးစီးတက်ရောက်ရန်အတွက် သတ်မှတ်သော ယာယီအချိန်အတွက် အချိန်အကွာအဝေး

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား သတ်မှတ်အခြေခံအတိုင်းအတာအရ အချိန်အကွာအဝေး

နေ့စွဲ- ၂၀၂၁.၁၁.၁၆

နေရာ- ဗ.က.မြို့













စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန် Contact Phone	လက်မှတ် Sign
၁။	န. သိန်းစုံ	ဥပဒေရေးရာဌာန	ဧရာဝတီ	၀၉ ၅၀၀၇၆၆၆	န. သိန်းစုံ
၂။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၃။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၄။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၅။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၆။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၇။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၈။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၉။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၁၀။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၁၁။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်
၁၂။	ဦးအောင်နိုင်	ဦးအောင်နိုင်	ဦးအောင်နိုင်	၀၉ ၅၀၀၇၆၆၆	ဦးအောင်နိုင်

တွဲစာတရားပြင်ဆင်မှု ဦးတီးထုတ်ဖော်မှုမိန့်နှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ခုတ်ယူအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၆. ၁. ၂၀၁၇

နေရာ- ဗဟိုဦးစီးဌာန

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၁	ကျော်စိုးလွင်	အမှုထမ်း ဖ. ဖ. ✓	လူ့စွန့်လှူမှုဌာန၊ ရန်ကုန်မြို့	၀၇ ၂၅၀၁၆၁၇၇၀၇	
၂	ဦးစိုးမိုးစိုး	ရပ်ကွက်အဖွဲ့ချုပ်	အထွေထွေအထောက်အကူဌာန	၀၉ ၆၆၆၆၀၀၀၀၀၀	
၃	ဒေါ်အေးအေး		အထွေထွေအထောက်အကူဌာန		
၄	ဦးစိုးမိုးစိုး		ရန်ကုန်မြို့နယ်၊ ရန်ကုန်မြို့	၀၉ ၆၆၆၆၀၀၀၀၀၀	
၅	ဒေါ်အေးအေး		အထွေထွေအထောက်အကူဌာန		
၆	ဦးစိုးမိုးစိုး		ရန်ကုန်မြို့နယ်၊ ရန်ကုန်မြို့		
၇	ဒေါ်အေးအေး		အထွေထွေအထောက်အကူဌာန		
၈	ဒေါ်အေးအေး		အထွေထွေအထောက်အကူဌာန		
၉	ဒေါ်အေးအေး		အထွေထွေအထောက်အကူဌာန		
၁၀	ဒေါ်အေးအေး		အထွေထွေအထောက်အကူဌာန		
၁၁	ဒေါ်အေးအေး		အထွေထွေအထောက်အကူဌာန		
၁၂	ဒေါ်အေးအေး		အထွေထွေအထောက်အကူဌာန		

ထွဲတေးကူးပြောင်းခွဲ ဂြိုဟ်တုဆက်သရန်ပုံစံတိုင်းနှင့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်ပြောကြားစာတွင်ဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၈.၁.၂၀၁၇

နေရာ- သဂဇ္ဈိ












စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၁။	ဒေါ်ခင်စန်း	မြို့ဝန်ကြီး	ဝန်ကြီးရုံး	၂၅၃၄၄၄၄၄	1/15
၂။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၃။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၄။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၅။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၆။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၇။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၈။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၉။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၁၀။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၁၁။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15
၁၂။	ဒေါ်ခင်စန်း	ဒုတိယဥက္ကဋ္ဌ	ဝန်ကြီးရုံး		1/15

တွဲထားသောမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ယတ်ဝန်ကျင့်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အစည်းအဝေး

နေ့စွဲ- ၂၆.၀၁.၂၀၁၅

နေရာ- ဒီဂျစ်မြို့

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၂၈	ဦးဖိုးသန့်လင်း	ဓားကျ	ဇေယျာ	၀၇-၄၂၀၀၆၁၆၇၀	
၂၉	ဦးထွန်းဈေးလတ်	အထူးစာအုပ်ဆိုင်	အာဟာရဆိုင်	၀၇-၄၀၈၀၆၇၈၁၅	
၃၀	ဒေါ်ခင်ဝင်းလှ		အာဟာရဆိုင် ကျောက်စု	၀၇-၇၇၁၇၃၂၂၁၀	
၃၁	ဦးမန္တလှိုင်		၇		
၃၂	ဒေါ်သန်းသန်း		အာဟာရဆိုင်ကျောက်စု	၀၇-၄၇၂၀၂၆၃၀၂၇	
၆၃	ဒေါ်စိုးဝင်း		၈		
၇၃	ဦးဘိုးအောင်	အထူးစာအုပ်ဆိုင်	အာဟာရဆိုင်		
၈၃	ဦးအောင်အောင်	ဌာနချုပ်	၈	၀၇-၇၇၂၆၁၇၁၆	
၉၃	ဦးစိုးဝင်း	အထူးစာအုပ်ဆိုင်	၈		
၁၀၃	ဦးလှိုင်	၈၃၃	၈		
၁၁၃	ဦးစိုးဝင်း		၈		

သို့သော်လည်းကောင်း၊ ဤသို့သတ်မှတ်ချက်များနှင့်ပတ်သက်သော ယတ်ဝန်ကျင့်ထိန်းသိမ်းရေးစည်းကမ်းချက်များနှင့်ဆက်သွယ်ရန်

စီမံကိန်းနှင့်သက်ဆိုင်သည့်အချက်အလက်များကို အတည်ပြုနိုင်ရန်အတွက် အောက်ဖော်ပြပါအတိုင်း အတည်ပြုရန်

ရက်စွဲ- ၂၀၁၈.၁.၂၀၁၉

နေရာ- မ.က.မြို့

စဉ် Sr.	အမည် Name	ရာထူး Position	အဖွဲ့အစည်း Organization/ Address	ဆက်သွယ်ရန် Contact Phone	လက်မှတ် Sign
၀၁	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၀၂	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၀၃	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၀၄	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၀၅	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၀၆	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၀၇	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၀၈	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၀၉	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၁၀	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၁၁	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း
၁၂	ဦးကျော်ကျော်သိန်း	အထွေထွေ	အထွေထွေအဖွဲ့အစည်း	၀၉-၄၄၄၄၄၄၄၄	ဦးကျော်ကျော်သိန်း














(၇)

တို့တယားကူးခြင်းနှင့် ဂြိုဟ်တုတိုက်ခတ်မှုများနှင့်ပတ်သက်သော ယာယီသတ်မှတ်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ခုတ်ယူအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၆.၁.၂၀၁၇

နေရာ- ဒီစီအိုင်

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၀၈	ဦးအောင်	စီမံကိန်းဌာနမှူး	မဟာမိတ်-၇၇၇၇၇၇	၀၇/၂၆၀၀၀၅၀၀၆	
၀၉	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၀	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၁	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၂	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၃	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၄	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၅	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၆	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၇	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၈	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၁၉	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	
၂၀	ဦးအောင်	စီမံကိန်းဌာနမှူး	မ	၀၇/၂၆၀၀၀၅၀၀၆	

တို့တောင်းပေးခြင်းခံယူပြီးတိုင်းတက်ရောက်မိမ့်တန်းနှင့်ပတ်သက်သော ယတ်ဝန်းကောင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်ခြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၂၆.၁.၂၀၁၇

နေရာ- မိလ (မြို့)

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၀၁	ခေါ်ခမ်းသွယ် ဇီဒီဒ်	ဥက္ကဋ္ဌ	၄၃၁၀၇၃၃	၀၇-၄၂၁၀၂၇၀၇	
၀၂	ဦးဝင်းကျော်	ဥက္ကဋ္ဌ	ကရင်လမ်း	၀၇-၄၂၁၀၇၃၁၅	
၀၃	ဦးကျော်မောင်	အတွင်းရေးမှူး	"	၀၇-၇၇၇၁၀၅၆၈၇	
၀၄					
၀၅					
၀၆					
၀၇					
၀၈					
၀၉					
၁၀					
၁၁					
၁၂					

တွဲထားသောစာမျက်နှာများတွင် ဖော်ပြပါအတိုင်း ဖော်ပြပါအတိုင်း ဖော်ပြပါအတိုင်း ဖော်ပြပါအတိုင်း

စီမံကိန်းနှင့်သက်ဆိုင်သည့်အား ခုတ်ယူခြင်းပြုလုပ်ရန်အတွက် အမတ်အား

နေ့စွဲ- ၂၈.၁.၂၀၁၇

နေရာ- ရန်ကုန်မြို့

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၁	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၂	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၃	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၄	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၅	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၆	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၇	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၈	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၉	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၁၀	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၁၁	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	
၁၂	ဦးလှအောင်		၁၀၀၀	၀၉၂၆၁၇၀၈၂၄၆၇	

ထိုစာထုတ်ပြန်ချက်ကို ဖြန့်ချိတက်ရောက်ရေးအဖွဲ့နှင့်ပတ်သက်သော ယတ်ဝန်ကျင်ထိရှိသည့်ဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား နယ်ပယ်အကြီးကြပ်ကြည့်ရှုစစ်ဆေးခံရသူအဖြစ် အစီရင်ခံစာအား

နေ့စွဲ- ၂၈.၁.၂၀၁၇ နေရာ- ဒလမြို့-












စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်နံပါတ် Contact Phone	လက်မှတ် Sign
၀၁	ဦးမင်းမိုး		ဒလမြို့		မြ
၂	ဦးမောင်ကျော်		မ.မြို့		ကျော်
၃	ဦးမောင်ကျော်		မောင်ကျော်		ကျော်
၄	ဦးမောင်ကျော်		မ.မြို့/ မောင်ကျော်		ကျော်
၅	ဦးမောင်ကျော်		မ.မြို့		ကျော်
၆	ဦးမောင်ကျော်		မောင်ကျော်		ကျော်
၇	ဦးမောင်ကျော်		မ.မြို့		ကျော်
၈	ဦးမောင်ကျော်		မ.မြို့	၀၉၂၅၀၄၆၂၄၇	ကျော်
၉					
၁၀					
၁၁					
၁၂					

တွဲထားသောခြေခံခွဲခြားတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော သတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ- ၇၈.၁.၇၀၁၇

နေရာ- မော့ခြံ

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်အနီး Contact Phone	လက်မှတ် Sign
၁။	ဦးအောင်ကျော်		မူလ၊ ဂျာနယ်	၀၇၇၇၇၇၇၇၇၇	
၂။	ဦးအောင်ကျော်		၃လ		
၃။	ဦးအောင်ကျော်		မူလ		
၄။	ဦးအောင်ကျော်		မူလ		
၅။	ဦးအောင်ကျော်		မူလ		
၆။	ဦးအောင်ကျော်		မူလ		
၇။	ဦးအောင်ကျော်		မူလ		
၈။	ဦးအောင်ကျော်		မူလ		
၉။	ဦးအောင်ကျော်		မူလ		
၁၀။	ဦးအောင်ကျော်		မူလ		
၁၁။	ဦးအောင်ကျော်		မူလ		

တွဲစာတားပြောင်းဖွဲ့ပြီးတိုင်းတက်ရောက်နိုင်မည့်ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဒုတိယအကြိမ်မြောက်တွေ့ဆုံဆွေးနွေးခြင်း အခေါ်အဝေါ်စာ

နေ့စွဲ- ၂၆.၁.၂၀၁၇ နေရာ- ၆ ကမ္ဘာမြို့

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ရုန်း Contact Phone	လက်မှတ် Sign
၀၁	ဒေါ်လှဝင်းမိုး		ကုလသမဂ္ဂ		
၂	မသန်းဇွဲ		"		
၃	ဇော်ဝင်းမိုး		"		
၄	ခင်ဝင်းမိုး		လက်ဝဲကုန်း		
၅	ဒေါ်အေးမိုး		၁		
၆	ဒေါ်အေးမိုး		၂		
၇	ဒေါ်အေးမိုး		၃		
၈	ဒေါ်အေးမိုး		၄		
၉	ဒေါ်အေးမိုး		၅		
၁၀	ဒေါ်အေးမိုး		၆		
၁၁	ဒေါ်အေးမိုး		၇		
၁၂	ဒေါ်အေးမိုး		၈		

တွဲထားတူးမြောင်းဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့်ပတ်သက်သော ယတ်ခန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဖုန်းနံပါတ်ဖြင့်ဆက်သွယ်ဆွေးနွေးခြင်း အခမ်းအနား

နေ့ရက်- ၂၀၂၄.၁.၂၀၂၄

နေရာ- မန္တလေး

စဉ် Sr.	အမည် Name	ရာထူး Position	ဌာန/လိပ်စာ Organization/ Address	ဆက်သွယ်ရန်ဖုန်း Contact Phone	လက်မှတ် Sign
၁။	ဦးအောင်ကျော်	MD အိုင်. (၁)	၂၀/၂၃၆ မန္တလေးမြို့ အောင်ကျော်လမ်း	၀၇၇၉၉၃၃၃၃၃၃	
၂။	ဦးအောင်ကျော်	MD အိုင်. (၂)	၂၀၂၃၆ မန္တလေးမြို့ အောင်ကျော်လမ်း	၀၇၇၉၉၃၃၃၃၃၃	
၃။					
၄။					
၅။					
၆။					
၇။					
၈။					
၉။					
၁၀။					
၁၁။					
၁၂။					









တွဲထားသောစာမျက်နှာများကို ဖြည့်စွက်ရန်အတွက် အောက်ဖော်ပြပါအတိုင်း ဖြည့်စွက်ရန်အတွက်

စီမံကိန်းနှင့်သက်ဆိုင်သူများအား ဖုန်းနံပါတ်ဖြင့်ဆက်သွယ်ဆွေးနွေးခြင်း အခမ်းအနား

နေ့စွဲ ၂၀၁၈.၁.၂၀၁၉

နေရာ-






ဒီပလိုမာ






စဉ် Sr.	အမည် Name	ရာထူး Position	အဖွဲ့အစည်း Organization / Address	ဆက်သွယ်ရန် Contact Phone	လက်မှတ် Sign
၁	Yoonwin Kang	Director	ISAN	+82-10-6246-6239	
၂	THE HO, NAM	Manager	ISAN	+82-10-5131-2144	
၃	TIJIN IM	Manager	GAIA	+82-10-9645-5362	
၄	CHIT HMIN @ Jessica	Manager	MBP	09787182093	
၅	SHI LINE TAI	Interpreter	GAIA	09430444032	
၆	Dau Khin Ohnmer Htine	REEM			
၇	Dau Phyu Phyu Shwe	REEM			
၈	Dau Lai Lai Win	REEM			
၉					
၁၀					
၁၁					
၁၂					

4. Kyimyindaing Township

၂၀၁၉ ခုနှစ်၊ ဇန်နဝါရီလ(၂၉)ရက်၊အင်္ဂါနေ့(၀၉:၀၀)နာရီအချိန်တွင် ရန်ကုန်အနောက်ပိုင်းခရိုင် ကြည့်မြင်တိုင်မြို့နယ် အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာနရုံးအစည်းအဝေးခန်းမ၌ ကျင်းပပြုလုပ်သည့် တွဲတေးတူးမြောင်း ဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့် ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ် ခြင်းအစီရင်ခံစာအတွက် ဒုတိယအကြိမ် စီမံကိန်းနှင့် သက်ဆိုင်သူများ တွေ့ဆုံဆွေးနွေးခြင်း (2nd Stakeholder Meeting) အခမ်းအနား တက်ရောက်မှုမှတ်တမ်း













အောက်ပါပုဂ္ဂိုလ်များအစည်းအဝေးတက်ရောက်ကြပါသည်-

စဉ်	အမည်	ဌာန	ရာထူး	လက်မှတ်	မှတ်ချက်
၁	ဦးဇာနည်ဝင်း	မြို့နယ်အုပ်ချုပ်ရေးမှူး မြို့နယ်အထွေထွေအုပ်ချုပ်ရေး ဦးစီးဌာန	ဥက္ကဋ္ဌ		
၂	ဦးဇော်ဝင်း	ပြည်သူ့လွှတ်တော်ကိုယ်စားလှယ်	အဖွဲ့ဝင်	တာဝန်	
၃	ဒေါက်တာ မောင်မောင်	အမျိုးသားလွှတ်တော် ကိုယ်စားလှယ်	အဖွဲ့ဝင်	တာဝန်	
၄	ဦးကျော်နန္ဒအောင်	တိုင်းဒေသကြီးလွှတ်တော် ကိုယ်စားလှယ် မဲဆန္ဒနယ်အမှတ်(၁)	အဖွဲ့ဝင်		
၅	ဦးခင်ဝင်း	တိုင်းဒေသကြီးလွှတ်တော် ကိုယ်စားလှယ် မဲဆန္ဒနယ်အမှတ်(၂)	အဖွဲ့ဝင်	တာဝန်	
၆	ဦးလှဌေး	စိုက်ပျိုးရေးဦးစီးဌာန	အဖွဲ့ဝင်		
၇	ဒေါက်တာ နှင်းနှင်းဦး	မြို့နယ်ဦးစီးမှူး မွေးမြူရေးနှင့်ကုသရေးဦးစီးဌာန	အဖွဲ့ဝင်		
၈	ဦးကျော်ထွန်းလင်း	တောအုပ် သစ်တောဦးစီးဌာန	အဖွဲ့ဝင်		

စဉ်	အမည်	ဌာန	ရာထူး	လက်မှတ်	မှတ်ချက်
၉	ဒေါ်မြင့်မြင့်ဝေ	မြို့နယ်ဦးစီးမှူး စီမံကိန်းရေးဆွဲရေးဦးစီးဌာန	အဖွဲ့ဝင်		
၁၀		ဥက္ကဋ္ဌ မြို့နယ်စည်ပင် သာယာရေးကော်မတီ	အဖွဲ့ဝင်		
၁၁	ဦးမောင်ကြီး(ခ) ဦးခင်ဇော်	တောင်သူလယ်သမားရေးရာ လူမှုအဖွဲ့အစည်း ကိုယ်စားလှယ်	အဖွဲ့ဝင်		
၁၂	ဦးတင်စိန်	တောင်သူလယ်သမားရေးရာ လူမှုအဖွဲ့အစည်း ကိုယ်စားလှယ်	အဖွဲ့ဝင်		
၁၃	ဦးကျော်ကျော်(ခ) ဒါးဂျူး	တောင်သူလယ်သမားရေးရာ လူမှုအဖွဲ့အစည်း ကိုယ်စားလှယ်	အဖွဲ့ဝင်		
၁၄	ဦးဖြိုးဝေကျော်	မြို့နယ်ဦးစီးမှူး လယ်ယာမြေစီမံခန့်ခွဲရေးနှင့် စာရင်းအင်းဦးစီးဌာန(တွံတေး)	အဖွဲ့ဝင်		
၁၅	ဦးဇမ်းရှင်းခမ်	အတွင်းရေးမှူး ဌာနစုမှူး၊ မြို့တော်စည်ပင် သာယာရေးကော်မတီ	အတွင်းရေးမှူး		
၁၆	ဦးဝေလင်းထွန်း	ဒု-မြို့နယ်အုပ်ချုပ်ရေးမှူး မြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီး ဌာန	တွဲဖက် အတွင်းရေးမှူး		










၂၀၁၉ ခုနှစ်၊ စန်နဝါရီလ(၂၉)ရက်၊အင်္ဂါနေ့(၀၉:၀၀)နာရီအချိန်တွင် ရန်ကုန်အနောက်ပိုင်းခရိုင် ကြည့်မြင်တိုင်မြို့နယ် အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာနရုံးအစည်းအဝေးခန်းမ၌ ကျင်းပပြုလုပ်သည့် တွဲတေးတူးမြောင်း ဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့် ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းအစီရင်ခံစာအတွက် ဒုတိယအကြိမ် စီမံကိန်းနှင့် သက်ဆိုင်သူများ တွေ့ဆုံဆွေးနွေးခြင်း (2nd Stakeholder Meeting) အခမ်းအနား တက်ရောက်မှုမှတ်တမ်း

အောက်ပါပုဂ္ဂိုလ်များအစည်းအဝေးတက်ရောက်ကြပါသည်-

စဉ်	အမည်	ရပ်ကွက်	ရာထူး	လက်မှတ်	မှတ်ချက်
၁	ဦးအေးရွှေ	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ရပ်ကွက်အုပ်ချုပ် ရေးမှူး		
၂	ဦးကောင်းထက်ဝင်း	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ရပ်ကွက်စာရေး		
၃	ဦးဗိုလ်	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ရပ်မိရပ်ဖ		
၄	ဦးစိုးမြင့်	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ရပ်မိရပ်ဖ		
၅	ဦးစိုးထင်	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ရပ်မိရပ်ဖ		
၆	ဦးဝင်းနု	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	အပိုင်တာဝန်ခံ		
၇	ဦးသိန်းလင်း	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	အပိုင်တာဝန်ခံ		
၈	ဦးဝင်းဦး	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ဆယ်အိမ်မှူး		
၉	ဦးစောစော	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ဆယ်အိမ်မှူး		
၁၀	ဦးစိုးသိန်း	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ဆယ်အိမ်မှူး		
၁၁	ဦးစိုးမိုး	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ဆယ်အိမ်မှူး		
၁၂	ဦးစိုးဝင်း	ဆိပ်ကြီးဦးမြင်းစင် ရပ်ကွက်	ဆယ်အိမ်မှူး		











၂၀၁၉ ခုနှစ်၊ ဇန်နဝါရီလ(၂၉)ရက်၊အင်္ဂါနေ့(၀၉:၀၀)နာရီအချိန်တွင် ရန်ကုန်အနောက်ပိုင်းခရိုင် ကြည့်မြင်တိုင်မြို့နယ် အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာနရုံးအစည်းအဝေးခန်းမ၌ ကျင်းပပြုလုပ်သည့် တွဲတေးတူးမြောင်း ဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့် ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ် ခြင်းအစီရင်ခံစာအတွက် ဒုတိယအကြိမ် စီမံကိန်းနှင့် သက်ဆိုင်သူများ တွေ့ဆုံဆွေးနွေးခြင်း (2nd Stakeholder Meeting) အခမ်းအနား တက်ရောက်မှုမှတ်တမ်း

အောက်ပါပုဂ္ဂိုလ်များအစည်းအဝေးတက်ရောက်ကြပါသည်-

စဉ်	အမည်	ဌာန	ရာထူး	လက်မှတ်	မှတ်ချက်
၁.	ဦးစား နော်	ငါးလှော် ငါးဖမ်းရေး	ဗိုလ်		
၂	ဦးမောင်မျိုးအောင်	သားကပ် ဘေး အစွဲလျာ စီမံကိန်း အဖွဲ့ဝင်	ဗိုလ်		
၃.	အောင်စာမင်းမောင်	မရဲကလျိုင်ကန်စိုက်ပျိုးရေးဦးစီးဌာန	ဥပဒေ		
၄	ဦးလှဌေး	မြို့နယ် ဦးစီးမှူး၊ မြို့နယ်စိုက်ပျိုးရေး ဦးစီးဌာန			
၅	ဦးခင်မြင့်	ခရိုင် ဆေး/ဗဟို ဗဟိုဌာနမှူး(လေ့လာ)	ဦး/ဒါ		
၆.	အောင်စိန်	ဆေးကုသရေးဌာန (ကျေးလက်) ခရိုင်မှူး(က-၁)	ဆေး/ဗဟို		
၇	ဒေါ်ခင်စုစု	ECW, YGN	ဦး/ဒါ		
၈။	ဦးစုတင်	"	ဦး-ဗဟို		
၉	ဦးစုတင်				
	ဒေါ်စင်စင်စု	YCDC, UPD, CPLAD	A.D		

၂၀၁၉ ခုနှစ်၊ ဇန်နဝါရီလ(၂၉)ရက်၊အင်္ဂါနေ့(၀၉:၀၀)နာရီအချိန်တွင် ရန်ကုန်အနောက်ပိုင်းခရိုင် ကြည့်မြင်တိုင်မြို့နယ် အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာနရုံးအစည်းအဝေးခန်းမ၌ ကျင်းပပြုလုပ်သည့် တွဲတေးတူးမြောင်း ဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့် ပတ်သက်သော ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ် ခြင်းအစီရင်ခံစာအတွက် ဒုတိယအကြိမ် စီမံကိန်းနှင့် သက်ဆိုင်သူများ တွေ့ဆုံဆွေးနွေးခြင်း (2nd Stakeholder Meeting) အခမ်းအနား တက်ရောက်မှုမှတ်တမ်း

အောက်ပါပုဂ္ဂိုလ်များအစည်းအဝေးတက်ရောက်ကြပါသည်-

စဉ်	အမည်	ဌာန	ရာထူး	လက်မှတ်	မှတ်ချက်
1	Eng U Ten Ton Win	Myanmar Engineering Society (MES)	Engineer		
2	U Myng Win	DMR	AO		
3	Yoonmin Kang	ISAN	Director		
4	NAM TAE HO	ISAU	Manager		
5	U IIN IM	GAIA Government	Manager		
6	SAI LINE TAI	G-7	Interpreter		
7	CHITHAN @JESSKA	MBRI	Manager		
8	ဦးစိုးဝင်း	စီမံခန့်ခွဲရေးဌာန	အထွေထွေအုပ်ချုပ်ရေးမှူး		
9	သက်လှစော	REM			
10	သက်လှစော	REM			
11	သက်လှစော	REM			

Appendix 9: Minutes of Focused Group Discussions

Meeting Dates	Content
30th October 2018 Thar Gyi Ward, Dala Township with local people	<ul style="list-style-type: none"> - Thanks to the project, there will be retaining walls. - Navigation will become easier. - According to what the local dwellers said, there is no serious conflicts between wards and there is water scarcity in the hot season. - It is preferable not to harm the local people. - It is better not to move the houses. If the resettlement is needed, housings for them should be considered first and have discussions with the local people. - Needs include compensation of land plots and new conditons should be considered that they do not have lower living standards than they do at the moment. - As the local people tried themselves with their own efforts to get electricity and built roads they should be as good as they are now. - “As there are fileds beside the roads, they preferred to be resettled at this place,” the dwellers said.
31st October 2018, Pyawbwe Lay Village, Twante Village with local people	<ul style="list-style-type: none"> - Livelihoods include that the local people have to commute to the other side of the river, handicraft businessess such as embrioderies, and fishing. - According to the local people, there is no conflict between villages. - The local people have known about this project from journals and newspaper. - It is appreciated that they are informed about the project face to face. - “Due to the project, their areas will be in better conditions but it can also harm their livelihoods,” the local people said. - When they were asked – If some areas are in the project area and have to be relocated, where do you want to resettle? - they responded that they want to resettle in the nearby village areas. - When they were asked – “ What kind of compensations do you want? – they said that they mainly want housings to live. - The main difficulty for their village for the time being, there is scarcity of drinking water during March and April as the lake in the village becomes dried.
1st November 2018 Seikkyi (West) Ward, Seikkyi Kanaungto Township with local people	<ul style="list-style-type: none"> - Livelihoods and businessess include weavings, bricklayings, helping in navigations by boats, and commuting to Yangon. - According to what the local dwellers said, there are no serious conflicts between wards and there is scarcity of drinking water in the hot season. - About the project has known via According to what the local dwellers said, there is no serious conflicts between wards and there is water scarcity in the hot season.

	<ul style="list-style-type: none"> - According to what the local dwellers said, there is no serious conflicts between wards and there is water scarcity in the hot season. - About the project facts are known via TV channels since last year and also in an indirect way. - It is preferable to know about the project in the face-to-face way. - As the local people have to depend on Yangon for their livelihoods , if they are meant to be relocated, they want to resettle in the places nearby. - If possible, they do not want to move to other places. Even if they have to move, it is advisable to be in the dry season. - The local people asked – “Where will they be relocated and what actions will be made if they refuse to move?” - Reclamation of lands and considerations for health issues should be taken into account.
24th December 2018, Taung Thu Gyi Restaurant, Seikkyi Khanaungto Township with Shipyard Association	<p>Asked by - U Kyaw Kyaw Than</p> <p>I want to know the project area. If the project area is from 0 mile to 6.5 miles, as you explained, our shipyard is in Kanaungto Creek. So, what kind of developments will be made for that area? As you know, the shipyards are located side-by-side and there are altogether 40 in number. The union government and the regional government have neglected our areas. I consider that these areas should be regarded as a zone of shipyards now. We have also reported that matter to the government. I also request you to report that matter if it is okay. We also have to pay taxes. In 2013-2014, the amount of taxes defined was convenient with the profits we got in these years. After that period, we were not okay to pay the defined taxes, as they were too much when compared with the profits. This issue had also been reported. We have been running shipyards over 60 years. If there will be development plans for the canal, I want to know what kind of considerations will be made for us. What considerations will be made for the development of our region? Now, as the construction of the “Dala Bridge” has just started, will any bridge be built for our region too? Water is scared in our region. So, is there any plan for that? The ships that were made in our shipyards have been using in the middle and lower Myanmar. These shipyards have benefited a lot of shipyard workers, owners and passengers. Although it is not that quick to build a new ship, old ships have been repaired in our shipyards once in two years. So, we wish that the considerations should officially be made for our shipyards by the now government too. As most of the shipyards in the Kanaungto Creek, I want to know what plans will be made for this creek too.</p> <p>Explained by: Daw Khin Ohnmar Htwe (REM)</p> <p>Thank you. As I have read about the project, there will be development plans for building embankments when the project is implemented from 0 mile to 6.5 mile. I think you have also known that there are other projects beside this project. The Kanaungto Creek is in this project area. As there will be impacts for the shipyards, we are here now to study about that. As far as I have known, a bridge to Seikkyi has been requested to be built.</p>

Whether it will be built or not is out of our knowledge. We have also known that there are plans for water issues too. We also mentioned about the shortage of water in Seikkyi in our report. DWIR will explain “how the Kanaungto Creek will be managed” at our next meeting. For now, the final project design has not been produced yet. Once the final design is produced, it will be sent to Korean Bank through the government. Only when the loan from Korea Bank, this project will initiate. Now is one the pre-stage of the project.

Asked by: U Kyi Myint

From 0 mile to 6.5 mile is in the canal. I want to know how long the Kanaungto Creek is included in the project. The whole Kanaungto Island?

Explained by: Daw Khin Ohnmar Htwe (REM)

The Kanaungto Creek is also included. The embankment will be built for the whole Kanaungto Island. Now is just the study stage. Once the final design is finished, DWIR will explain about it properly.

Asked by: U Kyaw Kyaw Than

The shipyards are located side-by-side. As the ships need to go between these shipyards, an exit/entrance is needed. If this project will include the construction of retaining walls and embankments, this issue should also be taken into account. Naturally, our shipyards need water for business purposes.

Explained by: U Mg Mg Lwin (DWIR)

Now, the project design has not been prepared yet. If the embankments will be built, proper considerations will be made for the docks. The design will be prepared by the Korean side. Moreover, the constructions will be done by Korean engineers. But the project developer is our Dept (DWIR) as I mentioned earlier. When the final project design is out and the implementations will start, public meetings will be held in a transparent way. We have also formed a Land Committee. If there can be losses, this committee will take actions according to the rate of the regional government. Now, it is still early to talk about it. Findings from the current study will be reported to Environmental Conservation Dept and there will be detailed surveys later on. And it will be explained later.

Asked by: U Zaw Min Shein

Stakeholders and public meetings should be held without fail to implement a project. In this area, there are shipyards, boats and sand and gravel mining ships. The government should take into account for tax ratings. All businesses should not be considered with equal amounts. Different docks make different profits. Some stopped operating already. So, taxes and income should be taken into account.

Asked by: U Kyaw Kyaw Than

Our shipyards have invested a lot. We need to pay an employee from 12000 MMK to 15000 MMK per day. When the water has swollen, business activities have to be stopped in the middle of the day. When the regular tide comes once in every 15 days, machines have to be hired to dredge and it costs about 30 lakhs, excluding the cost for buying oil to operate the machines. Other taxes have to be paid too. For a shipyard, at least 10

permanent workers are needed. We also have to take care of their families. For 1 shipyard, a lot of investments have to be made. The dock owners have also lead for the development in this area.

Asked by: U Ohn Maung

I have attended all the meetings. I feel like most of the discussions during meetings were not concerned with the project. According to what U Aung Kyaw Hmu said in the meeting, rocks- reinforced retaining walls will be built along the canal and 20-feet-wide embankments will also be built. Here, we have wet docks and dry docks. Wet docks cannot operate when the tide come. Dry docks can operate both during and after the tide. We started the docks since 1977. By then, the dock owners were united. As they also gave own funds, there was no fund from the government. Only the workers from the docks had to lead for the development in the area. I am glad to know that there will be constructions of retaining walls from 0 mile to 6.5 mile. As a project, all proper measures should be taken into account and made. I am glad that it is a good activity for our areas. I want to say that implementations should be made completely from 0 to 6.5 miles.

Explained by: Daw Khin Ohnmar Htwe (REM)

Before the meetings, we make announcements both from the newspapers and township administrators. The number of local people attended these meetings were lower than as we expected. We also want the local people attend the future meetings as invited.

Asked by: U Kyaw Kyaw Than

You studied about our areas before. The local people want to know the findings. So, if it is okay, please explain about the findings to the local people. We, the dock workers, want to know about them too, like the local people. As far as we heard about the news for the time being, the price of our docks has been decreasing.

Explained by: Daw Khin Ohnmar Htwe (REM)

Before the final project design, investigations have to be made for the possible impacts in the areas up to 30 meters (100 ft) from the canal. It is called “land conformation” in English. Before that, we have to inform the township administrator. As the Land Committee has also been formed, we have to inform them too. The township administrator told the ward and village administrators to accompany us. On the map, we defined the local people in the 100 ft area. We should also call these people. But, if we do so, the local people will be afraid more. So, we have to inform the ward and village administrators in advance. There are also DWIR staff together with us. We also understand that there will be concerns of the local people. In next meetings, we will invite all those concerned as much as we can. Now is just the pre-survey. Detail surveys will be carried out in the future.

Explained by - Ms. Grace (ISAN)

We understand that the businesses here have been operated since many years ago. Inland water transportation is important to navigate from place to place. We have read in the newspaper that inland water navigation improvements will be made. Yangon Regional Government will implement new city project in 2040. The Yangon-Dala Bridge is about to initiate soon.

	<p>Myanma Port Authority (MPA) has also been repairing the river banks. And also, MPA will also build a port in Yangon River. We don't know the time yet. Myanmar Government tried to get loans from the Korean Bank for maintaining the Twante Canal. This project covers 3 issues. The first one is that retaining walls will be fixed. Another one is to prevent flooding. Next one is for silting. Our project is to improve the inland water transports. The main thing is to prevent accidents caused by flooding. Once the embankments have been built, it will prevent flooding at the same time. As you said before, there is the problem caused by the regular tide once in two weeks. I wish you to think this project as one part for Yangon Region development. Dala and Twante is the first stage in implementing the developments of Yangon Region areas. According to my understandings, water transports are also important as road transportation is. I understand that there will be concerns for the project. I wish you to oversee the long-term benefits. For long-term benefits, short-term impacts will be properly managed indeed. Short-term plans should be implemented first but it will also be beneficial in the long-run. Although this project is for 30 meters (100 ft), as there are about 40 shipyards, the area is not defined completely. For other projects, it will be not that difficult to relocate the houses. But the docks are a different matter. I am the consultant hired by the Korean Bank which will give loans. I have to review whether the resettlement plans follow the rules and regulations from Myanmar and of the Korean Bank. As DWIR is the project developer of this project, I have to make consultations for DWIR. In the next meeting, the findings will be disclosed and the concerns will be discussed more.</p> <p>Discussed by: U Kyaw Kyaw Than</p> <p>Although the houses can be relocated, it is difficult to find the new location for the docks. We have concerns for our business activities.</p>
<p>24th December 2018, Township with Farmers</p>	<p>Asked by: U Thiha Myo Aung</p> <p>Will those who are in 100 ft away from the canal be included in the project area?</p> <p>Explained by: Daw Khin Ohnmar Htwe (REM)</p> <p>The final pro</p> <p>Hpayar Gyi Village, Twente ject design is not out yet. Basically, they will be included. Once the project design is finished, we will hold public meetings.</p> <p>Explained by: U Maung Maung Lwin (DWIR)</p> <p>Generally, they are included in the project area. But, the survey collected would not include all the properties. The percentage for everyone will be announced once the final design is finished. We have already established Land Committee. If there may be losses, this Land Committee will give compensations in accordance with the rates regulated by the Yangon Regional Government as this area is in Yangon Region.</p> <p>Asked by: U Thiha Myo Aung (100 Household Head, Peik Swel Village)</p> <p>If the project is confirmed, when will it start? The villagers have concerns about resettlements. If it is in the rainy season, it is not convenient. It'd be better to do in other seasons.</p>

Explained by: Daw Khin Ohnmar Htwe (REM)

It is still early to talk about resettlements. It will be implemented only after detail surveys and public consultations. The project period is from 2019 to 2024. We will finish detail surveys in March. I wish you'd better have no concerns for now.

Asked by: U Thiha Myo Aung

How are agricultural land and CN land differentiated? Explained

Explained by: U Maung Maung Lwin (DWIR)

We have lists for both agricultural land and CN lands. The project will implement retaining walls and embankments.

Asked by: U Thiha Myo Aung

Our fields need water from the canal. If the embankments are built, is there any passage for the water drainage?

Discussed by – Ms. Grace (ISAN)

- For what purpose is water used in this area? Drinking?

We drink the lake water.

- Is it enough?

Yes, it is. We use well water for other purposes.

- Is there an artesian well for every house?

About 50 %

-Considerations for water supply will be included in the management plan when the project starts its constructions for the canal development. I wish you attend the next meeting and give suggestions to us after careful listening. It can be expected how much of your land areas will be included in the project. If the land areas are within 30 meters from the canal, will all the properties or possessions of those who are doing businesses in these areas? How many percentages? Not all. About 50 % and lower.

When these portions of land are included in the project area, is it possible to continue the businesses with the land areas that are left?

It depends on how large or small it is. It is possible to continue doing the businesses with the land areas that are not in land acquisition but the profits will decrease. Now, this question is asked not as a representative of the project. If there is some land acquisition, do you want other land or money as compensations? If the households are included in the area, land plots and houses are wanted as compensations. For agricultural lands, as there are not plenty of agricultural lands in other places too, cash will be better.

- What about the others?

It is good in that way.

- This project will be implemented by the Myanmar government with the loans from the Korean Bank for the development of inland water transport. In that, DWIR is the owner of the project. The Korean Bank will just give the loans. Although the engineers will be from Korea, the project developer is DWIR. The loans come from the Korean government, not from private organizations. The concerns of the government of Korea are mainly to make

	<p>sure that this project will not harm the community and not to have environmental impacts by the project. The Korean Bank has its policies. In that, if there may be losses by the project, the project will have to compensate according to the laws and regulations of Myanmar. According to their policy, compensations must be given properly. Another policy is that all stakeholders will need to be participated in the project activities. Information must be shared transparently. This is really important. As the project is just in the pre-survey stage, it is really important to make sure that compensations will need to be taken into account properly.</p>
--	--

တံတားတူးမြောင်း မြစ်ချောင်းများဖွံ့ဖြိုးတိုးတက်ရေး
သဘာဝပတ်ဝန်းကျင် နှင့် လူမှုပတ်ဝန်းကျင်
ဆန်းစစ်လေ့လာခြင်း

အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူတို့ ထုတ်ဖော်တင်ပြခြင်း
(နယ်ပယ်တိုင်းတာသတ်မှတ်ခြင်း)

DIRECTORATE OF WATER RESOURCES
AND IMPROVEMENT OF RIVER SYSTEMS

၂၀ စက်တင်ဘာလ ၂၀၁၈

REM

ISAN

Yodanin

GC

1

အကြောင်းအရာ

- 1 ရည်ရွယ်ချက်
- 2 စီမံကိန်း ဖြည့်သုံးသင်ချက်
- 3 ပတ်ဝန်းကျင်သက်ရောက်မှုဆန်းစစ်လေ့လာခြင်း
- 4 ဖြစ်နိုင်ချေရှိသော ပတ်ဝန်းကျင် နှင့်လူမှုစီးပွားရေးဆိုင်ရာ သက်ရောက်မှုများ
- 5 အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူတို့ ထုတ်ဖော်တင်ပြခြင်း
- 6 ပတ်ဝန်းကျင်နှင့်လူမှုရေးဆိုင်ရာ ထိခိုက်မှုဆန်းစစ်ခြင်း EIA တွင် လေ့လာမည့် အကြောင်းအရာများ

2

စီမံကိန်းရည်ရွယ်ချက်

3


၁။ စီမံကိန်းရည်ရွယ်ချက်

ရည်ရွယ်ချက်


လေ့လာမည့် နယ်ပယ် တိုင်းတာသတ်မှတ်ခြင်း (EIA) ၏ အဓိက ရည်ရွယ်ချက်မှာ:

- ✓ စီမံကိန်းအကြောင်းအရာများအား သိရှိစေရန် နှင့် ပတ်ဝန်းကျင်ဆန်းစစ်လေ့လာခြင်းအား ရှင်းလင်းတင်ပြခြင်း
- ✓ စီမံကိန်းအပေါ် လူထုသဘောထားများ ရယူခြင်း
- ✓ သဘာဝပတ်ဝန်းကျင်နှင့် လူမှုပတ်ဝန်းကျင်ဆိုင်ရာ ဆန်းစစ်ခြင်း (EIA) တွင် လေ့လာမည့် အကြောင်းအရာများ ကိုသိရှိစေရန်


4




5



6



7



8

၃။ ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်လေ့လာခြင်း

ရည်ရွယ်ချက်

- စီမံကိန်း၏ ပတ်ဝန်းကျင် နှင့် လူမှုရေးရာ သက်ရောက်မှုများ ဖော်ပြနိုင်ရန်နှင့် ခေတ္တသို့မဟုတ်တစ်သက်တမ်း နှင့် ကာလရှည်ခံသော စီမံခန့်ခွဲမှုအား ရည်ညွှန်းပါသည်။
- မြန်မာ EIA လုပ်ထုံးလုပ်နည်း နှင့် ကိုဗိုယား EDCF Safeguard policy အားမှည့်နှစ်စက် လေးစားလိုက်နာစေရန်

EIA ခြုံငုံသုံးသပ်မှု

- စီမံကိန်းအမျိုးအစား: Phase 1 ရန်ကုန်
- တာဝန် : ၈ ဇန်နဝါရီ - ၂၈ ဒီဇင်ဘာ, ၂၀၁၈
- လုပ်ငန်းအကြီးအကဲများ: - ISAN + YOOSHIN + GAIA CONSULT + REM

Project scope

- **Temporal scope (about 12 Months after Inception)**

Spatial scope (Setting-study Limits: TBD)

- သာသနာ့ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ခြင်း (လူမှုရေးရာ) နှင့် လူမှုရေးရာသက်ရောက်မှုဆန်းစစ်ခြင်း နှင့် တိတ်မှတ် (သို့) ထွက်ခွာသက်ရောက်မှုဆန်းစစ်ခြင်းအားလုံးပါသည်။

9

၃။ ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်လေ့လာခြင်း

EIA အကောင်အထည်ဖော်မည့် အစီအစဉ် (လျာထားချက်)

- အောက်တိုဘာ ပထမ နှင့် ဒုတိယ အပတ် : အခြေခံ သဘာဝပတ်ဝန်းကျင် နှင့် လူမှုပတ်ဝန်းကျင် စစ်တမ်းကောက်ယူခြင်း
- အောက်တိုဘာနှောင်းပတ် : နယ်ပယ်တိုင်းတာသတ်မှတ်ခြင်း
- အစီရင်ခံစာအား ဝန်ကြီးဌာနသို့ တင်ပြခြင်း
- နိုဝင်ဘာ တတိယပတ် : ဝန်ကြီးဌာနမှ ဆုံးဖြတ်မှုများ ရယူခြင်း
- နိုဝင်ဘာ ဒုတိယပတ် : EIA အစီရင်ခံစာ မူကြမ်းပြင်ဆင်ခြင်း
- ဒီဇင်ဘာ ပထမပတ် : EIA အစီရင်ခံစာ မူကြမ်းအား ဝန်ကြီးဌာန သို့ တင်ပြခြင်း
- ဒီဇင်ဘာ တတိယပတ် : ဒုတိယအကြိမ် လူထုတွေ့ဆုံ ဆွေးနွေးခြင်း

10

၃။ ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်လေ့လာခြင်း

သဘာဝပတ်ဝန်းကျင် နှင့် လူမှုရေးပတ်ဝန်းကျင်ဆိုင်ရာ သက်ရောက်မှု ဆန်းစစ်လေ့လာခြင်းဆိုင်ရာ လုပ်ထုံးလုပ်နည်း

- ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ခြင်း လုပ်ထုံးလုပ်နည်း (ဒီဇင်ဘာ ၂၀၁၅) အပိုင်း ၈၄ နောက်ဆက်တွဲ (က) တွင် ဖော်ပြချက်အရ ကမ်းပါးမြို့ အလျား ≥ ၂ ကီလိုမီတာ အရ EIA ကိုဆောင်ရွက်ပါသည်။
- ကိုးဗိုယား EDCF Safeguard Policy အရ Category A* အောက်တွင် အကြီးဝင်ပါသည်။
- * Category A: သဘာဝပတ်ဝန်းကျင် နှင့် လူမှုပတ်ဝန်းကျင်ကို ထိခိုက်မှု ရှိနိုင်ပါသည်။

11

၄

အလားအလာရှိသော ပတ်ဝန်းကျင် နှင့် လူမှုရေးရာ သက်ရောက်မှုများ

12

၄၊ အလားအလာရှိသော ပတ်ဝန်းကျင် နှင့် လူမှုရေးရာ သက်ရောက်မှုများ


အလားအလာရှိသော ပတ်ဝန်းကျင် နှင့် လူမှုရေးရာ သက်ရောက်မှုများ

နယ်ပယ်တိုင်းတာသတ်မှတ်ခြင်း နည်းလမ်း

- စီမံကိန်း လုပ်ငန်း၏ ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ် အဓိကကျသော အကျိုးသက်ရောက်မှုများကို ကနဦး ဆန်းစစ်ခြင်း လုပ်ငန်းစဉ်တွင် စီစဉ်ခြင်းသွားပါမည်။
- ကနဦး ပန်းကျင်အခြေအနေများကို ဆန်းစစ်ခြင်းသည် အကျိုးမြတ်ဆုံးဖြစ်ရာတွင် နည်းလမ်းတကျ အပြန်အလှန်ချိတ်ဆက်မှုရှိအောင် စီစဉ်ခြင်းစေနိုင်စွမ်း ဖြစ်ပေါ်စေပါသည်။

Project AOI

- တိုက်ရိုက်ထိခိုက်နိုင်သော ဇုန်ဧရိယာ (ROW = 39.5km long and 25-30m wide)
- သွယ်ဝိုက်သက်နိုင်သော ဇုန်ဧရိယာ Indirect impact zone (ROW = 39.5km long and 500m wide)



13

၄၊ အလားအလာရှိသော ပတ်ဝန်းကျင် နှင့် လူမှုရေးရာ သက်ရောက်မှုများ

ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အဓိက ဆိုးကျိုးသက်ရောက်မှုများ

- ၁) စီမံကိန်းမြေနေရာ ရွေးချယ်မှု (ဆောက်လုပ်ရေးလုပ်ငန်း မစမီ) ကာလ
- ✓ မြေနေရာ ရွေးချယ်ရာတွင် စီမံကိန်း လုပ်ငန်းတစ်စိတ်တစ်ဒေသမှ ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်စေနိုင်သော ဆိုးကျိုးများ
- ✓ ဆောက်လုပ်မည့် ရေကာတာ နှင့် အသုံးပြုမည့် လမ်း ဖောက်လုပ်ခြင်းအတွက် လိုအပ်သော ဘေးတစ်ဖက်တစ်ချက်ရှိ မြေနေရာအတွက် ညှိနှိုင်းဆောင်ရွက်ခြင်း

14

၄၊ ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အဓိကဆိုးကျိုးသက်ရောက်မှုများ

ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အဓိကဆိုးကျိုးသက်ရောက်မှုများ

၁) စီမံကိန်းမြေနေရာ ရွေးချယ်မှု (ဆောက်လုပ်ရေးလုပ်ငန်း မစမီ) ကာလ

ထည့်သွင်းစဉ်းစားချက်များ	မျှော်မှန်းထားသော အကျိုးသက်ရောက်မှုများ (ဘေးထိုးမှု / လမ်းကျိုး -) သို့သော်ထင်ရှားချက်များ (H/M/L) (* ကနဦးရလဒ်များ TBC)	ဆိုးကျိုးများကို သက်သာခြေလျှော့ပေးမည့် နည်းလမ်းအသွယ်သွယ်
မြေနေရာ ရယူမှု	မြေနေရာ ရယူရာတွင် တုံတေး တူးမြောင်း တစ်လျှောက်တွင် နေထိုင်သူ အချို့ကို ရွှေ့ပြောင်းပေးရန် လိုအပ်နိုင်ပါသည်။ (-/M or H) ဂေဟစနစ် ဤစီမံကိန်း တည်နေရာ အတွင်းတွင် သတ်မှတ်ထားသော သဘာဝ ပတ်ဝန်းကျင်ထိန်းသိမ်းကာကွယ်ထား ထားသော ဧရိယာများ (သို့) ဦးစားပေး ဧရိယာ မတွေ့ရပါ။	➢ အဆိုပြုထားသော ရေကာတာ တစ်လျှောက် မြေနေရာ နှင့် တည်ဆောက်မည့် ဒီဇိုင်း ကို လျှောက်လွှာချက်ရာတွင် လက်ရှိ တူးမြောင်းတည်ရှိမှု အနေအထား၊ လူနေအိမ်ခြေများ နှင့် လမ်းအနေအထားများ ကို ထည့်သွင်းစဉ်းစားကာ ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝများပေါ်တွင် သက်ရောက် ထိခိုက်နိုင်မှုများကို လျော့ချပေးနိုင်ပါသည်။ ➢ စီရင်စောများကို ကာကွယ်ထိန်းသိမ်းသော စနစ်တစ်ခု ကို တည်ဆောက်ခြင်း သို့မဟုတ် ပြန်လည်ဖွဲ့စည်းရန် ထည့်သွင်းစဉ်းစားခြင်း

15

၄၊ ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အဓိကဆိုးကျိုးသက်ရောက်မှုများ

ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အဓိကဆိုးကျိုးသက်ရောက်မှုများ

- ၁) ဆောက်လုပ်ရေးကာလ
- ✓ ရန်ကုန်တိုင်းဒေသကြီးအတွင်းရှိ လူမှုစီးပွားဘဝ ဖွံ့ဖြိုးတိုးတက်ရေးအတွက် အခြေခံအုတ်မြစ်ချခြင်း နှင့် တုံတေး တူးမြောင်း တစ်လျှောက်တွင် လုံခြုံစိတ်ချရပြီး အကျိုးအမြတ်များစေနိုင်သော ကုန်းတွင်းပိုင်း ရေလမ်း သယ်ယူပို့ဆောင်ရေး နေရာတစ်ခု တစ်ခု ပြင်ဆင် ဖြစ်ပေါ်လာရေး
- ၈) မြစ်ကြောင်း ထိန်းသိမ်းခြင်း
- ✓ မြစ်ကြောင်းထိန်းသိမ်းခြင်းအားဖြင့် မြစ်ကြောင်းတစ်လျှောက် လုံခြုံစိတ်ချရသော မြစ်ကြောင်း သွားလာမှုများ (သင်္ဘော၊ ရေယာဉ် အစရှိသည်) သည် ကုန်သွယ်သူများအား ကုန်းတွင်း ရေလမ်းသယ်ယူပို့ဆောင်ရေး စနစ်ကို သုံးရန် စိတ်ဝင်စားမှု တိုးပွားလာစေခြင်း။
- ✓ ရန်ကုန်တိုင်းဒေသကြီးအတွင်း စီးပွားရေး ရေရှည် ဖွံ့ဖြိုးတိုးတက်လာစေရန် ရည်မှန်းခြင်း
- ✓ တူးမြောင်းတစ်လျှောက်ရှိ မြေများ၊ လူထု အသက်အိုးအိမ် စည်းစိမ်များ နောက်ထပ်ဆုံးရှုံးမှု မရှိစေရေး၊ လယ်ယာမြေများကို မြေတိုက်စားမှုမှ ကာကွယ်ပေးရေး နှင့် အခြားသော စီးပွားရေး နှင့် လူမှုဖူလုံရေး ဆုံးရှုံးမှုများကို တားဆီးပေးနိုင်စေရန်။
- ✓ မြစ်ကြောင်းထိန်းသိမ်းရေး တည်ဆောက်မှုလုပ်ငန်းများကြောင့် အချိန်ကာလအားဖြင့် ယာယီဖြစ်သော မပြောပလောက်သော ဆိုးကျိုးသက်ရောက်မှုများ ရှိလာနိုင်ပါသည်။
- ၁) ရေကာတာ
- ✓ ခေနောင်တို့၊ ဒလ နှင့် တုံတေး ရုပေါင်း ၃ ဖြို့နယ်ကို နှစ်စဉ် စီရင်စောတက်အကျကြောင့် ချော်ခြင်းမှကာကွယ်ပေးပြီး စိတ်ချ လုံခြုံမှု ရရှိစေပါမည်။
- ✓ ရေကာတာ ဆောက်လုပ်ရေးလုပ်ငန်းများ လုပ်စဉ်တွင် ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွား ပေါ်သို့ သက်ရောက်ထိခိုက်မှု များကို ကြိုတင် မျှော်မှန်းကာ လက်ဦးမှ ရယူဆောင်ရွက်ပါမည်။

16

ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အကျိုးသက်ရောက်မှုများ		
၁) ဆောက်လုပ်ရေးကာလ		
ထည့်သွင်းစဉ် ဦးစားချက်များ	မျှော်မှန်းထားသော အကျိုး သက်ရောက်မှုများ (ကောင်းကျိုး +/ ဆိုးကျိုး -) သိသာထင်ရှားချက်များ (H/M/L) (* ကန့်သတ်ချက်များ- TBC)	ဆိုးကျိုးများကို သက်သာခြေလျှော့ပေးမည့် နည်းလမ်းအသွယ်သွယ်
ရုပ်ပိုင်းဆိုင်ရာ ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ	(မြေတွင်း၊ အမြေ အောက်မြေ၊ နှင့် အောက်အောက်မြေ) မှ ထွက်ရှိသော ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ - ဆောက်လုပ်ရေးလုပ်ငန်းတွင် မော်တော်ယာဉ်နှင့် လုပ်ငန်းခွင်သုံး စက်ကိရိယာများ မှ လေထုညစ်ညမ်းမှု၊ မြေညစ်ညမ်းမှု၊ အနံ့အနံ့ကလေးများ ထွက်ရှိလာခြင်း (H or M)	ဆောက်လုပ်ရေးလုပ်ငန်းခွင်၊ စက်ယာဉ်၊ ကိရိယာများ ကို အခါအားလျော်စွာ ပုံမှန် ထိန်းသိမ်းစောင့်ရှောက်ရေး များကို စီမံဆောင်ရွက်ရန်။ ဆောက်လုပ်ရေး ပစ္စည်းနှင့် စွန့်ပစ်အပိုက်များကို ကိရိယာ၏ နံရံအောက်အောက်တွင် အသုံးပြုရန်။ သယ်ယူပို့ဆောင်ရာတွင် နှင့် ယာဉ်များကို သင်္ဘောနှင့် သယ်ယူပို့ဆောင်ရာတွင် မြေညစ်ညမ်းမှု၊ သဲများ နှင့် ကျောက်ခဲများ ထွက်ရှိခြင်း၊ မျက်နှာရေ အမြင့် အမြင့် အမြင့် အမြင့် ထွက်ရှိခြင်း။ ပျဉ်း ခြောက်သွေ့ပြီး လေတိုက်ခတ်မှု များသော ရာသီအချိန်အခါတွင် ဆောက်လုပ်ရေး နေရာအတွင်းနှင့် အနီးအနား ပတ်ဝန်း ကျင်ကို အဆက်မပြတ် ရေချိုး လောင်းခြင်း ။ ကျေးရွာများနှင့် လူနေမှု သိပ်သည်း ထူထပ်သော နေရာတွင် ဆောက်လုပ်ရေး လုပ်ငန်းများကို ည သို့ နံနက် ၅ နာရီ အတွင်း ဆောင်ရွက်မှု မပြုလုပ်စေရန် ရှောင်ရှားခြင်း။ ဆောက်လုပ်ရေးနှင့် သယ်ယူပို့ဆောင်ရေးအတွက် အသုံးပြု သော မော်တော်ယာဉ်များ ထိန်းသိမ်းစောင့်ရှောက်မှုကို ပုံမှန် စစ်ဆေးခြင်းနှင့် ကြိုတင်ကွပ်ကဲခြင်း။
ရုပ်ပိုင်းဆိုင်ရာ ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ	(မြေတွင်း၊ အမြေ အောက်မြေ၊ နှင့် အောက်အောက်မြေ) မှ ထွက်ရှိသော ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ - ဆောက်လုပ်ရေးလုပ်ငန်းများ ဆည်မှု၊ ယာဉ်သွားလာမှု များမှ ရွှေ့ပြောင်းမှုများကို မှတ်တမ်းတင်သည့် နှင့် ဆောက်လုပ်ရေးလုပ်ငန်းနှင့် တည်ဆောက်သည့် လုပ်ငန်းများမှ ထွက်ရှိလာသည့် မြေညစ်ညမ်းမှု၊ လမ်း နှင့် ယာဉ်သွားလာမှုများ နှင့် တိုင်ပင်ခြင်းလုပ်ငန်းများမှ ထွက်ရှိလာသည့် မြေညစ်ညမ်းမှုများ အနီးအနားရှိ သိမ်းဆည်းမှု နှင့် အခြားထိခိုက်မှုများ ပစ္စည်းများအား ထိခိုက်စေနိုင်ပါသည်။ (H or M)	

17

ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အကျိုးသက်ရောက်မှုများ		
ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အကျိုးသက်ရောက်မှုများ		
ထည့်သွင်းစဉ် ဦးစားချက်များ	မျှော်မှန်းထားသော အကျိုး သက်ရောက်မှုများ (ကောင်းကျိုး +/ ဆိုးကျိုး -) သိသာထင်ရှားချက်များ (H/M/L) (* ကန့်သတ်ချက်များ- TBC)	ဆိုးကျိုးများကို သက်သာခြေလျှော့ပေးမည့် နည်းလမ်းအသွယ်သွယ်
ရုပ်ပိုင်းဆိုင်ရာ ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ	ဆောက်လုပ်ရေးကာလတွင် စီးဆင်းမှုများနှင့် ရေတိုက်စားမှုများ၊ ရေအောက်မြေများက ပတ်ဝန်းကျင်ပေါ်သို့ (ရေအောက်အောက်) တွင် ထိခိုက်မှု ရှိစေနိုင်ပါသည်။ (H or M)	အပိုက်များကို မြေအောက်တွင် မြှုပ်နှံခြင်း နှင့် မြှုပ်နှံသည့် စွန့်ပစ်ပစ္စည်းများကို ဝိတ်ပေးထားပါသည်။ စွန့်ပစ်အပိုက်များ အသုံးပြုမှု ပုံမှန်များ ကို တည်ဆဲ စည်းမျဉ်းစည်းကမ်းများအတိုင်း သန့်ရှင်းရမည်။ သို့လျှင်ပစ္စည်းများကို အမှန်အတိုင်း တပ်ဆင်ခြင်း သို့မဟုတ် မြေအောက် သို့မဟုတ်မြေ နှင့် တားလင်းခြင်းအတွင်း သို့မဟုတ် ပစ္စည်းများ မျော့ပါ လွှင့်ထွက်မသွားစေရန်အတွက် ဘေးသက်တွင် ရေသွန်းခြင်းများ တားဆီးဆောင်ရွက်ပေးရမည်။ တောပစ္စည်းများ စက်ကိရိယာ နှင့် ဆောက်လုပ်ရေး လုပ်ငန်းခွင် ပစ္စည်းများအား ခြေထောက်မြေတွင် ပတ်ဝန်း ကျင်ထဲသို့ ပြန်ပို့ပြီး မရောက်ရှိစေရန် ကုန်မြင့် ခရီးယာ များပေါ်တွင် သို့မဟုတ်တားရံရမည်။
အပိုင်းဆိုင်ရာ ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ	အပိုင်းဆိုင်ရာ ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ (ရေအောက်မြေ) မှ ထွက်ရှိသော ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ - ဆောက်လုပ်ရေးလုပ်ငန်းများ ဆည်မှု၊ ယာဉ်သွားလာမှု များမှ ရွှေ့ပြောင်းမှုများကို မှတ်တမ်းတင်သည့် နှင့် ဆောက်လုပ်ရေးလုပ်ငန်းနှင့် တည်ဆောက်သည့် လုပ်ငန်းများမှ ထွက်ရှိလာသည့် မြေညစ်ညမ်းမှု၊ လမ်း နှင့် ယာဉ်သွားလာမှုများ နှင့် တိုင်ပင်ခြင်းလုပ်ငန်းများမှ ထွက်ရှိလာသည့် မြေညစ်ညမ်းမှုများ အနီးအနားရှိ သိမ်းဆည်းမှု နှင့် အခြားထိခိုက်မှုများ ပစ္စည်းများအား ထိခိုက်စေနိုင်ပါသည်။ (H or M)	အပိုင်းဆိုင်ရာ ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ (ရေအောက်မြေ) မှ ထွက်ရှိသော ပတ်ဝန်းကျင်ပေါ်သို့ သက်ရောက်မှုများ - ဆောက်လုပ်ရေးလုပ်ငန်းများ ဆည်မှု၊ ယာဉ်သွားလာမှု များမှ ရွှေ့ပြောင်းမှုများကို မှတ်တမ်းတင်သည့် နှင့် ဆောက်လုပ်ရေးလုပ်ငန်းနှင့် တည်ဆောက်သည့် လုပ်ငန်းများမှ ထွက်ရှိလာသည့် မြေညစ်ညမ်းမှု၊ လမ်း နှင့် ယာဉ်သွားလာမှုများ နှင့် တိုင်ပင်ခြင်းလုပ်ငန်းများမှ ထွက်ရှိလာသည့် မြေညစ်ညမ်းမှုများ အနီးအနားရှိ သိမ်းဆည်းမှု နှင့် အခြားထိခိုက်မှုများ ပစ္စည်းများအား ထိခိုက်စေနိုင်ပါသည်။ (H or M)


18

ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အကျိုးသက်ရောက်မှုများ		
၁) ဆောက်လုပ်ရေးကာလ		
ထည့်သွင်းစဉ် ဦးစားချက်များ	မျှော်မှန်းထားသော အကျိုး သက်ရောက်မှုများ (ကောင်းကျိုး +/ ဆိုးကျိုး -) သိသာထင်ရှားချက်များ (H/M/L) (* ကန့်သတ်ချက်များ- TBC)	ဆိုးကျိုးများကို သက်သာခြေလျှော့ပေးမည့် နည်းလမ်းအသွယ်သွယ်
ဒေသခံ ပြည်သူလူထု	✓ ရေကတော တည်ဆောက်ခြင်း လုပ်ငန်းခွင်များ သည် ဒေသခံ ပြည်သူလူထု၏ မြေနေရာ သုံးစွဲမှု နှင့် လူမှုရေး နှင့် ဓလေ့ထုံးတမ်းစဉ်လာများ အပေါ် တွင် ထိခိုက်မှု ရှိနိုင်ပါသည်။ (H) ✓ စီမံကိန်း ဆောင်ရွက်စဉ်ကာ လ ဆောက်လုပ်ရေး လုပ်ငန်းများ ဆောင်ရွက်ရာ မေ့ စေရန် နှင့် ငွေကြေး ၏ လိုအပ်ချက်များကို ဖြည့်ဆည်းရန် အမျိုးမျိုးသော စီပွားရေးလုပ်ငန်းများနှင့် ဆက်နွယ် ဟက်သက်မှုရှိသော လုပ်ငန်းများလည်း ပေါ်ပေါက် လာနိုင်ပါသည်။ (H or M) ✓ အခြားဒေသများမှ ဆောက်လုပ်ရေးလုပ်ငန်းများ အရ လိုက် အမြဲလိုက် ဆောက်လုပ်ခြင်းအားဖြင့် အမျိုးမျိုးသော လူမှုစီးပွားရေးဆိုင်ရာ ဖိအားများ နှင့် ကျဆက်ပြွန်းပွား လှုပ်ရှားမှုများ ပျံ့နှံ့စေခြင်းနှင့် ဒေသခံ ပြည် သူလူထု၏ ရိုးရာ ယဉ်ကျေးမှု ထုံးတမ်း စဉ်လာတို့ တွင် ထိခိုက်မှုများ ဖြစ်ပေါ်လာနိုင်ပါသည်။ (M)	ဆောက်လုပ်ရေးလုပ်ငန်းများအား ဒေသခံများနှင့် ရိုက်ရန် မပြုလုပ်ရန် ညွှန်ကြားချက်များ ထုတ်ပြန်ရမည်။ ကျန်းမာရေးနှင့် ဆိုးရွားစွာ ထိခိုက်မှု မဖြစ်စေရန်နှင့် လျော့ချနိုင်ရန် အတွက် အတိုင်ပင်ခံမှ ဆောက်လုပ်ရေး လုပ်ငန်းများအား လူထု ကျန်းမာရေးနှင့် လုံခြုံရေး အစီအမံ တားရံမှုများအား ညွှန်ကြားထားရမည်။ ထိခိုက်မှုရှိသော မတော်တရား တိုင်ကြား မြေရင်းပေး သောစနစ်ကို ဆောက်လုပ်ရေးနှင့် ဆက်နွယ်သော လုံခြုံမှု ရှိစေရန်နှင့် အခြားအခြေခံအားဖြင့် ရှိသည့်များကို အချိန်နှင့် အမျိုး ဆောင်ရွက်စီမံနိုင်ရန်အတွက် တားရံမှုရမည်။ ဆောက်လုပ်ရေးလုပ်ငန်းခွင်များ နှင့် ဆက်နွယ်သော လုပ်ငန်း အဝတ် နှင့် အလုပ်သမားများနှင့် ဆက်စပ်နေသော လုပ်ငန်းခွင်များတွင် လိုအပ်သော ပတ်ဝန်းကျင် ကျန်းမာ ရေး နှင့် ဘေးကင်း လုံခြုံမှုမရှိသော စနစ်များအား ဘေးရာ ရွာ တားရံရမည်။


19

ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အကျိုးသက်ရောက်မှုများ		
ပတ်ဝန်းကျင်နှင့် လူမှုစီးပွားဘဝအပေါ်တွင် အကျိုးသက်ရောက်မှုများ		
၁) လုပ်ငန်းလည်ပတ်စဉ်ကာလ		
✓ လုပ်ငန်းလည်ပတ်စဉ်တွင် လေထု၊ ရေထုနှင့် မြေထု ညစ်ညမ်းမှုများ မရှိနိုင်ပါ။ ✓ လုပ်ငန်း၏ ကောင်းကျိုးအနေဖြင့် ရေကြီးခြင်းကို ကာကွယ်ခြင်း၊ ရေကြောင်းလမ်းသွား ရေယာဉ် သင်္ဘောများ လုံခြုံစိတ်ချရသော ရေကြောင်းစနစ်ဖြင့် သွားလာရခြင်း စသည်တို့ကို မျှော်မှန်းထားပါသည်။		
၄) အခြား စီးပွားရေးဆိုင်ရာ အကျိုးသက်ရောက်မှုများ		
✓ စီမံကိန်းသည် ကုန်းတွင်းပိုင်း သတ်မှတ် ဓရိယာအတွင်းရှိ သက်ရှိ ပတ်ဝန်းကျင်ကို ပိုမို တိုးတက်ကောင်းမွန်စေပြီး ထိုတိုးတက်မှုသည် ရန်ကုန်မြို့တော်ထဲသို့ ရင်းနှီးမြှုပ်နှံမှုများကို ပါ တစ်ဖက်တစ်လမ်းမှ တိုးတက်စေမည် ဖြစ်ပါသည်။ ✓ ဤစီမံကိန်းသည် ဒေသတွင်း စီးပွားရေးကို မြှင့်တင်ပေးနိုင်မည် ဖြစ်ပါသည်။ ✓ ဒေသတွင်း စီးပွားရေး နှင့် ငွေကြေးကြေးရေး အခွန်သက္ကာ ကြီးမားတိုးတက်လာစေခြင်း		


20




21



22



23



24

၅။ အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူသို့ ထုတ်ဖော်တင်ပြခြင်း

အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူသို့ ထုတ်ဖော်တင်ပြခြင်း

ဝန်ကြီးဌာနသို့ အစီရင်ခံစာ တင်သွင်းပြီးသည့်ကာလအတွင်း

စီမံကိန်းအဆိုပြုသူသည် ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီအရင်ခံစာကို ဦးစီးဌာနသို့ တင်သွင်းပြီးနောက် ၁၅ရက်ထက်နောက်မကျစေဘဲ၊ ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်း အစီရင်ခံစာကို လူမှုအဖွဲ့အစည်း၊ စီမံကိန်းကြောင့်ထိခိုက်ခံစားရသူများ၊ သက်ဆိုင်ရာအဖွဲ့အစည်းများ၊ ဒေသခံလူမှုအဖွဲ့အစည်းများနှင့် အခြားအကျိုးသက်ရောက်သူများသိရှိနိုင်ရန် သတင်းစာကဲ့သို့ ဘေဘဲ နိုင်ငံပိုင် မီဒီယာများမှလည်းကောင်း၊ စီမံကိန်းသို့ ဗဟုတိုက် စီမံကိန်းအဆိုပြုသူ၏ ပတ်ဘလိတ်သို့လည်းကောင်း စာကြည့်တိုက်များ၊ ပြည်သူ့ခန်းမများစသည့်အများပြည်သူဆိုင်ရာနေရာများတွင်လည်းကောင်း စီမံကိန်းအဆိုပြုသူ၏ ရုံးဌာနများတွင်လည်းကောင်း ထုတ်ဖော်ကြော်ငြာရမည်။

25

၅။ အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူသို့ ထုတ်ဝေတင်ပြခြင်း
အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူသို့ ထုတ်ဝေတင်ပြခြင်း
Activities So Far : 1st Mission Activities Korea Eximbank

Mission Activities






Meeting with Local Consultant (MDOES) (2018.01.31 PM)	Site Survey (Boat) (with F/S Tcam) (2018.02.01 All Day)	Site Survey (Car) (with F/S Tcam) (2018.02.02 All Day)
Meeting with Local Consultant (HEM) (2018.02.02 PM)	Add Meeting with PMU (Aung Kyaw Hmutu) (2018.02.03 PM)	Meeting with MONREC in Naypyidaw (2018.02.05 AM)

26

၅။ အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူသို့ ထုတ်ဖော်တင်ပြခြင်း

အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူသို့ ထုတ်ဖော်တင်ပြခြင်း

Mission Activities

<p>Pre-kick Meeting with IFPRI in Yangon (2018.01.31 PM)</p> 	<p>Meeting with MONEER in Naypyidaw (2018.02.05 AM)</p> 	<p>Meeting with MOC in Naypyidaw (2018.02.05 PM)</p> 
<p>Meeting with Dala Township Meeting (2018.02.06 AM)</p> 	<p>Meeting with Twante Township Meeting (2018.02.06 AM)</p> 	<p>Meeting with Ubonaungga Township Meeting (2018.02.06 PM)</p> 

27

၅။ အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူထံမှ ထုတ်ဖော်တင်ပြခြင်း

အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူထံမှ ထုတ်ဖော်တင်ပြခြင်း

ခန့်သတ်တို၊ တုံ့တေး နှင့် ဒလ မြို့နယ်များတွင် မြို့နယ်အဆင့် ညှိနှိုင်းဆွေးနွေးခြင်း အစည်းအဝေးများ အား သက်ဆိုင်ရာ မြို့နယ် အုပ်ချုပ်ရေးမှူးရုံးများနှင့် ဧပရယ်လ ၂၄၊ ၂၅ နှင့် ၂၆ ရက်တို့တွင် ပြုလုပ် ခဲ့ပြီး စီမံကိန်းနှင့် သတင်းအချက်အလက်များအား ဆွေးနွေးတင်ပြခဲ့ပါသည်။

မြို့နယ် အုပ်ချုပ်ရေးမှူးရုံးများမှ အဓိက တောင်းဆိုချက်များမှာ-

- ၁) အသုံးပြုမည့် မြေဧရိယာ
- ၂) ဆွေးနွေးပွဲ ပြုလုပ်မည့် နေရာ နှင့် အချိန် ရက်စွဲ အတိအကျ တင်ပြခြင်း
- ၃) ဆွေးနွေးပွဲ အကြောင်းအရာ နှင့် ပြုလုပ်မည့် အချိန်ကို ကျေးရွာနေပြည်သူလူထု ကောင်းစွာ အသိပေး သတင်းပေးခြင်း နှင့် ပွင့်လင်းမြင်သာစွာ ဆွေး နွေးတင်ပြခြင်း

28

၅။ အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူ့လို. ထုတ်ဖော်တင်ပြခြင်း
အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူ့လို. ထုတ်ဖော်တင်ပြခြင်း

29

၆
ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း

30

၆။ ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း
ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း

ပံ့ပိုးသတ်မှတ်ချက်
လိုအပ်သော နည်းလမ်းဥပဒေ နှင့် လုပ်ထုံးလုပ်နည်းများ

1. မြန်မာနိုင်ငံတွင် လက်ရှိထုတ်ပြန်ထားရှိသည့် ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဥပဒေ (၂၀၁၂)၊ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးနည်းဥပဒေများ (၂၀၁၄)၊ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးလုပ်ထုံးလုပ်နည်း အရ လိုက်နာဆောင်ရွက်မည်ဖြစ်သည်။
2. Export-Import Bank-Korea ၏ Economic Developing Cooperation Fund-EDCF အားသီးခြားလိုက်နာဆောင်ရွက်ပေးရန်အလို့ငှာ အခြေခံထားလေ့လာသွားမည် ဖြစ်ပါသည်။
3. ထို့အပြင် နိုင်ငံတကာမှ လက်ခံထားရှိသော အလေ့အကျင့်များအား အခြေခံထားသည့် Asain Development Bank- ADB နှင့် World Bank ၏ ပတ်ဝန်းကျင်နှင့် လုံခြုံရေးဆိုင်ရာပေါ်လစီများကိုလည်း အခြေခံဆောင်ရွက်သွားမည်ဖြစ်ပါသည်။

<http://www.worldbank.org/en/programs/environmental-and-social-policies-for-projects/brief/environmental-and-social-safeguards-policies>
<https://www.adb.org/site/safeguards/overview>


31

၆။ ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း
ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း

အခြေခံ ပတ်ဝန်းကျင်အရည်အသွေး လေ့လာခြင်း

Survey Items	အစုစုအတွက် နှင့် တည်နေရာ	Parameters	Sampling Method
လေအရည်အသွေး တိုင်းတာခြင်း	၄ (TBD)	PM10, PM2.5, SO ₂ , NO ₂ , CO, wind Speed, & Weather condition, Temperature, Wind, wind directions	၂၄ နာရီတိုင်းတာမှု
အသံ ရှည်လျှော့ တိုင်းတာခြင်း	၄ locations(TBD)	ရည်မှန်း အတိုင်းအတာ	နေရာတစ်ခုချင်းစီတွက် မနက်၊ နေ့လယ်၊ ညနေ တွင်တိုင်းတာမည်။
တုန်ခါမှု တိုင်းတာခြင်း	၄ locations(TBD)	တုန်ခါမှု အတိုင်းအတာ	နေရာတစ်ခုချင်းစီတွက် မနက်၊ နေ့လယ်၊ ညနေ တွင်တိုင်းတာမည်။
ရေအရည်အသွေး တိုင်းတာခြင်း	၆ locations(TBD)	Water Temperature, pH, DO, Turbidity, BOD, COD, T-N, T-P, TSS, Total Coliform Bacteria(TCB), Oil & Grease, Total Chromium, Cu, Zn, Pb, Cd, Mercury, Arsenic, NH ₄ -N, Cr (VI), Ni, NO ₃ -N, Fe, CN, Salinity	မိုင်တစ်ခုစီတွင် တစ်ကြိမ်တိုင်းတာမည်။

32



33

၆။ ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း

ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း
အခြေခံ ပတ်ဝန်းကျင်အရည်အသွေး လေ့လာခြင်း

ဇီဝမျိုးစုံမျိုးကွဲစစ်တမ်းကောက်ယူခြင်း
လေ့လာမည့်နေရာ - Project AOI (တိုက်ရိုက်၊ သွယ်ဝိုက် ဆက်စပ်သည့် နေရာများ)

အောက်ပါဇီဝမျိုးစုံစစ်တမ်းကိုလေ့လာသွားမည်ဖြစ်သည်။

- သစ်တော : သစ်တောအမျိုးအစားများ
- အပင်မျိုးစားစိတ်များ
- အကောင်မျိုးစိတ်များ(နို့တိုက်၊ တွားတွားသတ္တဝါ၊ ကုန်းနေရေနေ၊ ကြက်ဘဲ၊ နှင့် ငါး)

34

၆။ ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း

ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း
လူမှုစီးပွားရေး လေ့လာခြင်း

လေ့လာမည့်အကြောင်းအရာများ

- လူဦးရေ ပြန့်နှံ့နေထိုင်မှု
- မြေယာအသုံးချမှုအခြေအနေ
- လူမှုစီးပွားရေး
- ရုပ်ပိုင်းဆိုင်ရာသဘာဝ ပတ်ဝန်းကျင် အရင်းအမြစ်များ ရရှိမှု အခွင့်အလမ်း
- စီမံကိန်းကြောင့် အဓိက ထိခိုက်ခံစားနေရမည့်သူများ ၊ အိမ်ထောင်စုများ
- ရွေးကောင်းယဉ်ကျေးမှု နှင့် ဘာသာရေးဆိုင်ရာ အဆောက်အအုံများ

35


၆။ ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း

ရည်ညွှန်းချက်များသတ်မှတ်ခြင်း
မြေယာသိမ်းဆည်းခြင်း နှင့် ပြန်လည်ထူထောင်ခြင်းအစီအစဉ်

မြေယာသိမ်းဆည်းခြင်း နှင့် ပြန်လည်ထူထောင်ခြင်းအစီအစဉ်

- သဘာဝသဘာဝကိုအကျိုးပြုခြင်း
- ရွေ့ပြောင်းရန်လျာထားခံရနိုင်သော အလားအလာရှိသူများအား လျော့နည်းသက်သာစေရန် စီမံကိန်းဒီဇိုင်းအား ထိခိုက်မှုအနည်းဆုံးဖြစ်အောင် ဆောင်ရွက်ရမည်။
- လူထုနှင့်သက်ဆိုင်သော အခြေခံအဆောက်အအုံများ နှင့် မြေယာသိမ်းဆည်းခြင်း လျော်ကြေး များအတွက် ပြန်မာနိုင်ငံ၏ ဥပဒေရေးရာ နှင့်အဖွဲ့အစည်း မူဘောင်အတွင်းလုပ်ဆောင်ရမည်။
- ကနဦးလေ့လာခြင်း
- ရရှိမှု အခွင့်အရေး စီးပွားရေးမြှင့်တင်မှုများ အားထည့်သွင်းစဉ်းစားရမည်။
- ဝင်ငွေ နှင့် အသက်မွေးဝမ်းကျောင်းများ အတွက်ငွေကြေးထောက်ပံ့မှု အစီအစဉ်ရေးဆွဲထားမည်။
- မြေယာသိမ်းဆည်းခြင်း နှင့် လျော်ကြေးများ အကောင်အထည်ဖော်မှု (တိုင်းတာမှု နှင့် သတင်းပို့မှု) အစီအစဉ် (ခန့်မှန်းချေ အချိန်ဇယား တာဝန်ရှိ အေဂျင်စီများ နှင့် ငွေကြေးအရင်းအမြစ်) စသည်တို့ ထည့်သွင်းစဉ်းစားရမည်။

36



37

တွံတေးတူးမြောင်း ဘက်စုံဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်း သဘာဝပတ်ဝန်းကျင် နှင့် လူမှုပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်လေ့လာခြင်း

အများပြည်သူတို့ သတင်းအချက်အလက်ထုတ်ဖော်တင်ပြခြင်း နှင့်
တိုင်ပင်ဆွေးနွေးခြင်း
(ပတ်ဝန်းကျင်ထိခိုက်သက်ရောက်မှု ဆန်းစစ်လေ့လာခြင်းများ)



၂၀၁၉ ခုနှစ် ဇန်နဝါရီလ ၂၆ - ၂၉ ရက်ထိ




1

အကြောင်းအရာ

- ၁) စီမံကိန်းအကြောင်း ခြုံငုံဖော်ပြချက်
- ၂) ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်လေ့လာထားမှုများ အခြေအနေ
- ၃) ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်လေ့လာခြင်း၏ ရည်ရွယ်ချက်များ
- ၄) ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်လေ့လာသော နည်းလမ်းများ
- ၅) အဓိက သက်ရောက်မှုများကို ဆန်းစစ်ခြင်းနှင့် လျှော့ချရေးနည်းလမ်းများ
- ၆) သဘာဝဘေးအန္တရာယ်သက်ရောက်မှုများကို ဆန်းစစ်ခြင်း
- ၇) ဖြစ်ပေါ်နိုင်သော သက်ရောက်မှုများကို ဆန်းစစ်ခြင်း
- ၈) စီမံကိန်းကြောင့် ရရှိလာနိုင်သော အကျိုးကျေးဇူးများ
- ၉) အခြားသက်ရောက်နိုင်မှုများနှင့် လျှော့ချရေးနည်းလမ်းများ
- ၁၀) ရှေ့ဆက်လုပ်ငန်းစဉ်များ အစီအစဉ်

2

စီမံကိန်းအကြောင်း ခြုံငုံဖော်ပြချက်




အစိတ်အပိုင်း ၁ - ရေကြောင်းပြုပြင်ထိန်းသိမ်းခြင်း
၁-၁ - ကမ်းခြေ ကာကွယ်ခြင်း
၁-၂ - မြစ်ကြမ်းပြင်တိုက်စားမှု ကာကွယ်ခြင်း

အစိတ်အပိုင်း ၂ - ရေကြီးမှုကာကွယ်ခြင်း
၂-၁ - ဆိပ်ကြီး-ခရောင်တုံ
၂-၂- အလ
၂-၃- တွံတေး

3


စီမံကိန်းအကြောင်း ခြုံငုံဖော်ပြချက်

အစိတ်အပိုင်း ၁ - ရေကြောင်းပြုပြင်ထိန်းသိမ်းခြင်း ၊ ကမ်းခြေကာကွယ်ခြင်း (၅.၈၈ ကီလိုမီတာ)
: မြစ်ကြမ်းပြင်တိုက်စားမှု ကာကွယ်ခြင်း (၈မီတာ = ၅၅၀၀ စတုရန်းမီတာ)




4


3




5



6









7



8

Phase		Process Plan (8 months)							
Main Task		Month 1	Month2	Month 3	Month 4	Month 5	Month 6	Month 7	Month 8
1 step	Establishing ESIA implementation plan through preliminary survey								
	Project Proposal Submission								
2 step	Scoping investigation & stakeholder analysis								
	Information disclosure and public consultation (1st)								
	Scoping and TOR writing and submission								
	Scoping and TOR review & approval (by MONREC)								
	ESIA Investigation								
3 step	Information disclosure and public consultation (2nd)								
	Drafting ESIA report								
4 step	ESIA report review and approval (by MONREC)								
	Report Plan								
Mission to Myanmar									

Legend:
■ The task of ESIA team
■ The task of Myanmar

<p>Pre-kick Meeting with DWIR in Yangon (2018.01.31 PM)</p> 	<p>Meeting with MONREC in Naypyidaw (2018.02.05 AM)</p> 	<p>Meeting with MOC in Naypyidaw (2018.02.05 PM)</p> 
<p>Meeting with Dala Township Meeting (2018.02.06 AM)</p> 	<p>Meeting with Twante Township Meeting (2018.02.06 AM)</p> 	<p>Meeting with Khanaungto Township Meeting (2018.02.06 PM)</p> 

<p>Working Group meeting with PMU in Yangon (2018.04.25 AM)</p>	<p>Meeting with Dala Township Meeting (2018.04.02 PM)</p>	<p>Meeting with Khanaungto Township Meeting (2018.04.26 PM)</p>
		
<p>Site Survey (2018.04.26) 1</p>	<p>Site Survey (2018.04.26) 2</p>	<p>Site Survey (2018.04.26) 3</p>
		

[illegible]

3

ပထမအကြိမ်ဆွေးနွေးပွဲမှရရှိသော အကြံပြုချက်များ အကျဉ်းချုပ်

- တူးမြောင်းနယ်နိမိတ်အတွင်းရှိမြေယာ နှင့် အဆောက်အအုံများအတွက် လျော်ကြေးငွေများပေးရန်
- ရန်ကုန်မြစ်နှင့်တိုးမြှင့်မှုများမှ ရေငန်ဝင်ရောက်ခြင်းကြောင့် စိုက်ပျိုးမြေများအား သက်ရောက်မှုများ၊ မြစ်ကမ်းပါးများ ရေတိုက်စားမှုကြောင့် ပျက်စီးမှုများ
- စီမံကိန်းအကောင်အထည်ဖော်ဆောင်ရာတွင် အရည်အသွေးပြည့်မီရန် စီစဉ်ဆောင်ရွက်ရန်နှင့် ရေရှည်ထိန်းသိမ်းသွားရန်
- စီမံကိန်းပြီးသွားပါက ဒီရေတောအပင်များ မြစ်ကမ်းပါးထိန်းတာဝန် တစ်လျှောက်တွင် ပြန်လည်စိုက်ပျိုးပေးရန်
- တွဲတေးတူးမြောင်းအတွင်းသွားလာနေသော သင်္ဘောများအား ပန်ကြီးဌာနမှ ထုတ်ပြန်ထားသော စည်းမျဉ်း စည်းကမ်းများအတိုင်း လိုက်နာရန် DWIR မှ ကြပ်မတ်ရန် တောင်းဆိုခြင်း
- ပတ်ဝန်းကျင်ထိခိုက်မှု အစီရင်ခံစာအတွက် လိုအပ်သော အချက်အလက်များအား စနစ်တကျ မှန်ကန်စွာကောက်ယူရန်



ရည်မှန်းချက်

- EIA လုပ်ထုံးလုပ်နည်း ၂၀၁၅ ၊ ပုဒ်မ ၅၀ ၊ ၆၁ နှင့် ၆၅ အရ လူထုတွေ့ဆုံပွဲများကို ကျင်းပရန်

ရည်ရွယ်ချက်များ

- စီမံကိန်းနှင့် ပတ်သက်၍ သက်ဆိုင်ရာမှ အဆိုပြုထားသော အချက်အလက်များကို အချိန်နှင့် တစ်ပြေးညီ ဖော်ထုတ်ရန်
- အများပြည်သူနှင့် လူထုအခြေပြုအဖွဲ့အစည်းများသို့ ဖြစ်နိုင်ချေရှိသော သက်ရောက်မှုများကို ပွင့်လင်းမြင်သာစွာ ဖော်ပြရန်
- စီမံကိန်းကြောင့် ဖြစ်ပေါ်လာသော ကြိုတင်မျှော်မှန်းထားသည့် သဘာဝပတ်ဝန်းကျင်နှင့် လူမှုဆိုင်ရာအပေါ်တွင် သက်ရောက်နိုင်မှုများကို လျော့ပါးသက်သာစေရေးနည်းလမ်းများကို ဆွေးနွေးတင်ပြရန်။

သက်ရောက်မှုများကို အကဲဖြတ်သော နည်းစနစ်များ

အဓိကကျသော အချက်အလက်များ

- ပဏာမ ဆန်းစစ်ခြင်း နှင့် နယ်မြေသတ်မှတ်ခြင်း
- ရှိရင်းစွဲ အခြေခံသတင်းအချက်အလက်များ
- အခြားဖြစ်နိုင်စွယ်ရာနည်းလမ်းများ ရွေးချယ်ခြင်းနှင့် စီမံကိန်းအစီအစဉ်
- အဓိကကျသော ကိစ္စရပ်များနှင့် ထိန်းသိမ်းစောင့်ရှောက်ရေးစီမံခန့်ခွဲမှုအစီအစဉ်အပေါ် သက်ရောက်မှုကို ဆန်းစစ်ခြင်း
- သက်ရောက်မှုများကို သတ်မှတ်ခြင်း နှင့် အဆင့်အလိုက် အကဲဖြတ်ခြင်း
- ကြွင်းကျန်နိုင်သော သက်ရောက်မှုများကို ခွဲခြားဖော်ထုတ်ခြင်း
- လျော့ချရေးနှင့် စောင့်ကြည့်ခြင်း အစီအစဉ်များ

ဆန်းစစ်ချက်များ	Scale				
	၁	၂	၃	၄	၅
ပဏာမ (M)	မသိသာ	နည်း	အလယ်အလတ်	မြင့်မား	အလွန်မြင့်မား
အချိန်ကာလ (D)	၀ - ၁ နှစ်အတွင်း	၂ - ၅ နှစ်အတွင်း	၆ - ၁၅ နှစ်အတွင်း	လုပ်ငန်းလည်ပတ်နေချိန်ကာလတစ်လျှောက်လုံး	လုပ်ငန်းပိတ်သိမ်းပြီးနောက်
အတိုင်းအတာ (E)	သတ်မှတ်နေရာအတွင်း	ဧရိယာအတွင်း	ဒေသအတွင်း	နိုင်ငံအတွင်း	နိုင်ငံရပ်ခြား
ဖြစ်နိုင်ခြေ (P)	ဖြစ်နိုင်ခြေ အလွန်မရှိ	မဖြစ်နိုင်	ဖြစ်နိုင်ခြေရှိ	ဖြစ်နိုင်ခြေ များများရှိ	ဖြစ်နိုင်ခြေ သေချာမှုရှိ

ထပ်ဆင့်ဆန်းစစ်မှု	သက်ရောက်မှု အဆင့်
၁၅ အောက်	သက်ရောက်မှု မရှိ (-)
၁၅ - ၂၀	နည်း (U)
၂၀ - ၄၄	အလယ်အလတ်အဆင့် (C)
၄၅ - ၅၉	မြင့်မား (B)
၆၀ နှင့် အထက်	Very high significant (A)


ရင်းလင်းချက်



သဘာဝဆိုင်ရာသဘာဝအချက် (SP) = (ပဏာမ + ကာလ + အတိုင်းအတာ) *

ဖြစ်နိုင်ချေ

Overall event magnitude is scored from low (15) to very high (>60) by adding the individual parameter scores:

5 10 15 20 25 30 35 40 45 50 55 60 15





လေထုထုတ်လွှတ်မှုများအပေါ် သက်ရောက်မှု ဆန်းစစ်ချက်				
သက်ရောက်မှု ဖြစ်စေနိုင်သော အကြောင်းရင်းများ	<p>ဇယား ၁။ မြေပြင်၊ မြေအောက်၊ လေထုနှင့် ဆောက်လုပ်ရေးလုပ်ငန်းခွင် - မော်တော်ယာဉ်များနှင့် နိုင်ငံခြား</p> <p>ဖုန်မှုန့်များ (Particulate matters, PM₁₀ and PM_{2.5}) ထုတ်လွှတ်မှုမှာ အများဆုံး ဖြစ်နိုင်ပါသည်။ မော်တော်ယာဉ် အသုံးပြုမှုများမှ ဆာလဖိုင်ဒိုင်အောက်ဆိုဒ်ထုတ်လွှတ်မှုများ ရှိလာနိုင်ပါသည်။ ပတ်ဝန်းကျင် သက်ရောက်မှု : ဆောက်လုပ်ရေး လုပ်ငန်းခွင် အလုပ်သမားများ ကျန်းမာရေး နှင့် စီမံကိန်း အနီးဝန်းကျင်ရှိ ပြည်သူ့ကျန်းမာရေးကို သက်ရောက်မှု ရှိလာနိုင်ပါသည်။</p>			
ပမာဏ	မထူးခြား	နည်း	အလယ်အလတ်	မြင့်
အချိန်ကာလ	၀-၁ နှစ်အတွင်း	၁-၅ နှစ်အတွင်း	၆-၁၅ နှစ်အတွင်း	၁၅ နှစ်အတွင်း
အတိုင်းအတာ	သတ်မှတ်ထားသော နေရာ	သတ်မှတ်နေပါအတွင်း	သတ်မှတ်နေပါအတွင်း	နိုင်ငံခြား
ဖြစ်နိုင်ခြေ	အချိုးကျ : ဆောက်လုပ်ရေးလုပ်ငန်းခွင်အနီး စက်များတပ်ဆင်ခြင်း၊ ထိခိုက်ခြင်း လုပ်ငန်းနေရာများ၏ အနီးဝန်းကျင်ရှိ လူများအပေါ် သက်ရောက်နိုင်ပါသည်။ ဖုန်မှုန့် ထွက်ရှိမှုမှာ အများဆုံး ဖြစ်နိုင်ပါသည်။	ဖြစ်နိုင်ခြေ အလွန်နိမ့်	ဖြစ်နိုင်ခြေ မရှိ	ဖြစ်နိုင်ခြေ မရှိ
သက်ရောက်မှု အဆင့်	<p>အချိုးကျ : လေထုထုတ်လွှတ်မှုမှာ မြင့်မားနိုင်သော်လည်း အချိန်ကာလတိုအတွင်းတွင်သာ ဖြစ်၍ အမြဲပြတ် ပြတ်တောက်ပြီး ပြတ်တောက်သော ဖြစ်နိုင်ပါသည်။ ဆောက်လုပ်ရေးလုပ်ငန်းခွင်မှလည်း တစ်နေရာတည်းတွင် ရှိနေမည် မဟုတ်ဘဲ တစ်နေရာပြီး တစ်နေရာ ချွေပြောင်းနေမည် ဖြစ်ပြီး လုပ်ငန်းခွင်နှင့် အနီးဝန်းကျင်ရှိ လူများကိုသာ သက်ရောက်စေနိုင်မည်ဖြစ်ပါသည်။ ဆောက်လုပ်ရေးလုပ်ငန်းခွင် ပြီးဆုံးသွားပါက သက်ရောက်မှု ရှိနိုင်တော့မည် မဟုတ်ပါ။</p> <p>ပမာဏ (၄) + အချိန်ကာလ (၂) + အတိုင်းအတာ (၁) * ဖြစ်နိုင်ခြေ (၃) = ၂၀</p>			

လျော့ပါးသက်သာစေရေး အစီအစဉ်

- ဖုန်မှုန့်ထွက်သည့် နေရာများအားရှေ့ပြန်ခြင်း
- လူများသွားလာသည့် လမ်းများပေါ်တွင် မော်တော်ယာဉ်၏ အမြန်နှုန်း ကန့်သတ်ထားခြင်း
- ဆောက်လုပ်ရေးလုပ်ငန်း/မြေဖျော့တင်ဆောင်လာသော ယာဉ်များ အား ဓနစ်တကျဖုံးအုပ်ထားခြင်း
- ကြိုတင်ကာတွယ် ထိန်းသိမ်းမှုစနစ်များ ထားရှိခြင်း
- နေ့စဉ်မော်တော်ယာဉ် နှင့် ယာဉ်သင်္ဘောများ စစ်ဆေးခြင်း
- လေတိုက်နှုန်းမြင့်မားသော နေရာများတွင် ဖုန်ထွက်စေသည့် လုပ်ဆောင်မှုများအား ရပ်တန့် ထားခြင်း
- ကောင်းသော လုပ်ငန်းအလေ့အကျင့်များအား လိုက်နာခြင်း
- ပစ္စည်းများအား အသုံးမပြုနိုင်သည့် ဝိတ်ထားခြင်း
- မော်တော်ယာဉ်များသွားလာမှုနှင့်ဆက်သွယ်သော အချိန်ခဏအား လျော့ချခြင်း
- သိမ်းတင်ဆောင်လာသော အခါ ဓနစ်တကျ ဖုံးအုပ်ထားခြင်း

မော်တော်ယာဉ်များ

- မော်တော်အင်ဂျင်များ နှင့် အခြားစက်ပစ္စည်းများအား မလိုလားအပ်သော ညစ်ညမ်းမှုများ အမြဲတမ်းရှေ့မှ လိုအပ်သည့် လုပ်ငန်းများ
- တတ်နိုင်သမျှ လျှပ်စစ်အင်အားစက်နှင့် နည်းလမ်းများအသုံးပြုရမည်။
- ဆောက်လုပ်ရေးပစ္စည်းကိရိယာများ နှင့် မော်တော်ယာဉ်များကို ဆောက်လုပ်ရေးခြင်းနေရာတွင် ကျွမ်းကျင်သူများနှင့် ပြုပြင်ထိန်းသိမ်းရမည်။

အမှန်များထိန်းသိမ်းခြင်း

- (အထူးသဖြင့် ပစ္စည်းများသိုလှောင်ရာ နေရာများအား လေတိုက်စားမှု လျော့ချရန် အစိုးရနှင့်အသုံးပြုထားခြင်း သို့မဟုတ်)
- လေတိုက်စားမှုအားလျော့ချရန် အသုံးမပြုသော ဝိတ်များအား ဖုံးအုပ်ထားခြင်း
- ကာများသွားလာမှု ကားသိမ်းများ ဆောက်လုပ်ရေးအတွင်းအပြင် မှ ထွက်ရှိလာသော ဖုန်မှုန့်များ ဖုန်မှုန့် သက်သာစေရန် ရေဖြန်းခြင်း
- ဆောက်လုပ်ရေးလုပ်ငန်းခွင်အတွင်း သွားလာမှုနှင့် နည်းပါးစေခြင်း
- သစ်ပင်ထုတ်ထားသော နေရာများတွင် သစ်ပင်များပြန်လည်စိုက်ပျိုးခြင်းများကို ပြုလုပ်ခြင်း။

ဆုညံ့မှ နှင့် တုန်ခါမှု

ဆုညံ့မှ နှင့် တုန်ခါမှု တိုင်းတာသည့် ကိရိယာ

Parameter	Instrument	Model	Manufacture
Noise (A-weighted loudness equivalent (L_{Aeq}))	Sound level meter	SL-4023SD	Lutron
Vibration (Vibration level (L_{Veq}))	Vibration level meter	VM-55	Rion Co. Ltd. (Japan)

Equivalent Noise Level (L_{Aeq}) and Vibration Level (L_{V10}) Source: REM Survey, 2018 (Twaente Canal Project)

Survey Point	Equivalent Noise Level (L_{Aeq} dB)		Vibration Level (L_{V10})	
	Day-time (7:00 AM - 10:00 PM)	Night-time (10:00 PM - 7:00 AM)	Day-time (7:00 AM - 10:00 PM)	Night-time (10:00 PM - 7:00 AM)
AQNV1	74	64	46	40
AQNV2	79	66	43	37
AQNV3	72	58	37	34
AQNV4	71	70	36	29
Target Value (Industrial, commercial)	70	70	-	-
Target Value (Residential)	55	45	65	60



21

ဆုညံ့မှ နှင့် တုန်ခါမှုမှ သိသာထင်ရှားသော သက်ရောက်မှု

သက်ရောက်မှု အရင်းအမြစ်	စက်ယန္တရား: မြေကွဲဖော်ခြင်း လုပ်ငန်းများ၊ လုပ်ငန်းများ၊ bulldozers, excavators, loaders, အချိုးအမျှသော သယ်ယူပို့ဆောင်ရေးယန္တရားများ၊ မြေပြင်လုပ်ငန်းများ၊ သံတုများ၊ ပစ္စည်းများ၊ ကရိန်းများ နှင့် ဓာတ်လှေကား တစ်ဆင့်ခြင်း လုပ်ငန်းများမှ တုန်ခါခြင်း လေးလံသောစက်ယန္တရားများ နှင့် အချိုးအမျှသောစက်ယန္တရားများမှ တွင်တုန်ခါမှုများဖြစ်ပေါ်နိုင်သည်။ ပတ်ဝန်းကျင် Contamination: လုပ်ငန်းခွင်ကျွန်းမာရေး ဆုညံ့မှအား ရေရှည်ထိတွေ့ပါက အကြားအာရုံထိခိုက်နိုင်ပြီး ပင်ပန်းနွမ်းမယ်မှု စိတ်ပိုင်းမှ အိပ်မပျော်ခြင်းများဖြစ်ပေါ်နိုင်သည်။		
ပမာဏ	မတူခြင်း	အလယ်အလတ်	မြင့်
အချိန်ကာလ	၀-၁ နှစ်အတွင်း	၁-၅ နှစ်အတွင်း	၅-၁၀ နှစ်အတွင်း
အတိုင်းအတာ	အတိအကျသော နေရာ	သတ်မှတ်နေသောအတွင်း	သတ်မှတ်နေသောအတွင်း
ဖြစ်နိုင်ခြေ	တိုက်ရိုက်ထိခိုက်ခြင်း	တိုက်ရိုက်ထိခိုက်ခြင်း	တိုက်ရိုက်ထိခိုက်ခြင်း
သက်ရောက်မှုအဆင့်	Magnitude (4) + Extent (1) * Probability (4) = 28		

ဆုညံ့မှ နှင့် တုန်ခါမှုမှ လျော့ချနိုင်သော သက်ရောက်မှုများ
 အဆိုပါကာလအတွင်း ဆုညံ့မှထုတ်လုပ်မှု ဆိုင်ရာသက်ရောက်မှု အားလျှော့ချနိုင်ရန်အတွက် ကြိုတင်သိမြင်နေသော်လည်း အဆိုပါကာလအတွင်း ဆုညံ့မှထုတ်လုပ်မှု ဆိုင်ရာသက်ရောက်မှု အားလျှော့ချနိုင်ရန်အတွက် ကြိုတင်သိမြင်နေသော်လည်း construction phase of the twaente township are:
 • ပစ္စည်းကိရိယာများ လုံလောက်စွာထားရှိခြင်း (fit with noise mufflers);
 • အသုံးမပြုသည့် အင်ဂျင်နှင့် စက်ယန္တရားများ ပစ္စည်းကိရိယာများကို လျော့ချရန်
 • အင်ဂျင်နှင့် စက်ယန္တရားများ ပစ္စည်းကိရိယာများကို ကောင်းစွာထားရှိရန်
 • အသံဆုညံ့မှနှင့်ပတ်သက်၍ ပြည်သူလူထု တစ်ပြိုင်နက်တည်း သိရှိသော ပြုလုပ်သည့်အား ဆောင်ရွက်ပေးရန်။
 • သတိပေးဆီးဘုတ်များ နှင့် တက်သ်ရောက်မှုတစ်ခုစီပစ္စည်းများ ထားရှိရန်
 • သာမန်လုပ်ငန်းမျိုးတွင် အနောက်အလယ်တန်းစားသော ဆောက်လုပ်ရေးအသံများအားထားခြင်းရန်

22

ရေအရည်အသွေး

- မျက်နှာပြင်ရေ
- မြေအောက်ရေ

တိုင်းတာသည့် ကာလ

ဒီရေကျစဉ်အတွင်း မျက်နှာပြင်ရေ နမူနာတိုင်းတာမှုကို စက်တင်ဘာ ၁၆ မှ ၃၀ရက် ၂၀၁၈ တွင်လည်းကောင်း၊

မြေအောက်ရေနမူနာအား ၅ရက် ဒီဇင်ဘာလ ၂၀၁၈ တွင် ကောက်ယူခဲ့ပါသည်။



ရေနမူနာခွဲခြမ်းစိတ်ဖြာခြင်းအား ရန်ကုန် REM-UAE ဓာတ်ခွဲခန်း နှင့် SGS ထိုင်းနိုင်ငံရှိ ဓာတ်ခွဲခန်းသို့ ပို့ဆောင်သည်။

မျက်နှာပြင်ရေ နှင့် မြေအောက်ရေ စစ်ဆေးမှုရလဒ်အား ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်း အစီရင်ခံစာတွင် ထည့်သွင်းဖော်ပြထားပါသည်။

မျက်နှာပြင်ရေ နှင့် မြေအောက်ရေ မြန်မာစံချိန်စံနှုန်းမရှိပါ။

23

Survey Results Of Surface Water Quality (ebb tide in September 2018)

No.	Item	Unit	SW1	SW2	SW3	SW4	SW5	SW6
1	Temperature (water)	°C	27.54	27.49	29.82	27.61	30.05	31.59
2	pH	-	8.73	8.22	8.21	8.10	8.31	8.29
3	Dissolved Oxygen (DO)	mg/l	5.25	4.84	4.36	5.02	5.23	4.27
4	Salinity	psu	1.0	1.3	1.5	1.5	2.2	2.0
5	Turbidity	FNU	439	458	463	475	521	528
6	Ammonium-Nitrogen	mg/l	0.09	0.16	0.12	<0.02	0.09	0.10
7	Arsenic	mg/l	0.001	0.0021	0.0009	0.0006	ND	0.0003
8	BOD5	mg/l	1.5	1.7	2.5	1.6	1.7	1.4
9	COD	mg/l	46.1	49.2	55.5	49.2	52.3	57.1
10	Cadmium	mg/l	ND	ND	ND	ND	ND	ND
11	Chromium (hexavalent)	mg/l	ND	ND	ND	ND	ND	ND
12	Chromium (total)	mg/l	ND	0.025	ND	ND	ND	ND
13	Copper	mg/l	0.008	0.012	0.005	0.004	0.004	0.004
14	Cyanide	mg/l	ND	ND	ND	ND	ND	ND
15	Iron	mg/l	8.46	15.1	16.2	5.69	5.76	3.21
16	Lead	mg/l	ND	ND	ND	ND	ND	ND
17	Mercury	mg/l	ND	0.0002	0.0004	0.0002	0.0003	0.0002
18	Nickel	mg/l	0.026	0.05	0.018	0.02	0.019	0.006
19	Nitrate-Nitrogen	mg/l	0.09	0.06	0.09	0.07	0.07	0.09
20	Oil & Grease	mg/l	ND	3	4	3	ND	3
21	Suspended Solids	mg/l	231	27.3	366	341	309	230
22	Total Nitrogen	mg/l	0.56	0.61	0.67	0.59	0.63	0.41
23	Total Phosphorus	mg/l	0.05	0.05	0.1	0.05	0.05	0.07
24	Zinc	mg/l	0.014	0.028	0.009	ND	ND	0.007
25	Total Coliform	MPN/100ml	>160,000	54,000	160,000	92,000	35,000	>160,000

24

23

Survey Results Of Surface Water Quality (Flood Tide in December 2018)

No.	Item	Unit	SW1	SW2	SW3	SW4	SW5	SW6
1	Temperature (water)	°C	26.52	26.59	27.07	27.15	28.30	28.70
2	pH	-	7.39	7.41	7.18	7.16	7.15	7.17
3	Dissolved Oxygen (DO)	mg/l	5.57	6.05	5.49	5.65	5.49	5.56
4	Salinity	psu	1.2	1.4	1.8	2.0	2.5	2.3
5	Turbidity	FNU	355	209	696	635	549	510
6	Ammonium-Nitrogen	mg/l	0.15	0.16	0.16	0.14	0.24	0.16
7	Arsenic	mg/l	ND	ND	0.0028	0.0018	0.002	0.0015
8	BOD ₅	mg/l	ND	ND	1.0	1.2	1.3	ND
9	COD	mg/l	38.3	39.9	35.1	38.3	41.5	38.5
10	Cadmium	mg/l	ND	ND	ND	ND	ND	ND
11	Chromium (hexavalent)	mg/l	ND	ND	ND	ND	ND	ND
12	Chromium (total)	mg/l	ND	ND	ND	ND	ND	ND
13	Copper	mg/l	ND	ND	0.008	0.005	0.003	0.005
14	Cyanide	mg/l	ND	ND	ND	ND	ND	ND
15	Iron	mg/l	3.02	4.3	16.8	12.3	9.94	11.0
16	Lead	mg/l	ND	ND	ND	ND	ND	ND
17	Mercury	mg/l	0.0003	0.0002	0.0005	0.0005	0.0004	0.0002
18	Nickel	mg/l	0.005	0.014	0.042	0.036	0.029	0.032
19	Nitrate-Nitrogen	mg/l	0.09	0.11	0.14	0.18	0.16	0.16
20	Oil & Grease	mg/l	4	4	3	3	3	4
21	Suspended Solids	mg/l	157	79.6	335	248	197	191
22	Total Nitrogen	mg/l	0.83	1.05	0.14	1.14	1.08	1.10
23	Total Phosphorus	mg/l	ND	0.01	0.01	ND	0.02	0.01
24	Zinc	mg/l	ND	ND	0.023	0.016	0.012	0.014
25	Total Coliform	MPN/100ml	1,100	>160,000	35,000	54,000	>160,000	54,000

25

25

Survey Results of Ground Water Quality

No.	Item	Unit	GW
1	Transparency	-	High
2	Depth	m	40
3	Temperature	°C	24.43
4	pH	-	6.19
5	Dissolved Oxygen (DO)	mg/l	2.3
6	Turbidity	FNU	96
7	Total Dissolved Solid	ppm	3318.2
8	Ammonia	mg/l	0.5
9	BOD ₅	mg/l	1.2
10	COD	mg/l	ND
11	Cyanide	mg/l	ND
12	Fluoride	mg/l	0.29
13	Nitrate-Nitrogen	mg/l	36.4
14	Oil & Grease	mg/l	30
15	Sulfate	mg/l	164
16	Sulfide	mg/l	ND
17	Suspended Solids	mg/l	23.6
18	Total Hardness	mg/l	313
19	Total Organic	mg/l	4.42
20	Total Coliform	MPN/100ml	7.8

26

26

ရေအရည်အသွေး

သက်ရောက်မှု ဖြစ်စေနိုင်သော အကြောင်းရင်းများ	<p>ခေါ်ပြုမှု၊ ရေအသုံးပြုမှုသည် -</p> <ul style="list-style-type: none"> ပန်တန်နှင့် အလုပ်သမားများမှ ရေသုံးစွဲမှု ဘိလပ်မြေဖျက်ခံရမှု ရေအသုံးပြုမှု ဇန်နဝါယာလ်လမ်း၊ ရေလောင်းခြင်း နှင့် မြေပြင်ခြင်းလုပ်ငန်းများ ၊ ဆောက်လုပ်ရေးသုံးယာဉ်များ ဆေးကြောခြင်း နှင့် လုပ်ငန်းခွင်နေရာ သန့်ရှင်းရေးလုပ်ခြင်း စီးသတ်နစ်အတွက် ထားရှိခြင်း <p>ပတ်ဝန်းကျင်ဆိုင်ရာ ထည့်သွင်းစဉ်းစားချက် ၊ ပန်းကုင်ရေကို ဆောက်လုပ်ရေးနှင့် နေရာရှင်းလင်းရေး လုပ်ငန်းများ ၊ အလုပ်သမားများမှ ထွက်သော စွန့်ပစ်ရေ ၊ မောင်းအေးရင်းလုပ်ငန်းများအတွက် ပိုက်လိုက်ခြင်း ၊ စီမံကိန်းလုပ်ပတ်ချိန်တွင် မတော်တဆ ဖိစီးစိတ်ဓါတ်ခြင်းများ ဖျက်နားခြင်းရေနှင့် မြေအောက်ရေထဲသို့ စွန့်ပစ်ရေများ ၊ နေရာပြင်ဆင်ခြင်းများ ၊ စက်ဆီ ချောဆီများ မတော်တဆ စိတ်စင်းမှုများ ပါဝင်ရောက်နိုင်ပါ သည်။ မြေအောက်ရေသည် ပိုက်လိုက်ခြင်းလုပ်ငန်းများ ၊ စက်ဆီ ချောဆီများ မြေကြီးထဲသို့ စိမ့်ဝင်ခြင်းများ သက်ရောက်စေနိုင်ပါသည်။ ထိုသက်ရောက်မှုများသည် တူးမြောင်းထဲမှရေကို ဆောက်လုပ်ရေးအတွက် အသုံးပြုသော သမားကို ကျန်းမာရေး ထိခိုက်စေနိုင်ပါသည်။</p>
ပမာဏ	မထူပြော နည်း ၊ အလယ်အလတ် ၊ မြင့် ၊ အလွန်မြင့်
အချိန်ကာလ	<p>တိုက်ရိုက်ဆိုင်ရာခြင်း မြေရေ ချောင်းရေများသည် ဆောက်လုပ်ရေးလုပ်ငန်းများဖြစ်သော မောင်းအေးရင်းလုပ်ငန်း နှင့် မြေပြင်ခြင်းလုပ်ငန်းများမှ စွန့်ပစ်ရေများကို စီးသွယ်ရာ ရှိပါသည်။ ဆောက်လုပ်ရေး လဟာပြင်နေရာမှ ဘိလပ်မြေဖျက်ခံရမှု နှင့် ကွန်ကရစ်အိမ်များသည်လည်း မိုးရွာသည့် အချိန်တွင် မိုးရေနှင့်အတူ စီးသွယ်လာမှု ရှိပါသည်။ မြေအောက်ရေများလည်း ပိုက်လိုက်ခြင်းလုပ်ငန်းများ၊ စက်ဆီ ချောဆီများ မတော်တဆ စိတ်စင်းမှု မြေကြီးထဲသို့ စိမ့်ဝင်ခြင်းအားဖြင့် ထိခိုက်နိုင်စွယ်ရာ ရှိပါသည်။</p> <p>တိုက်ရိုက်ဆိုင်ရာခြင်း မြေရေ ချောင်းရေများသည် ဆောက်လုပ်ရေးလုပ်ငန်းမှာ ၂-၅ နှစ်အတွင်းတွင်သာ ဖြစ်၍ သက်ရောက်မှုမှာ ယာယီသာ ဖြစ်နိုင်ပါသည်။</p>
အတိုင်းအတာ	<p>၀-၁ နှစ်အတွင်း ၊ ၁-၅ နှစ်အတွင်း ၊ ၆-၁၅ နှစ်အတွင်း ၊ တစ်သက်တာ ၊ စီမံကိန်းကော်မရှင်ချုပ်ချုပ်</p> <p>တိုက်ရိုက်ဆိုင်ရာခြင်း ဆောက်လုပ်ရေးလုပ်ငန်းမှာ ၂-၅ နှစ်အတွင်းတွင်သာ တစ်ခါတစ်ရံတွင် တူးမြောင်းအောက်ပိုင်း ၊ ဆောက်လုပ်ရေးလုပ်ငန်းအောက်ကန် တွင် ပိုက်လိုက်ခြင်းလုပ်ငန်းများ ရေများကြောင့် ရေနေကန်ကန်နေမှုများ တွေ့ရှိနိုင်ပြီး ဤသက်ရောက်မှုသည် တူးမြောင်းရေကို ဆောက်လုပ်နေသူ များ ရှိပါက ၎င်းတို့အပေါ်တွင် ထိခိုက်နိုင်ပါသည်။</p>
ဖြစ်နိုင်ခြေ	<p>ဖြစ်နိုင်ခြေ အလွန်နိမ့် ၊ ဖြစ်နိုင်ခြေ နိမ့် ၊ ဖြစ်နိုင်ခြေ မြင့် ၊ ဖြစ်နိုင်ခြေ အလွန်မြင့်</p> <p>တိုက်ရိုက်ဆိုင်ရာခြင်း မြေရေ ချောင်းရေများသည် ဆောက်လုပ်ရေးသုံး စက်ကိရိယာများ ယာဉ်များကို ဆေးကြောခြင်း နှင့် မြေကွဲခြင်း မြေ ညှိခြင်း စသော ဆောက်လုပ်ရေးလုပ်ငန်းများကြောင့်လည်း ညစ်ညမ်းနိုင်ပါသည်။ ဆောက်လုပ်ရေးနေရာအောက်ပိုင်း တူးမြောင်းအောက်ရှိလူများ သည် ထိုလုပ်ငန်းများ လုပ်နေချိန်နှင့် စက်ဆီ ချောဆီများ မတော်တဆ စိတ်ကျရာမှ ဤသက်ရောက်မှုကို စီးသွယ်နိုင်စွယ် ရှိပါသည်။</p>
သက်ရောက်မှု အဆင့်	<p>Magnitude (4) + Duration (2) + Extent (1) * Probability (3) = 21</p> <p>နည်း (U)</p>

27

27

ရေအရည်အသွေးအပေါ် သက်ရောက်မှု လျော့ပါးစေရေးနည်းလမ်းများ

- ပိတ်ဆို့ နေသော နေရာများအား ယာယီရေစီးမြောင်းများ သွယ်ကာ စီးဆင်းစေခြင်း
- အန္တရာယ်ရှိသော စွန့်ပစ်ပစ္စည်းများအတွက် အမှိုက်ပုံးများထားရှိခြင်း ၊ စွန့်ပစ် အရည်များ မြေကြီးနှင့် မြေအောက်ရေထဲ သို့ စိမ့်ဝင်မှုမရှိစေရန် ကာကွယ်ခြင်း
- အန္တရာယ်ရှိသော ပစ္စည်းများကို သိုလှောင်ရာတွင် မစိမ့်ဝင်နိုင်သော ကြမ်းပြင် ၊ အမှိုက်အကာနှင့် သင့်လျော်သော နေရာထားသို့မှ နှင့် ရေမြောင်းသွယ်တန်းမှ စနစ် ထားရှိခြင်း
- ပြုပြင်ထိန်းသိမ်းရေး နှင့် စက်ပစ္စည်းများ နှင့် မော်တော်ယာဉ်များကို ပုံမှန်စစ်ဆေးခြင်းအားဖြင့် စက်ဆီ ချောဆီများ ယိုစိတ်မှု များကို လျော့နည်းစေခြင်း
- မျက်နှာပြင်ရေနှင့် မြေအောက်ရေထဲသို့ မသန့် စင်သောရေများ စီးဝင်မှု မရှိအောင် ကာကွယ်ခြင်း
- ဆောက်လုပ်ရေးလုပ်ငန်းမှ မြေကြီးများ ၊ ဘိလပ်မြေဖျက်ရည်များ ၊ ဆီ နှင့် အခြား စွန့်ပစ်ပစ္စည်းများ ၊ လုပ်ငန်းခွင်တွင်း အမှိုက်စုပုံမှုများ ရှိနိုင်သောကြောင့် စက်ကိရိယာများကို ရေဆေးခြင်းကို တင်းကြပ်ခြင်း နှင့် လုပ်ငန်းခွင်မှ မြေကြီးများဆုံး ရှုံးမှုကို ကာကွယ်ခြင်းအားဖြင့် ရေထုညစ်ညမ်းမှု မဖြစ်အောင် ကာကွယ်ခြင်း
- ပစ္စည်းများ သိုလှောင်မှု နှင့် ကိုင်တွယ်သုံးစွဲမှုတွင် သင်တန်းပေးထားသော ကျွမ်းကျင်သော ပန်တန်ကိုင်သူ လုပ်ကိုင်စေ ခြင်း နှင့် စိတ်စင်းမှုများကို ချက်ချင်းပြန်လည်သန့်စင်စေခြင်း



28


28

<p>၁) အနုပညာရှိမသော စွန့်ပစ်ပစ္စည်းများ</p> <ul style="list-style-type: none"> ကုန်ကုန်ရေ အတိမ်၊ ကြေးသွယ်၊ မြေသွယ် ပစ္စည်းများ သစ်သား၊ ဇရံ နှင့် ပလတ်စတစ်များ (စွန့်ပစ်ပစ္စည်းများထည့်ထားသော၊ ထုပ်ပိုးပစ္စည်း၊ ပလတ်စတစ်နီရိုပ်ပတ်ထားသော ဂီကုန်များ အားလုံး အကုန်ပလိသည့်) သေနင်္ဂ၊ ဖိစပ်ပစ္စည်း၊ ကြေးနီ၊ သံထည်၊ စတား၊ ဒဏ်၊ ကြေးဝါ၊ သတ္တုစပ်ပစ္စည်းများ၊ ခဲ၊ ကော်ကွက်တိုများ နှင့် သတ္တုများ မြေကြီးခဲ၊ ကျောက်တုံးကျောက်ခဲများ နှင့် အခြား အပျက်အစီးများ ကွပ်ပဆမ် (သုံးခဲများ) ကဒီထုပ်ပိုးများ ရည်ထည်၊ အဝတ်များ၊ ရှိတ်များ ထုတ်လုပ်ပြီးသော ပစ္စည်းများ 	<p>၃) ရှိမနေသည့်ပစ္စည်းများ</p> <ul style="list-style-type: none"> စာဂျာနယ် (တစ်ခါသုံးနှင့် အခြား) အသုံးပြုပြီးသော ကော့ဘုတ် ခဲတံများ ကဒီထုပ်ပိုးများ မုခ်အကြွင်းအကျန်များ <p>၄) ပုဂံသို့ကွယ်ပစ်ပစ္စည်းများ</p> <ul style="list-style-type: none"> အစားအသောက်များ၊ မကုန်မခန်းနိုင်အောင် ချက်ပြုတ်ခြင်း <p>၅) အခြားစွန့်ပစ်ပစ္စည်းများ</p> <ul style="list-style-type: none"> ဆီနှင့် အဆီများ ပုံနံ၊ စွန့်ပစ်ရသော နေ့စဉ်သုံး ပစ္စည်းများ
<p>၂) အနုပညာရှိမသော စွန့်ပစ်ပစ္စည်းများ</p> <ul style="list-style-type: none"> ကျောက်ဂွမ်းနံ၊ များ ဒီကွက်က ပစ္စည်းများ 	

- အမှိုက်များကို စောက်ယူသိမ်းဆည်းရာတွင် အမှိုက်အမျိုးအစားအလိုက် အမှိုက်ပုံးများကို ခွဲခြားထားခြင်း
- အမှိုက်ပုံးများကို အရောင်များ၊ စာတမ်းများ၊ ရေထိုးထားခြင်း၊ အန္တရာယ်ရှိသော စွန့်ပစ်ပစ္စည်းများကို အရောင်၊ ရှေးသုံး စွန့်ပစ်ပစ္စည်းများကို အရောင်၊ ပုံသုံးလွယ်ပစ္စည်းများကို အသီးရောင် အသင့်ခြင်း
- အမှိုက်ပုံးများကို အစုအထားချိုခြင်း
- သိမ်းဆည်းခြင်းနှင့် ကိုင်လွယ်ရာတွင် ပြည့်တွင်း ပြည့်ပ စည်းမျဉ်းစည်းကမ်းများဖြင့် ကိုက်ညီမှုရှိအောင် စီမံခြင်း
- အသားပြုထားသော ဆီများကို ပြန်လည် သုံးစွဲခြင်း
- မီးသတ်ကာကွယ်ရေးစနစ်ထားရှိခြင်း
- စွန့်ပစ်ပစ္စည်းများကို သင့်လျော်သော လိုင်စင်ရ စွန့်ပစ်ပစ္စည်း အဖွဲ့အစည်းများနှင့် ချိတ်ဆက် ဆောင်ရွက်ခြင်း
- သင့်လျော်သော စွန့်ပစ်ပစ္စည်း စွန့်ပစ်ရန် နေရာကို သတ်မှတ်ထားရှိခြင်း

29

30



30



ဝီထိမ်းနီနီကွဲများအပေါ် သက်ရောက်မှု ဆန်းစစ်ခြင်းနှင့် လေ့လာရေး နည်းလမ်း

31


[illegible]

Figure 5.6-1 Habitat map of the project ROW and indirect impact zone.

32

31

32

ဒီရေတော

ဒီရေတောများကို ရန်ကုန်မြစ် အနောက်ဘက်ကမ်းပါး၊ ခနောင်တိုရောင်းကမ်းပါးနှင့် တွဲတေးတူးမြောင်း တစ်လျှောက်တွင် တွေ့ရှိရပါသည်။ ဒီရေတောအပင်မှာ ယေဘုယျအားဖြင့် အမြင့် တစ်မီတာခွဲထက်ကျော်လွန်၍ ပင်လယ်ရေ မျက်နှာပြင် အထက်ရှိ အကူဝါ ကမ်းရိုးတန်း ပတ်ဝန်းကျင်နှင့် မြစ်ဝ တို့၏ ဒီရေရောက်ရန်တွင် ပေါက်ရောက်သည့် အပင်၊ ချုံပတ်အပင် ဖြစ်ပါသည်။ ဒီရေတောဆိုသည်မှာ အဆိုပါ အပင်၊ ချုံပင်များ စွဲ စည်းပါ သက်ရှိများပါဝင်နေသော နေထိုင်ရာ ဒီရေရောက် ဒေသတစ်ခု ဖြစ်ပါသည်။



No.	Scientific Name	Family Name	Vanicular Name	Habit
1	Acanthus ilicifolius L.	Acanthaceae	Khaya	S
2	Nyssa frutescens Wurmbe	Arecaceae	Dani	ST
3	Sonneratia caseolaris (L) Engl.	Sonneratiaceae	Lamu	T

တူးမြောင်းတစ်လျှောက်ရှိ ဒီရေတော အများစုမှာ DWIR မှ မြစ်ကမ်းပါးထိန်းသိမ်းရေးအတွက် စိုက်ပျိုးထားခြင်း ဖြစ်ပါသည်။

33

အပင်များ

ROW နှင့် ကြားခံရန်အတွင်းတွင် စိုက်ပျိုးခြင်း၊ ဒီရေတောနှင့် အပင်များ စိုက်ပျိုးထားသည့် နေရာဟူ၍ သက်ရှိများနေထိုင်ရာဒေသ (၂) ခု တွေ့ရှိရပါသည်။ ROW နှင့် ကြားခံရန်အတွင်းတွင် နဂါးအတိုင်းရှိနေသည့် သစ်တောဟူ၍ မတွေ့ရပါ။

တိုက်ရိုက်သက်ရောက်မှုရှိနိုင်သည့်ရန် နှင့် သွယ်ဝိုက်သက်ရောက်မှုရှိနိုင်သည့်ရန် အဖြစ် သတ်မှတ်ထားသည့် ကြားခံရန် ဧရိယာနှင့် ROW အတွင်းမှ အပင်မျိုးစိတ်ပေါင်း (၇၆) မျိုး ကောက်ယူ ရရှိခဲ့ပါသည်။ အပင်မျိုးစိတ်တစ်မျိုးဖြစ်သည့် ထန်းပင်မှာ IUCN ၏ ကမ္ဘာလုံးဆိုင်ရာ အန္တရာယ် စာရင်းဝင် အဖြစ် သတ်မှတ်ခံထားရသော်လည်း သစ်တောဦးစီးဌာနမှ ထုတ်ပြန်ထားသည့် မြန်မာ IUCN စာရင်းတွင် ဖော်ပြထားခြင်း မရှိသည့်ကို တွေ့ရပါသည်။

လေ့လာသည့် ဧရိယာမှ ခွဲခြားဖော်ထုတ်ထားသည့် အပင်မျိုးစိတ်များမှာ အတွေ့ရများသော အပင်မျိုးစိတ်များ ဖြစ်သည့်အတွက် ပတ်ဝန်းကျင်တန်ဖိုးအရ နိမ့်သည်ဟု ယူဆ၍ ရပါသည်။ သို့သော်လည်း ဆောက်လုပ်ရေး လုပ်ငန်းများ လုပ်ကိုင်နေစဉ်တွင် လုပ်ငန်းဆောင်ရွက်မည့် ဧရိယာ အတွင်းရှိ အပင်များမှာ ရှင်းလင်းခံရနိုင်ဖွယ် ရှိပါသည်။

သတ္တဝါများ

ကွင်းဆင်းလေ့လာချိန်အတွင်း လိပ်ပြာမျိုးစိတ် ၂၂ မျိုး၊ နို့တိုက်သတ္တဝါမျိုးစိတ် ၅ မျိုး၊ ကုန်းနေနေရန်နှင့် တွားတွားသတ္တဝါမျိုးစိတ် ၁၀ မျိုး၊ ငှက်မျိုးစိတ် ၅၅ မျိုး နှင့် ငါးမျိုးစိတ် ၂၃ မျိုးကို တူးမြောင်းဧရိယာမှ ကောက်ယူရရှိခဲ့ပါသည်။

IUCN Red List အရ ငါးဖယ်အောင်းသည် မျိုးသုဉ်းရန်အန္တရာယ်ကျရောက်လွန်းပါးမျိုးစိတ် တစ်ခုအဖြစ် သတ်မှတ်ထားသော်လည်း မြန်မာနိုင်ငံမှ ထုတ်ပြန်ထားသည့် ကာကွယ်ထားသည့် မျိုးစိတ်များ စာရင်းတွင် မပါရှိပါ။ မြန်မာနိုင်ငံတွင် တိုင်းရင်းသားအတွက် ငြိမ်းခြောက်မှုများမှာ မသိရှိရပါ။ အခြားမျိုးစိတ်များမှာ IUCN တွင် မျိုးသုဉ်းရန် အန္တရာယ်အဆင့် သတ်မှတ်ချက် မပြုရသေးသော မျိုးစိတ်များ ဖြစ်ပြီး ထိုဧရိယာတွင် ဒေသရင်း မျိုးစိတ်များ မတွေ့ရှိရပါ။

34

ဝီဝမျိုးစုံမျိုးကွဲများအပေါ် သက်ရောက်မှု ဆန်းစစ်ခြင်း				
သက်ရောက်မှု အရင်းအမြစ်	<p>မော်ဒယ်များ တူးမြောင်းတစ်လျှောက် စီတာ ၃၀ ROW အတွင်း ဆောက်လုပ်ရေး လုပ်ငန်းနှင့် မြေညှိခြင်းများ ဆောင်ရွက်ရန်အတွက် အပင်များရှင်းလင်းခြင်းနှင့် ကမ်းပါးရှင်းလင်းခြင်းများကြောင့် ပတ်ဝန်းကျင်ရှိ အပင်နှင့် သတ္တဝါများ ပါဝင်သည့် ဝီဝမျိုးစုံမျိုးကွဲများပေါ်တွင် တိုက်ရိုက် သက်ရောက်မှုများ ရှိပါသည်။ ဖေဖော်ဝါရီလတွင် လေ့လာမှုကို တိုက်ရိုက်သက်ရောက်မှု ဖြစ်နိုင်သည့် စီတာ ၃၀ ROW အတွင်း ဆောင်ရွက်ထားပါသည်။ တူးမြောင်းတစ်လျှောက် စီတာ ၃၀ အတွင်းရှိ အချို့နေရာများသည် ငါးလုပ်ငန်း၊ ကမ်းရိုးတန်းနှင့် အထွတ်မျိုးစိတ်များအတွက် အာဟာရထောက်ပံ့ပေးသည့် ကမ်းရိုးတန်းပေါက်စပ် ထိန်းသိမ်းခြင်း၏ သွန်သင်မှုကိုဖြစ်သော ဒီရေတောမျိုးစိတ်များ၊ ချုံပင်များနှင့် အပင်ယိုများဖြင့် ဖုံးလွှမ်းထားပါသည်။ ဒီရေတောများမှာ တာရိုက်နီကုတ်သို့သာ ပြင်းထန်သော ရာသီဥတုကို ဟန့်တားရန် ကမ်းရိုးတန်း တည်ရှိနိုင်ရန်နှင့် မြေဆီလွှာ တိုက်စားမှု လျော့ချရန် ကြားခံရန်အဖြစ် ဆောင်ရွက်ပေးပါသည်။</p> <p>သဘာဝပတ်ဝန်းကျင် စွန့်ပစ်မှုများ</p> <ul style="list-style-type: none"> မြေထိန်းမှု ဆောက်လုပ်ခြင်းနှင့် ကမ်းပါး ကာကွယ်ခြင်းများကြောင့် အပင်များနှင့် သတ္တဝါများ နေထိုင်ရာဒေသများ ဆုံးရှုံးခြင်း။ ရန်ကုန်မြစ်အတွင်း မြစ်ကြီးမြစ် တိုက်စားမှု ကာကွယ်ခြင်းနှင့် တွဲတေးတူးမြောင်း တည်ဆောက်ရေး လုပ်ငန်းများ ဆောင်ရွက်စဉ်ကာလအတွင်း မြစ်နှင့် တူးမြောင်းပေါက်စပ်အပေါ် သက်ရောက်မှုများ ရှိခြင်း။ တည်ဆောက်ရေး ကာလအတွင်း ယာဉ်ယန္တရား သွားလာမှုကြောင့် စီမံကိန်း ဧရိယာတွင်း သက်ရှိများနေထိုင်ရာဒေသများ နှောင့်ယှက်ခံရခြင်း။ သက်ရှိများနေထိုင်ရာဒေသများ အပြုတမ်း ဆုံးရှုံးခြင်းနှင့် ဒီရေတော အပါအဝင် မြေထိန်းမှု ဆောက်လုပ်ရေး လုပ်ငန်းအနီး ပတ်ဝန်းကျင်ရှိ သက်ရှိများနေထိုင်ရာဒေသများ နှောင့်ယှက်ခံရခြင်း။ 			
ပမာဏ	တူးမြောင်းမရှိ	န	အလယ်အလတ်	မြင့်
အချိန်ကာလ	အချိန်ကျ: တည်ဆောက်ရေး ဧရိယာအတွက် အပင်ရှင်းလင်းခြင်း ဆောင်ရွက်မည့် တူးမြောင်းတစ်လျှောက် စီတာ ၃၀ ကို တိုက်ရိုက်သက်ရောက်မှုရှိ အဖြစ် ထည့်သွင်း စဉ်းစားထားပါသည်။ စီတာ ၃၀ ROW အတွင်းတွင် အပင်ယိုများ၊ ချုံပင်များ နှင့် ဒီရေတော အပင်များ ဖုံးလွှမ်းမှုကိုပါထည့်သွင်း တိုက်ရိုက်သက်ရောက်နိုင်သော ROW နှင့် သွယ်ဝိုက်သက်ရောက်နိုင်သော ROW အတွင်းတွင် အသားတစ်စုံတစ်ရာများ မရှိပါ အသားကြောင်ဆီသော အဆိုပါ ဧရိယာသည် လူနေအိမ်များနှင့် နီးကပ်သောကြောင့် ဖြစ်ပါသည်။	၂၅ နှစ်	၆-၁၅ နှစ်	စီမံကိန်း ရှိနေသမျှကာလပတ်လုံး
အတိုင်အတာ	အချိန်ကျ: တည်ဆောက်ရေးကာလမှာ အဆိုပါ အစီအစဉ်တွင် ၂၅ နှစ် ကြာမြင့်ပါသည်။ တည်ဆောက်ရေးကာလအတွင်းတွင်သာ ယာယီ သက်ရောက်မှုများ ရှိလိမ့်မည်။	သတ်မှတ်သောသေချာရာ	သတ်မှတ်သောသေချာရာ	သတ်မှတ်သောသေချာရာ
မြစ်နိုင်ငံချေ	အချိန်ကျ: တိုက်ရိုက်သက်ရောက်မှုမရှိဟန် စီတာ ၃၀ ROW နှင့် သွယ်ဝိုက်သက်ရောက်မှုရှိ စီတာ ၂၀ အတွင်းတွင်သာ အမြင့်ပိုင်းဆိုင်ရာ သက်ရောက်မှုသာ ဖြစ်နိုင်ပါသည်။	မြစ်နိုင်ငံချေ အလွန်မရှိ	မြစ်နိုင်ငံချေ	မြစ်နိုင်ငံချေ အလွန်မရှိ
သက်ရောက်မှုအဆင့်	အချိန်ကျ: အပင်ရှင်းလင်းခြင်း လုပ်ငန်းဆောင်ရွက်မည့် စီတာ ၃၀ ROW အတွင်းတွင်သာ သက်ရောက်မှု ပြင်းထန်သည်။	Magnitude (4) + Duration (2) + Extent (2) * Probability (4) = 32		အလယ်အလတ် (C)

လျော့ချရေး နည်းလမ်းများ

- ဆောက်လုပ်ရေး လုပ်ငန်းခွင်တွင် အပင်များရှင်းလင်းရေး နှင့် နေရင်းဒေသများ နှောင့်ယှက်ခံရမှုကို နည်းပါးစေရန် အပင်ရှင်းလင်းမည့် နယ်နိမိတ် သတ်မှတ်၍ ဆောင်ရွက်ရမည်။
- မလိုအပ်ဘဲ အပင်ရှင်းလင်းခြင်းများ ရှောင်ရှားရမည်။
- ဒေသ ဝီဝမျိုးစုံမျိုးကွဲများ ထိန်းသိမ်းရန်အတွက် အလုပ်သမားအားလုံးကို ပတ်ဝန်းကျင်နှင့် သက်ဆိုင်သော သင်တန်းများပေးခြင်းနှင့် စီမံကိန်း ဧရိယာ၏ သဘာဝ သဘာဝကို မိတ်ဆက်ပေးခြင်း
- တာဝန် နှင့် ROW တစ်လျှောက် အပင်များပြန်လည် စိုက်ပျိုးမည့် အစီအစဉ် ရေးဆွဲထားရမည်။
- ဆောက်လုပ်ရေး စခန်းများရှိ အလုပ်သမားများကို စီမံကိန်း ဧရိယာ အနီးရှိ ရေအရင်းအမြစ်များတွင် ငါးဖမ်းခြင်းများ မပြုလုပ်ရန် တင်းကြပ်စွာ တားမြစ်ရမည်။

➢ တူးမြောင်း ဧရိယာအတွင်းရှိ ဒီရေတောများ ပျံ့နှံ့မှုမှာ ဟိုတစ်ခု ဖြစ်၍ ဒီရေတော မျိုးစိတ် ၃ မျိုး ကောက်ယူရရှိခဲ့ပါသည်။ တူးမြောင်းတစ်လျှောက်ရှိ ဒီရေတောအများစုမှာ DWIR မှ မြစ်ကမ်းပါး ကာကွယ်ရန်အတွက် စိုက်ပျိုးထားခြင်း ဖြစ်ပါသည်။

➢ DWIR သစ်တောဦးစီးဌာန နှင့် ပတ်ဝန်းကျင် ထိန်းသိမ်းရေး ဝန်ကြီးဌာနတို့နှင့် ပူးပေါင်း၍ ပျိုးခင်းတွင် တည်သော မျိုးစိတ်များ ပျိုးထောင်ပြီး ပြန်လည်စိုက်ပျိုးခြင်း ကဲ့သို့သော ဒီရေတောများပြန်လည်စိုက်ပျိုးမည့် အစီအစဉ်များကို အကောင်အထည်ဖော်ရမည်။

36

သဘာဝဘေးအန္တရာယ်သက်ရောက်မှုများကို လန်စစ်ခြင်း- ကောင်းကျိုး၊ မြင့်မား				
သက်ရောက်မှု အရင်းအမြစ်	<p>တို့ဘေးကွပ်းခြင်း၊ အန္တရာယ်များကို အခွင့်အလမ်းတောင်းခံသည့် အခွင့်အလမ်းများသည် ရေကြီးမှုများ၊ မကြာခဏ ဖြစ်ပေါ်လေ့ရှိပါသည်။ ထိုစိမ်းကန်များသည်လည်းကောင်း၊ ဆိပ်ကမ်းများနှင့်လည်းကောင်း၊ အလယ်အလတ် နှင့် တွေ့ဆုံနေသည့် နယ်များမှာ နှစ်စဉ်ရေကြီးမှု အကျိုးခံစားရနိုင်ပါသည်။ မုန်တိုင်း နှင့် လေပြင်းတိုင်းများလည်း ဘေးကင်းနိုင်ပါသည်။</p> <p>တို့ဘေးကွပ်းခြင်း၊ တစ်လျှောက် ခြေမီလျှောက် တိုက်ခတ်ခြင်း နှင့် ကမ်းရိုးတန်းကာကွယ်ခြင်းတို့သို့ဘေး ကောင်းကျိုးလက်ကောက်သက်ရောက်မှုများ ရရှိနိုင်ပါသည်။</p>			
ပမာဏ	မတူခြင်း	နည်း	အလယ်အလတ်	မြင့်
အန္တရာယ်	<p>အန္တရာယ် စိမ်းကန် အပိုင်း ၁ သည် ရေကြောင်းထိန်းသိမ်းခြင်းနှင့် ကမ်းရိုးတန်းကာကွယ်ခြင်း တစ်ခုပါသည်။ စိမ်းကန်အပိုင်း ၁ စီ အဓိက ကောင်းကျိုးများ ရရှိကုန်တိုင်းအသင့်ကြိုအတွင်း လူမှု စီးပွားတိုးတက်ရေးနှင့် မြစ် ဖြူ တွေ့ဆုံနေသည့်အခြေအနေတစ်လျှောက် စိတ်ချပုံရိပ် ရှိသော ကုန်တွင်းရေလမ်းဆုံနယ်များ ပေါ်ပေါက်လာစေ ရေး ဖြစ်ပါသည်။</p> <p>၁၀ နှစ် ၂၅ နှစ် ၆၀ နှစ်</p>			
အချိန်ကာလ	၁၀ နှစ်	၂၅ နှစ်	၆၀ နှစ်	စိမ်းကန် နှင့်သမ္မတ ကမ်းရိုး တစ်ခုပါသည်။
	<p>အန္တရာယ် တည်ဆောက်ရေးကဏ္ဍမှာ အချိန် အစီအစဉ်တွင် ၂၅ နှစ် ကြာမြင့်မည်။ တည်ဆောက်ရေးကဏ္ဍအတွင်းတွင်သာ လာသံ သက်ရောက်မှုများ ရှိနိုင်ပါသည်။</p>			
အတိုင်းအတာ	<p>သတ်မှတ်ထားသောနေရာ သတ်မှတ်နေရာအတွင်း သတ်မှတ်နေရာအတွင်း နိုင်ငံအတွင်း နိုင်ငံအပြင်</p>			
ဖြစ်နိုင်ချေ	<p>အန္တရာယ် ကုန်တွင်းတည်ရှိရာ ဆိပ်ကမ်းများနှင့် တွေ့ဆုံသော အလယ်အလတ် နှင့် တွေ့ဆုံနေသည့် နယ်များမှာ နှစ်စဉ်ရေကြီးမှု အကျိုးခံစားရနိုင်ပါသည်။</p> <p>မြစ်နှင့်မြေ အလွန်မြင့် မြစ်နှင့်မြေမြင့် မြစ်နှင့်မြေမြင့် မြစ်နှင့်မြေမြင့်</p>			
အန္တရာယ်	<p>အန္တရာယ် စိမ်းကန်တည်ရှိရာ နယ်မြေအတွင်းတွင် သေဆုံးမှုများ သက်ရောက်မှုများ ရှိနိုင်ပါသည်။</p>			
သက်ရောက်မှုအဆင့်	<p>Magnitude (4) + Duration (4) + Extent (3) * Probability (5) = 55</p>			

၃ ဆုံးတန်း စကားတန်းများကို ဖြုတ်သန့်စစ်ခြင်း

[illegible]

မြိုင်ကွင်းသဘာဝ	စိမ်းကုန်း၊ စိတာ ၃၀ အတွင်းရှိ လူနေထိုင်မှုများအား ခုတ်ထွင်ပစ်ပြီး လင်းရောင်မြိုင်စေသောကြောင့် မြိုင်ကွင်းအနည်အင်းများ ပြောင်းလဲပုံသားနိုင်ပါသည်။	3	2	1	3	18 (-)	✓	
ယဉ်ကျေးမှုအမွေအနှစ်	စိမ်းကုန်း၊ စိတာ ၃၀ အတွင်းတွင် ယဉ်ကျေးမှု အမွေအနှစ် အဆောက်အအုံများ မရှိပါ။	1	2	1	1	4		✓
လူမှုစီးပွား	စိမ်းကုန်းအဆောက်လုပ်ရေးနေရာများတွင် မြေယာသိုင်းမြို့နယ်နှင့် စိမ်းကုန်းသော ပြောင်းရွှေ့ များ ကြုံတွေ့ ချိတ်ပါသည်။	4	4	3	5	35 (-)	✓	
သဘာဝ ဓာတ်အမွေအနှစ်	စိမ်းကုန်းလုပ်ငန်းများကြောင့် မည်သည့်သဘာဝသောအန္တရာယ်နှင့်မျှ ဟက်ဆက်ဆက်နွယ်လိမ့် မည်။ နှစ်စဉ်ရေကြီးမှု သဘာဝသောအန္တရာယ်ပင် လေ့ရှိပြီးသက်သာသောနေ့ရက်ပါသည်။	1	2	1	1	4		✓
လုပ်ငန်းများ ကျိုးပဲ့မှုအစွေ	စိမ်းကုန်းအဆောက်လုပ်ရေးနေရာများတွင် မြေယာသိုင်းမြို့နယ်နှင့် စိမ်းကုန်းသော ပြောင်းရွှေ့ များ ကြုံတွေ့ ချိတ်ပါသည်။	3	2	4	3	27 (-)	✓	
လူထုကျန်းမာရေး	စိမ်းကုန်းအဆောက်လုပ်ရေးနေရာများတွင် မြေယာသိုင်းမြို့နယ်နှင့် စိမ်းကုန်းသော ပြောင်းရွှေ့ များ ကြုံတွေ့ ချိတ်ပါသည်။	3	2	1	3	18 (-)	✓	

(+) = Positive Impact
 (-) = Negative Impact
 No Remark (+ nor -) = Neutral
 <15 = No Impact

Overall event magnitude is scored from low (15) to very high (>60) by adding the individual parameter scores:

-	No Impact	U (Low)	G (Moderate)	B (High)	A (Very High)						
5	10	15	20	25	30	35	40	45	50	55	60

40

10

ကောင်းကျိုးများကို ဆန်းစစ်လေ့လာခြင်း

ဆန်းစစ်ရန်များ	Descriptions	M	D	E	P	စီမံကိန်းလုပ်ဆောင်ကြီးကြပ်မှု	လျော့ချစေရန်လမ်းညွှန်များ	
							လို	မလို
သဘာဝ ဘေးအန္တရာယ်	စီမံကိန်းတွင် မြစ်ကြောင်းထိန်းသိမ်းရေး၊ ရေတိမ်းမဲ့ နှင့် ရေကြီးမှု ကာကွယ်ရေး ဆောက်လုပ်မှုလုပ်ငန်း များကြောင့် ရာသီဥတု ကွဲလွဲမှုများတွင် မြစ်တဝှမ်း သော အသံတွင်း နှစ်စဉ်ရေကြီးမှုမှာ လျော့ပါးသက် သာသွားနိုင်ပါသည်။	4	4	3	5	55 (+)		✓
လူမှု ဆက်သွယ်ရေး	အသံသယအချို့ကို ဆောက်လုပ်ရေးလုပ်ငန်းများ၊ ကုန်တွင်းရေကြောင်းရေသွားလေ့များမှာပင် အ လုပ်အကိုင်အစဉ်အလမ်းများ၊ ဝန်ဆောင်မှု၊ လူမှုစီး ပွားသဘာဝများ ဖွံ့ဖြိုးတိုးတက်လာစေနိုင်ပါသည်။ တုံ့ပြန်မှုများမှာ သက်တမ်းရှည်တိုတိုသက်ရောက်မှု စီမံကိန်းကြောင့် ရေကြောင်းရေသွားလေ့များတွင် ရေ ကြောင်းသွားလာရေး နှစ်စဉ်ကောင်းမွန်လာပြီး ယခင် ထက် လုံခြုံစိတ်ချရသော သွားလာမှုပုံစံ ဖြစ်သော ကြောင့် အသက်အရွယ်အရွယ် ဖြစ်ပွားမှုများ လျော့ နည်းလာနိုင်ပြီး အသံတွင်း ဖွံ့ဖြိုးတိုးတက်စေနိုင်ပါ သည်။	4	4	2	5	50 (+)		✓
မြေထိခိုက်မှု	စီမံကိန်းတွင် ကမ်းထိန်းနံရံ တည်ဆောက်မှု ပါဝင် သောကြောင့် တူးမြောင်းတစ်လျှောက်တွင် မြေပြိုမှု များ နောက်ထပ်ကြိမ်တွင် ဖြစ်ပွားနိုင်ပါသည်။ အသံတွင်း နှစ်စဉ်သို့ ပြည်သူများအချို့တွင် စီမံ ကိန်း၏ CSR လုပ်ငန်းအကောင်အထည်ဖော် ဆောင်ရွက်မှုများမှ တဆင့် ဆေးကုသရေးနှင့် သက်ဆိုင်သော စောင့်ရှောက်မှု အစရှိသော ကောင်းကျိုးများအား လက်ခံရရှိနိုင်ပါသည်။	3	4	1	4	32 (+)		✓
မြေထိခိုက်မှု ကျိုးအန္တရာယ်	အသံတွင်း CSR လုပ်ငန်းအကောင်အထည်ဖော် ဆောင်ရွက်မှုများမှ တဆင့် ဆေးကုသရေးနှင့် သက်ဆိုင်သော စောင့်ရှောက်မှု အစရှိသော ကောင်းကျိုးများအား လက်ခံရရှိနိုင်ပါသည်။	3	4	3	3	30 (+)		✓

အခြားသက်ရောက်နိုင်မှုများကို ဆန်းစစ်ခြင်း နှင့် လျော့ချရေး နည်းလမ်းများ

နယ်နိမိတ်စည်းခြားသက်ရောက်မှု

- နိုင်ငံတကာမှ အလုပ်သမားနှင့် ပစ္စည်းများ၊ ဝန်ဆောင်မှုများ ရှိလာနိုင်ပါသည်။ ဆက်စပ်သက်ရောက်မှုမှာ -
- အခြားသော စီမံကိန်းများမှ ကြွင်းကျန်သက်ရောက်မှုများ
- အခြားစီမံကိန်းများမှ သက်ရောက်မှုများနှင့် ပေါင်းစပ်သွားခြင်း

ဆက်စပ်သက်ရောက်မှု

- အချိန်ထပ်တူကျခြင်း
- နေရာထပ်တူကျခြင်း

ဆုံးရှုံးမှု အန္တရာယ် လျော့နည်းစေရေး အစီအစဉ်

- အခြေခံအကြောင်းရင်းဖြစ်ကို ရှာပြီး အန္တရာယ်စီမံခန့်ခွဲရေး လုပ်ငန်းစဉ်တွင် အစောပိုင်းထဲက ထည့်သွင်း စဉ်းစားထားခြင်း
- ဘေးအန္တရာယ်များ ဆက်စပ်မှုနှင့် အကြောင်းရင်းဖြစ်ကို အကဲဖြတ်ခြင်း
- အခြားလျော့ပါးစေရေးနည်းလမ်းများ၊ နည်းစနစ်များ နှင့် ပစ္စည်းများကို သတ်မှတ်ခြင်း
- လျော့ပါးစေရေးနည်းလမ်းများကို ဆန်းစစ်ခြင်း
- သီးခြား ဘေးအန္တရာယ် လျော့ပါးစေရေးနည်းလမ်းများကို ရွေးချယ် အသုံးပြုခြင်း
- စီမံကိန်း အကောင်အထည်ဖော်ဆောင်ရာတွင် ပါဝင်သက်ဆိုင်သူများအားလုံးကို အစီအစဉ်ထားရှိမှုများအား အကြောင်းကြားထားခြင်း

ဆက်လက်လုပ်ဆောင်ရမည့် လုပ်ငန်းစဉ်များ

Phase	Main Task	Process Plan (8 months)							
		Month 1	Month 2	Month 3	Month 4	Month 5	Month 6	Month 7	Month 8
1 step	Establishing ESIA implementation plan through preliminary survey								
2 step	Project Proposal Submission								
	Scoping investigation & stakeholder analysis								
	Information disclosure and public consultation (1st)								
	Scoping and TOR writing and submission								
3 step	ESIA Investigation								
	Information disclosure and public consultation (2nd)								
4 step	Drafting ESIA report								
	ESIA report review and approval (by MONREC)								
	Report Plan								
	Mission to Myanmar								

- ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာမူကြမ်းပြုစုခြင်း
- အစီရင်ခံစာမူကြမ်းအားပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဦးစီးဌာနသို့ တင်သွင်းခြင်း
- အစီရင်ခံစာမူကြမ်းအား အများပြည်သူသိရှိရန် ထုတ်ဖော်ခြင်း
- အစီရင်ခံစာမူကြမ်းအားသုံးသပ်ခြင်းနှင့် အတည်ပြုခြင်း (ECD)
- ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဦးစီးဌာနမှ အတည်ပြုခြင်း

ကျေးဇူးအထူးတင်ရှိပါသည်။



**တံတားတူးမြောင်း
မြစ်ချောင်းများဖွံ့ဖြိုးဘက်စုံတိုးတက်ရေးစီမံကိန်း
သဘာဝပတ်ဝန်းကျင် နှင့် လူမှုပတ်ဝန်းကျင်
ဆန်းစစ်လေ့လာခြင်း**


**သက်ဆိုင်သူများနှင့်ဒုတိယအကြိမ်
တွေ့ဆုံခြင်းအစည်းအဝေး**

၂၆.၁.၂၀၁၉

1



2



3

အများပြည်သူနှင့် တိုင်ပင်ဆွေးနွေးခြင်းနှင့် အများပြည်သူတို့ သတင်းအချက်အလက်ထုတ်ဖော်တင်ပြခြင်း


EIA အစီရင်ခံစာ ပြင်ဆင်ချိန်ကာလအတွင်း

စီမံကိန်းအဆိုပြုသူသည် အောက်ဖော်ပြပါ တိုင်ပင်ဆွေးနွေးမှုလုပ်ငန်းစဉ်ကို ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအတွက် စုံစမ်းစစ်ဆေးခြင်း၏ အစိတ်အပိုင်းအဖြစ် ဆောင်ရွက်ရမည်။


(က) အဆိုပြုစီမံကိန်း၊ ယင်း၏ဆိုးကျိုးသက်ရောက်မှုများနှင့် သက်ဆိုင်သော သတင်းအချက်အလက်များကိုအများပြည်သူနှင့်လူမှုအဖွဲ့အစည်းများသိရှိနိုင်စေရန် ဖြစ်စေရန် သက်ဆိုင်ရာအဖွဲ့အစည်းနှင့် နိုင်ငံပိုင်မီဒီယာများမှ လည်းကောင်း၊ စီမံကိန်းသို့ မဟုတ် စီမံကိန်းအဆိုပြုသူ၏ ဝက်သ်ဆိုက်မှလည်းကောင်း စာကြည့်တိုက်များ၊ ပြည်သူ့ ခန်းမများစသည့်အများပြည်သူဆိုင်ရာနေရာများတွင်လည်းကောင်း စီမံကိန်းလုပ်ငန်းနေရာတွင် အများပြည်သူအောင် ဆင်းဘုတ်များ ဖွဲ့စည်းလုပ်ငန်းလည်းကောင်း၊ အခြားသင့်လျော်သော နည်းလမ်းဖြင့်လည်းကောင်း သတင်းစာရှင်းလင်းပွဲများ တွေ့ဆုံဆွေးနွေးခန်း ပြုလုပ်၍လည်းကောင်းအချိန်နှင့် တစ်ပြေးညီဖော်ထုတ်တင်ပြခြင်း

(ခ) စီမံကိန်းကြောင့် ထိခိုက်စားရသူများ အုပ်ချုပ်ရေးအဖွဲ့အစည်းများ၊ ရပ်ရွာအခြေပြ အဖွဲ့အစည်းများ၊ လူမှုအဖွဲ့အစည်းများပါဝင်သည့် အမျိုးသားအဆင့်၊ နေပြည်တော်ကောင်စီနယ်မြေ၊ တိုင်းဒေသကြီး သို့မဟုတ် ပြည်နယ်အဆင့်နှင့် ဒေသအဆင့် တိုင်ပင်ဆွေးနွေးပွဲများ စီစဉ်ကျင်းပခြင်း။


4




5



6



7



8

ကြည့်မြင်တိုင်မြို့နယ်

ကျေးရွာ/ရပ်ကွက်	အိမ်ထောင်စု	အဆောက်အအုံ ပိုင်ရှင်	မြေပိုင်ရှင်	စုစုပေါင်း
ငဇင်	66	53	21	74
ဦးမြား	67	60	12	72
ဆိပ်ကြီး	190	188	18	206
စုစုပေါင်း	323	301	51	352


13

ဇရိယာ - ခ



14

ဇရိယာ - ည




15

ဇရိယာ - ဃ



16

တွံတေးမြို့နယ်



17

ဆိပ်ကြီးခနောင်တိုနှင့်ကြည့်မြင်တိုင်မြို့နယ်



18

ဒလဆိပ်ကြီးခနောင်တိုမြို့နယ်



19

လူမှုစီးပွားစစ်တမ်းကွင်းဆင်းကောက်ယူခြင်း


မြို့နယ်အလိုက် အိမ်အိမ်ခြေနှင့်လူဦးရေ

မြို့နယ်	အိမ်	အိမ်ထောင်စု	လူဦးရေ		
			ကျား	မ	စုစုပေါင်း
တွံတေး	၅၀၃၃၅	၅၂၉၃၅	၁၁၂၅၁	၁၁၅၅၈၅	၂၂၆၈၃၆
ဒလ	၂၂၅၇၃	၂၅၁၁၆	၈၄၆၇၁	၈၈၁၈၆	၁၇၂၈၅၇
ဆိပ်ကြီးခနောင်တို	၇၄၉၂	၇၈၉၀	၁၇၀၆၈	၁၆၉၃၅	၃၄၀၀၃
ကြည့်မြင်တိုင်	၁၃၀၀၁	၂၂၅၅၁	၅၂၆၂၇	၅၈၈၈၇	၁၁၁၅၁၄


20

မြို့နယ်	စီမံကိန်းသက်ရောက်မည့်သူများ (ခန့်မှန်း)	နမူနာကောက်ယူခြင်း
တွံတေး	၂၇၉	၉၃
ဒလ	၇၁၇	၇၇
ဆိပ်ကြီးခရောင်တို	၁၂၂၀	၁၆၀
ကျည်မြင်တိုင်	၃၅၂	၂၃


21




22




23




24




25




26




27




28




29




30




31




32




33




34




35




36




37




38



39



40



41


အုပ်စုလိုက်ဆွေးနွေးခြင်း Focus Group Discussion, FGD

No.	နေ့စွဲ	
1	30.10.2018	တာကြီးရပ်ကွက်ဒေသမြို့နယ် #
2	31.10.2018	ပျော်ဘွယ်လေးရွာတွဲတေးမြို့နယ်
3	1.11.2018	ဆိပ်ကြီး အနောက်ရပ်ကွက်၊ ဆိပ်ကြီးခရိုင်တိုမြို့နယ်
4	24.12.2018	လွန်းကျင်းလုပ်ငန်းရင်အသင်းဆိပ်ကြီးခရိုင်တိုမြို့နယ်
5	24.12.2018	လယ်သမားအစုအဖွဲ့၊ တွဲတေးမြို့နယ်

42




43




44

ကြည့်မြင်တိုင်မြို့နယ်




49



50

မြေနေရာနှင့် အဆောက်အအုံများ



51

လူမှုစီးပွားအပေါ် သက်ရောက်မှု ၁:

မြေနေရာ ဆုံးရှုံးမှု : သက်ရောက်မှုမရှိသော

- တူးမြောင်း နယ်နိမိတ် ၃၀ မီတာ အတွင်းရှိ မြေပိုင်ရှင်များသည် ၎င်းတို့၏ မြေနေရာနှင့် အဆောက်အအုံများကို ဆုံးရှုံးနိုင်ဖွယ် ရှာခြင်းပါသည်။

- ယခုလက်ရှိရှိ စစ်တမ်းများအရ တွေ့တား ၊ ဒလ ၊ ဆိပ်ငြိမ်းနေရင်းတို့ ၊ နှင့် ကြည့်မြင်တိုင် ၄ မြို့နယ်မှ စုစုပေါင်း အိမ်ထောင်စု ၂၀၈၉ စု ၊ အဆောက်အအုံပေါင်း ၂၀၈၉ ခု ၊ မြေပိုင်ရှင် ၅၁၇ ဦး ထိ ရှိနိုင်ရန် မျှော်မှန်းထားပြီး အသေးစိတ် တိုင်းတာခြင်း ပြုလုပ်ရန် နှင့် စီမံကိန်း အကောင်အထည်ဖော်ဆောင်ရွက်ရန် အခြား ဖြစ်နိုင်ခြေများကိုလည်း ဆန်းစစ်ရန် လိုအပ်ပါ သေးသည်။

- ဆောက်လုပ်ရေးကုလအတွင်း ဆောက်လုပ်ရေးနေရာ/မြေနေရာ : မြေယာများတွင် လယ်မြေများ ၊ လူနေအိမ်မြေများ ၊ သဘောကျမ်းများ ပါဝင်နိုင်ပါသည်။ သစ်တောမြေနှင့် အသုံးပြုထားခြင်း မရှိသောမြေများလည်း ပါဝင်နိုင်ပါသည်။

- စီမံကိန်းဖော်ဆောင်သူများအနေနှင့် ယခု တူးမြောင်းစီမံကိန်း မြေနေရာနှင့် မြေယာအသုံးချမှု ၊ ပြန်လည်နေရာချထားရေး အင်အားစုများကို ဆောက်လုပ်ထားရန် လိုအပ်ပါသည်။

Social Concern: The impact is likely to lead involuntary resettlement of those affected land/ structure and agricultural land owners. If the project is too long to implement than the expected schedule as in design prediction, the impact is likely to increase more and more for those affected persons.

ယဉ်ကျေးမှု	small	Moderate	High	Very High
အကျိုးအမြတ်	0-1 year	2-5 year	6-15 year	Life of operation
အကျိုးအမြတ်	Post Closure			
အကျိုးအမြတ်	Limited to the site	Limited to the local area	Limited to the region	National
အကျိုးအမြတ်	International			
ဖြစ်နိုင်ခြေ	Very improbable	Improbable	Probable	Highly probable
ဖြစ်နိုင်ခြေ	Definite			
သက်ရောက်မှုအဆင့်	Magnitude (5) + Duration (4) + Extent (2) * Probability (5) = 55			

52

လူမှုစီးပွားအပေါ်သက်ရောက်မှု ၂ :

သဘောကျင်းလုပ်ငန်းများ - သက်ရောက်နိုင်မှု မြင့်မား

- သဘောကျသည့်လုပ်ငန်းခြင်းများကို ဆောက်လုပ်နေသောလူထု သက်ရောက်နိုင်ပါသည်။
 - သဘောကျသည့်နေရာကို ရောင်းချရန် ဒီဇိုင်းထည့်သွင်းစဉ်းစားခြင်း မပြုပါက သဘောကျသည့် လုပ်ငန်းမပေါင်း ပုဂံ
 - သက်သေခံမှုမရှိ ဖိနှိပ်ပါသည်။
 - တူးမြောင်းနေရာ ROW ကို ပြန်လည်သက်သေခံမှုခြင်း ထိုသက်ရောက်မှုအား လျော့ချပေးနိုင်ပါသည်။
 - ကြိုင်းချက်ရန် သော သက်ရောက်မှု အနည်းငယ်အတွက်သာ လေ့ကျင့်ထည့်သွင်းစဉ်းစားရပါမည်။
- ဘေးအန္တရာယ်** **Description:** The likelihood of impact is expected to lead the shyward operators who are operating

<p>အခြေခံအချက်အလက်</p> <p>ပြင်ဆင်ရန်သော အခက်အခဲ</p> <p>အခြေခံအချက်အလက်</p>	<p>Description: Description: The likelihood of impact is expected to lead the shipyard owners who are operating the wet and dry dockyards for 60 years. Their investment for this business is huge in amount and their economic income is likely to disturb from the specific project functions, such as making the barriers for their entrance/exit of their ships, reducing and/or minimizing the income generation rate, etc.</p> <p>Social Concern: The impact is related to income/business loss and the amount is extremely huge to compensate and the special proper consultations will have to be undertaken for those who will be impacted as the impact for income loss of shipyard workers are also presented.</p>				
<p>ယဉာဏ</p>	<p>Insignificant</p>	<p>small</p>	<p>Moderate</p>	<p>High</p>	<p>Very High</p>
<p>အခက်အခဲ</p>	<p>Rationale: The impact is predicted as high level due to huge investment amount of a shipyard in total number of 40 and the daily income loss for the shipyard work.</p>				
<p>အခက်အခဲ</p>	<p>0-1 year</p>	<p>2-5 year</p>	<p>6-15 year</p>	<p>Life of operation</p>	<p>Post Closure</p>
<p>အခက်အခဲ</p>	<p>Rationale: Loss of the economic activity will be permanent after receiving acquisition process.</p>				
<p>အခက်အခဲ</p>	<p>Limited to the site</p>	<p>Limited to the local area</p>	<p>Limited to the region</p>	<p>National</p>	<p>International</p>
<p>အခက်အခဲ</p>	<p>Rationale: The impact is expected to income loss for specific area that can be affected by the project activity in direct way.</p>				
<p>ပြင်ဆင်ရန်</p>	<p>Very improbable</p>	<p>Improbable</p>	<p>Probable</p>	<p>Highly probable</p>	<p>Definite</p>
<p>သက်ရောက်မှုအဆင့်</p>	<p>Rationale: The income loss is highly probable with huge investment amount and this minimization for income generation might be expected as usual after the project later on.</p>				
<p>သက်ရောက်မှုအဆင့်</p>	<p>Magnitude (5) * Duration (4) + Extent (2) * Probability (5) = 55</p>				
<p>သက်ရောက်မှုအဆင့်</p>	<p>အဆင့် 5 (High)</p>				

53

လှူမှုစီးပွားအပေါ်သက်ရောက်မှု ၃:

မြစ်ရေသုံးစီးပွားရေးလုပ်ငန်းများ ၊ အလယ်အလတ် အဆင့်

- ဖူးမြောင်းတစ်လျှောက် ဆောက်လုပ်ရေးလုပ်ငန်းများကြောင့် လှေငယ်ပိုင်ရှင်များအတွက် လှေဆိပ် နေရာများ ၊ တံငါသည်များအတွက် ပင်ဋေလမ်းများကို ချက်ရောက်မှု ဖြစ်နေနိုင်ပါသည်။
 -ငါးဖမ်းနေရာများကို ပြောင်းရွှေ့ခြင်း ၊ လှေဆိပ်နေရာများကို နေရာရွှေ့ခြင်းအားဖြင့် ထိုသက်ရောက်မှုများ ကို လျော့ချနိုင်ပါသည်။

သက်ရောက်မှု ဖြစ်နိုင်သော အကြောင်းရင်းများ	<p>Description: Temporary disturbance of fishery activities and small boat owners who are operating the private inland water transportation sectors shall be inevitable due to disturbance of small quays along the canal by project construction activities such as retaining walls, flood embankment, etc.</p> <p>Social Concern: The impact is predicted as low due to temporary disturbance of their operation quays for small boats that will also affected to stevedores at that quay.</p>				
	Insignificant	small	Moderate	High	Very High
သဘာဝ	<p>The impact is predicted as low due to temporary disturbance of their operation quays for small boats that will also affected to stevedores at that quay.</p>				
အချိန်ကာလ	0-1 year	1-5 year	6-15 year	Life of operation	Post Closure
အဆိုးဆုံးသဘာဝ	<p>Rationale: the impacts would be only temporary during construction and their operation would be restored after the project.</p>				
	Limited to the site	Limited to the local area	Limited to the region	National	International
ဖြစ်နိုင်ခြေ	<p>Rationale: The extent will be reflected to regional area for transportation of goods from and to somewhere in the region upon demands.</p>				
	Very improbable	Improbable	Probable	Highly probable	Definite
သက်ရောက်မှုအဆင့်	<p>Rationale: The probability is high during the project construction phase of the project although positive effects can be expected during the operation phase.</p>				
	Magnitude (2) + Duration (2) + Extent (1) * Probability (3) = 15				
					နည်း (U)

54

**ပြန်လည်နေရာချထားရေး
အစီအစဉ်**

- [illegible]

[illegible]


မကျေနပ်ချက်များနှင့် နစ်နာမှုများကို တိုင်ကြားရန် အစီအစဉ်

- Grievance Owner
- Address/Contact
- Knowledge on Project
- Measure on entitlement
- Measure on affected land
- Land classification
- Lost Assets
- Crop
- Others
- Compensation Rate
- Compensation in cash/in kind

ပြေသာသနိယသမ္ဘူနှင့် ပြန်လည်နေရာချထားရေး

အထက်တွင် ဖော်ပြထားသည့်အတိုင်း သက်ရောက်မှု ဖြစ်နိုင်သည့် ဒလ၊ တုံ၊ တော၊ ဆိပ်ကြီး၊ နောင်တို နှင့် ကြည့်မြင်တိုင် (၄) မြို့နယ်တွင် ပြန်လည်နေရာချထားရေး အစီအစဉ်များကို လုပ်ဆောင်သွားပါမည်။

1. ဆောက်လုပ်ရေးနေရာ ၊
 ဆောက်လုပ်ရေးကာလအတွင်း လိုအပ်သည့်
 ခြေယာ သိမ်းဆည်းမှု၊
 ပြေအမျိုးအစားအားဖြင့်၊ ပိုင်ဆိုင်မှု၊
 အရွယ်အစား၊ အမျိုးအစားအလိုက်
 နှစ်နာကြေး၊ ဈေးနှုန်း၊
2. ဆောက်လုပ်ရေးအဆင့်ကာလအတွင်း
 ယာယီပြန်လည်နေရာရထားရေး
 မှတ်တမ်း၊
 နောက်ဆုံးရွေးချယ်သတ်မှတ်ခြင်းများကို
 အတည်ပြု သတ်မှတ်ရန် လိုအပ်ပါသည်။



55

ရှေ့ဆက်ဆောင်ရွက်ရမည့်အချက်များ

ပြန်လည်နေရာချထားရေးအစီအစဉ်

၁။မြေယာလျော်ကြေးနှင့်မြေနေရာချထားရေးညှိနှိုင်းကော်မတီ

၂။အသေးစိတ်တိုင်းတာကွင်းဆင်းခြင်း

- မြေယာ ဆုံးရှုံးမှု/မြေယာပိုင်ဆိုင်မှုအထောက်အထား
- အဆောက်အဦများ ဆုံးရှုံးမှု
- သီးနှံဆုံးရှုံးမှု
- အသက်မွေးဝမ်းကြောင်းပြန်လည်နေရာချထားမှု
- အခြားထောက်ပံ့မှုများ
- လျော်ကြေးတွက်ချက်မှု
- မြေယာပြန်လည်နေရာချထားမှုနှင့်လျော်ကြေးငွေ

56

ကျေးဇူးအထူးတင်ရှိပါသည်။

Appendix 11: List of Participants of PCM during the Scoping Stage

Meeting Dates	Discussions
20.9.2018, 9:00 AM to 12:00 PM, City Hall, Twante Township	<p>Opening remark by Township Administrator, U Moe Khine Tun I would like to say "Mingalabar" to Twante Township resident and Twante regional parliamentarians, representatives from Twante regional government, members of natural resources conservation committee, officials from various government Depts, NGO, CSO members, local people and all those who attended this public consultation. This project will be led by ISAN Team from Korea and REM Co. Ltd as the third party to carry out ESIA. This meeting is for the public to give opinions and put ideas to ESIA. Feel free to ask anything. I would like to encourage all of you to give constructive ideas and suggestions, which may support to the development of the project.</p> <p>Introduction and Presentation of the project by U Aung Kyaw Hmuu (DWIR) <ul style="list-style-type: none"> • See the file of DWIR presentation </p> <p>Explanation of ESIA presentation by Daw Khin Ohnmar Htwe, Social Consultant from REM <ul style="list-style-type: none"> • See the file of REM presentation </p> <p>Questions, Answers and Suggestions by Participants Discussion by Ko Sai Min Tun (CSO) Q: Per the REM presentation file, there are only 3 months left for ESIA survey. I think it is too short to make this survey. So can it finish right time? The resident just found out about the project now and I think this is late. Project area is from 0 mile to 6.5 miles, so how is 21 miles?</p> <p>Answer by Daw Khin Ohnmar Htwe (REM) A 1: This project wasn't just started, it has been studied since April and give some information to GAD. Before we informed residents, we had to do some of the processes step by step as well. It is left only 3 months in the contract period, but we are not sure how long it will take and it is dependent on the MONREC (Ministry) as well.</p> <p>Answer by U Aung Kyaw Hmuu (DWIR) A 1: It is based on the government budget; we can't do all along the canal yet. We have to do the priority one in the most damaged part and dangerous part of the canal _from 0 mile to 3.5 miles as the phase 1. We will inform to Exim bank about the short period as well.</p> <p>Answer by Township Administrator, U Moe Khine Tun A 1: It is government plan so the township level like us did not know previously. There is nothing to hide from the residents and other communities about the project. GAD side just found out 3 days ago.</p> <p>Discussion by Ko Aung Ko (CSO) - Bo Joke Village A 1: Twante Canal is very important to Yangon river and Irrawaddy river. I would like to suggest making sure for the right ESIA survey. Because I have bad experience about the ESIA report like different survey result in different places. The project size is a bit larger so we should be more careful about the survey.</p>

Answer by U Aung Kyaw Hmuu (DWIR)

A 1: We are very careful about the survey and will think about the least impact on the environment and the local residents. After REM got the full information about the project we will share more about the project at the 2nd Public Consultation Meeting.

Discussion by U Swe Tin (Fish and Prawn livestock at Pa Thi Village)

Q 1: Project include size from 0 mile to over 20 miles or per phase or along the canal?

Q 2: Previous time, there were Canal Law and the committee who is maintaining and controlling canal usage. Do these laws still exist or not? Residents have to pay some amount of the money to that committee to maintain the Canal.

Q 3: There are a lot of creeks from villages to Canal, how is the situation for creek?

Q 4: There are some shops and houses along the Canal, so what will happen? Will they be affected? Any plan to seize or move?

Answer by U Aung Kyaw Hmuu (DWIR)

A 1: Myanmar government has not gotten fully funded for that project yet, so from 0 mile to 6.5 miles will start priority as the project phase I. Government size and local resident are all aware that the current problems and situations exist along the 21 miles as well. So I(DWIR) will try to make small construction in that area.

A 2: Canal Law (1905) and the committee are still alive and working. Resident have to pay some amount of the money to committee to maintain the canal, those moneys directly goes to Government finances. Now we are not using that money, this project is funded by Korea Government.

A 3: For the creek, we prefer to maintain naturally. We will not block the creek, if needed we will make new way/method to transport for the current users/residents. DWIR plan to make some construction along the 16 miles which will be funded by DWIR Dept budget.

A 4: Twante Township is not fully included in current project phase I, from 0 mile to 2 miles which are along the canal could be include in project, so that no need to worry about those shops and houses from Twante City yet. Whenever we plan the project, we will get the public feedback and always consider the public's voice.

Discussion by U Man Oo (Villager)

Q 1: There are many trading shops (Broker's sale center) along the Twante Canal, there should be a big jetty in that area. It can make for good business and improve residents' income.

Q 2: Will Ministry of Transportation & Communication upgrade the jetty along the canal? Bigger size?

Q 3: Canal land ownership area? In the previous year, some of the canal land have collapsed already in water. How much area is still left for the canal?

Q 4: Who is responsible person/Dept for compensation issue? Compensation

	<p>situation status?</p> <p>Q 5: Some of the users are using the boat anyhow in the canal (Eg High speech, indiscipline), so that government should control under the Rules and Regulations of using boat in Canal.</p> <p>Answer by U Aung Kyaw Hmuu (DWIR)</p> <p>A 1: No need to worry for Twante city site, that part is not included in this project yet. For the next project, we will think about your idea and information.</p> <p>A 2: For previous jetty, DWIR planned to make big and strong jetty along the canal but there is no enough space to make big size jetty. (Have to make space for road as well.) So I focused on strong technical structure that is why some of the jetty were small size. In future, I plan to make big and strong jetty priority.</p> <p>A 3: Original canal land is huge and big size along the canal. The original land is not parallel style and different kind of size area along the canal. Original constructed area for canal was 25 feet, the original land size was much more than that. In Khanaungto township, some of the canal land area were token as the township road. In 2005 data, total Canal land area were 2,500 acres. Now it could be 2,300 acres.</p> <p>A 4: DWIR or REM, nobody will pay for those compensation. We all follow the procedures, Rules and Regulations based on the Township Land Record Dept, Land Confirmation Dept. The effected person can get the exact amount which is calculated by government.</p> <p>A 5: It is under Township level administration Dept, they will answer it.</p> <p>Discussion by Ko Latt Myo (Archaeologist Group, CSO)</p> <p>Q 1: Previous Canal design was drawn by English Designer; Korea team should study the previous design(Suggestion). In the village, there are a lot of private wells then it can get the fresh water from well and it is leaking to canal part from the soil and it becomes small hole. In the other side, the salt water from the Yangon River going into the canal with salt water. The canal bank soil become a place where fresh water and salt water meeting point. That's why solid test should be included when REM do for survey (Suggestion). Government should control the drilling water from the ground and should plan to get the other water sources for residents.</p> <p>Answer by U Aung Kyaw Hmuu (DWIR)</p> <p>A 1: Thanks for sharing the discussion and suggestion. Soil test survey is very important for the actual detailed design so that definitely we will make soil test.</p> <p>Discussion by Ko Zaw Zaw (A Nar Gat Linn, CSO)</p> <p>Q 1: Please seriously consider for the compensation for effected person. There was some issue in Thilawa SEZ project compensation case, project owner didn't give to right person and something illegal case between GAD and residents etc.</p> <p>Q 2: Please seriously think about for plantation of mangrove at the bank of the canal area.</p> <p>Q 3: Government have to focus on Quality Control test (QC), construction tender winner companies always cheating the project in the long history and strongly</p>
--	---

	<p>recommend to check the QC.</p> <p>Q 4: Related Dept should take action carrying the charcoal by ship along the canal, it could make some impact to the local resident and environment</p> <p>Answer by U Aung Kyaw Hmuu (DWIR)</p> <p>A 1: We all follow the procedures, Rules and Regulations based on the Township Land Record Dept, Land Confirmation Dept. The affected person can get the exact compensation amount which is calculated by government.</p> <p>A 2: Government to plant mangrove at the bank (Not all along the bank).</p> <p>A 3: Regional Government also seriously consider for the Quality Control (QC) and strongly regards to tender winner company. This project is funded by Korea; we have to follow EDCF safeguard policy as well. This project would be under controlled by Myanmar Government and Korea Government</p> <p>A 4: I will inform related Depts and Ministers to control that kind of things and take action.</p> <p>Thanks speech by U Aung Kyaw Hmuu</p>
21.9.2018, 9:00 AM to 12:00 PM, City Hall, Dala Township	<p>Introduction and Presentation of the project by U Aung Kyaw Hmuu (Director, DWIR)</p> <ul style="list-style-type: none"> • See the file of DWIR presentation <p>Explanation of ESIA Presentation by Daw Khin Ohnmar Htwe, Social Consultant from REM</p> <ul style="list-style-type: none"> • See the file of REM presentation <p>Questions, Answers and Suggestions by Participants</p> <p>Discussion by Resident</p> <p>Q 1: In 2007, there was big collapse of 120 feet. In 2017 it happened again. Government worked on some areas but it is still happening day by day. Local residents are very worried about that, so when will the project be started? Next year?</p> <p>Answer by U Aung Kyaw Hmuu (DWIR)</p> <p>A 1: We will try to start next year, in 2019 and will start the priority areas first.</p> <p>Discussion by U Tint Naing (Resident)</p> <p>Q 1: These are clay pottery business near the canal area in Twante township, sometime they took the soil (raw material for clay pot) from the canal land and it can effect/damage to canal. Any plan to control that kind of thing?</p> <p>Q 2: There is New Yangon City Development Plan as a new city in Dala township, is there any plan for waste water disposal system in the NYCD? Will it affect the Twante Canal?</p> <p>Answer by U Aung Kyaw Hmuu (DWIR)</p> <p>A 1: DWIR will control the residents who are taking the soil from the canal land. Sometimes it is difficult to control because they come and take only in the night time.</p> <p>A 2: It is new City Development Plan smart city so that there are their own waste water disposal system and good sanitary system in new city. It won't affect the canal.</p>

	<p>Discussion by U Khin Maung Ni (YCDC) Q 1: In the presentation DWIR mention Bank Protection plan also included, so is there any plan to construct the dam and bridge for the jetty and creek where are connected with the village along the canal.</p> <p>Answer by U Aung Kyaw Hmuu (DWIR) A 1: Yes, we plan to construct the. Before that we will come and discuss the detailed design with the township YCDC and local resident and will choose the best design for all.</p> <p>Discussion by Residents Q 1: Canal is in the lower part of the Yangon river and Tow river, so that salt water can easily go down to the canal. In 2009-2010, salt water level reached in 9 miles' area. I would like to suggest to check the salt water test survey after get the survey result please share with us.</p> <p>Q 2: Mouth of the Canal is the joint place of Yangon River and Toe River, it can be damaged by salt water near canal and can cause further collapses. Salt water can affect the agriculture sector near that area.</p> <p>Answer by Daw Khin Ohnmar Htwe (REM) A 1: Salt water test will be including in EIA survey test. Thank you for sharing your knowledge.</p> <p>Answer by U Aung Kyaw Hmuu (DWIR) A 2: Government plans to solve as soon as possible, if that part is not include yet in this project.</p> <p>Discussion by Resident Q 1: Twante, Dala and Khanaungto Townships could be the mega city in future. If it is constructed the road along the bank, it will be good for the residents and can get high standard of living. If we can get fresh water from Toe River to Khanaungto and also construct the bridge between Khanaungto and Dala, it will be the best for Khanaungto residents.</p> <p>Answer by U Aung Kyaw Hmuu (DWIR) A1 : Government always think about providing fresh water to these three township. Even Yangon does not have full access to fresh water. In phase 2 project, we plan to store fresh water from 0 mile to 21 miles. (But we don't know when it will start). Regional government also plan to find the water source for New City as well. I think there is bridge construction project in New Yangon City Development for Khanaungto (But I am not sure for this).</p> <p>Thanks speech by U Aung Kyaw Hmuu</p>
<p>21.9.2018, 1:30 PM to 3:10 PM, City Hall, Seikkyi Khanaungto Township</p>	<p>Opening remark by Township Administrator, U Zaw Thein</p> <p>I would like to say "Mingalabar" to Khanaungto Township resident and Khanaungto regional parliamentarians, representatives from regional government, members of natural resources conservation committee, officials from various government Depts, NGO, CSO members, local people and all those who attended this public consultation. I would like to explain some history of the canal. In 1873, it is 21 miles in length, aimed at Myanmar's economic development through improving shipping trade. Seitgyi Khnaungto plays an important role in the Twante canal project. Khanaunto land area is in the middle of the Twante canal with small land size and suffers the most from floods. I would like to say</p>

	<p>special thanks to Korea Organization which funded this project and our Myanmar government as well. This project will be led by ISAN Team from Korea and REM Co.Ltd as the third party to carry out ESIA. This meeting is for the public to give opinions and put ideas to ESIA. Feel free to ask anything. I would like to encourage all of you to give constructive ideas and suggestions, which may support the development of the project.</p> <p>Introduction and Presentation of the project by U Aung Kyaw Hmuu (DWIR)</p> <ul style="list-style-type: none"> • See the file of DWIR presentation <p>Explanation of ESIA that was carried out in 2013 by Daw Khin Ohnmar Htwe, Social Consultant from REM</p> <ul style="list-style-type: none"> • See the file of REM presentation <p>Questions, Answers and Suggestions by Participants</p> <p>Discussion by Daw Sandar Min (Minister, Yangon Region)</p> <p>Q 1: Who is the responsible person/team for the project? Who will guarantee the execution of this project? This project will cost USD 69.244 billion and it has to be paid by the Citizens to Korea government, who will monitor the project? (Korea or Myanmar)</p> <p>Q 2: Is there any monitoring team for this project?</p> <p>Answer by U Aung Kyaw Hmuu (DWIR)</p> <p>A1: This project will be led and monitored by DWIR, Ministry of Transport and Communication, and funded by Korea Eximbank. Before they granted the loan for this project, they performed all the ground survey of the canal. Korea construction will be carrying out this project under control of the EDCF safeguard policy by Eximbank and suggested by DWIR. Korea Construction companies have to submit the proposal to Exiambank by bidding system. Eximbank will pass the list of the Korean construction companies to DWIR. DWIR will choose which are qualified, have international experience, and other essential criteria by marking system and report back to Eximbank. Before the confirmation, DWIR and selected construction company will discuss the financial issue first. There are two parts for the project – one is design (Korea+Local) and another one is construction (Korea+Local). Those two parts always must be in alignment with the Eximbank's rules and regulations and EDCF safeguard policies. There is the Quality Control (PC) team.</p> <p>A 2: There is no third part for the project.</p> <p>Discussion by Local people</p> <p>Q 1: I hope this project can be finished on time. Now is the project starting to get ready? For example, the Dala Bridge was not finished during the actual project period so that I hope this project won't be the same.</p> <p>Q 2: Which part of the Khanaungto township area will start?</p> <p>Q 3: How will give the guarantee of this project? Quality control?</p> <p>Answer by U Aung Kyaw Hmuu (DWIR)</p> <p>A 1: This project is different from the Dala bridge project. It is also based on the Government election situation in Myanmar and Korea. Some of the proposals</p>
--	---

	<p>have to be submitted again and reviewed again by the new governments.</p> <p>A 2: After getting the detailed design, we can consider which part of the canal should start or not. We have to do important and essential components first. (Access Road, ground situation) As of now, we can't say which part will be worked on first.</p> <p>A 3: Korea construction company will be construct this project under control of the EDCF safeguard policy by Exim bank and suggested by DWIR. This project is international level and criteria, no need to worry for quality control and guarantee.</p> <p>Discussion by U ____ (Aye Village Administrator, Kyi Myin Daing Township)</p> <p>Q 1: In 2012-2013, after excavation the Pan Hlaing river the villagers can't even use the boat at the mouth of the Pan Hlaing river but inside of the river is too deep like a big lake. It was difficult for villager's livelihood. That project was done by government money (national money), but it's useless. It is wasting money. We don't want that kind of similar project again.</p> <p>Answer by U Aung Kyaw Hmuu (DWIR)</p> <p>A 1: That project was done by irrigation Dept and was funded by their Deptal budget, not the government project and international level project which is funded by Korea government. This project is different situation with Pan hlaing project. Current government isn't allowing to do anyhow like previous and Eximbank will not allow anyhow.</p> <p>Answer by U Tin Tun Naing (Union Parliamentarian, NLD)</p> <p>A 1: Pan Hlaing river project was different with this project. It was done by irrigation Dept budget which is set by government and constructed local technical. Now this project is funded by Eximbank and will construct the international level company and also will be under the EDCF safeguard policies. Current government and funded country (Korea Exiambank) will not allow to do anyhow, all should be under Rules & Regulations. Project owner will provide suitable compensation and plan for resident, all action will be acted under the procedures, Rules and Regulations based on the Township Land Record Dept, Land Confirmation Dept.</p> <p>Briefly explanation of EDCF guideline by Mr.Lee, Sang Hoon (Yooshin, ISAN Consortium)</p> <p>Special thanks to all attendees. Korea Government funded the project, and the loan came from Korea Citizen' taxes for all Myanmar Citizens' development. Korea Government strongly cooperated with DWIR for this project. In 2016, EDCF made strong policies for EIA procedures and we all have to follow the EDCF safeguard policy thus nothing to worry for quality control. When the project is started, Myanmar Quality Control (PC) Team will monitor together with Korea Quality Control (PC)Team. Before the project start, our Korea site already considered all problems for the Myanmar people and we will do all our best for this project. Thank you so much all.</p> <p>Thanks speech by U Aung Kyaw Hmuu</p>
--	---

<p>15.11.2018, 3:00pm, GAD Office, Meeting Hall, Kyimyindaing Township</p>	<p>U Mg Mg Lwin (DWIR)- He introduced about the history, current situation and propose project of Twente cannal by powerpoint presentation.</p> <p>U Thura Aung (REM) - He Explained about the Environmental Impact Assessment(EIA), potential impacts and contents of study in the improvement of Twente Cannel project by powerpoint presentation.</p> <p>U Nanda Kyaw (Parliament Member) - He said that the other side of Kyimyindaing is still weak development and there have land related issue. So, be careful when the project implementation.</p> <p>We are welcome the project, we would like to help and cooperate as much as we can.</p>
---	--

Appendix 12: List of Participants of PCM during the EIA Stage

Meeting Dates	Discussions	Participants
26.1.2019, 9:00 am to noon , Township Sports Building, SeikkyiKanaungto Township	<ul style="list-style-type: none"> - Opening speech by U Tin Tun Naing, Member of Union Parliament from SeikkyiKanaungto Township - Introduction of the Project by U Aung Kyaw Hmu, Director of DWIR - Explanation about current environmental and social conditions and potential impacts by Daw Lai Lai Win and Daw Khin Ohnmar Htwe from REM <p>U Hla Mg (Myanmar Red Cross Association)</p> <p>1. I would like to say “thank you” for implementing this project in our township. Our township is the one of the smallest townships in the Yangon Region. I want to know about the resettlement plan. During the project implementation, there should be job opportunities for the local people for general work, even not for the expert positions.</p> <p>U Ohn Mg (Local Person) -</p> <p>2. In our childhood days, it had been easy to navigate in the Twante canal. Later on, bank erosions and whirlpools have occurred. As far as we know, this project includes the construction of rock retaining walls and embankments. In 2012, the customs office building was lowered gradually. It was caused by the erosion. To prevent continuous lowering of this building, the water from the Ayeyarwaddy River was prevented to flow into the Twante canal and it led to little water flow into the Kanaungto Creek. As the consequence, there had been more sedimentation in our township and the sediments leveled up to 100 ft. In the past, the Kanaungto Creek occupied 18 ft in depth. Now, it has only about 9 ft in depth. Due to the constructions in 2012, water becomes shallow nowadays. So, if possible, the reinforced rock retaining walls are requested to be built just at the Twante side, not at the Kanaungto side. The roads in our township are narrow. Embankments roads are thus should be built too. It would be better to build a bridge to Dala Township from SeikkyiKanaungto. We have already requested to build the bridge. If not necessary, some constructions should not be made at the Kanaungto side, and more concentrations should be paid to the Twante Canal side. It will save unnecessary implementation costs.</p>	139persons

U Lay Naing (Local person) -

This project is welcomed. It should be implemented since long ago. There should be recreation parks between the canal and the town. It will make the town more beautiful. Lampposts should be placed along the road beside the canal. As the project will take about 5 years, there can be more buildings and it will bring negative consequences too. In the past, ships cannot stop at the bank. During these years, there have been bank erosion as the ships stop along the bank. As the project will consider for compensations, there might be more houses along the canal. Therefore, it is suggested to relocate the houses even before the project starts. There is no more place in our region to relocate if there are bank erosions. So, mitigation measures should be considered for 0 mile to 3.5 miles firstly.

U Aung Kyaw Hmu (DWIR)-

1. For resettlements, there is a land committee for every township. Daw Nilar Kyaw, the minister of roads and transports, is the chairperson of these committees. All the findings will be investigated in coordination with the land committee. Land compensation rates are different for different townships according to their locations. Compensations will be considered in accordance with these rates. We do not directly manage the compensations of lands. There are the government's legal frameworks for these cases. Land compensations will be made in line with the decisions made by the land committee. As this committee will take these responsibilities, it will make careful considerations for the local people. Now has been the stage of selecting consulting and monitoring organizations. It was finished in February. When these organizations come, there will be the project design in details. But there will not be job opportunities soon after these organizations come. About 1 year later, there will be organizations for implementations and at this stage local people will have job opportunities. In our considerations, we also include to prioritize the local people to get employments.

2. In 2009, after the destruction of the edge from 3.5 mile, there has been more water flow into the canal and less flow of water into the Kanaungto Creek. It led to more sedimentations in the creek. At some places, there have been whirlpools and bank erosions caused by the fast flow of water. Therefore, the retaining walls have to be built along the Kanaung creek with the budget of the regional government. It is true that the

	<p>water level has been lower but the erosions are still happening. If the constructions of retaining walls are not welcomed by the Kanaungto side, more negotiations will have to be made. According to the current project design, there are over 1200 households as it is reported by REM. This amount is too large. When we requested for the loans, it must be stated that this project would include plans to prevent floodings as one of their standards. So, it is hard to deviate from the original plan. Since from the beginning, the considerations to prevent floodings as a benefit for the local people. At the same time, there are also considerations for the people who depend on water and its flow for business purposes. And there are mitigation measures for the livelihood opportunities of the local people. But, we have not made negotiations with the Korean organization. We took into considerations of the most suitable ways. The main objectives include considerations to prevent floodings and whirelpools and to minimize their impacts on the local community. Thus, we will make sure to meet these objectives. The communities along the bank are facing with problems and it also harms the communities when there are floods. We will consider both issues and find the most suitable ways. The benefits must outweigh the unnecessary losses. This project have the resettlement plans for the people from the project area. As the flood prolems should not be left to consider, we planned to build a reinforced rock retaining wall and embankment from 0 mile to 3.5 miles along the Twante canal. A new road will be built in parallel with the existing one and it will prevent flooding. From 3 miles to 6 miles, it is okay to build reinforced rock retaining wall and embankment. If there may be any losses, we will take actions in accordance with the rules and regulations of the state. For the Kanaungto side, we expected to build 9-ft reinforced brick retaining walls instead of building reinforced stone retaining wall. This brick wall is expected to be built behind the docks instead of blocking them from the front. We will have to discuss with the design experts from Korea later.</p> <p>3. We had already announced that 31st July 2018 to be the last date. We will not consider the houses after this period. We already have records for that.</p> <p>U KyawThan (Shipyard Owner) -</p> <p>We have read in the newspaper that 67 millions budgets have already permitted for the Twante Canal improvement project. Our concern is for the Kanaungto</p>	
--	---	--

side. Is there any budget permitted? How much will it be? Have all the related ministries known and discussed about that? It means that we want all the related ministries to know in case if there is any separate plan from a different Dept. After the Dala bridge has been built, the people from Kanaungto will have to go via Twante to go to Yangon. Even if we still cannot have a bridge for vehicles to pass, we wish to have a bridge functionable only for the people to go. We want to know what level of the government has given permissions for this project. You also talked about environmental sanitation. For that, there are both natural causes and man-made causes. Some latrines discharge sewage into the creek directly. I want to know whether there is already any survey for these cases.

U Zaw Min Shein (Shipyard Owner) -

As the project will be carried out by the foreign loans, it is the citizens who will have to give it back. I want you to use the loans as less budget as possible by defining the important and unimportant issues. It is suggested that you should think carefully which one is more beneficial --- to dredge the silts or to build retaining walls.

U Maung Maung Lat (Engineer, Myanmar Telecommunications)-

There should be a facebook page to announce the things we just discussed so that those who could not join the meetings can also know everything about the project.

U Aung Kyaw Hmu (DWIR) -

1. It is not easy to get foreign loans. It has to discuss in the Hluttaw from various perspectives. The government Depts have to submit to the planning Dept and be in the lists. As our country is a developing country, the developed countries consider to give loans to us, but not for the great profits. For this project, the interest rate is just 0.01 percent. If the developed countries want to help Myanmar, they have to make discussions with the union government. Only then, the union government has to look at the plans in the list and decide which one should be prioritised depending on the level of urgency. Then, it has to be discussed with the responsible ministry. At this time, there must be a FS report in hand. Supports include two portions- for conducting a FS report and for project implementation. The supporting organization gave suitable suggestions. We cannot do whatever we want. As they act as the third party, they give fair suggestions depending on suitability.

	<p>The final report has to be disclosed to the international communities. Also, this meeting is held according to the international guidelines. Loans sum up to 500 million dollars. From that amount, over 70 million dollars is for the Twante Canal Development project originally. From this 70 millions, we planned to use over 60 million dollars. For the Canal, it is estimated to use 61.3 million dollars. Not only the canal, but the Kanaungto creek will be included. Then, the other side must agree to give loans and our side decides that it is feasible according to the FS report. Next, this agreement has to be submitted to the union level respectively – first to the ministry and then to the union cabinet. Only when the Hluttaw agrees to receive loans, contracts have to be made. To sign on the loan agreement, there are also standards. As this loan is mainly for the benefits of the citizens, it is required to follow their guidelines and local rules and regulations. It is called EDCF guideline. This loan is from EDCF, Korean development Aid. They have their standards. They will not accept if we do not meet their standards. For us, we also consider not to have unnecessary costs. For the consulting part, the amount they asked was much at first. We had to negotiate for about 8 months so that there is any unnecessary cost. We are responsible to use reasonable amount for consultation process. This project was announced both in the Hluttaw and to the union government. And it has permissions from the president and the ministry.</p> <p>It is true that the loans must be paid back by the citizens. Our Dept will not use the loans directly. We will have to pay these loans to the consulting organization and the implementation organization. These will have to be given directly to both organizations by cheques. Our Dept will only use some portions of loans for compensations.</p> <p>2. For information sharing, we have our website. We will update about the project on our website. Moreover, we will distribute hard copies to the respective general administration Depts.</p> <p>Daw Khin Ohnmar Htwe (REM)-</p> <p>When we assessed the noise levels, it showed that it was above the normal standards. These are also due to the ships, vehicles, and the noises from the docks. During implementation stage, we reported that the noise level must be lowered in accordance with our monitorings. We will give recommendations for that in our report too.</p>	
--	---	--

	<p>U Tin Tun Naing (Member of Union Parliament) -</p> <p>I would like to thank all the people who attended today's meeting. The representative from the related government Dept also explained about the project clearly. We will not neglect the concerns and challenges of our people. Both the union government and the loan-giving organization will not allow if we do not listen to the voices of the local people. As a member of parliament, we will take make negotiations with the relevant organizations on behalf of our people. We will not allow if negative impacts outweigh the positive ones as this loans must be paid back by the taxes of our people. Now, it is just the beginning. I would like the local people to participate in the meetings and make discussions. We will listen to all the voices of the people and their concerns. And, we will find the most convenient ways to minimize the impacts of the project.</p>	
<p>28.1.2019, 9:00 am to 11:00 am , Meeting Room, General Administration Dept, Twante Township</p>	<p>- Introduction of the Project by U Aung Kyaw Hmu, Director of DWIR</p> <p>- Explanation about current environmental and social conditions and potential impacts by Daw Lai Lai Win and Daw Khin Ohnmar Htwe from REM</p> <p>U Kyaw Naing (Tharsi Village)</p> <p>I want to know when will be the relocation of households. If it still needs time, we will have to repair the houses. If it is in the rainy season, it is not convenient.</p> <p>U Aung Kyaw Hmu (DWIR)</p> <p>I will explain one by one. We still need 9 months to draw the project design. After that, the implementating organizations will come 3 months later. During one year, houses in the project area will need to move. But, it still needs 9 months. We plan to start after the rainy season. The rainy season will start in August. We will start the implementations in the late rainy season.</p> <p>U Aung Kyi Myint (Tharsi Village)</p> <p>About the project, vehicles used our village road in the past. It damaged our roads. We don't want it again as we have to use about 40 million MMK to repair the road per year.</p> <p>U Aung Kyaw Hmu (DWIR)</p> <p>Last year, the project was operated by 3 companies. We have already asked them about that matter. The vehicles were also private ones in addition to the ones from the companies. In the future, we will build new roads that will join the project areas and the main road directly. We aim that these new roads will be usable for the local</p>	<p>178 persons</p>

	<p>people in the future and we build them with good qualities. As this road will join the main road to the project areas, the local people should propose them to build in good qualities. We will build the new roads once the operations start.</p> <p>Ko Kyaw Swar Htike (Satsan Village, Latpangwa Village Tract)</p> <p>As we have to depend on Yangon for our livings , if we have to be resettled, we don't want to go very far. We are also included in the project area.</p> <p>U Aung Kyaw Hmu (DWIR) -</p> <p>If Satsan village is near the Kanaungto creek, not much of the areas will be included to resettle. Only the brick wall will be built to prevent flooding. There is a land committee to manage land issues. We will relocate you to the places nearby if you are living in the affected area. For CN lands, they will be relocated in other CN areas. You won't need to move very far.</p> <p>U Khin Shwe (Latpankone Village) -</p> <p>Our house is located just beside the creek. We have many family members in our household. If we have to move, it will not be easy for us to make livings in the future. We understand that we need to move for the development of the port. Even so, I would like you to consider to relocate us in the places nearby.</p> <p>U Aung Kyaw Hmu (DWIR) -</p> <p>People from the right portion of Latpankone are quite lucky enough. Because as you are living near the CN road, we will relocate you nearer to the CN road. So, it will be easier for transportation, and the price the new place will be higher. We will not relocate you to very far places as we understand your concerns. The new places will be as good as the old places and even they can be better.</p> <p>Daw Cho Cho Lat (Sel Ain Tan Village) -</p> <p>If we have to move, we still want to live near our village. As we have access to electricity, we want to get electricity at the new place.</p> <p>U Aung Kyaw Hmu (DWIR) -</p> <p>If you need to move and your house is accessible to electricity, we will get access to electricity in the new place. The officers from the Dept of electricity are also in the committee. We will not let you move to very far places. We will make sure to relocate as near as possible.</p> <p>U Hla Myint (Phayargyisu Village) -</p> <p>Many of our villagers are farmers. If you build</p>	
--	--	--

	<p>embankments, we are afraid that we will not get water from the creek as it can block the water way. So, I want you include water passages to the fields in building embankments.</p> <p>U Aung Kyaw Hmu (DWIR) - We will include water passages if we build embankments. We will do surely. I also want you to propose that to the organization that will draw the design. We will also note this case and will tell them. I wish REM to write about it in the report.</p> <p>U Nay Naing Oo (Parliamentarian, Yangon Region) The project design should take into account these issues. Once the final design is ready, it should be disclosed to the local people.</p> <p>I would like to say thank you to the environmental and social consulting company and the local people who attended today meeting.</p>	
<p>28.1.2019, 2:00 pm to 4:00 pm, Meeting Room, General Administration Dept, Dala Township</p>	<ul style="list-style-type: none"> - Introduction of the Project by U Aung Kyaw Hmu, Director of DWIR - Explanation about current environmental and social conditions by Daw Lei Lei Win and Daw Khin Ohnmar Htwe from REM <p>U Myint Naing (Ward Leader, Targyi Ward) – If the houses need to be moved, it is suggested to give us the lands as compensations.</p> <p>U Aung Kyaw Hmu (DWIR) - We will make sure to minimize the impacts by the project. If you need to move, we have plans to relocate you to the nearest places of your original places.</p> <p>U Tun Tin Myint (Household Leader, Targyi Ward)- This meeting is to make many citizens know or just for some people. As it is a development project for our country, it should be announced to the whole public. All the project affected households should be informed, not just one or two households. Currently, there have been bank erosions from 0 mile to 3.5 miles. And we saw some operations of the machines along the bank. When we asked the members of parliament, they said they were not informed about it too. So, it should be transparent for the project implementations.</p> <p>U Aung Kyaw Hmu (DWIR) - Current operations are not concerned with the Twante Canal Devevelopment Project. It is by the regional government's budget. The Twante Canal Development Project is just in the stage of preparing ESIA reports. For the invitation process, we publicised in the newspapers. We also invited all interested people through respective</p>	119 persons

	<p>township general administration officers. If you see something confusing in our explanations, you may contact the address shown earlier. We will make sure to minimize the negative impacts of the project. If there are bank erosions, you can inform us through respective township government offices. We have plans to prioritise the issues in accordance with the level of severity and importance.</p> <p>Daw Khin Nilar Htike (Local People)</p> <p>As the rainy season is about to come, shall we repair our houses or not. If we have to move, I want to know when it will be.</p> <p>U Aung Kyaw Hmu (DWIR)</p> <p>It will take 9 months to finish the detailed design. Only 10 months later, the final design and decisions will be accomplished. For the time being, we will conduct surveys and decide which design will be of minimum impacts. So, basically, until next 10 months, you don't need to move. Currently, we have decided to build brick walls instead of reinforced rock embankments to minimize the impacts.</p> <p>U Tun Tin Myint (100 Household Leader, Targyi Ward) -</p> <p>In Targyi Ward, there is a signboard which says "Myanmar Port Authority's Areas, No Invasion Allowed". But we have seen that some of these areas were sold. I want you to consider these issues.</p> <p>U Aung Kyaw Hmu (DWIR)</p> <p>It should be replied by Myanmar Port Authority as this is under their authority. We are responsible for CN land. It is necessary for the administrators not to sign for any CN land sales. You can contact us. We will take necessary actions for these cases. I want the local people to be responsible too.</p> <p>U Tun Yin (Parliamentarian, Yangon Region)</p> <p>I am glad that the project implementations will have minimal negative impacts. If some households need to be resettled, it will be in line with standards. What I found out is that some of the areas along the bank are enclosed with fences. As far as I know, these are CN land around 0 mile. I am not clear why this area is owned by Myanmar Port Authority. In this rainy season, about 22 houses near the bank must be moved due to bank erosions. Please inform every issue in the community. We will discuss with the respective government Depts.</p> <p>Daw Khin Hla Hla (Local People, Parliament</p>	
--	---	--

	<p>Member Office)</p> <p>I would like to receive the facts explained in this meeting so that I could explain back to others. Our area has creeks. For the conservation of the creeks, we need to have trees. If not, we will not be able to protect natural disasters such as floodings and tsunamis.</p> <p>Daw Khin Ohnmar Htwe (REM) -</p> <p>Thank you. We announced in the newspaper for inviting to attend this meeting. Also, respective villages and wards were informed through township general administration Dept. The purpose of this meeting is also to share the information to the local people. As you suggested, we will distribute the meeting minutes and explanations with a book through the township generation administration Dept to villages and wards. When the final report is ready, we will give copies in the Myanmar language to GAD. You can contact GAD and read these copies. As you recommended, we will put recommendations about mangroves replantation by the cooperation of DWIR and GAD .</p>	
<p>29.1.2019, 9:00 am to 11:00 am, Meeting Room, General Administration Dept, Kyimyindine Township</p>	<ul style="list-style-type: none"> - Explanation about the project by U Mg Mg Lwin, Deputy Director from DWIR - Explanation about the environmental and social conditions and potential impacts by Daw Lei Lei Win and Daw Khin Ohnmar Htwe from REM <p>U Sein Than (10 Household Leader, Seikgyi UMya Ngarsin Ward) -</p> <p>In Kyimyindine Township, there are many houses along the bank. I want to know how they will be compensated if they have to move.</p> <p>U Mg Mg Lwin (DWIR) -</p> <p>About land issues, every township has a land committee chaired by Daw Nilar Kyaw, minister for roads and transport. If there shall be any losses, they will discuss with our Dept and will take proper actions to compensate money or land. And, the compensated land will be at the nearest to the original area.</p> <p>U Aye Shwe (Ward Leader, Seikgyi UMya Ngarsin Ward)</p> <p>In our childhood, the voice from one side could be heard from the other side. Nowadays, there are lots of bank erosions. We are glad to know that this project will also prevent bank erosions. Thank you to all respective Depts. We will also coordinate in this project.</p> <p>U Zarni Win (Township Administrator)</p> <p>As this project will include embankments, it is advisable that the ports should be convenient for the ships to stop</p>	42 persons

	<p>by. This case should be taken into account in the design. Only then, it will be helpful for transportation.</p> <p>U Mg Mg Lwin (DWIR) - We will consider about that in the detailed design.</p> <p>U HlaMyint (Local People, Seikgyi UMya Ngarsin Ward) There are religious buildings along the banks of Seikkyi, U Mya and Ngar Sin Wards. I want to know how they will be considered.</p> <p>Daw Khin Ohnmar Htwe (REM) - We will include about that in our report. During our surveys, we also found out these buildings. In our report, there are recommendations for the relocation of religious buildings. Moreover, we will recommend that more careful attention should be paid for the religious buildings. This meeting is to get the suggestions of the local people.</p> <p>U Ye Swe (Deputy Director, Environmental Conservation Dept) We have to conduct this kind of meeting for 3 times in accordance with the government procedures. Our Dept is to review the assessments. There are over 180 third parties. Third parties neither represent the government nor the business organization. In other words, our government Dept issued licenses to them as the representatives the citizens. People are afraid when they hear the word “project”. At this point, I would like to tell you that there are two kinds of projects – development projects and business projects. Our people should know about it clearly. And, we want our people to be a part of the project.</p> <p>U Htway Maung (Local People, Seikgyi UMya Ngar sin Ward) This project is welcomed. Thank you for coming and having meeting with us. I also wish this project to succeed. If we have to move because of the project, we want to move to the places nearby.</p> <p>U Zaw Win (Parliamentarian, Yangon Region) - Are all Seikkyi, U Mya and Ngarsin Wards included in the project area? When can we know the detail design of the project? Is it more appropriate to hold this meeting in Seikkyi, U Mya and Ngarsin? The voices of the local people are also crucial for the project. Without their consent, this project will not be succeeded.</p> <p>U Maung Maung Lwin (DWIR) - The detail project design will be ready 9 months later and it will be publicised transparently. This project is to</p>	
--	--	--

	<p>prevent flooding, saline intrusion and bank erosions.</p> <p>Daw Khin Ohnmar Htwe (REM) - According to our observations, all 3 wards, Seikkyi, U Mya and Ngarsin, are included. The project affected area is about 100 ft. Although the direct affected area is just in 100 ft, we also studied indirect impacts, especially environmental impacts, for the places from 200ft to 500ft, especially For those who are in 100 ft area, we studied their socioeconomic conditions. The exact lists of projected affected people will be announced soon. At this time, we will coordinate with the local people.</p> <p>U Tin Sein (Farmer Association) - Chief minister said that old wards would not be included in the new city project. But, if the people from these wards want to be included in the project, he said that he would consider. You should also take into account this fact.</p> <p>Daw Khin Ohnmar Htwe (REM) - Thank you. Because of these reasons, we conduct this kind of public meeting and get the ideas of the local people. Once the final project design is ready, we will also disclose again to the public. Public meetings will be held too.</p> <p>U SoeThura (Local People, Seikgyi UMya Ngar sin Ward) People from our side are quite poor. But, we can get access to health, social and educational facilities from the other side. If we need to move, health, social and education opportunities should also be considered for us.</p> <p>Daw Khin Ohnmar Htwe (REM) Resettlement and compensations will be managed by the township land committee. Before resettlements, third-parties like us will make sure that the project affected people do not have any harm. As this is a union level project, DWIR will be the leader. For the time being, we are just doing environmental and social surveys. After the assessment, it must be reported to get loans. Only after getting loans, we will need to discuss again. It is still early to say that you are included in the project area. Even so, a series of discussions will be made with the local people.</p> <p>U Zaw Win (Parliamentarian, Yangon Region) – This present stage is the study of EIA. After the EIA report' submission, we will discuss the loan with Korea Bank. I think we have to discuss it several time.</p> <p>U Tin Sein (Farmer Association) The bank beside our village was straight in the past. But</p>	
--	--	--

	<p>it becomes U shape due to erosions. It should be managed as Sinmalite side.</p> <p>Daw Khin Ohnmar Htwe (REM)</p> <p>It will be reported to DWIR as you suggested.</p> <p>Daw San San Htwe (YCDC)</p> <p>According to my experience, before the actual operations I would like to suggest that you should make video recordings for the buildings along the roads to the project area so that it will be evidences for the future use if there are any damage to the buildings.</p> <p>Daw Khin Ohnmar Htwe (REM)</p> <p>Thank you for your advice. During our survey time, we took the pictures of the buildings as records. They will be recorded for the detail surveys too.</p> <p>U Zarni Win (Township Administrator)</p> <p>There may be side-effects for other areas. This project will take nine more months for final project design. During this period, there can be new buildings in the project area. So, you should have video recordings. Respective village and ward administrators should be careful about too.</p> <p>Daw Khin Ohnmar Htwe (REM)</p> <p>The cut-off date for this project was already considered as 31st July 2018. Our data are estimations. The numbers cannot be more than that. We have records as pictures and GPS.</p>	
--	---	--

Appendix 13: Socioeconomic Survey Questionnaire Form

Socio-Economic Survey Questionnaire for Twante Canal Improvement Project By the Isan Consortium & REM, Oct 2018

INTRODUCTION:

This questionnaire is designed for Twante Canal Improvement project which is planned in Dala, Twante, Sekigi Kanaungto township. This survey seeks to explore the socio-economic features of the project area and the opinions of people with an aim to identify potential social impacts. Your contribution will help us assess the potential social impacts and develop mitigation measures.

INTERVIEWEE'S BASIC INFORMATION:

IV Serial No. _____

Village Name & Head: _____

Household Address. & Name: _____

(* Location map (attachment) _ pls mark the HH interviewed)

Interviewee Name & Age: _____

Relationship to Household head: _____

Gender: 1 () Male 2 () Female

Interview date: _____

1()	Interview is administered to the household head
2()	Interview is administered to a family member

Page 1

A. HOUSEHOLD CHARACTERISTICS

A1. Total number of household(*) members: _____
(*Conventional Household defined the 2014 Census: as being comprised of one or more persons who are either related or unrelated and share living quarters in either a stand-alone unit or a compound. Members of a conventional household eat meals together, usually prepared from the same cooking pot. In most case, one person is acknowledged by household members to be the head of the household)

A3. Name	A4. Gender 1. Female 2. Male	A5. Ethnic Group 1. Bamar 2. Mon 3. Shan 4. Karen 5. Others (Specify)	A6. Age: 1. Minor (~18) 2. Young adult (19-35) 3. Mature Adult (36-50) 4. Elder (51+)	A7. Relationship to Head 1. Household Head 2. Wife/Husband 3. Son 4. Daughter 5. Son/daughter In-Law 6. Grandchild 7. Parent 8. Brother/Sister 9. Grandparent 10. Others (Specify) 999. I do not know	A8. Marital Status 1. Single 2. Married 3. Divorced 4. Widowed 5. Separated 999. I do not know
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					

Page 2

A9. Is the family member literate or illiterate? 1. Illiterate 2. Literate	A10. What is the current/last school that the family member is attending/has graduated? 1. Below school age 2. No formal education 3. Primary School Student 4. Primary School graduate 5. Middle school Student 6. Middle school graduate 7. High School student 8. High School graduate 9. Vocational School of Higher Education Student 10. Vocational School of Higher Education Graduate 11. University Student 12. University Graduate 13. Master & Doctor etc. 999. I do not know
1	
2	
3	
4	
5	
6	
7	
8	
9	
10	

Page 3

A11. How long have you been living here as household/family?
_____ YEARS

A12. What is your religion?
1 () Buddhist
2 () Christian
3 () Hindu
4 () Muslim
6 () Believe spri() Others

B. INCOME, EXPENDITURE AND LIFESTYLES

B1. What is the average yearly/monthly income of the household?
.....(Kyat) yearly/monthly/Other: _____

B2. What are the main income sources of you/your family& monthly/yearly income amount (on the average)? (Check the top three items (only) according to the income amount)

Type of industry	Type of income source	Importance rating (1/2/3)	Income amount (monthly/yearly)
Primary	Farming (rice/fruit/vegetables/pulse/bean/others: _____) (Pls Go to B 6.)		Kyat (m/y)
	Fishing (by own mini boat/ employed by fishing company: _____) (Pls Go to B 5.)		Kyat (m/y)
	Wood and wood products (carpentry) (Pls Go to B 6.)		Kyat (m/y)
	Others: _____ (Pls Go to B 6.)		Kyat (m/y)
	Shipyard (Pls Go to B 6.)		Kyat (m/y)
Manufacturing	Xxx (Pls Go to B 6.)		Kyat (m/y)
	Other business, please specify: _____ (Pls Go to B 6.)		Kyat (m/y)
Service	Wholesale and retail trade (owner/employee) (Pls Go to B 6.)		Kyat (m/y)

Page 4

	Transportation (owner/employee) (Pls Go to B.6.)		Kyat (m/y)
	Public Service (Education/Government/Social work) (Pls Go to B.6.)		Kyat (m/y)
	Administrative (IT/Office) (Pls Go to B.6.)		
	Professional (doctor/finance/lawyer/Other: _____) (Pls Go to B.6.)		Kyat (m/y)
	Other service activities (Entertainment/Domestic Employ/Hospitality). Pls specify: _____ (Pls Go to B.6.)		Kyat (m/y)
	Assistance from family members/ relatives (Remittance etc.) (Pls Go to B.6.)		Kyat (m/y)
Assistance beneficiary	Aids/assistance from the governments: _____ (Pls Go to B.6.)		Kyat (m/y)
	Aids/assistance from NGOs: _____ (Pls Go to B.6.)		Kyat (m/y)
Other	Please specify: _____ (Pls Go to B.6.)		Kyat (m/y)

B3. Has there been any increase of the total income of you/your family over the last several (3-5) years?

1 () Yes. Pls explain _____
2 () No

B4. How much do you/your family spend monthly/yearly on average?

1)(Kyat)/ yearly/monthly/
2) Others. Pls specify: _____

B5-1.[For fishery population] How often do you fish in Twante Canal and Yangon river?

1. Almost every day as like fisher(Go to I3.1)
2. More than one week as like leisure(Go to I3.1)
3. I don't interested in fishing
4. None

B5-2. [For fishery population] What are main kind of fish in the river(mayor fishing spot) ?

Page 5

B5-3 [For fishery population] Do you have fish farm in the river?(if yes, describe sorts of fish and location)

B6. What are the top three highest expenditure of your family and how much monthly/yearly? (Please specify the <Income amount> on the far right column the top three highest expenditure items (only) although they are not in the top three in the ranking.)

Type of Expenditure	Specific	Importance rating (1/2/3)	Income amount* (monthly/yearly)
B6.1. Rental fee: _____			Kyat (m/y)
Residence &Shop rental	Others: _____		Kyat (m/y)
B6.2. Food & beverage: _____			Kyat (m/y)
B6.3. Education	School fee for children _____		
	Education of self: _____		
	Occupational training _____		
	Others: _____		Kyat (m/y)
B6.4. Transport	Fuel for privately owned vehicles _____		Kyat (m/y)
	Public land transport fees (bus, taxi etc.) _____		Kyat (m/y)
	Inland water transport (public boat/private boat) _____		Kyat (m/y)
B6.5. Utilities (Electricity & Water)	B.5.5.1.Water (Tap water/groundwater/rainwater/Others: _____)		Kyat (m/y)
	Electricity (grid-connected/Battery/solar/Others: _____/No access)		Kyat (m/y)
B6.6. Medical	Regular check-up _____		
	Sickness/illness _____		Kyat (m/y)
B6.7. Others	Others: _____		Kyat (m/y)
	Please specify: _____		

B7. How much do you/your family save yearly?(Kyat) (If the interviewee does not save, write zero and go to Section C)

B8. Do you/your family have any debt?

1 () Yes 2 () No (Pls go to Section C)

B9. If Yes, what is the total amount from which creditor?

Total: _____ Kyat

Page 6

From: Private individual/ Bank and other privation institutions/ Public institutions / Others:

C. ASSET & PROPERTIES

C.1. Land & Structures for Residence

C1.1. What is your ownership status of your house?

- 1 () Owner of the house
- 2 () Renter (If so how much is the rent?)
(1) Kyat/monthly
(2) In-kind payment: Pls specify: _____
(3) Not paying at all.
(4) I don't know.
- 3 () Provided by employer
- 4 () Other: _____
- 5 () I do not know

C1.2. What is the main residential building material? (The surveyor should make observation and confirm it with the interviewee - Tick all that apply.)

Wall	Roof	Floor
1 () Brick	1. xx	1. xx
2 () Concrete	2. xx	2. xx
3 () Wooden	3. xx	3. xx
4 () Stone	4. xxx	4. xxx
5 () Soil	[...]	[...]
6 () Other (specify):		
7 () I do not know		

C1.3. How many rooms are there in your house (including the living room)? Rooms

Page 7

C1.4. How many residential building structures do you have in your yard?
_____ units (1/2/3 ...)

C1.5. What is the average size of your residential buildings approximately?
Total: _____ (sqm/ha/local measurement unit XXXX) (aggregating all the building size)

C1.6. What is your ownership status of the land your house(residential building) is located?

- 1 () Owner of the land/yard
- 2 () Renter (If so how much is the rent?)
(1) Kyat/monthly
(2) In-kind payment: Pls specify: _____
(3) Not paying at all.
(4) I don't know.
- 3 () Provided by employer
- 4 () Other:
- 5 () I do not know

C1.7. Do you have any crops/plants/trees which you have planted and farming in your yard? (The surveyor should make observation and confirm it with the interviewee - Tick all that apply.)

Crops	Plants (vegetables and other commercial plants (e.g. herb, medicinal plants etc.)	Trees (fruit and other commercial trees (e.g. teak)
1. xx / ____ Unit	1. xx / ____ Unit	1. xx / ____ Unit
2. xx / ____ Unit	2. xx / ____ Unit	2. xx / ____ Unit
3. xx / ____ Unit	3. xx / ____ Unit	3. xx / ____ Unit
4. xxx / ____ Unit	4. xxx / ____ Unit	4. xxx / ____ Unit
5. Others: ____ / ____ Unit	5. Others: ____ / ____ Unit	5. Others: ____ / ____ Unit

C.2. Land & Structure for Economic Activities

Page 8

C2.1. Do you/your family have any agricultural/farming land? (Separate from the yard of the residential area: See C1.6)

1. Yes 2. No (Go to Section D)

C2.2. Do you/your family own the land yourself?
1. Yes 2. No (Go to Section C#)

[C2.3~C2.11: Farming Land- Pls answer if applicable]

[illegible]

Land #3								
[...]								

[C2.12~C2.20: Land for Shipyard- Pls answer if applicable]

C2.12. Land (1) Address: _____ _____ _____	C2.13. Is your land adjacent to? Twante Canal? 1. Yes _____ (Go to C2.11) 2. No _____ (Go to C3C)	C2.14. Land Size: Ha/sqm / local measurement unit X * Interviewer will check if the identified land lot is located within the ROW of the Project (check; the map together)	C2.15.Ownership status 1. Legal owner 3. I rent this land from private (rent fee: Monthly: _____ Kyat) 4. I rent this land from government 5. Informal squatter (Canal Land) 6. Other (please specify): _____	C2.16 Is there any building and structures within the lots? 1. Yes (Go to C2.17) 2. No _____	C2.17. How many buildings & structures do you have? _____ (units) _____ (Pls see C2.1.17: 2)	C2.18 List all building/structures (e.g., storage, workshop/e etc.) & Size (_____/sqm/ha/ local measurement unit XXXXX)	C2.19 What is the average income from the ship yard business? _____ Monthly/Y early _____ kyat	C2.20 Has your land/buildings/structures ever been affected by the flooding and other disasters related to the Twante Canal and the Yangon River? 1. Yes _____ 2. No (Go to C3) C2.20.2. Please explain (when which event/ impacts, damage made): _____ Pls explain the reason:	
Land #2									

[illegible]

C 3. Other Types of Assets

C 3.1. Animals (kettles)

Cows	Pigs	Chicken	Others:
Heads	heads	heads	heads

C 3.2 Boats & Ships

1) Boats (Type: _____/Size: _____)/ _____ Units
2) Ship (Type: _____/Size: _____)/ _____ Units

C3.3. What kind of home appliance do you have?

1 () Television
2 () Refrigerator
3 () Aircon
4 () Satellite dish
5 () Mobile phone

C3.4.What kind of vehicles do you have& how many?

1 () Bicycle/ ____ Units
2 () Motor Bike/ ____ Units
3 () Passenger car/ ____ Units
4 () Pick up truck / ____ Units
5 () Boat / ____ Units
6 () Tractor / ____ Units

C.3.5. Other Asset Type:

1) Pls specify: _____ / _____ Units
2) Pls specify: _____ / _____ Units

D.ACCESS TO UTILITIES, BASIC SOCIAL INFRASTRUCTURE

D. 1 Water & Sanitation

D1.1. Do you have any problems with water supply?

1. () Yes 2. () No (go to D7) 3. () I don't know (or No comment) (Go to D1.3)

D1.2. What are your problems with water supply? (tick all that apply.)

1 () Water cuts. How frequent?.....
2 () Not clean
3 () Expensive
4 () Difficult to access: What is the distance to fetch water from your residence? : approx.
meter / min on foot/ Others:

D1.3.1, Drinking water source ?

- 1 () Township water (piped water) (Go to D 1.4)
- 2 () Purchased bottled water (Go to D 1.4)
- 3 () Common tap (Go to D 1.4)
- 4 () Ground water well (public and private well etc. Go to D1.3.2)
- 5 () Water pot (Go to D 1.4)
- 6 () Open Source(reservoir or river) (Go to D 1.4)

D1.3.2. When you drink the ground water, do you taste salty?

1. () Yes 2. () No (go to D1.6) 3. () I don't know (or No comment)

D1.4. Do you have any problems with drinking water supply?

1. () Yes 2. () No (go to DI.6) 3. () I don't know (or No comment)

D1.5. What are your problems with drinking water supply? (tick as much as relevant. Can be more than one)

1 () Not clean/dangerous to drink
2 () Expensive
3 () Difficult to access
4 () Low quality (taste/odor/color etc.- Pls tick all applicable.)
5 () Other (please state).....

D1.6. Do you boil water before drinking?

1. () Yes 2. () No (go to D1.0) 3. () Sometimes
D1.7. You said that your domestic and drinking water are not clean. Do you think the water has become unclean recently (i.e. in the last 5 years or so)? (*For those who answer otherwise: Skip this Q and go to D1.8)
1. () Yes
2. () No (go to D1.10)
3. () I don't know (or No comment) (go to D1.10)
D1.8. Do you know the reason why the water has become/is unclean?
1. () Yes. Pls explain: _____
2. () No I don't know.
D1.9. What problem do you/your family have due to the unclean water?
1. () Diarrhea
2. () Skin disease
3. () Other water-borne disease such as _____
4. () Bad odor
5. () Others. Pls specify: _____
D1.10. What type of toilet facility do you have?
1. () Interior WC with toilet flush tank
2. () Exterior WC with toilet flush tank
3. () Interior toilet without flush tank
4. () Exterior toilet without flush tank
5. () Public WC
6. () Other (please specify).....
D1.11. What type of wastewater treatment system do you have in your house?
1. () Community sewerage system
2. () Septic tank disposed regularly by municipality
3. () Septic tank disposed regularly by him/herself
4. () Discharged directly to a river/ land
5. () Other (please specify).....
6. () I do not know
D1.12. How are the solid wastes from your house and working place disposed?
1. () Municipality collects regularly
2. () Disposed to a predefined landfill
3. () Disposed to a wild disposal area
4. () Disposed irregularly
5. () Disposed to the river/lake
6. () Burning
7. () Other
8. () I do not know

Page 13

D2. Energy

D2.13. Do you have electricity in your house?

1. Yes 2. No (Go to D2)

D2.14. Do you experience any problems with electricity supply?

1. Yes 2. No (Go to D2)

D2.35. What kind of problems do you experience? (Tick as relevant, you may tick more than one)

1. () Electricity cuts. How frequent?.....
2. () Low voltage
3. () Changing voltage
4. () Other. Please specify

D2.4. Which fuel do you mainly use for cooking? (Tick all applicable)

1. () fuel wood
2. () gas
3. () natural gas
4. () fuel oil
5. () electricity
6. () Other.....

D3. Health Condition & Service Facilities

D3.1. Have you or your family recently fallen sick in the last 3 years?

1. () Yes
2. () No (Go to D1.13)
3. () I don't know (or No comment) (Go to D1.13)

D3.2. What sickness have you suffered in the last 5 years?

1. () Diarrhea: _____ times
2. () Skin disease: _____ times
3. () Hepatitis A and E: _____ times
4. () (Typhoid) fever: _____ times
5. () Cholera: _____ times
6. () Japanese Encephalitis: _____ times
7. () Malaria: _____ times
9. () Others: Pls specify: _____

D3.3. Did you receive medical treatment at that time?

1. () Yes

Page 14

- (1) General Hospital: _____ m/km distant from my residence
(2) Clinic in the Vicinity: _____ m/km distant from my residence.
(3) Others: Pls specify: _____ m/km distant from my residence
2. () No: Pls explain why not: _____
3. () I don't know (or No comment)

D 3.4. What is the nearest clinic/hospital from your resident place?

D3.4.1. Name of the Facility: _____

D3.4.2. Distance for your residence: _____ m/km

D 3.5. Do you have to cross the canal in order to go to see doctor / for medical treatment?

1. Yes
2. No
3. Others: _____

D3.6. Have you/your family had any difficulties to access to the medical services due to the long distance?

1. Yes. Pls explain the problem you encountered: _____
2. No.

D4. School/Education Service Facilities (*Pls skip D3 if you/your family members are not attending school/education)

D 4.1. What is/are the school/education facilities you/your family members go to? (Pls list all that apply.)

Education/School facility #1	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
Education/School facility #2	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
Education/School facility #3	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
[...]	

Page 15

D4.2. Do you have to cross the canal in order to go to school/to take education?

1. Yes
2. No
3. Others: _____

D4.3. Have you/your family had any difficulties to go to school/attend education course due to the long distance?

1. Yes. Pls explain the problem you encountered: _____
2. No.

D5. Religious/Cultural Service Facilities

D 5.1. Are you/your family a member of a Religious Community?

1. Yes.
D5.1.1. Type: Buddhism/Protestant Christianity/Catholic/Hindu/Muslim/Taoist/Others: _____

D5.1.2. How many times do you attend the religious services? (Everyday/Every week/ _____ times a week/month/year)

2. No. (Pls go to D5.5)

D 5.2. Where is the service center(s) (church/ temple/mosque etc.) you or your family attend to?

Religious service facility #1	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
Religious service facility #2	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
Religious service facility #3	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
[...]	

Page 16

D 5.3. Do you have to cross the canal in order to go to the religious center?

1. Yes

2. No

3. Others: _____

D5.4. Have you/your family had any difficulties to go to the religious center due to the long distance?

1. Yes. Pls explain the problem you encountered: _____

2. No.

D 5.5. Are you/your family a member of a Cultural Community/Civil Society/Occupational Association etc.?

1. Yes. Name: _____

2. No.

3. No comment

D 5.6. Where is the location of the community center(s) (organization office(s)) you or your family go to?

Community service facility #1	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
Community facility #2	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
Community facility #3	■ Name of the Facility: _____ ■ Distance for your residence: _____ m/km
[...]	

D 5.7. Do you have to cross the canal in order to go to the community center?

1. Yes

2. No

3. Others: _____

Page 17

D5.8. Have you/your family had any difficulties to go to the community center due to the long distance?

1. Yes. Pls explain the problem you encountered: _____

2. No.

D. 6. Crossing of the Twante Canal

D 6.1 How many time do you cross the Twante Canal in week?

1. Every week to commute opposite river side

2. Almost 3 times a week to shopping

3. Less than one a week

4. None

E. IMPACTS ON ECO SYSTEMS & COMMUNITIES

I. ENVIRONMETAL IMPACES EXPECTED

E1. Are there any of the following sits/facilities that are expected to be affected by the project?

Items	Types of Impacts_Pls describe.	Location (* Interviewer to locate the identified locations on the map)
Cultural sites/Structures		
Religious sites/Structures		
Others: Pls specify: _____		
Community hall/Facilities		
School/education center		
Hospital/Health centers		
Other public buildings/facilities		

H. PERCEPTIONS AND EXPECTATIONS

Page 18

H1. Have you heard of this project before?

1 () Yes

2 () No(* The Interviewee to explain the brief overview of the project then Go to H3)

3 () No comment (* The Interviewee to explain the brief overview of the project then Go to H3)

H2.How did you learn about the project? Please tick all the relevant channels of information..

1. Village committee & Township meeting	
2. TV&Radio, newspaper	
3. Facebook& Social media	
4. Posters by local government and relevant agencies (GAD and/or DWIR)	
5. Community & Neighbors	
6. Governmental officers	
7. Other (please specify): _____	

H3. Do you welcome the project in your village/township?

1 () Yes, pls briefly explain the reason _____

2 () No, pls briefly explain the reason _____

H4. What do you think would be the benefits of the project?

Pls select from the Table below (*Interviewer to list ①-⑧) the highest three benefits for you/your family, your community/village and for Myanmar.

1. For yourself/ your family (Choose from the selection table)	2. For the community/village	3. For the country
Others: _____	Others: _____	Others: _____

Page 19

* Selection Table

Expected benefits	① Socioeconomic development ② Safe and efficient inland water transport system ③ Safe ship trip navigation ④ Income increase and improved living standards Reduced annual tide flooding/inundation along the canal (less chance of accidents: life and livelihood loss and facility destructions etc.) ⑤ Farm land protection from land erosion ⑥ Improvement living environment ⑦ Boost tourisms and local economy
-------------------	---

E5. How do you think the Project Proponent/the Government could maximize the benefits of the project? Pls suggest.

H6. What kind of adverse effects can the project cause?

Pls select from the Table below (*Interviewer to list ①-⑧) the most serious three adverse impacts of the project for you/your family, your community/village and for Myanmar.

1. For yourself/your family (Choose from the selection table)	2. For the community/village	3. For the country
Others _____	Others _____	Others _____

* Selection Table

Expected Negative impacts _ Environmental	① Noise from the construction and traffic ② Decline in water quality ③ Air pollution
--	--

Page 20

	④ Vibration
Expected Negative impacts _ Social	⑤ Inconvenience of movement ⑥ Relocation (e.g. eviction) ⑦ Loss of income ⑧ Loss of jobs/economic opportunities ⑨ Intervention/disruption of business. Pls specify: _____ ⑩ Change in land usage and socio cultural environment ⑪ Conflicts among residents/community members ⑫ Conflicts between residents/community members and construction workers ⑬ Demolition/Damages of the community/religious/cultural sites and facilities (Pls specify: _____)

H7. How do you think the Project Proponent/the Government could reduce the expected adverse impacts of the project? Pls suggest.

H8. What are the most important issues related with the project for your village/township?

1.
2.
3.
4.

H9. Any comments, opinion, suggestions of the project?

Thank you very much for your cooperation.